

**For Notes & Frame Prep
See Sheet 2**

DOOR SPECIFICATION

Door Thickness: 1-3/4"
(45mm) Min.

Door Construction: Wood or composite door with fire or panic rating as required. Door may require metal channel edge which may alter backset dimensions. Consult door manufacturers listings.

Exit Device Ratings:



2160-LBR, 2165-LBR,
Panic Exit Door up to 4' x 8'

2160F90-LBR, 90
Minute Rated Fire Exit
Doors up to 4' x 8'

2160-LBR-10, 2165-
LBR-10, Panic Exit Door
up to 4' x 10'

2160F90-LBR-10, 90
Minute Rated Fire Exit
Doors up to 4' x 10'

Door Edge Detail



<p>RESPONSIBILITY DOOR AND FRAME MANUFACTURERS ARE RESPONSIBLE FOR PROVIDING ADEQUATE CONSTRUCTION OR REINFORCEMENTS FOR PROPER INSTALLATION OF HARDWARE SHOWN. ALL ARCHITECTURAL BUILDERS HARDWARE MUST BE INSTALLED ON PROPERLY REINFORCED DOORS AND FRAMES, REGARDLESS OF TYPE, MATERIAL, OR METHOD OF CONSTRUCTION.</p>
<p>2160(F90) LBR Series 2160-LBR-10, 2160(F90)-LBR-10 Concealed Vertical Rod Exit Devices Application for Wood Door & Metal Frame Less Bottom Rod 1-855-557-5078 Ext. 2 www.accentra-assaabloy.com</p>

Experience a safer
and more open world


Copyright © 2017, 2024, 2025, ASSA ABLOY ACCENTRA™ Access and Egress Hardware Group, Inc. All rights reserved. Reproduction in whole or in part without the express written permission of ASSA ABLOY Access and Egress Hardware Group, Inc. is prohibited.

ACCENTRA

ASSA ABLOY

SUPERSEDES	04/24	DO NOT SCALE DRAWING
TEMPLATE NUMBER	7421-1065	SHEET 1 of 2 DATE 06/25

761 Top Strike Preparation (See Note 6)



Notes:

1. Do not scale drawing.
2. Dimensions are in inches (mm).
3. Preparation is typical for both hands.
4. Minimum door stile width: 4-1/2 (114).
5. Prepare mounting holes when installing the device.
6. Drawing shows elevation (frame bisected on strike center), bottom view looking up and side view.
7. Provide adequate structural support to maintain door integrity after device installation with power tools, door use, or abuse.
8. Door located in frame for door silencers. If not used, compensate this dimension to seat the door against the stop without rattle.
9. Device mount to hinge stile (not shown) requires hole location and preparation during device installation. Door structural requirements are similar for both stiles.
10. For outside trim preparation see appropriate trim template.
11. For labeled door pairs only. Reinforce door as needed for heat activated interlocking bolt. See template 7470-1700.

RESPONSIBILITY
DOOR AND FRAME MANUFACTURERS ARE
RESPONSIBLE FOR PROVIDING ADEQUATE
CONSTRUCTION OR REINFORCEMENTS FOR
PROPER INSTALLATION OF HARDWARE SHOWN.
ALL ARCHITECTURAL BUILDERS HARDWARE MUST
BE INSTALLED ON PROPERLY REINFORCED
DOORS AND FRAMES, REGARDLESS OF TYPE,
MATERIAL, OR METHOD OF CONSTRUCTION.

2160(F90) LBR Series 2160-LBR-10, 2160(F90)-LBR-10
Concealed Vertical Rod Exit Devices
Application for Wood Door &
Metal Frame Less Bottom Rod
1-855-557-5078 Ext. 2
www.accentra-assaabloy.com

ACCENTRA®
ASSA ABLOY