



VeraSolSM

VeraSol* Product Certificate

*Previously Lighting Global Quality Assurance

Pico Solar Home System 3000 (Assembled in Ethiopia)

Expiration Date: May 31, 2022¹

Verify here: <https://data.verasol.org/products/sek/fs-pshs3000>

This document verifies that the Pico Solar Home System 3000 (Assembled in Ethiopia) was tested according to the following test methods and conformed with the following standards:

Test methods: IEC TS 62257-9-5:2018²
Quality standards: Lighting Global Pico PV Quality Standards³

Testing Details

Product Name: Pico Solar Home System 3000 (Assembled in Ethiopia)
Model Number: PSHS 3000
Company Name: Fosera Group
Country of Origin: Thailand, Ethiopia
Company Contact: Thomas Koepke, info.ethio@fosera.com
Original QTM Sample Size: n=6
Renewal Test Conducted: yes
Sample Procurement Method: Random warehouse sampling
Testing Laboratory: Shenzhen Academy of Metrology and Quality Inspection, Shenzhen, China and Schatz Energy Research Center, Arcata, CA USA

Documentation

Specifications sheet with verified test results and original version of this verification:
<https://data.verasol.org/products/sek/fs-pshs3000>

Ari Reeves
Senior Manager, CLASP

¹ VeraSol requires re-testing every two years or upon major product revisions, and in special cases reserves the right to grant an extension on results validity.

² <https://verasol.org/solutions/test-methods>

³ <https://verasol.org/solutions/quality-standards>

Type Approval

Pico Solar Home System 3000 (Assembled in Ethiopia)

Verify here: <https://data.verasol.org/products/sek/fs-pshs3000>

Category	Quality Standard	Verdict
Truth In Advertising	Manufacturer, Product Name and Model Number accurately specified	Pass
	Performance and component ratings accurately specified. Any description of the product that appears on the packaging, inside the package and in any media shall be truthful and accurate. No statements mislead buyers or end users about the utility of the product. Numeric ratings deviate no more than 15% from actual performance (note that it is acceptable for actual performance to exceed advertised performance).	Pass
	Port voltage and current specifications, if provided, are accurate. Included appliances function when connected to ports. Power output of ports is sufficient to power appliances that are advertised but not included. Ports that are intended for a function other than providing power, such as data ports, are not required to meet this standard.	Pass
Lumen Maintenance	Average relative light output $\geq 90\%$ of initial light output at 2,000 hours with only one sample allowed to fall below 85% OR All 6 samples maintain $\geq 95\%$ of initial light output at 1,000 hours	Pass
Circuit and Overload Protection	Products include a current limiting mechanism to prevent irreversible damage to the system. The mechanism is easily resettable or replaceable by the user, or automatically resets. If replaceable fuses are used for circuit protection, sizes are labeled on the product and listed in the user manual, and, if fuses are replaceable by the user, at least one spare fuse is included with the product. Included appliances are not required to meet this standard unless they have ports that are intended to provide power.	Pass
AC-DC Charger Safety	Any included AC-DC charger carries approval from a recognized consumer electronics safety regulator	n/a
Hazardous Substances Ban	No battery contains cadmium or mercury at levels greater than trace amounts	Pass

Type Approval

Pico Solar Home System 3000 (Assembled in Ethiopia)

Verify here: <https://data.verasol.org/products/sek/fs-pshs3000>

Category	Quality Standard	Verdict
Battery Protection	Protected by an appropriate charge controller that prolongs battery life and protects the safety of the user. 5 out of 6 samples meet the requirements outlined in Lighting Global Quality Standards. Lithium batteries carry IEC 62281, IEC 62133-2, UL 1642 or UN 38.3 certification and have overcharge protection for individual cells or sets of parallel-connected cells. Batteries of included appliances must also meet this standard.	Pass
Battery Durability	The average capacity loss of 6 samples does not exceed 25% and only one sample may have a capacity loss greater than 35% following the battery durability storage test as defined in IEC TS 62257-9-5 Annex BB	Pass
PV Overvoltage Protection	If the battery is disconnected or isolated, the system must not be damaged and the load terminals shall maintain a voltage that is safe for their intended uses.	Pass
Miswiring Protection	The user interface is designed to minimize the likelihood of making improper connections. If improper or reversed connections can easily be made, they cause no damage to the system or harm to the user.	Pass
Physical Ingress Protection	IP2X for all products, IP3X (or 2X + circuit protection) for PV modules, IP5X for fixed outdoor products	Pass
Water Ingress Protection	Degree of protection required is based on product type: Fixed separate (indoor): No protection required Portable separate: Occasional exposure to rain Portable integrated: Frequent exposure to rain Fixed integrated (outdoor): Permanent outdoor exposure PV modules: Outdoor rooftop installation	Pass
Drop Test	Fixed separate (indoor): No requirement All other products: 5 out of 6 samples are functional after drop test; none result in dangerous failures.	Pass
Soldering and Electronics Workmanship	The system and any included appliances are rated "Good" or Fair" for workmanship quality as defined in Annex F of IEC TS 62257-9-5. At most, one sample may fail to function when initially evaluated.	Pass
Mechanical Durability	All samples and included appliances are functional after Switch, Connector, Gooseneck and Strain Relief tests; none result in dangerous failures	Pass
Minimum Warranty Terms	Accurately specified and consumer-facing; minimum coverage of at least one year on manufacturing defects under normal use, including the battery and included appliances.	Pass

Type Approval

Pico Solar Home System 3000 (Assembled in Ethiopia)

Verify here: <https://data.verasol.org/products/sek/fs-pshs3000>

Category	Quality Standard	Verdict
Performance Reporting	Light output and the corresponding solar run time are reported on the product packaging for at least the brightest setting.	Pass
	Impact of mobile phone charging on product performance is described on packaging.	Pass

Test Methods & Quality Standards

Products are tested according to the test methods described in IEC TS 62257-9-5:2018 and meet the Lighting Global Pico PV Quality Standards.

Additional details on the requirements listed above are available here:
<https://verasol.org/solutions/quality-standards>

About VeraSol

An evolution of Lighting Global Quality Assurance, VeraSol supports high-performing, durable off-grid products that expand access to modern energy services. VeraSol builds upon the strong foundation for quality assurance laid by the World Bank Group and expands its services to encompass off-grid appliances, productive use equipment, and component-based solar home systems. VeraSol is managed by CLASP in collaboration with the Schatz Energy Research Center at Humboldt State University. Foundational support is provided by the World Bank Group's Lighting Global program, UKaid, IKEA Foundation, and others. Please visit [VeraSol.org](https://verasol.org) for more information.

Disclaimer

To the extent permitted by law, CLASP makes no (and expressly disclaims all) warranties, express, implied or statutory, with respect to the product(s) certified under this agreement, including without limitation any implied warranty of merchantability, fitness for a particular purpose, noninfringement, or arising from course of performance, dealing, usage or trade. Additionally, CLASP disclaims that the product will perform in certain ways and that it meets any national standards. Without limiting the generality of the foregoing, CLASP makes no claim, representation, or warranty of any kind as to the utility of the products for customer's intended uses.

Contact

info@verasol.org