



ދަރުކަ ބަލާ ދަނޑު ސަލާމަތް ސަލާމަތް ސަލާމަތް ސަލާމަތް ސަލާމަތް

## Qualification of Bidders

The bid document shall comprise the following information in the given format and order, which MWSC shall use to determine whether the Bidder possesses relevant experience, technical capacity to undertake the project works and to complete successfully in accordance to the bid. Any bid did not accompany the following in the given **format and order** shall be rejected by the Employer as non-responsive.

- Bid form. Must be filled stamped and signed. Amount stated in the bid document **should be exclusive of GST** and should tally with the **amount stated in the BOQ**.
- MIRA tax clearance **(06 months prior to the bid submission deadline). Must be clear.**
- MNPHI Contractors Registration Certificate
- Business Registration Certificate at Economic Ministry
- GST Registration
- Priced BOQ. **Must be filled and complete. BOQ should not be altered. Bidder's rates should not be more than two decimals.**
- Work schedule. **Should tally with the duration stated in Bid form**
- Site Organization chart
- List of Key Personnel's proposed for the project in the given format "List of Key Personnel's" under Section-V Sample forms.
- List of Skilled & Unskilled workforce proposed for execution of the works in the given format "List of Skilled & Unskilled workforce" under Section-V Sample forms.
- List of Machineries and Equipment proposed for the project in the given format "List of Machineries and Equipment" under Section-V Sample forms.
- Experience – Part 1 List of Similar Projects completed over last five years in the given format "Form of Experience" under Section-V Sample forms.
- Experience – Part 2 list of Ongoing MWSC Projects in the given format "Form of Experience" under Section-V Sample forms. Applicable for bidders with ongoing contract commitments with MWSC.

## Scope of Works

### Location of the Works

The site for the works proposed under this contract is the island of **Gdh. Fiyoari**.

### Description of the Works.

This is a Schedule of Rates Contract for the construction of sewerage treatment plant. The major works to be undertaken include;

- a) Construction of RCC tanks for STP
- b) Construction of operating platform, handrails, ladder etc.
- c) Construction of Pump shelters- 2nos
- d) Construction of sludge drying bed and shelter
- e) Construction of STP boundary fence and gate
- f) Construction of MCC room
- g) Construction of Light post – 5nos
- h) Excavation & laying of STP area pipelines (underground lines)

### NOTE:

- 1. All the items on the bills are for supplying and construction unless otherwise specified.
- 2. The contractor should arrange transportation and storage facilities for all the materials
- 3. Sulfate Resistant cement should be utilized for the construction works of STP tanks
- 4. The rate shall include dewatering and disposal of water according to site condition/away from existing building areas.
- 5. Contractor shall clear the site of excavation if required (including bushes and tree cutting). MWSC will pay for compensation for the trees to the required authority if needed.
- 6. Excavations should be done with safety measures like proper care and shoring for the houses and their boundaries. The contractor should be responsible for proper safeguard to the nearby houses.
- 7. The contractor is responsible for any damages to the cables and equipment such as panel boards, other utility service lines, surrounding structures, etc. during the pipe laying. The contractor shall indemnify the respective party against all losses or claims.
- 8. MWSC will arrange the excavator for site cleaning works including its Operator. Diesel is required for the Vehicle and labor to the clearance to be arranged by the Contractor. Also, MWSC will pay for the compensation of the trees to the required authority if needed.

### Summary of evaluation criteria with weights

#	Criteria	Weighting %
1	Price	70%
2	Duration	30%