



Gamu Regional Hospital
L.Gan



Project: Installing ceiling panel system and air conditioning system in Operation theatre

Scope: Upgrading OT AC and Ceiling
Supplying, complete installation, commisioning OT upgrade work

1	Ceiling Panel System (OT 1 and 2)	Full system	2				
Use PVC coated system (OT Sizes 21ft L x 19ft W x 12ft H)							
2	Air Conditioning (OT 1 and 2)	For full floor	2				
Suitable airconditioning system including Air handling unit - AHU (with coil, with heater/humidifier if necessary) must be provided or existing airconditioning system should be integrated to Laminar air flow system. ensure incoming air is filtered with HEPA filter (AC Unit Should not be smaller than 36000BTU)							
Air speed should be minimum 2m/s and maximum 5m/s							
Air condition system should be approved for use in Operation theater							
							Sub total
							GST
							Total

