

**L.Dhanbidhoo Health Centre boundary wall Renovation Works**

#	Work Detail	Unit	Qty	Rate	Amount
<b>1</b>	<b>Boundary Wall Renovation</b>				
1.1	Masonry Works with 4" hollow Block (cement motar mix is 1:5)	m <sup>2</sup>	207.6		-
1.2	Plaster Works - 20mm thick Plaster (cement motar mix 1:5)	m <sup>2</sup>	415.2		-
1.3	Foundation Beam	m <sup>3</sup>	5.6		-
1.4	Capping Beam	m <sup>3</sup>	4.7		-
1.5	Column	m <sup>3</sup>	2.4		-
1.6	Painting Works (including Wall sealer)	m <sup>2</sup>	523		-
				Total	-
				8% GST	-
				Total incl. GST	-

Note: Rate Should include demolition of Existing wall, Excavation for Foundation and other necessary works.

