

**BILL OF QUANTITIES**  
**COMMUNITY GYM OUTDOOR AREA K.GURAIIDHOO**

**CLIENT : K.GURAIIDHOO COUNCIL**

SUMMARY OF BILLS OF QUANTITIES  
**COMMUNITY GYM OUTDOOR AREA K.GURAI DHOO**

DESCRIPTION	Material Cost	Labour Cost	AMOUNT
1.0.01	-	-	-
Bill No: 02 - EXCAVATION AND FILLING	-	-	-
Bill No: 03 - SEATING	-	-	-
Bill No: 04 - FLOORING	-	-	-
<b>TOTAL AMOUNT</b>	-	-	-
<b>GST 8%</b>			-
<b>TOTAL AMOUNT including GST</b>			-

COMMUNITY GYM OUTDOOR AREA K.GURAI DHOO

Republic of Maldives

BILL OF QUANTITIES		BILL OF QUANTITIES		BILL OF QUANTITIES		BILL OF QUANTITIES	
ITEM		ITEM		ITEM		ITEM	
1.0.00		1.0.01		1.0.02		1.0.03	
1.1.00	<p><b>GENERAL NOTES</b></p> <p><u>Abbreviations</u>                      m - metre                      nr - numbers                      m3 - cubic metres                      m2 - square metres                      m - linear metre                      t - tons                      inc. - including                      mm - millimetre                      SS - stainless steel                      GI - galvanized iron</p>						
1.2.00	<p><b>SITE MANAGEMENT COSTS</b></p> <p>Allow for all on and off site management cost including costs of foreman and assistants, temporary services, telephone, fax, hoardings &amp; similar.</p>	item	1.00			-	-
<b>TOTAL OF BILL №: 01 - Carried Over To Summary</b>						-	-
2.0.00	<b>Bill №: 02 - EXCAVATION AND FILLING</b>						
2.1.00	<p><b>GENERAL</b></p> <p>(a) Rates shall include for: leveling, grading, trimming, compacting to faces of excavation, keep sides plumb, backfilling, consolidating, and disposing surplus soil.</p>						
2.2.00	<p><b>SITE CLEARING</b></p> <p>2.2.01 Clear the area of site from rubbish and vegetable matters, stumps, roots. Rates shall include for removal of trees and tree stumps and disposal of such materials</p>	m <sup>2</sup>	350.00			-	-
2.3.00	<b>EXCAVATION</b>						

ITEM	ITEM			ITEM			ITEM	
2.3.01	Excavation quantities are measured to the faces of concrete members. Rates shall include for all the additional excavation required to place the formwork. Rates shall include for backfilling. Excavation	m <sup>3</sup>	30.48			-	-	-
<b>2.4.00</b>	<b>FILLING</b>							
2.4.01	Rate shall include for: levelling, grading, trimming, compacting and similar Compacted earth filling under ground slab	m <sup>2</sup>	25.00			-	-	-
<b>2.5.00</b>	<b>DAMP-PROOF MEMBRANE</b>							
2.5.01	Rate shall include for: dressing around and sealing to all penetrations,laps and turnups. Polythene damp proof membrane (500 gauge)	m <sup>2</sup>	101.60			-	-	-
<b>2.8.00</b>	<b>TOTAL OF BILL №: 02 - Carried Over To Summary</b>					-	-	-
<b>04.0.00</b>	<b>Bill №: 03 - SEATING</b>							
	<b>GENERAL</b>							
4.1.01	SEATING MASONRY WORK	m <sup>2</sup>	209.00			-	-	-
	3" Solid Bricks	Nos	4,807.00			-	-	-
	Cement	Bag	48.07			-	-	-
	Coarse Sand	Bag	240.35			-	-	-
4.1.02	SEATING PLASTERING WORK	m <sup>2</sup>	419.00			-	-	-
	Cement	Bag	69.83			-	-	-
	Coarse Sand	Bag	279.33			-	-	-
	Fine Sand	Bag	279.33			-	-	-
4.1.03	75 MM SEATING CONCRETE PANEL	m <sup>3</sup>	4.94			-	-	-
	Cement	Bag	39.52			-	-	-
	Coarse Sand	Bag	79.04			-	-	-
	Aggregate	Bag	118.56			-	-	-
	Admixture	Bag	3.95			-	-	-
	6 mm Steel bar	Nos	240.00			-	-	-
4.1.04	100 MM WATER FEATURE	m <sup>3</sup>	1.55			-	-	-

