BILL OF QUANTITIES

PROJECT: Vacant 3 flats renovation 2023 CLIENT: MINISTRY OF EDUCATION TF (Thauleemee Fund)

SUMMARY BILL OF QUANTITIES				
#	Bill name	Amount		
1	Hard wood door instalation	MVR 0.00		
2	Aluminium Toilet door instalation	MVR 0.00		
3	Painting interior one room apartments	MVR 0.00		
4	Painting interior Two room apartments	MVR 0.00		
5	Toilet installation	MVR 0.00		
6	Muslim shower installation	MVR 0.00		
7	Wash basin Installation	MVR 0.00		
8	Head shower installation	MVR 0.00		
9	Water Leak	MVR 0.00		
10	Electrical wiring	MVR 0.00		
-	TOTAL	MVR 0.00		
	GST 8%	MVR 0.00		
	AMOUNT	MVR 0.00		

	SUMMARY BILL OF QUANTITIES	
#	Bill name	Amount
1	Removal of the existing kitchen sets	MVR 0.00
2	Supply and Installation of Kitchen set	MVR 0.00
3	Supply and installation of Under cabinet ventilation hood	MVR 0.00
4	Supply and installation of Sink Tap and Sink	MVR 0.00
5	Supply and installation of two burner countertop gas stove	MVR 0.00
	TOTAL	MVR 0.00
	GST 8%	MVR 0.00
	AMOUNT	MVR 0.00

Total Project Value MVR 0.00

BILL OF QUANTITIES 1

#	Bill name	Qty	Unit	Price	Amount
1	Removal of the existing kitchen sets				
	Removal and discarding of the existing kitchen				
	sets. Contractor must see that no damages are				
	done to the property all prevention shall take				
	place on site to protect the property from being				
	damaged while the removal of the existing kitchen				
	set. If any damages are caused it should be				
	rectified by the contractor.	2.00	no.		
2	Supply and Installation of Kitchen set				
	Replacing the kitchen sets and installing new ones.				
	Design will be same as the one being removed.				
	Price shall include all hinges (should be soft				
	closing), cabinets knobs, handles, granite(Surface				
	top to be approved), and all needed fittings.				
	Shifting of existing electrical sockets	2.00	no.		
4	Supply and installation of Under cabinet				
-	ventilation hood				
	Supply and istalation of hood for the kitchen.				
	needs to be approved from theclient before				
	purchase	2.00	no.		
5	Supply and installation of Sink Tap and Sink				
	Sink Tap and Sink shall be a SS coated, Sink Tap				
	shall be a long neck Tap that needs to be approved				
	from theclient before purchase and shall be				
	installed and checkd for any water leaks. This shall				
	include all needed fittings for the installation.	2.00	no.		
	Supply and installation of two burner countertop	2.00	110.		
6	gas stove				
	needs to be approved from the client before				
	purchacese	2.00	no.		
L				TOTAL	MVR 0.00
				GST 8%	MVR 0.00
				AMONT	MVR 0.00

BILL OF QUANTITIES

#	Bill name	Qty	Unit	Price	Amount
π	Ministry of educat				Amount
1	Hard wood door instalation				
-					
	Existing doors shall be removed by				
	the contractor. Door shall be a solid				
	wood door which has to be hinged				
	on to a solid timber frame with 4				
	hinge nos. 125 X 30 X 3 stainless				
	steel bearing hinges, providing door				
	stopper, Lever Handle Locks as per				
	samples approved and as per site				
	requirements. Price shall include the				
	installation of 2 inch boader for door				
	frame.	5.00	no.		
2	Aluminium Toilet door instalation	-			
	ToiletDoor shall be made using				
	aluminium clading and aluminium				
	profiles which has to be hinged 3				
	hinges nos. 125 X 30 X 3 stainless				
	steel bearing hinges, providing door				
	stopper, door handles and lock. as				
	per samples approved and as per site				
	requirements.	3.00	no.		
3	Painting interior one room				
5	apartments				
	all loose paint shall be scraped, if				
	needed putty should be applied and				
	sanded for surface prepration. All				
	walls including toilets ceiling also will				
	have to be painted with one code of				
	wall sealer and 2 codes of paint. as				
	per samples approved and as per site				
	requirements.	1.00	no.		
4	Painting interior Two room				
	apartments				
	all loose paint shall be scraped, if				
	needed putty should be applied and				
	sanded for surface prepration. All				
	walls including toilets ceiling also will				
	have to be painted with one code of				
	wall sealer and 2 codes of paint. as				
	per samples approved and as per site				
	requirements.	2.00	no.		

5	Toilet installation				
	Removal and discarding of the				
	existing commode toilet and				
	installing of an coto or equivalent				
	commode toilet. as per samples				
	approved and as per site				
	requirements.	3.00	no.		
6	Muslim shower installation				
	Removal and discarding of the				
	existing hand shower and installing				
	of an water tek or equivalent hand				
	shower. as per samples approved				
	and as per site requirements.	3.00	no.		
7	Wash basin Installation				
	Removal and discarding of the				
	existing wash basin and installing of				
	an coto or equivalent wash basin. as				
	per samples approved and as per site				
	requirements and installation of a				
	mirror measuring "19 inches X 26				
	inches "	3.00	no.		
8	Head shower installation				
	Removal and discarding of the				
	existing Head shower and installing				
	of an coto or equivalent head				
	shower. As per samples approved				
	and as per site requirements.	3.00	no.		
9	Water Leak	0.00			
	Identify water leak and fixing of				
	water leak and dampness from walls				
	and ceiling leaks.	3.00	no.		
10	Electrical wiring		1		
	rewiring and Fixing some electric				
	points faulty sockets and switches	1.00	no.		
				TOTAL	MVR 0.0
				GST 8%	MVR 0.0
				AMOUNT	MVR 0.0