



دکنی حکومت سرگرمیوں کے لیے سروس فراہم کرنے والی کمپنی

## Qualification of Bidders

The bid document shall comprise the following information in the given format and order, which MWSC shall use to determine whether the Bidder possesses relevant experience, technical capacity to undertake the project works and to complete successfully in accordance to the bid. Any bid did not accompanied by the following in the given **format and order** shall be rejected by the Employer as non-responsive.

- Bid form. Must be filled stamped and signed. Amount stated in the bid document **should be exclusive of GST** and should tally with the **amount stated in the BOQ**.
- MIRA tax clearance **(within 06 months). Must be clear.**
- MNPHI Contractors Registration Certificate
- Business Registration Certificate at Economic Ministry
- GST Registration
- Priced BOQ. **Must be filled and complete. BOQ should not be altered. Bidder's rates should not be more than two decimals.**
- Work schedule. **Should tally with the duration stated in Bid form**
- Site Organization chart
- **Resource allocation proposed for the project** in the given format "Resource allocation plan" under Section II - Sample Tendering Forms
- Experience – Part 1 list of Similar Projects completed over last five years in the given format "Form of Experience" under Section-V Sample forms.
- Experience – Part 2 list of Ongoing MWSC Projects in the given format "Form of Experience" under Section II - Sample Tendering Forms. *(Applicable for bidders with ongoing contract commitments with MWSC)*

## Scope of Works

### Location of Work:

The site for the works proposed under this contract is the Island of B. Kendhoo

### Description of works.

This is a Schedule of Rates Contract for the construction of sewage treatment plant. The major works to be under taken include;

- a) Construction of RCC tanks for STP
- b) Construction of operating platform, hand rails, ladder etc.
- c) Construction of Pump shelters- 2nos
- d) Construction of sludge drying bed and shelter
- e) Construction of STP boundary fence and gate
- f) Construction of MCC room
- g) Construction of Light post – 5nos
- h) Excavation & laying of STP area pipe lines (underground lines)

### **NOTE:**

1. All the items on the bills are for supplying and construction unless otherwise specified.
2. The contractor should arrange transportation and storage facilities for all the materials
3. Sulfate Resistant cement should be utilized for the construction works of STP tanks.  
**Contractor shall arrange SRC cement for STP concrete works.**
4. The rate shall include dewatering and disposal of water according to site condition/away from existing building areas.
5. Contractor shall clear the site of excavation if required (including bushes and tree cutting). MWSC will pay for compensation for the trees to the required authority if needed.
6. Excavations should be done with safety measures like proper care and shoring for the houses and their boundaries. The contractor should be responsible for proper safeguard to the nearby houses.
7. The contractor is responsible for any damages to the cables and equipment such as panel boards, other utility service lines, surrounding structures, etc. during the pipe laying. The contractor shall indemnify the respective party against all losses or claims.
8. MWSC will arrange the excavator for site cleaning works including its Operator. Diesel is

required for the Vehicle and labor to the clearance to be arranged by the Contractor. Also, MWSC will pay for the compensation of the trees to the required authority if needed.

- 9. Rusting is observed in the STP reinforcement work, so the contractor shall consider rust removal when submitting the bid proposal and contractor shall provide a suitable rust removal methodology for approval during the project execution stage.

Summary of evaluation criteria with weights

Part - A

#	Criteria	Weighting %
1	Price	70%
2	Duration	30%

Part - B

#	Criteria	Capability
3	Resource	Pass/Fail