

TECHNICAL SPECIFICATIONS

Infrastructure and Building Development

Auxiliary Services

Maldives Police Service

Tel: (960) 9790053, Fax: (960) 3321297

Email: infrastructure@police.gov.mv

TABLE OF CONTENTS

1. PRELIMINARIES.....	5
1.1 STANDARD AND CODES.....	5
1.2 DRAWINGS AND SPECIFICATIONS.....	5
1.3 TRANSPORTATION TO THE SITE.....	5
1.4 SCHEDULE AND EXECUTION PLAN.....	5
1.5 REPAIRING AND CORRECTION.....	5
1.6 WORKMANSHIP AND MATERIALS.....	5
1.7 OBVIOUS WORK.....	6
1.8 PROTECTION.....	6
1.9 SCAFFOLDING.....	6
1.10 CONSTRUCTION MACHINERY, PLANTS AND EQUIPMENT'S.....	6
1.11 SAMPLES.....	6
1.12 ORDERING MATERIALS.....	7
1.13 CONTRACTOR'S SITE AREA.....	7
1.14 PROGRESS MEETINGS.....	7
1.15 LOADING IN EXCESS OF DESIGN LOAD.....	7
1.16 HANDING OVER.....	7
2. CONCRETE WORKS.....	8
2.1 GENERAL.....	8
2.2 CEMENT.....	8
2.3 AGGREGATE.....	8
2.4 WATER.....	10
2.5 HANDLING AND STORAGE OF MATERIAL.....	10
2.6 MIX PROPORTION AND STRENGTH.....	10
2.7 PRODUCTION OF CONCRETE.....	10
2.8 TRANSPORTING AND PLACING.....	11
2.9 CONCRETE CURING.....	12
2.10 TEST.....	12
2.11 CONCRETE.....	13
2.12 DEFECTIVE CONCRETE AND FINISHES.....	13
3. CONCRETE FORMWORK.....	14
3.1 STRUCTURE AND MATERIAL.....	14
3.2 PERFORMANCE.....	14
4. STEEL REINFORCEMENT.....	17
4.1 MATERIAL.....	17
4.2 CLEANING.....	17
4.3 BENDING AND LAPS.....	17
4.4 REINFORCEMENT COVER.....	17
4.5 PLACING.....	17
5. MASONRY.....	18
5.1 MATERIALS.....	18
5.2 GENERAL.....	18
5.3 BLOCK WORK.....	18
6. PLASTERING.....	20
6.1 GENERAL.....	20
6.2 MATERIALS AND STORAGE.....	20
6.3 MIXING RATIO.....	20
6.4 THICKNESS OF COATING.....	20
6.5 FINISH.....	21
6.6 GENERAL PREPARATION.....	21
6.7 EXTERNAL PLASTERING.....	21

6.8	INTERNAL PLASTERING	22
6.9	EXTERNAL RENDERING	22
6.10	METAL MESH LATHING / REINFORCEMENT FOR PLASTERED/COATINGS.	22
7. CARPENTRY, JOINERY AND FURNITURE		24
7.1	MATERIALS	24
7.2	PRESERVATION OF TIMBER	24
7.3.3	HARDWARE	24
7.4	DIMENSIONS AND FINISH.....	24
7.5	WORKMANSHIP	24
8. DOORS AND WINDOWS		26
8.1	DOORS AND WINDOWS.....	26
8.2	LOUVERS.....	27
8.3	TOP HUNG WINDOWS, VENTILATORS AND SIDE HUNG DOORS	27
8.4	INSTALLATION	28
8.5	SEALING JOINTS	28
8.6	GLASS INSTALLATION	29
9. TILING.....		30
9.1	GENERAL	30
9.2	MANUFACTURERS	30
9.3	CERAMIC AND VITREOUS TILE MATERIALS	30
9.4	MORTAR MATERIALS	30
9.5	CEMENT COLOUR	30
9.6	WATERPROOFING	30
9.7	INSTALLATION REQUIREMENTS.....	30
9.8	FLOOR TILE INSTALLATION.....	31
9.9	WALL TILE INSTALLATION.....	31
9.10	GROUTING.....	31
9.11	DEFECTS IN TILES AND TILE LAYING	32
9.12	GUARANTEES	32
10. PAINTING		32
10.1	MATERIAL.....	32
10.2	DEFINITION OF TERMINOLOGY	33
10.3	PAINT FINISH SYMBOLS	33
10.4	PAINTING IN GENERAL	33
10.5	PROCEDURE OF PAINTING	34
11. PLUMBING		37
11.1	GENERAL	37
11.2	DRAWINGS AND INFORMATION REQUIRED.....	37
11.3	RECORD DRAWING.....	38
11.4	OPERATING AND MAINTENANCE INSTRUCTIONS.....	38
11.5	TESTS	38
11.6	WORK IN COMMON PIPING	39
11.7	WATER SUPPLY WORK	41
11.8	SPACING OF SUPPORTS	41
11.9	DRAINAGE WORK	42
11.10	LAYING OF PIPES.....	42
11.12	SEWERS.....	42
11.13	U.P.V.C PIPES.....	43
11.14	BENDS AND OTHER SPECIALS	43
11.15	SUPPORT FOR U.P.V.C PIPES.....	43
11.16	SEWER PIPES.....	44
11.17	AIR VALVES.....	44
11.18	SCOUR WASHOUT VALVE	44
11.19	FOOT VALVES AND STRAINERS.....	44
11.20	PRESSURE REDUCERS.....	44

11.21	EQUILIBRIUM BALL VALVES	44
11.22	FITTINGS	44
11.23	FIXTURES AND ACCESSORIES	45
11.24	AS BUILT DRAWINGS.....	45
11.25	MISCELLANEOUS.....	45
12.	ELECTRICAL INSTALLATIONS.....	46
12.1	GENERAL	46
12.1.7	SCOPE OF WORK	46
12.1.7.2	STANDARDS AND CODES	46
12.1.7.3	DRAWINGS AND SPECIFICATIONS	46
12.1.7.4	SCHEDULE AND EXECUTION PLAN	47
12.1.7.5	OBVIOUS WORK	47
12.1.8	PREQUALIFICATION.....	47
12.1.9	QUALIFICATION	47
12.1.10	RULES AND REGULATIONS.....	47
12.1.11	STANDARDS	47
12.1.12	TEST REPORTS	48
12.2	CONDUIT AND CONDUIT ACCESSORIES	48
12.3	WIRES, CABLES AND CORDS	48
12.4	WIRING ACCESSORIES	49
12.6	TESTING	50
12.7	INSTALLATION INSTRUCTION	51
12.8	DISTRIBUTION BOARD.....	51

1. PRELIMINARIES

1.1 Standard and Codes

The Contractor shall, perform the Works in compliance with all regulations, standard specifications or statutes of the Government of Maldives unless otherwise conform to this specification.

The current British Standard Specifications and Codes of Practice shall apply to and form part of these specifications unless otherwise specified in respect of all materials and works to which they have application.

1.2 Drawings and Specifications

Drawings and Specifications are intended to complement each other, so that if anything is shown on the Drawings, but not mentioned in the specifications or vice versa, it is to be furnished and built as though specifically set forth in all three. If any discrepancies, errors, ambiguities or omissions occur in the Drawings or Specifications, the same shall be referred to the Consultant before proceeding with the Works, and the Consultant decision on such discrepancies, errors, ambiguities or omissions shall be final.

In addition to the Drawings and Specifications attached hereto, the Consultant will during the progress of the Works furnish additional Drawings, Specifications, and instructions as may be necessary, in the opinion of the Consultant for the purpose of the proper and adequate execution and maintenance of the Works, and the Contractor shall make his work conform. Such drawings and instructions shall be deemed to be part of the Contract Documents.

1.3 Transportation to the Site

The Contractor shall provide all necessary transport, handling and storage of all materials, components and the like to their points of installation on site including transport to and from storage. The Contractor shall provide all necessary transport of labor to and from the site.

1.4 Schedule and Execution Plan

The Contractor shall prepare and submit to the Consultant for approval the construction schedule and an execution plan of temporary facilities, stockyards, etc., before the start of the Works.

1.5 Repairing and Correction

Any breakage(s) or defect(s) of existing buildings, road utilities, or part(s) of them caused by the Works including transportation for the works shall be repaired or corrected by the Contractor with his responsibility.

1.6 Workmanship and Materials

All workmanship shall be of the best standard. All goods and materials to be incorporated in the Works must be new, unused, of the most recent or current models and incorporate all recent improvements in design and materials unless provided otherwise in the contract.

The Contractor shall submit for the approval of the Consultant a list of names and addresses of the manufacturers and trade marks or names of all the various types of materials and goods he propose to use in the Works. The list shall include reference to the specifications clause or article to which the materials and goods apply.

Materials shall be obtained from approved sources and used in accordance with the manufacturer's printed instructions. In the absence of a specification all materials shall comply

with a relevant standard. The consultant shall order the removal of any materials, which he has not approved.

No orders for materials and goods shall be placed until approval has been obtained for the materials and goods from the consultant.

The Contractor shall note that it is his responsibility to include in his price for the cost of the materials and products as specified and no adjustment will be allowed shall the consultant reject the alternatives.

1.7 Obvious Work

Where an item of work is obviously required for the type of work being undertaken then it shall be deemed to have been included even though the item is not specifically mentioned or shown in the Drawings or Specifications.

1.8 Protection

The Contractor shall have the Works and adjoining properties protected from inclement weather. Any loss or damage caused by weather, carelessness or lack of skill of workers, accident or otherwise shall be of such property that is affected. The Contractor shall provide all necessary dustsheets, barriers and guardrails and clear away at completion.

The work shall be suspended for such time as may be directed and/or approve by the Consultant if the specified quality of work is difficult to maintain during inclement weather.

1.9 Scaffolding

The Contractor shall provide, erect, maintain, dismantle and clear away at completion proper and adequate including that required for subcontractor and suppliers. Putlog holes shall be made good to match the adjacent surface as the scaffolding is dismantled.

The Contractor shall be responsible for all safety precautions in connection with the scaffolding including the provision of all bracing, scaffold boards, toe boards and the like and for entire sufficiency for the work.

1.10 Construction Machinery, Plants and Equipment's

All necessary construction machines shall be provided and maintained by the Contractor and shall be approved by the Consultant.

If cranes or any other type of plant which places any load on the structure are proposed, all details of such plant shall be submitted to the Consultant for approval before the work is actually commenced. If approved by the Consultant and contractually acceptable, permission may be given for the structure to be strengthened, in order to carry out loads, and the Contractor shall be responsible for any resulting additional costs.

The Contractor shall be responsible for making good to the satisfaction of the Consultant any damage to the permanent structure that may be caused by his plant and equipment.

1.11 Samples

The Contractor shall furnish for the approval with reasonable promptness, all samples as directed by the consultant. The Consultant shall check and approve such materials with reasonable promptness only for conformance with the design concept of the Works and for compliance with the information given in the Contract Document. The Work shall be in accordance with the approved samples

All samples shall be delivered to the Consultant's office with all charges in connection therewith paid by the Contractor and deemed to be included in the Contract Price.

Duplicate final approved samples, in addition to any required for the Contractor's use, shall be furnished to the Consultant, one for office use and one for the site.

Samples shall be furnished so as not to delay fabrication, allowing the consultant reasonable time for consideration of the sample submitted.

Each sample shall be properly labeled with the name and quality of the material, manufacturer's name, name of project, the contractor's name and date of submission, and the specification clause to which the sample refers.

1.12 Ordering Materials

The Bills of Quantities shall not be used as a basis for ordering materials and the Contractor is entirely responsible for assessing the quantities of materials to be ordered.

Upon receipt of the Consultant's order to commence the Works, the Contractor shall immediately place orders for all required materials and will be held responsible for any delays occurring due to late placing of such orders.

The Contractor shall pay all expenses, taxes and dues etc. incurred on the procurement of materials from abroad

1.13 Contractor's Site Area

Throughout the period of the Contract the Contractor shall maintain the area of his operation within the limits of the Site in a clean, tidy and safe condition by arranging materials and the like in an orderly manner. All rubbish, debris, waste materials and the like shall be systematically cleared from the Site as it accumulates.

The Contractor shall take all steps necessary as directed by the Consultant to minimize or eliminate dust, noise or any other nuisance, which may occur. Plant emitting dust, smoke, excessive noise or other nuisance shall not be permitted.

1.14 Progress Meetings

During the course of the Works, progress meetings shall be held at fortnightly intervals for the purpose of coordinating the Contractor's works and to ensure that full compliance is maintained.

Minutes of such meetings shall be recorded; copies will be distributed to all persons concerned and full effect shall be given to all instructions contained therein.

1.15 Loading in Excess of Design Load

No loading in excess of the design loading shall be placed on any portion of the structure without the written permission of the Consultant

1.16 Handing Over

Prior to handing over the proposed development the Contractor shall gain the approvals and respective Completion Certificates from all the local government authorities and the like that the work has been completed in accordance with their requirements.

Any payment in connection therewith shall be paid by the Contractor.

2. CONCRETE WORKS

2.1 General

Materials used in the Works shall be new, of the qualities and kinds specified herein and equal to approve samples. Delivery shall be made sufficiently in advance to enable further samples to be taken and tested if required. No materials shall be used until approved and materials not approved shall be immediately removed from the Works.

Materials shall be transported, handled and stored on the site or elsewhere in such a manner to prevent damage, deterioration or contamination.

2.2 Cement

Cement shall be Ordinary Portland cement of an approved brand.

Cement shall conform to BS 12.

Cement shall be of recent manufacturer and used within 6 months of manufactured date.

The Contractor shall with each fresh consignment of cement delivered to the site furnish the Consultant with a copy of the Manufacturer's statement of compliance with the above Standard Specifications together with the date of manufacture, certified by an independent agency in the country of origin and its date of delivery to Site.

Check tests will be required by the Consultant. These tests shall be carried out at the Contractor's expense.

Any cement failing to meet the required standards will be rejected and replaced at the Contractor's expense.

Any cement not conforming to BS 12 shall not be used unless otherwise approved by the Consultant.

2.3 Aggregate

Fine aggregate shall be river sand conforming to BS 882.

Coarse aggregate shall be crushed stone excluding limestone or derivatives of limestone conforming to BS 812.

Aggregate shall not contain injurious amount of rubbish, dirt, organic impurities and other foreign matters.

Strength of aggregate shall be more than that of hardened concrete paste.

Shape of coarse aggregate shall not be flat or slender.

Aggregate to be used in concrete shall possess the qualities indicated in the following tables.

Manufactured sand and blast furnace slag to be use in concrete shall not be used unless otherwise specified or approved by the Consultant

In case of using fine aggregate of 0.01% or more water soluble chloride content, the necessary measures for corrosion inhibiting of reinforcement shall be instructed by the Consultant

The maximum size of coarse aggregate shall be 25 mm

Sources of aggregate shall be to the approval of the Consultant and samples of aggregate from the proposed source shall be submitted to the Consultant at least 28 days before its intended use.

Quality of Aggregates

Aggregate type	Open dry specific gravity	Percentage of water absorption (%)	Percentage of solid volume for the evaluation of particle shape (%)	Clay lump (%)	Loss in washing test (%)	Organic impurity (%)	Water soluble chloride (%)
Coarse aggregate	≤ 2.5	≤ 3.0	≥ 55	≤ 0.25	≤ 1.0	0	≤ 0.25
Fine aggregate	≥ 2.5	≤ 3.5	–	≤ 1.0	≤ 3.0	0	≤ 0.01

* Color of test solution not to be darker than standard solution

Grading requirements for aggregates

Percentage passing each sieve by weight (%)

Agg.	Max. size (mm)	Nominal sieve size (mm)											
		40	30	25	20	15	10	5	2.5	1.2	0.6	0.3	0.15
Coarse	25	100	100	90 ↓ 100	60 ↓ 90		20 ↓ 50	0 ↓ 10	0 ↓ 5				
	20			100 ↓ 100	90 ↓ 100		20 ↓ 55	0 ↓ 10	0 ↓ 50				
Fine							100 ↓ 100	90 ↓ 100	80 ↓ 100	50 ↓ 90	25 ↓ 65	10 ↓ 35	2 ↓ 10

2.4 Water

Water shall not contain injurious amount of impurities that may adversely affect concrete and reinforcement.

Ground water shall not be used for concrete works.

Water shall be obtained from a public supply where possible, and shall be taken from any other sources only if approved by the Consultant.

Only water of approved quality shall be used for washing out formwork, curing concrete and similar surfaces.

2.5 Handling and Storage of Material

2.5.1 Cement

Cement shall be stored in a manner to prevent weathering.

Bagged cement shall be piled no more than 10 bags so as to permit easy inspection

Cement caked even to the slightest extent shall not be used. Such cement and rejected cement shall be immediately separated from other bags of cement so that they shall not be mistaken for others.

2.5.3 Aggregate

Aggregate shall be stored in a manner effectively separating coarse and fine aggregate according to type and shall be prevented from inclusion of dirt, rubbish and other undesirable foreign matters.

Coarse aggregate shall be unloaded and piled in a manner not to cause segregation of small and large particles. Aggregate to be stored in piles shall be in mounds of moderate height and at a location where good drainage is provided.

2.6 Mix Proportion and Strength

Mix ratio for reinforced concrete shall be in the proportion 1:2:3 (cement: fine aggregate: coarse aggregate) by dry volume.

Mix ratio for lean concrete shall be in the proportion 1:2:6 (cement: fine aggregate: coarse aggregate) by dry volume.

Water-cement ratio for concrete shall be 0.4% to 0.45%

The specified design strength of reinforced concrete shall be 25 N/mm². The required slump of concrete shall be 100 mm.

Design mix proportion shall be to obtain required workability, consistency and durability.

2.7 Production of Concrete

2.7.1 Field-mixed Concrete Plant

The Contractor shall select the necessary facilities for storage, batching, mixing and transporting of each of the materials and submit them for approval of the Consultant prior to start work.

2.7.2 Measuring

All materials shall be measure by volume for each batch and water may be measured volumetrically.

Cement shall be measured by number of bags unless automatic cement weight measure is in use.

2.7.3 Mixing Control

Concrete mixture shall be constantly controlled to obtain required workability and mixed strength. Mixing time for each batch shall be not more than 3 minutes.

2.7.4 Quality Control

The Contractor shall conduct tests for quality control toward insuring that concrete of the required quality is constantly produced.

The Contractor shall have all quality control tests report ready for submission as required by the Consultant.

2.7.5 Quality Inspection of Concrete at the Point of Placement

The Contractor shall conduct tests on concrete at the point of placement. When test results meet the tolerances given below, the concrete shall be qualified to have passed the tests.

(a) The tolerance between actual slump and required slump of the concrete shall be ± 2.0 mm

For the estimation of compressive strength of concrete in compressive strength tests, when the average value of compressive strength of concrete obtained in a test is not less than the specified design strength, it shall be qualified to have passed the test. In case of failure to the above requirements, the Contractor shall take necessary measures such as to perform appropriate test as instructed by the Consultant.

2.7.6 Tolerance

The dimensional tolerances in location and cross section of concrete member used for designing and construction of formwork shall conform to the following table.

2.8 Transporting and Placing

2.8.1 General

The Contractor shall establish manner and schedule for transporting and placing of concrete and obtain approval of the Consultant.

Concrete shall be transported in a manner to minimize segregation, spill, age and other changes in quality thereof.

Concrete shall be placed and consolidated in a manner to insure uniformity and optimum density.

In case of rain or other conditions that may affect the quality of concrete during concreting, the Contractor shall take necessary measures as instructed by the Consultant.

2.8.2 Time Limit

The time limit from start of mixing to completion of placing of a batch as rule, shall be 30 minutes.

2.8.3 Preparation prior to Placing.

The place where concrete is to be deposited shall be cleaned and sheathing shall be sprinkled with water. Subsequently, water accumulated in the form shall be removed.

2.8.4 **Construction Joint**

Joint surfaces shall be cleaned, made free of laitance and other foreign matters, and wetted prior to concreting. Joint surface shall be roughened if directed by the Consultant.

The locations of shapes of construction joints shall be consulted and approved by the Consultant.

2.8.5 **Concrete Placing**

Concrete placing shall be proceeded to keep the surface of placed concrete as horizontal as possible.

Concrete shall be continuously poured to compact around reinforcing bars and corners of formwork.

The maximum time interval between placement of continuous concreting shall not exceed 0.5 hours. However, when special measures are taken this time limit may be changed according to instruction or approval of the Consultant.

2.8.6 **Consolidation**

Vibrating of concrete and tapping of formwork shall be performed to wall, column and other places difficult for concrete to proceed. Proper number of workers for placing and compacting concrete shall be arranged.

Vibrator shall be operated for concrete called for water tightness, difficult portion for concrete to proceed and other cases directed by the Consultant. However, vibrator shall not be touched reinforcing bars and shall not be operated more than 30 seconds at same spot.

Concrete shall be placed 300 - 600 mm thickness at once in case vibrator is performing. In case flexible-insert-vibrator is called for, concrete shall not be placed thicker than the length of the insert or vibrator at one pouring.

2.8.7 **Placing Speed**

Concrete shall be placed at the speed suited for the workability of the concrete and condition of the place of placement, which insures proper consolidation of concrete.

2.9 **Concrete Curing**

2.9.1 **Curing Method**

After concrete has been placed, the concrete surface shall be kept moist by sprayed with water or by other appropriate methods, and shall be protected from direct sunlight and rapid drying. The top surface of slabs shall be kept flooded with water at all times after concreting for the duration of curing period. This curing period shall be for not less than 14 days.

As a rule, no foot traffic or loads shall be permitted on concrete for at least 24 hours after placement.

2.10 **Test**

2.10.1 **General**

The contractor shall be required to conduct all tests according to BS method and procedure.

Test, as a rule, shall be conducted at the locations directed or at the testing institutions approved by the Consultant.

The Consultant shall conduct test, as a rule.

In case of failure in test, measure shall be taken as instructed by the Consultant.

The Contractor shall keep test records during the work and for 2 years after completion of the contracted work.

2.10.2 **Material**

Cement Test

- (1) Setting test.
- (2) Soundness test.
- (3) Compressive strength test.

Note: Item (1) shall be conducted once in every manufacturer.

Item (2) & (3) shall be conducted once in every 2,000 bags.

Aggregate test:

- (1) Grading and fineness modules.

2.11 **Concrete**

2.11.1 **Fresh concrete**

Slump, air content, shall be conducted daily, and more often at request of the Consultant. Compressive strength test of concrete. Test for estimation on strength of concrete in structure:

In order to assume estimated strength of concrete in structure, compressive strength test shall be conducted for prepared test pieces on the 7th day and 28th day and those test pieces shall be made for sampling at placing of concreting.

Strength test shall be conducted for each of the following conditions: each days pour, each class of concrete, each change of supplies or source and each 100 cubic meter of concrete or fraction thereof. The number of test pieces to be used in a test shall be not less than 3 for each test of the 7th day and the 28th day unless otherwise instructed by the Consultant.

Test pieces shall be made in accordance with British Standards, and sampling shall be taken as near as possible at the point of placement.

Test pieces shall be stored without being disturbed and shall be covered during the first 24 hours, and carefully transported specimens to the testing laboratory. Test pieces shall be cured in water after de-moulding. The temperature of test pieces shall be kept as close as possible to the temperature of the concrete in structure until the time of testing.

2.12 **Defective Concrete and Finishes**

Honeycombed surfaces shall be made good or on the instruction of the Consultant be cut out by the Contractor and make good at his own expense.

Concealed concrete faces shall left as from the formwork except honeycombed surfaces shall be made good. Faces of concrete to be rendered shall be roughened by approved means to form a key. Faces of concrete that are to have finished other than those specified shall be prepared in an approved manner as instructed by the Consultant.

3. CONCRETE FORMWORK

3.1 Structure and Material

3.1.1 Structure

Formwork shall be performed to obtain accurate concrete in accordance with the designated drawings.

Formwork shall be firmed and secured to bear the force of concreting and tightened to avoid cement paste seeping.

3.1.2 Materials

Sheathing for formwork shall be waterproof plywood of not less than 12 mm thick. Joint of sheathing shall be butt joint and firmly assembled. In case of using wood board for sheathing, boards shall be 15 mm thick and applied planer. Joint shall be tongued and grooved unless otherwise approved by the Consultant.

Form liners shall be sound and suitable materials to accurately and safely cast the insitu concrete structure as shown on the Drawings.

Timber form boards for sheathing where used for fair-faced concrete shall be of such new materials as not to cause any defects to the surface of the concrete. Special care shall be taken in fabrication, storage and protection of these boards.

3.1.3 Other Material

Fastening hardware to be used shall be those with allowable tensile strength guaranteed by manufacturer through strength tests.

Form oil shall not have injurious effects on quality of concrete nor to bonding of surface finishing materials and shall be subject to approval of the Consultant.

3.2 Performance

3.2.1 Design of formwork

Formwork shall be designed to withstand construction loads during concreting, lateral pressure of fresh concrete, shock and vibrators due to concrete placing.

Formwork shall be free of injurious leakage of water, easy to remove, and shall not damage concrete at removal.

Supports shall be provided with the adequate horizontal and diagonal bracing and/or stays to prevent collapsing, heaving and twisting of formwork due to horizontal loads working during concrete placing.

Standard Values of Dimensional tolerances

Item	Tolerance (mm)
Tolerance in distance from datum line of each floor to respective members	+ 10
Tolerance in cross section of columns, beams and walls	- 5 , + 10
Tolerance in thickness of floor and roof slabs	0, +10

3.2.3 Fabrication and Erection

Erection of formwork, and transportation and storage of materials thereof shall be started only after previously placed concrete has reached an age which acceptance of these loads will not have any adverse effect on the concrete.

Sheathing shall be fabricated and installed accurately to match the locations, shapes and dimensions of members called for in the Drawings.

Sheathing shall be installed tightly so as not to permit cement paste or mortar to escape from joints.

Pipes, boxes and other embedded hardware shall be properly secured to sheathing or others so that they will not move during concrete placing.

Supports shall be erected plumb. Supports at any two vertically consecutive floors shall be erected as near as possible to identical locations on a common plane.

Shoring shall be erected paying special attention to safety.

If sheathing is reused, the surface in contact with the concrete shall be thoroughly cleaned off and sufficiently repaired before reuse. In case of using for fair-faced concrete, the same sheathings shall be used twice after approval of the Consultant.

3.2.4 Inspection

Formwork shall be inspected by the Consultant prior to placing of concrete.

3.2.5 Striking of forms

The minimum period for keeping the forms in position and for watering after laying the concrete shall be as stated below, except otherwise specified in drawings. Forms shall be removed in such a manner as to ensure the complete safety of the structure, so that there is no shock or vibration as would damage the reinforced concrete.

The responsibility for the safety of the concrete shall rest entirely with the Contractor and the Contractor shall be held liable for any damage done and shall have to make good the same at his own expenses.

The Contractor shall inform the Consultant when he intends to remove shuttering and shall obtain his consent, but the consent of the Consultant shall not relieve the Contractor of his responsibility.

The minimum time for formwork to remain in place shall be as per the following table.

Vertical sides of beams, slabs and columns	24 hours
Soffits of slab	10 days
Soffits of beams	21 days
Cantilevers	28 days

3.2.6 Relocation of Support

Supports under concrete shall be not relocated

3.2.7 Removal of formwork

Formwork shall be removed gently, after its removal has been approved by the Consultant.

Inspection by the Consultant shall be obtained immediately after the removal of sheathing and defects shall be immediately remedied according to instruction of the Consultant.

After shoring have been removed, members shall be carefully observed for cracking and deflection, when found, they shall be reported immediately to the Consultant.

4. STEEL REINFORCEMENT

4.1 Material

Reinforcing steel shall be of the dimensions given in the Drawings.

Reinforcing bars shall comply with the requirement of B.S.4449 and welded wire fabric, square bar fabric and expanded metal shall comply with appropriate part of B.S.4483.

Dia 6mm reinforcing steel shall be round mild steel bars, and 12mm, 16mm, 20mm and 25mm shall be deformed high strength bars.

Any other non-specified reinforcing steel shall be used only with the approval of the Consultant.

All reinforcing steel and binding wire shall be stored under cover and shall be at least 250mm above the ground.

4.2 Cleaning

Reinforcing bars shall be cleaned before use so that it is free from rust, oil, dirt or other coatings that reduce bond.

4.3 Bending and Laps

The reinforcement shall be bent cold in an approved bar bending machine.

Preferably bars of full length shall be used. Lapping of bars where necessary shall conform to BS1487 'Bending Dimensions of Bars of Concrete reinforcement.'

4.4 Reinforcement Cover

Concrete cover for reinforcement shall be as follows:

FOR ANY STEEL IN UNDER GROUND CONCRETE	50	MM
CLEAR COVER IN SLABS	25-30	MM
CLEAR COVER IN BEAMS SOFFIT	30-35	MM
CLEAR COVER IN SIDES OF BEAMS	30	MM
CLEAR COVER IN COLUMNS	40	MM

4.5 Placing

Reinforcement intended for contact when passing each other shall be securely tied together with binding wire

Binders and stirrups shall tightly embrace the longitudinal reinforcement to which they shall be security bound or spot welded

Binding wire shall be turned in from the formwork and shall not project beyond reinforcing bars.

All reinforcement shall be inspected by the Consultant and approved before concrete is placed in the forms.

5. MASONRY

5.1 Materials

Material used for masonry and plastering work shall conform to Section 3 - CONCRETE WORKS.

Masonry work shall be done with bricks or blocks of approved quality unless specified otherwise.

The blocks shall be free from excessive amounts of salt or other impurities and shall be inspected and approved by the Consultant.

5.2 General

5.2.1 Execution Drawing

Work shall be complied with this specification unless otherwise stated on particular Specification or Drawings. Any work not specified shall be discussed and directed by the Consultant.

5.2.2 Stake-Board

Stake-board shall be provided at each 5m in length and shall be inspected by the Consultant for the accuracy, firmness and security. However, suitable ruler, plumb bob and leveler shall be provided for minor performance of cement block.

Transportation and storing;

Care shall be taken for damage during transportation of materials and any defect of natural finished concrete blocks shall be rejected.

5.2.3 Curing

Any shock or load shall not be applied until concrete mortar or other fills hardened. Corner, projection and top of cement block work shall be protected from rain, dryness, cold, damage and stain by covering.

Void between blocks shall not be intruded by rainwater.

5.3 Block work

5.3.1 Material

Blocks shall be of standard quality low permeability blocks with no defects and sample shall be submitted for approval of the Consultant

Blocks shall be cement solid blocks of 100mm, 150mm and 200mm thickness. The average compression strength shall be not less than 2.8N/mm² and shall comply with the relevant British Standard.

5.3.2 Placing Blocks

Cement blocks shall be saturated with water and joint shall be cleaned.

Bonding mortar shall be used immediately after mix, and mixed mortar left for more than one hour shall be rejected.

Vertical and horizontal joint of blocks shall be filled completely and suitable with mortar on line shall not be moved or rearranged. Joint and surface of block of exposed finished block wall shall be cleaned immediately after joint is filled.

Mortar for joint shall be touched with steel trowel before hardened and exposed joint shall be finished with uniform width and planned without roughness or cavity.

Height for placing block per day shall be maximum 1.2 m unless otherwise specified.

5.3.3 Joints

The thickness of joints shall not exceed 10 mm and the joints shall be rated (13 mm dup.) when the mortar is still floor, so as to provide for proper bond for the plaster. Any mortar which falls on the floor from these joints or removed due to raking of joints shall not be reused.

5.3.4 Lintel

Lintel shall be reinforced concrete as approved or directed by the Consultant.

Main reinforcing bar shall be anchored more than 40D (40 x diameter of the bar) at both end.

In case lintel is prefabricated, shop drawing shall be submitted for approval of the Consultant.

5.3.5 Frame of Opening

In case frame is temporarily installed before placing of blocks, frame shall be firmly placed and joiner shall be bonded with mortar as placing each block at side and top of frame.

In case frame is installed after placing of blocks, joiner shall be bonded with additional mortar at space or every two blocks or more.

Back of frame shall be filled and compacted with mortar by providing shuttering board.

Wood plug and anchor bolt shall be covered with mortar or concrete.

5.3.6 Piping

Principally, piping shall not be placed in block wall unless piping block is in use.

In case chipping and piping on face of blocks is unavoidable, performance shall confirm to instruction of the Consultant.

Joiner and supporter for exposed piping shall be buried at joint which back is filled or otherwise approved by the Consultant.

6. PLASTERING

6.1 General

All masonry walls shall have smooth finished cement plaster on both sides with a surface setting coat of neat cement applied within an hour of the completion of rendering.

Cement rendering to floor shall be same as above.

6.2 Materials and Storage

Plaster materials which are affected by moisture such as plaster and cement shall be stored properly.

Materials used for plastering shall conform to those of Section 3 - Concrete Works. Grading of sand, however, shall be as in table below

Grading of sand	Mortar plastering	Plastering
5mm sifting thorough 100%	for first coat	for first coat and dubbing out
0.15mm sifting less than 10%	for finish coat	
2.5mm sifting through 100%	for finish coat	for second coat
0.15mm sifting less than 10%		

White cement or filler or similar shall conform to the requirements of Portland cement, BS.12.

The use of mixtures shall be approved by the Consultant's representative. The amount of admixture shall be such that it affects mortar strength very little.

6.3 Mixing ratio

Mixing volume ratio of mortar shall be as in table below:

Base	Area of application	First coat cement: sand	Dabbing out cement: sand	Finish coat cement: sand
Masonry blocks	Floor	-	-	1:4
	Interior wall	1:4	1:4	1:4
	Exterior wall	1:4	1:4	1:4

6.4 Thickness of Coating

Standard thickness of coating (mm)

Base	Area of application	First coat	Dubbing out	Second coat	Finish coat	Total
Masonry block	Floor	-	-	-	as per dwg	as per dwg
	Interior wall	8	-	8	4	15
	Exterior wall	13	-	12	4	25

Thickness of coating shall be standard thickness of coating unless otherwise indicated on the Drawings.

6.5 Finish

Type of finish and work schedule

Type	Work Schedule	Notes
1. Smooth Trowel finish	1. Shall be applied flat by metal trowel 2. Shall be finished by pressing with the trowel.	Before applying second coat, corner and edge shall be screed well.
2. Wooden float finish	Shall be applied by wooden float	

6.6 General Preparation

Remove efflorescence, laitance, dirt and other loose material by thoroughly dry brushing.

Remove all traces of paint, grease, dirt and other materials incompatible with coating by scrubbing with water containing detergent and washing off with plenty applying coatings unless specified other wise.

In Situ Concrete Surfaces: Scrub with water containing detergents to ensure complete removal of mould oil, surface retardants and other materials in compatible with coating. Rinse with clean water and allow drying unless specified otherwise.

Organic Growths: Treat with fungicide to manufacturer’s recommendations and bush off.

Hacking For Key: roughen specified surfaces thoroughly and evenly by removing the entire surface to a depth of 3mm by scrubbing, bush hammering or abrasive blasting. Clean surfaces by washing and brushing.

Smooth Concrete Surfaces: where no keying or mix or bonding agent is specified, wet smooth concrete surfaces immediately before plastering.

6.7 External Plastering

Dissimilar Solid Backgrounds for Plastering: where plaster is to be continued with out break across joints between dissimilar solid backgrounds which are rigidly bonded together, cover the joints with a 200mm wide mesh strip (back grounds in the same plane) or with the corner mesh (internal angle) fixed at not more than 600mm centers along both edges, unless specified or otherwise.

Dissimilar Solid Backgrounds for Plaster: where plaster is to be continued without break and without change of plane across the face of a 300mm and rigidly bonded to the background.

Cover the face of the column /beam/ lintel with building paper extending 25 mm on the adjacent background.

Over lay with expanded metal lathing extending 50mm beyond the edges of the paper and securely fixed with masonry nails at not less than 100mm centers along both edges.

Alternatively, an approved paper and mesh lathing may be used.

Dissimilar Solid Backgrounds for Rendering: where rendering is to be continued without break across joints between dissimilar solid backgrounds which are in the same plan and rigidly bounded together, cover joints with a 150mm wide strip of building paper overlaid with 300mm wide metal lathing fixed at not more than 600mm centers along both edges unless specified otherwise.

Service Chases: cover with steel mesh strip fixed at not more than 600mm centers along both edges.

Conduits bedded in under coat to be covered with 90mm wide jute scrim budded in finishing coat mix, pressed flat and toweled in. Do not lap ends of scrim.

6.8 Internal Plastering

Accuracy of plaster 15mm thick or more: maximum permissible gap between a 1800mm straight edge and any point on the surface to be 3mm.

Dubbing Out: if necessary to correct inaccuracies, dub out in thickness of not more than 10mm in same mix as first coat. Allow each coat to set before the first is applied. Cross scratch surface of each dubbing out coat immediately after set.

Metal Mesh Lathing: Work undercoat well in to interstices to obtain maximum key.

Under Coats: generally to be not less than 8mm with thickness greater than 16mm applied as two equal coats. Rule to an even surface and cross scratch - end coat to provide a key for the next hand applied coat.

Cement Based Under Coats: all to dry out thoroughly but not rapidly, to ensure that drying shrinkage is substantially complete before applying next coat.

Dissimilar Backgrounds: where scrim or lathing or beads are not specified, cut through plaster with a fine blade in a neat, straight line at junctions of:

Plastered rigid sheet and plastered solid backgrounds.

Dissimilar solid backgrounds.

Smooth Finish: trowel or float to product a tight matt, smooth surface with no hollows abrupt change of level or trowel marks. Do not use water brush and avoid excessive toweling and over polishing.

6.9 External Rendering

Dubbing Out: if necessary to correct inaccuracies, dub out in thicknesses of not more than 10mm in same mix as first coat. Allow each coat to dry before the next is applied. Cross scratch surface of each dubbing out coat immediately after set.

Under Coats for hand applied finishes:

Apply first undercoat or dubbing out coat by throwing from a trowel.

Coats to be no less than 8mm thick, with thickness greater than 16mm applied as two equal coats. On weak backgrounds first under coat to be not less than 10mm thick.

Brush down each under coat to remove dust and loose particles and wet thoroughly before application of next coat.

Cross scratch under coat without penetrating the coat, to provide key for following coat(s).

Drying: Keep each coat damp for the first three days by covering with polythene sheet and/or spraying with water. Thereafter prevent from drying out too rapidly. Work in shade when ever possible.

Allow each coat to dry out thoroughly to ensure that drying shrinkage is substantially complete before applying next coat.

Playing Floated Finish: Finish with wood or other suitably faced float to give an even texture.

Do not draw excessive laitance to surfaces.

6.10 Metal Mesh Lathing / Reinforcement For Plastered/Coatings.

Lathing to be provided as reinforcement for plastering in columns, walls or specified in drawings products.

6.10.2 Products:

Plain Expanded Metal Lathing: To B.S 1369 with a minimum weight of 1.9 kg/mm².
Manufacturer to approval of the Consultant.

Wire Ties: Unless other specified, annealed iron , galvanized to B.S 443.

Clout Nails: galvanized steel or stainless steel nails to B.S 1202: Part 1, table 3.

Staples: Galvanized steel wire staples to B.S 1494: Part 2.

6.10.3 **Workmanship**

Framing: fix securely and accurately to help ensure that coatings on lathing , when finished, are true to line and level , within specified tolerances and free from cracks, rippling, hollows, ridges and sudden changes of levels.

Runners/Bearers spanning between concrete beams/ribs: fix with 3mm wire ties twisted around 38 mm X 10 gauge screws driven well into fixing blocks or plugs in sides of beams/ribs.

Wire Ties: twisted ends tightly together, cut off surplus and bend ends of wire away from face of coating.

Plain Expanded Metal Lathing:

(a) Stretch lathing and fix securely in accordance with manufacturers recommendations to give a taut, firm base for plaster/ rendering.

(b) Fix with the long way of the mesh at right angles to supports and with all strands sloping in the same direction.

(b) Lap side edges not less than 25mm. Lap ends 50mm at supports and 75mm between supports. Laps must not occur within 100mm of angles or bends.

7. CARPENTRY, JOINERY AND FURNITURE

7.1 Materials

Timber and plaster board internal wall partitions and concealed/suspended ceilings shall be in accordance with the requirements of BS 1186 'Quantity of Timber and Plaster boards Workmanship in Joinery', Part 1, 'Quality of Timber'.

Timber and plaster board products shall be subject to the inspection and approval of the Consultant.

Timber shall be seasoned to stable moisture content compatible with the finished use, straight and true and free from wind, warp and distortion and in lengths suitable for the members required.

All timber shall be in long lengths and laps, scars or splices shall be over a bearing surface. Where obtainable, finishing timber exposed to view shall be in single lengths.

7.2 Preservation of Timber

All timber shall be treated for insect attack and is to be of the correct moisture content and free from surface moisture content and dirt.

All timber ceiling and low wall partition frames etc. shall be treated for insect attack with approved timber preservative. No extra payment shall be made for such coating and will be considered inclusive in the rate of the respective item in the BOQ.

Treatment shall be carried out after all cutting and shaping is completed.

7.3.3 Hardware

Hardware shall be standard quality and samples shall be submitted to the Consultant for approval.

All hinges shall be stainless steel or brass and shall be approved by the Consultant.

The dimensions and quality of hardware shall meet the requirements and shall not be rested, deformed or defective.

7.4 Dimensions and Finish

All dimensions of timber and plaster boards given are finished dimensions.

All elements and others of structural nature, which are exposed, must be machine planed to a smooth finish.

All unexposed shall be machine planed to a rough finish.

All joinery work shall be dressed on all four sides and hand dressed where necessary and sanded to all exposed surfaces. All arises in any way accessible shall be sanded and smoothed off.

All furniture shall be in good quality and durability.

7.5 Workmanship

All connections whether nailed, screwed, glued, mortised or dove-tailed shall be accurately made and properly executed to provide sound, satisfactory connections for the class of work required.

Timbers and plaster boards containing defects or distortions shall not be used.

All joinery shall be manufactured by skilled tradesman with accurate tolerances and set out and with tools, jigs, machines and equipment appropriate for the work.

Assembly of the joinery units and joinery frames, etc. shall be by means of glued connections appropriate to the work - mortise and tenon, housing and doweling, etc. where practicable including the use of glued blocks wherever required. Nailing, screwing shall only be used with prior approval of the Consultant; corrugated fasteners shall not be used for effecting connection.

All office furniture units shall be in good quality and conditions. All defect furniture will not be acceptable.

8. DOORS AND WINDOWS

8.1 Doors and Windows

All windows and doors are to be constructed by approved specialist suppliers of medium section to the particular requirements noted on the drawings as to weight and profile. All sections shall generally conform to relevant British Standard Specifications.

All frames shall be made to fit the actual openings with a 3 mm clearance all around. Discrepancies in overall width or height exceeding 3mm will not be allowed and the frames will be rejected in such cases. Any small discrepancies shall have the gaps suitably backed and filled with gun-applied water repellent mastic sealant

All sealants used in the assembly of, and in the fixing of cladding and window framing, shall be non-setting to allow thermal movement without detriment to those joint sealants used for peripheral caulking and shall be one part silicone sealant and shall conform to BS 4245. All spliced joints between mullions shall be sealed with an approved silicone product, compatible with other sealants and packing used.

The auxiliary components in sashes as locks, pivots, sliding gear etc. shall comprise of stainless steel or resisting materials.

The tolerance is to be as follows:

- | | |
|-----------------------------------|-------------|
| a) Inside width of frame | 3mm Maximum |
| b) Inside height of frame | 3mm Maximum |
| c) Depth of frame | 2mm Maximum |
| d) Opposite side, Inside distance | 2mm Maximum |

The performance - associated requirements are

- 1) Strength (resistance to wind pressure and other forces applied in use)
- 2) Air tightness or ability to cut out drafts.
- 3) Water - tightness against rain or dew.
- 4) Sound arresting effect to (shut off noise from outside as well as inside).
- 5) Fire rated doors at least 1 hour minimum (See Doors/windows schedule drawings for verification)

All surfaces shall have a specified powder coated protective surface layer of minimum 60-80 Micron thickness.

Glazing shall be done as specified by the Consultant. Glass shall be Blue reflective, or as specified in the drawings. Thickness shall be according to the size of panels as given hereunder.

Not exceeding 1 sq. ft.	2mm
Exceeding 1 sq. ft. but not exceeding 2 sq. ft.	3mm
Exceeding 2 sq. ft. but not exceeding 4 sq. ft	4mm
Exceeding 4 sq. ft. but not exceeding 6 sq. ft	5mm
Exceeding 6 sq. ft.	6mm

Prior to import and / or purchase of the Doors and Windows, the relevant specification of the manufacturer, along with samples has to be submitted to the Consultant for approval. This clause shall not be contravened on any account.

The fitting shall be done with utmost care not to spoil the finishes given by the manufactures, and any cleaning done shall be done with cleaners etc. as specified by the Manufactures.

The Contractor shall provide all items, articles, materials, operations, mentioned, or scheduled on the drawings, including all the labour materials, including fixing devices, equipment and incidentals necessary as required for their completion.

The Contractor shall submit shop drawings and/or samples of each type of doors, windows, railings and other items of metal work to the Consultant for approval. The shop drawings shall show full size sections of doors and windows etc. thickness of metal, details of construction hardware as well as connection of windows, doors and other metal work to adjacent work.

Doors and shutters shall be manufactured by an approved manufacturer and shall be of sections, sizes combination and details shown on the drawings. The frame member shall be one piece, corners shall be electrically welded, ground smooth and true and glazing bare shall be threaded or interlocked as approved by the Consultant.

Glazing for doors and windows shall be of specified thickness and of approved quality and shall conform to specification of glazing. Fixing for glazing shall be done with aluminium Snap-On beading as per detail drawing and instructions. Necessary continuous rubber gaskets of approved make shall be provided.

Colour for doors and windows shall be approved by the Consultant.

8.2 Louvers

Samples shall be submitted for approval.

All metal louvers shall be installed according to manufacturer's instructions.

All units shall be installed plum, well fitted and securely attached to supporting frames.

8.3 Top hung windows, ventilators and side hung doors

All windows and doors shall be weather stripped. The weather protection shall be achieved by a positive compressive action against the section and shall not depend on external contact. At every contact between two profiles two weather stripping sections shall be provided to complete weather protection.

The bottom section for hinges must be capable of being adjusted vertically if necessary. The gap between section and the floor shall be covered with a pair of special splay-tube sections.

The shutter sections for both windows as well as doors shall be hollow section type and shall be overall size 57 x 45 mm and the door sections shall be overall size 81 x 45 mm (including flanges).

The shutters of the windows and doors shall be assembled with stainless steel pins and nylon washers. Handles shall be powder-coated aluminum finished to match the aluminum sections and mounted with self-lubricating nylon washers.

A mortise cylinder rim automatic deadlock of high quality with double pin tumbler shall be used.

Windows shall have powder-coated aluminum handles, colour as framing and a latching mechanism securing the shutter to the frame both at the top and bottom

Required fittings;

Single action door closer concealed in the head bar of the outer frame and mounted on an adjacent pivot at the threshold and deadlock fitted.

The left hand leaf of double doors with flush bolts at head and sill with deadlock fitted to the right hand leaf

Escape doors to have panic bolts assembly with vertical elements concealed in the sill and door closer as in 8.3

8.4 Installation

Door/window work shall be installed adjusted and glazed by experienced workmen all in accordance with the manufacturer's installation instructions and in full conformity with the approved shop drawings, samples and other submitted data. Under no circumstances shall materials be installed on surfaces that contain condensation, dirt, grease or other foreign encountered materials that would hinder or prevent proper installation and functioning for the use intended.

Door/window work shall be carefully and accurately assembled with proper and approved provision for contraction and expansion and set in correct locations as per approved detailed shop drawings, all level, square, plumb and aligned with other work. All joints between framing and structural building shall be sealed in order to be watertight and weatherproof and to satisfy all other requirements of the Consultant.

Frames shall be designed and manufactured with a maximum 2.5mm tolerance around the opening in the structure. These joints are to be finished by applying an approved sealant into a polystyrene foam backing strip.

All Door/window works are to be fully protected for the duration of the contract from damage by other trades. The Consultant shall approve the method of protection.

If for any reason final finishes become scratched, abraded or damaged during transport, delivery, storage or erection, it shall be the Contractor's responsibility to remove or repair those defective areas or components as directed and to the complete satisfaction of the Consultant.

Repair work shall be identical to the manufacturer's applied finish with regard to gloss, finish and visual appearance. Field touch up of painted doors/windows is permitted only with the written permission of the Consultant. Where touch up is not an authorized means of repair the damaged materials must be replaced by new.

Upon completion of work all protective coverings from all exposed surfaces shall be removed. All surfaces shall be cleaned using soap or detergents as recommended by the door/window manufacturers to remove sealants, discoloration and any other foreign material. Defection of any type determined by the Consultant shall be repaired at the Contractor's expense.

Extreme care shall be taken when cleaning the exterior portion to protect all other adjacent works.

8.5 Sealing joints

The Contractor shall ensure that joints are dry and remove all loose material, dust and grease.

Joints shall be prepared in accordance with sealant manufacturer's recommendations using recommended solvents and primers where necessary.

Adjoining surfaces which would be impossible to clean if smeared with sealant shall be masked.

Backing strips shall be inserted in all joints to be pointed with sealant. When using backing strips, the Contractor shall not leave gaps and shall not reduce depth of joint for sealant to less than the minimum recommended by the manufacturer.

Cavities shall be filled and jointed with sealant in accordance with the manufacturer's recommendations. Sealant shall be tooled to form a smooth flat bead.

Excess sealant shall be removed from adjoining surfaces using cleaning materials recommended by the sealant manufacture, and shall be left clean.

8.6 Glass installation

Workmanship shall generally be in accordance with CP 152 and respective British Standards.

The glass is to be delivered to the site with adequate protection to prevent damage and where possible it is to be fixed in position immediately after delivery. When fixed the Contractor is to take all necessary precautions to prevent damage during succeeding building operations and will be entirely responsible for the replacement of any broken or damaged glass at his own cost.

The Contractor is to be solely responsible for determining the exact sizes of glass required, including a tolerance of 2mm to each edge and he is recommended to check the necessary dimensions on site.

No glazing is to be carried out until rebates have been painted with primer. Glazing beads as applicable are also to be primed before fixing.

All mastic is to be neatly struck off to agree exactly with site lines inside and out.

Rates are to include for all necessary springs, clips, setting blocks, location blocks and distance pieces and for taking off and later re-fixing loose beads.

Glass apertures in timber doors are to be bedded in chamois leather glazing strip, black ribbon velvet or P.V.C. glazing strip to the approval of the Consultant.

9. TILING

9.1 General

Glazed Ceramic Tile shall comply with British Standard specification No. 1281 and shall be approved sizes as shown on Drawings and the product of a reputable manufacturers approved by the Consultant.

Unglazed Ceramic Tile shall comply with the requirements of British Standard No.1286 and shall be of approved sizes as shown on the drawings and the product of a reputable manufacturer.

9.2 Manufacturers

All tiles shall only be used with prior written approval of the Consultant.

9.3 Ceramic and Vitreous Tile Materials

9.3.1 Ceramic and Vitreous clay Wall Tiles:

All tiles for wall installation shall have cushion edge, impervious porcelain and highly glazed surface. Colours shall be as selected by the Consultant and shall include trimmers, corner pieces, bull nose and all other special shapes indicated or required. All this shall be free from flaws, cracks and crazing.

9.3.2 Floor Ceramic and Vitreous Tiles

Non-slip ceramic tile for shall be used on all floor locations. Floor tiles shall be specially prepared for floor use but shall have all the qualities of ceramic tiles listed above for wall use.

9.4 Mortar Materials

Standard brand of light gray or white Portland Cement as specified in drawings, conforming to current British Standard specifications shall be used.

Sand: shall be clean, sharp, river sand, conforming to British Standard Specifications and graded fine to coarse within the following limits: 100% passing 8 sieve, 90% to 100% passing 16 sieve, 60% to 90% passing 30 sieve, 25% to 55% passing 50 sieve and 0% to 15% passing 100 sieve.

9.5 Cement Colour

Dry cement colour, chemically inert, non fading, alkali fast, mineral pigment, as approved shall be used wherever refinished.

9.6 Waterproofing

Floors of toilet areas, corridors, terrace and planter boxes shall be treated with an appropriate water proofing coating, approved by the Consultant

9.7 Installation Requirements

As far as possible, tile lay out work shall be in such ways that no tile less than half size occurs.

Align joints in wall tile vertically and horizontally except where other patterns are shown or specified, Align joints in floor tiles at right angles to each other straight with walls to conform to the patterns selected.

Verify locations of accessories before installing tiles. Work shall be coordinated with plumbing and other trades before starting of tile work.

Installation of ceramic and vitreous tile shall be in accordance with manufacturer's instructions.

9.8 Floor Tile Installation

All ceramic and vitreous clay tile floors shall be in Portland cement setting beds. Concrete surfaces shall be cleaned and surface of concrete shall be wetted prior to placing of setting bed mortar. Tiles shall be immersed in water for minimum of 4 hours before setting.

Setting Bed Mortar Mix: shall consist of one (1) part Portland cement and two (2) parts dry sand, by volume, to which not more than 1/10 part of hydrated lime may be added.

When mixed with water, the mortar mix shall be of such consistency and workability as to produce maximum density. Determine consistency by stroking the mortar surface with a trowel. Whereof correct consistency; the trowled surface readily assumes a smoothed, slickened appearance.

Spread setting bed mortar and screed to provide smooth, dense beds with true planes pitched to drains. The thickness of bed shall be such that the floor tile will finish flush with adjacent finished flooring, but bedding shall have average thickness of 38mm.

After bed has set sufficiently to be worked over, trowel or brush a thin layer, 3mm in thickness, of neat Portland cement paste over the surface of the back of tile.

Do not prepare larger setting bed than can be covered with tile before the mortar sets.

Press tile firmly into the bed tapping with wood blocks to obtain firm bedding of total tile area and a smooth top surface.

All tiles shall be properly aligned with straight joints in even widths. Joints width shall be determined by spacers on ceramic tiles. Tamping shall be completed within one (1) hour after placing tile. Adjust work out of line within this period.

Tiles shall be fitted closely around pipes running through walls and floors. Pitch floors to drains.

9.9 Wall Tile Installation

Base Plaster 13mm thick applied to masonry wall shall be one-part Portland cement, three-parts of river sand by volume. Where additional thickness build-up is required to conform to indicated lines, apply as separate coat at no cost to employer.

Setting bed of tiles shall be done with cement slurry. The thickness of slurry bed shall be 3mm thick minimum for setting tiles and walls.

Installation of tiles shall be in accordance with standards and applicable requirements previously specified for floor tile.

Tiles shall be installed in perfect vertical plumb and as per the pattern and joints as shown on drawings

9.10 Grouting

Grouting shall not commence for at least 24 hours after placing of tiles.

Grout for floor and wall ceramic and vitreous tiles shall be waterproof, neat white Portland cement with dry cement colour added as directed by the Consultant. If white grout is selected, cement shall be white.

Grout mixed to a creamy consistency in accordance with manufacturer's directions shall be used for joint filling. Maximum width of joints shall be 3mm.

Force maximum grout into the joints with trowel. Before grout sets, strike or tool joints to base of cushion and fill all skips and gaps. Do not permit setting bed materials to show through grouted joints.

Cure grout joints by maintaining damp condition for three (3) days by sponging down, or other methods approved by the Consultant. Allow floors to set 48 hours before permitting ordinary foot traffic.

9.11 Defects in Tiles and Tile Laying

The surface of all tiled floors shall be perfectly in level and shall be executed by experienced workers in the field of tile setting.

A sample panel of laid tiles of each type shall be approved by the Consultant before commencement of tile setting.

Chipped or damaged tiles installed by the Contractor shall be rejected and shall have to be replaced by the Contractor at his own cost and risk.

9.12 Guarantees

Manufacturer shall provide his standard guarantees for work under this section. However, such guarantees shall be in addition to not in lieu of all other liabilities which manufacturers and Contractor may have by other provisions of the Contract Document

10. PAINTING

10.1 Material

All paints shall be approved by the Consultant for colour, quality and type. All painting work shall be carried out in accordance with the paint manufacturer's specifications unless otherwise directed by the Consultant.

Paints from manufacturers not listed above shall only be used with prior written approval of the Consultant

Paint shall be ready mixed and all paints, varnishes, enamels, lacquer stains, paste fillers and similar materials shall be delivered to the site in the original containers with the seals unbroken and labels intact. Each container shall give the manufacturer's name, type of paint, colour of paint and

instructions for reducing. Thinning shall be done only in accordance with the manufacturer's directions.

Use of product by the same manufacturer shall be a general rule in each stage of work in this Specification.

Colour, luster, colour scheme and finish shall be decided by the Consultant after checking sample paint test.

The painting shall be performed by experienced and competent painter.

Where walls are specified to be painted, all columns, arches, groove, rough surfaces, reveals, soffits and returns, etc. shall be included and no extra shall be payable.

10.2 Definition of Terminology

10.2.1 Surface Sealing

Surface to be painted shall be sealed to have uniform suction and prevent lye from oozing out.

10.2.2 Spot Puttying

All cracks and depressions shall be filled flush with putty.

10.2.3 Puttying

All surfaces to be painted shall be puttied uniformly flat surface.

10.2.4 Spot painting

Spot puttied area shall be touched up by paint

10.2.5 Touch-up

Any damaged area after the prime coat has been applied shall be touched up

10.2.6 Drying hour

The drying time of double coated paint shall be measured at the temperature of 20°C and humidity of 70%.

10.2.7 Amount of paint

The amount shall be standard amount of paint itself not including thinner. It shall increase or decrease depending on shape and surface condition in the process of painting.

10.3 Paint Finish Symbols

OB	Oil-Based paint finish
EP	Polyvinyl acetate resin emulsion paint finish
AEP	Synthetic resin emulsion paint finish
EXP	Export Resin Paint finish

10.4 Painting in General

10.4.1 Preparation of Paint

Mixing: Paint content with pigment shall be thoroughly stirred to make a uniform consistency.

Thinning: Portable water shall be used for thinning of emulsion paint and water-soluble paint. Proper thinner, product of the same manufacturer as paint, as a rule, shall be used for other types of painting. Percentage of thinning and viscosity shall be conducted with direction of

manufacturer or catalogue as they vary with the method of paint, temperature, type of material to be painted.

Allowable period of Use: Paint mixed with more than 2 types shall be used with direction of a manufacturer or catalogue as allowable period of use, mixing ratio and mixing method vary. The paint which has passed allowable period of use shall not be used.

10.4.2 Conditions of Painting

Work shall not be executed in the following situations

When humidity is above 85%

When raining or it is forecast

When dusts are present

When temperature of surface is high under hot weather and bubbles are likely to develop on the painted surface.

Conditions of Surface to be painted: Work shall not be executed or proper means shall be taken in the following situations.

When surface is damp and wet

When condensation is likely to develop on the surface.

All nail holes on veneer, board. etc., shall be covered with proper rust-proof paint before the subsequent painting is applied in accordance with this specification.

10.4.3 Performance

Paint shall be evenly and uniformed applied on the surface. Areas of difficult application such as pointed part, internal angle, welded part, etc. shall be thoroughly painted and double coated as necessary to deep uniform coating thickness.

Painting shall be properly done by carefully selecting the painting method by the shape of surface and types of paint.

10.4.4 Protection

Dangerous material such as paint, thinner, etc., excluding emulsion paint and water-soluble paint shall be kept in accordance with regulations concerned.

10.5 Procedure of Painting

10.5.1 Exterior - Surface of Mortar, Plaster and Concrete

Oil based paint finish (gloss)

Coating Process	No. of Coats	Type of Paint	Drying hour	Amount (kg/m ²)
1. Surface preparation		Dry, clean and free from impurities		
2. Surface sealing	1	Sealer for Oil based paint	longer than 4	

			hours	
4. Grinding		Grind with proper grinding tool		
5. Spot painting		Oil based paint		
6. Second coating	1	Oil based paint	longer than 4 hours	0.10-0.13
7. Finish coating	2	Oil based paint	longer than 4 hours	0.10-0.13

Notes:

- Degree of dryness on the surface to be painted shall be kept under 6% in water content and below PH 9.5
- Puttying and sanding process shall be allowed to omit depending on the conditions of the surface.
- Drying time of putty shall be long enough for sanding to proceed.
- Amount of sealer for surface sealing shall be adjusted with direction of the Consultant as it varies with the surface conditions.

10.5.6 Interior - Mortar, plaster, concrete, etc.

Polyvinyl acetate resin emulsion paint finish (matt)

Coating Process	No. of Coats	Type of Paint	Drying hour	Amount (kg/m ²)
1. Surface preparation		Dry, clean and free from impurities		
2. Surface sealing	1	Sealer for emulsion paint	longer than 4 hrs	
3. Puttying		Putty for emulsion paint		
4. Grinding		Grind with proper grinding tool		
5. Spot painting		Polyvinyl acetate resin emulsion paint		
6. Second Coating	1	Polyvinyl acetate resin emulsion paint	longer than 4 hrs	0.11-0.13
7. Finish Coating	1	Polyvinyl acetate resin emulsion paint	longer than 4 hrs	0.11-0.13

Notes:

- Degree of dryness on the surface to be painted shall be kept under 6% in water content and below PH 9.5
- Puttying and sanding process shall allowed to omit depending on the conditions of the surface.
- Drying time of putty shall be long enough for sanding to proceed.
- Amount of sealer for surface sealing shall be adjusted with direction of the Consultant as it varies with the surface conditions.

10.5.7 Exterior - Iron Products in General

OB – Oil Based Paint

Coating Process	No. of Coats	Type of Paint	Drying hour	Amount (kg/m ²)
1. Surface preparation		Completely remove rust, moisture, oil and other impurities by sander, cleaner and surface.		
2. First Coating 24 hours	1	Rust proof oil paint	longer than 24 hours	0.13-0.15
3. Touch-up		Touch-up rustproof oil paint		
4. First Coating	1	Rustproof oil paint	longer than 24 hrs	0.13-0.15
5. Second coating	1	Oil Based Paint	longer than 15 hrs	0.11-0.15
6. Finish coating	1	Oil Based Paint	longer than 15 hrs	0.11-0.15

Note:

Paint for touch-up painting shall be the same as used for first coat in process No. 2

10.5.8

Floor - Concrete and Mortar**EXP - Epoxy resin paint finish**

Coating Process	No. of Coats	Type of Paint	Drying hour	Amount (kg/m ²)
1. Surface treatment		Dry, clean and free from impurities		
2. First coating	1	First coating paint for epoxy	Longer than 24 hrs	
3. Finish Coating	2	Epoxy resin paint	Longer than 24 hrs	

Notes:

(a) Degree of dryness on the surface to be painted shall be kept under 6% in water content and below PH 9.5.

(b) Amount of paint and number of paint shall be as directed by the Consultant as they vary with the conditions of surface and required thickness of coating.

(c) Painted surface shall be kept out of use for more than 7 days after application of final coat.

11. PLUMBING

11.1 General

The materials used and workmanship shall be of highest quality and grade unless otherwise specified shall conform to the latest specifications of British Standards and Codes of Practice for “Water Supply “Sanitary, Pipe Work “Building Drainage “ Surface Water and Sub- Soil Drainage” and applicable to details and work indicated on the Drawing and Bill of Quantities. In case of any discrepancy / ambiguity the decision of the Consultants shall be final, and the contractor will act and perform accordingly.

The work shall be executed strictly in accordance with the rules and regulations set by the relevant local authority of the Maldives.

The Contractor shall be responsible for obtaining the necessary approvals and test certificates from the concerned departments of Maldives.

Plumbing work shall be carried out by licensed plumbers and shall produce the copy of the license along with the tenders, or approved by the Consultant

Any damage done by the Contractor to any existing work during the course of execution of his work shall be made good by him at his own cost. Failing which it shall be get done by the Consultants at Contractor’s risk and cost.

The Contractor shall be responsible to connect the drainage and water supply to the mains and to obtain the necessary approvals and certificates from the relevant authorities of the Maldives.

All connections to mains and meter installation shall be arranged by the Contractor and payment of fees thereof, if any, shall also be made by him.

The Contractor shall be responsible for the watch and ward of all fittings until the Works is fully completed and handed over to the owner.

The levels, measurements and other information concerning the existing site as shown on the drawings or as described as are supposed to be correct. The Contractor shall, however, verify them by himself and no extra claim whatsoever shall be entertained on account of the errors or omissions in such matters or on account of the descriptions turning out to be different from what was expected.

The Consultant shall instruct the Contractor to purchase and use such materials of particular make or from particular source as may in his opinion be necessary for proper and reasonable compliance with the specification and execution of the Works.

After all plumbing fixtures and equipment have been set ready for use, and before the Contractor leaves the job, he shall thoroughly clean all fixtures installed by him, removing all plaster, stickers, rust stains and other foreign matter of discolouration on fixtures, leaving every part in acceptable condition and ready for use to the satisfaction of the Consultants.

11.2 Drawings and Information Required

The Contractor shall submit shop drawing for the entire installation including installation details for all items required or asked for approval of the Consultant.

Approved by the Consultant of shop drawing for any material, apparatus, devices and layout, shall not relieve the Contractor from the responsibility of furnishing same of proper dimension, size, quantity and all performance characteristic to efficiently perform the requirements and intent of the Contract Documents. Such approval shall not relieve the Contractor from responsibility for errors of any sort in the shop drawing.

If the shop drawings deviate from the contract Documents the Contractor shall advise the Consultants of the deviations in writing accompanying the shop drawings including the reasons for the deviations.

At the start of the Project the Contractor shall periodically and thereafter submit to the Consultants list of all shop drawings which will be submitted in the course of the project. The list shall show the disposition of each item including date of submission approval etc. The list shall be kept up to date through the entire course of construction.

11.3 Record Drawing

During Construction the Contractor shall keep an accurate record of all deviations between the work as shown on the Contract Drawings and that which is actually installed.

The Contractor shall secure from the Consultants after approval of his Shop Drawing a complete set of drawing and note changes thereon in ink.

The Contractor shall make a complete record of all changes and revisions in the original design which exist in the completed work.

The cost of furnishing above prints and preparing these for record “ shall be deemed to be include in the tendered cost and its effects spread over other items of work, and as such item shall not be a subject to payment”. When all revisions showing the work as finally installed the corrected Original Transparencies shall be submitted to the Consultants before final payment for the completed work will be made.

11.4 Operating and Maintenance Instructions

Three sets of operating and maintenance instruction covering completely the operation and maintenance of all plumbing equipment, controls, heaters, pumps and the like shall be furnished to the Owner, by the Contractor.

11.5 Tests

The entire system of drains, waste and vent piping inside and outside the building shall be tested by the Contractor under a water test, which shall include the entire system from the lowest point to the highest pipes above the roof.

The water test shall be made in accordance with all local requirements. Every portion of the system shall be tested to a hydrostatic pressure equivalent to latest 15 feet head of water. After filling, the Contractor shall shut off water supply and shall allow it to stand 2 hours under test during which time there shall be no loss or leakage.

The Contractor shall furnish and pay for device, material supplies, labour and power require for all tests. All tests shall be made in the presence and to the satisfaction of Consultant.

Defects disclosed by the test shall be repaired or if required by the Consultant defective work shall be replaced with new work without any extra charge to the Owner. Test shall be operated as directed until the work is proved satisfactory.

Fixture shall be tested for soundness, stability of support and satisfactory operation.

The Contractor shall notify the Consultant at least one week in advance of making the required test, so that arrangements may be made for their presence to witness the test.

Equipment shall be tested in service and the Contractor shall demonstrate that the equipment performs the work intended for it and that it complies with the requirement of these specification for such equipment, to the satisfaction of Consultants.

The rates shall include for all costs associated with tests.

11.6 Work in Common Piping

11.6.1 Material

Piping and fitting material shall be uPVC, Hard Impact PVC. or High Temperature PVC. and approved by the Consultant.

Piping material shall comply with requirements of water supply and sewerage and other relevant authorities.

Materials for the piping and service requirements shall basically conform to the service pressures encountered.

11.6.2 Providing Drawings and Manuals

The Contractor shall submit one set of originals and further two copies of layout drawings to the Consultant after completion of the Works. These drawings must give the following information:

- (a) Run of all piping and diameter on all floors and the vertical stacks.
- (b) Location and sizes of all control valves, access panels and other equipment.
- (c) Location of all manholes and their sizes.

No completion certificate will be issued until the drawings are submitted.

The Contractor shall submit to the Consultant for approval, samples, shop drawings, manufacturer's drawings, equipment characteristics and capacity data etc. of all equipment, accessories devices etc. that he proposes to use in the installation.

11.6.3 Samples

The Contractor shall provide samples of all sanitary fittings, pipes and specials manhole cover and frames, gratings and water supply pipes and fittings etc. and shall be deposited with the Consultant (which will be returned to the Contractor at the completion of the Works) and shall obtain approval from the Consultant before using in the Works. Any material rejected by the Consultant shall be removed from the site within 24 hours of rejection.

11.6.4 Drawings

The works shall be done in conformity with the plans and within the requirements of the general architectural, electrical and structural plans. This work shall be properly coordinated with the work of the other trades. Hangers and sleeves shall be furnished in time for their installation as other work proceeds.

The plumbing drawings are diagrammatic, but shall be followed as closely as actual construction. All deviations from drawings required to conform to the building construction shall be made by the Contractor at his own expense.

The architectural drawings shall take precedence over the plumbing drawings as to all dimensions.

Large size details shall take precedence over small size drawings. The special dimensions in the specifications or schedule of quantities or instructions of the Consultant shall supersede the drawings. The Contractor shall verify all dimensions at site.

The recommend position of the fittings, fixtures, control valves, tanks etc. as shown on the drawings will be adhered to as far as practicable.

Shall there be any discrepancy due to incomplete description ambiguity or omission in the drawings and other documents, whether original or supplementary, forming the contract, either

found on completion or during the currency of the installations work, the Contractor shall immediately, on discovering the same, draw the attention of the Consultants and the Consultants decision in final and binding on the Contractor.

11.6.5 Existing pipes

The site shall be examined for field drains and those, when found, shall be either entirely removed or diverted, trenches filled with dry earth in 200mm to 300mm layers and consolidated as directed by the Consultant.

11.6.7 Excavation

All excavations shall be timbered to the satisfaction of the Consultant and the type of timber shall be suitable to the kind of earth encountered. Fixing of timber and removal after completion of work shall be done as directed by the Consultant.

Shall any water accumulated in the trenches, headings or other excavation, the Contractor shall do such work as may be necessary to drain away the accumulated water and shall install pumps as may be required to keep the excavation and trenches dry. The Contractor shall ensure that the flow water in trenches or excavation does not injure or remove cement or aggregate of any concrete that has not set. No subsoil water shall be discharged into open drains or sewer at the site.

In refilling trenches after excavation this shall be done in layers of 150mm after consolidating each layer. Special care shall be to see that the earth is packed uniformly and no injury to the pipe.

Rates for excavation shall include for backfilling in consolidated layers where necessary and as directed by the Consultant.

11.6.8 Piping

The Contractor shall, as soon as possible after the award of the contract, prepare and submit to the Consultant for approval, working drawings showing exact locations and pipe runs for all pipework, the layout and setting up of equipment and the connection of piping to the equipment. Such drawings shall include details and methods of supports, anchors and sleeves etc.

Pipe runs shown in the drawings are approximate and intended to indicate the general run and locations only. The exact locations of all pipe work shall be determined on Site.

All pipes, fittings etc. shall be kept closed against moisture and foreign matters when stored at site and during installation.

All pipes shall be fixed clear of one another and be so arranged as to provide easy access for maintenance and repair.

All plumbing work shall be carried out by suitably qualified plumbers in accordance with the British Code of Practice and Regulations and requirements of related Authorities.

Materials for the piping and service requirements shall basically conform to the service pressures encountered.

Each part of the installation of the plumbing work shall be completed in all details as shown in the drawings or as specified and provided with all necessary control valves, etc. that will be necessary for their satisfactory operation.

All piping shall be run plumb, and straight and parallel to walls, except drain line which shall pitch 6mm per 300mm in the direction of flow.

Pockets, unnecessary traps, turns and offsets shall be avoided. When traps or pockets are unavoidable they shall be valved drains.

Piping installed on the concrete slab shall be firmly fixed or anchored to the floor with packing to prevent damage to pipes. Pipes shall not be bent with bender where cross with other pipe or change to upward.

Where pipes are to be laid directly in the ground, bed shall be sufficiently compacted, necessary protection for piping shall be taken.

Backfill shall be done after the approval of the Consultant in such a manner not to damage the pipeline and shall be restored to the original stage.

Where pipes penetrate through waterproof part or fire partition or fire wall, pipe sleeves shall be provided and clearance between pipe sleeve and pipe shall be filled with caulking material approved by the Consultant.

Pipes, fittings, valves and accessories shall be thoroughly cleaned, both internally and externally before installation and shall be cleaned before putting into service.

Plumbing work shall be completed in accordance with the details shown on the Drawings or as specified and provided with all necessary control valves, etc. that will be necessary for their satisfactory operation.

All pipes shall be cut square and true to the pipe axis by means of suitable tools without reducing pipe diameter and cut ends shall be finished smooth. Before making connections, chips, dirt and other foreign matter shall be removed from inside interior of each pipe. Fixing of hangars and embedding of pipe sleeves shall be carried out without delay along with the progress of the work where required.

Pipe connections for the water supply system shall be by uP.V.C high pressure. Jointing shall be generally by means of solvent cement according to manufacturer's instructions

Vertical pipe shall be braced at more than 2 point in every story.

11.7 Water Supply Work

11.7.1 Materials

Pipes, joints and fittings for water supply work shall be high pressure uP.V.C.

Materials and workmanship shall comply with the local water supply authority requirements.

11.7.2 Water Pump

The specifications herein stated are basic guides only. Other items not so indicated but which are obviously necessary for the proper operation of the system as intended shall be supplied and installed, in accordance with accepted Consulting standard.

Manuals of operation and maintenance and list of spare parts shall be supplied together with the equipment.

The contractor shall submit at least four copies of pump performance curves showing among others, the pump rating and efficiency, properly marked out.

A metal name plate indication in indelible letters for the correct specification of the pump and motor shall be properly attached to the assembly at a location such that the information written thereon can be conveniently read by all concerned.

Well water pump: Flow rate = 60L/min, Head = 70m, Type : End suction Hydro pneumatic pump, 220/440V, 3-Phase, 50 Hz.

11.8 Spacing of supports

Support spacing for uP.V.C pipes shall be as follows

Nominal Dia.	upto 40	more than 50
Space (m)	1.2	1.5

11.9 Drainage Work

11.9.1 General

High Pressure uPVC pipe and fittings shall be used for all drainage work including vent pipes.

Joints shall be made by the cold-jointing method, and the pipe interior shall have not offset at the joint interfering with the flow. Joint adhesive shall be good quality and shall not be affected by heat and shock.

Where horizontal drain branch joints the main, such branch shall be connected to the main in a substantially horizontal position and at an acute angle of not more than 45 degree to the main in all cases.

11.9.2 Vent stack pipes

Vent pipe shall be vertically branched out upward from a horizontal drain branch pipe or other appropriate point. Horizontal branching of the vent pipe shall be done on approval of the Consultant.

Where vent pipes on each floor are to be connected to the vent stack, all connections shall be made at least 150mm above the respective overflow edges of fixture on that floor.

The provision of the preceding item shall also apply to the connection of vent stack vent pipe.

Vent stack shall be connected to the waste stack or soil stack at the lowest part to stack pipe.

Where vent pipe is to be connected to the horizontal drain pipe, such angle shall be more than 45 degree to upward.

Vent stack shall be extended 600 mm from the top of the roof or lead to the wall and top of pipe shall be covered with vent cap.

11.10 Laying of Pipes

The pipes shall be laid to proper lines and levels as shown in the plans and directed by the Consultant, as the main is laid, the front pipes in the trench shall always be closed with a plug either of iron or wood and security fastened. The plug shall not be removed except when pipe laying is resumed or for purposes of testing.

11.12 Sewers

After the cement has had time to set, the pipes shall be tested in length between manholes in following manner.

In the lowest manhole/intercepting trap as the case may be, a plug shall be inserted in the pipe. The disc in the pipe at the upper manhole shall be fitted with a filling pipe with a right angle bend and an air cock.

The pipe line shall then be filled with water by means of the pipe connection on the upper disc. The air cock on the upper disc shall be kept open while the pipeline is being filled to permit the escape of air.

When the pipes are filled with water and air excluded, the air cock shall be shut and the water shall be poured into conical filler, attached to the filling pipe until the water remains in the filter.

The filling pipe shall then be raised and fastened so that the height of surface of the water in the filler above the invert of the pipe is 1828 mm which will be usual test pressure for S.W pipes.

If the water level does not fall more than 16mm (12mm) in a length of 91.4 meter the test may be considered satisfactory.

The Contractor shall make good all defective work at his own expense

11.13 U.P.V.C Pipes

Manufacturer’s instruction shall be followed in pipes to be used for water mains. Where specified, pipes shall have integral rubber ring joints and where solvent cement joints are specified, a sufficient number of expansion/contraction joints shall be incorporated in the length of mains to allow for variation of temperature to the recommendation of the pipe manufacturers.

These pipes shall be effectively protected from the direct rays of sun immediately after they are laid and until permission is given for the trenches to be refilled by the Consultant. Subject to such permission being obtained, trenches shall be refilled without delay. Final connection at a fixed point shall be deemed unto the majority of the length of the pipe line has been covered by backfill in order to reduce the effect of expansion and contraction caused by temperature variations .

11.14 Bends and other Specials

In fixing bends care shall be taken to see that the axis of the bend is truly vertical or horizontal as the case may be and the spigot of the bend is well in the socket of the pipe with which a joint has to be formed. The Contractor shall be called on to replace any faulty work at his own expense.

11.15 Support for U.P.V.C Pipes

When U.P.V.C pipe lines incorporate metal valves or other heavy fittings, it is essential to support the valves directly rather than allowing their weight to be carried by the uPVC pipe and support shall be placed on either side of the fittings mentioned above. Moulded plastic fitting also shall be supported.

Maximum allowable horizontal support distance for uPVC are given below.

Nominal bore	12 mm (1/2")	18 mm (3/8")	25 mm (1")	32 mm (1¼")	38 mm (1½")	50 mm (2")
Support distance	533 mm (1'9")	616 mm (2'0")	686 mm (2'3")	764mm (2'6")	840 mm (2'9")	915 mm (3'0")
Nominal bore	75 mm (3")	100 mm (4")				
Support distance	1220 mm (4'0")	1290 mm (4'6")				

For vertical installation supports, distances shall be doubled.

11.16 Sewer pipes

All 'P', 'S', 'T' junctions bends etc. required shall be furnished and set without extra charge and shall conform to the pipe specifications as to quality

11.17 Air Valves

These valves to be fitted as per drawings and Bill of Quantities shall be tested and accompanied by a certifying their efficiency.

The floating ball in the valve shall be suitable metal or vulcanite or rubber specially manufactured for tropical conditions.

11.18 Scour Washout Valve

These shall be provided at portions shown in place and shall contain in one unit a flanged scour valve with short connection pieces, cast iron bend and T pieces for connection to main pipe.

The rate shall also provide for short length of straight pipe to a convenient as per details complete with covers and surface boxes

11.19 Foot valves and Strainers

Foot valve and strainers shall be of reputable manufacture approved by the Consultant and shall be fitted with flushing lever attachment where specified.

11.20 Pressure Reducers

Pressure reducing valves shall be of the equilibrium type of approved manufacture and capable of reducing the pressure to the valve required as per plan and Bill of Quantities.

11.21 Equilibrium Ball Valves

These shall be of reputable manufacture approved by the Consultant and be of the angle pattern with gun metal valve seats guide bush, copper float with wrought iron lever and links with bronze pins.

11.22 Fittings

All sanitary pipes, gullies, water closets/bidets, squatting basins, sinks bath tubs etc. to be of approved design and to be obtained from approved Manufacture and to be of the best stoneware, glazed inside and outside, with burnt hard and sound, free from flaws, blisters, cracks and other imperfections and best quality commonly called 'Firsts'.

Rates shall include for all bends, junctions, traps, cleaning, painting, fixing clear of wall etc. complete as specified as per Bill of Quantities.

All pipes, fittings, flushing cisterns, valves, stop cocks, taps, tanks, surface boxes etc. to be of the best of their kinds and in addition to complying with previous clauses to be from approved Manufacturers and all taps, cocks, valves etc. to be screwed down pipe. Taps to be of brass/nickel coated and valves to be of gunmetal. All tanks to be made fly-proof and to the complete satisfaction of the Consultant.

Rates shall include for all cutting and waste, bends, taps junctures, cleaning eyes, tees

11.23 Fixtures and Accessories

All sanitary wares shall be manufactured by one of the following manufacturers.

1. Cotto
2. American Briggs
3. Armitage Shanks
4. Star sanitary ware

Sanitary ware from manufacturers not listed above shall only be used with prior written approval of the Consultant

11.24 As built Drawings

The Plumbing Contractor, shall mark down with red pencil on two sets of plumbing plans all the revisions, omissions and/or additions to the various plumbing installation drawings as the construction progress. One set of the plans as marked shall be submitted to the Consultant after completion of the work.

11.25 Miscellaneous

Throughout the construction period, open ends of all installed pipelines shall be kept closed by temporary plugs. Drainage lines shall not be used to conduct dirty construction wash-washer, especially, those with cement, to avoid possible clogging.

A temporary potable water supply shall be available to construction workers at each building floor as construction work progresses.

A temporary human Excrete Disposal System shall be provided by the Contractor to serve the workers during the construction period.

12. ELECTRICAL INSTALLATIONS

12.1 General

The work shall be carried out strictly in accordance with the standard specifications and shall also conform to the requirements of Electricity Rules in force in Male', Republic of Maldives.

All materials to be used in the Works shall be of standard make and shall bear the certification marks of local authorities. All materials shall be approved by the Consultant before use in the Works.

Earthing shall invariably be done in the presence of the Consultant or his representative.

All the conduits shall be continuously earthed. Check nuts shall be provided at the point where the conduct enters the I.C. box and junction box.

The Contractor shall arrange for the inspection of all Medium Pressure Installation by the Electrical inspector of the local electric supply authority from where the electricity connections has to be obtained, and see that they are passed by him.

The Contractor shall be responsible for all necessary permits, approvals, fees and deposits etc., required for the completion of the electrical works in accordance with the Contract.

12.1.7 Scope of work

The work consists of furnishing all tools, plants, labour, materials and equipment and performing the internal electrical Works comprising of:

- Light and power wiring
- Fans and fixtures
- Wires and cables
- Lightening and Earthing System
- Telephone system
- Cable Trench and Cable tray system

12.1.7.2 Standards and Codes

- (a) The Contractor should perform all the work in compliance with all regulations, standard specifications or states of the government of Maldives unless in conformity to this specification.
- (b) The current British Standard Specifications and Codes of practice shall apply to, and form part of these specifications, unless otherwise specified in respect of all materials and works to which they have application.

12.1.7.3 Drawings and Specifications

- (a) Drawings and Specifications are intended to complement each other, so that if anything is shown on the Drawings, but not mentioned in the specifications or vice versa, it is to be furnished and built as though specifically set forth in all three. If any discrepancies, errors, ambiguities or omissions occur in the Drawings or Specifications, the same shall be referred to the Consultant before proceeding with the works, and the Consultant's decision on such discrepancies, errors, ambiguities or omissions shall be final.

- (b) In addition to the Drawings and Specifications attached hereto, the consultant my furnish additional drawings, specifications and instruction. Such drawings and instructions should be deemed as a part of this document.

12.1.7.4 **Schedule and Execution Plan**

- (a) The Contractor should prepare and submit to the Consultant for the approval the construction schedule and an execution plan before stating the work. If the contractor fails to follow the execution plan for any reason, a new execution plan with the reason should be submitted to the Consultant within 7 days.

12.1.7.5 **Obvious Work**

- (a) Where an item of work is obviously required for the type of work being undertaken then it should be deemed to have been included even though the item is not specifically mentioned or shown in the Drawings or Specifications.

12.1.8 **Prequalification**

The Electrification Work shall be carried out only by a licensed contractor authorized to under take such work under the Maldives Electricity Bureau.

12.1.9 **Qualification**

A licensed Electrical Contractors shall have the following qualifications:

Must have in his employment a competent Electrical Engineer registered with Maldives Electricity Bureau.

Must have in its employment an Electrical Consultant having certificate of competency who will exclusively supervise this work.

Must have necessary tools, plant and instruments.

Must have adequate experience of similar works.

If a contractor does not posses the above qualifications he shall be allowed to sublet the Work to a competent Sub-Contractor provided an application for his pre-qualification is made to the engineer for his approval. Decision of the Engineer in this case shall be binding on the Contractor.

12.1.10 **Rules and Regulations**

The installation in general shall be carried out in conformity with the Electricity Rules, 1937 (UK), and the latest edition of the Regulations for the Electrical Equipment of Buildings issued by the Institution of Electrical Engineers, London (I.E.). However, in case of conflict between these Specifications and the I.E. Regulations, these Specifications shall be followed.

12.1.11 **Standards**

The latest relevant British Specifications, and I.E. recommendations shall be applicable and be followed for the equipment specified herein.

12.1.12 Test Reports

The Contractor shall be responsible for the submitting the test reports/certificates and get the installation inspected passed by the Maldives Electricity Bureau.

12.2 Conduit and Conduit accessories

12.2.1 Conduit Pipe

The conduit for the wiring of lights, socket outlets and other systems shall be made of PVC confirming to BSS 3505/1968 Class-D.

The conduit shall have following wall thickness and standard weights:

Pipe Size	Wt/100Rft.	Wall thickness
20mm dia	3.4 Kg	0.04 to 0.05
25mm dia	4.5 Kg	0.045 to 0.055

Steel conduit shall conform to BSS 31/latest. The conduit shall be enameled with good quality non-cracking and non-flaking black paint.

12.3 Wires, Cables and Cords

12.3.1 Wires & Cords

The wires & cords for the conduit wiring shall be single core, made of stranded copper conductors, PVC insulated, tested to B.S. 6004, 1975. The voltage grade shall be 300/500 volts or 450/750 V unless otherwise specified on Drawings and Bills of Quantities.

All the wire and cables shall be of the approved standard of Maldives Electricity Bureau.

- (a) For light or fan point wiring with 1.5 mm square or as specified in the BOQ.
- (b) For light circuit wiring with 2.5 mm square or as specified in the BOQ.
- (c) For power plug 15A wiring with 4mm square or as specified in the BOQ.

12.3.2 Conduit Accessories

The use of factory made round PVC junction boxes shall be used and shall have nipples to receive PVC pipe with force fit, shall be used for ceiling outlets. The wall type junction box shall also be PVC. 12.2.2.2 Each junction box shall be provided with one piece cover which shall be fitted on the box with screws.

Conduit accessories such as switch boxes, socket outlet boxes, pull boxes and inspection boxes shall be made of PVC having dust tight covers. All boxes shall have required number of conduit entry holes. All the rectangular or square shaped boxes shall have nipples to receive PVC conduit force fit.

Manufactured smooth bends shall be used where conduit changes direction. Bending of Conduit by heating or otherwise shall be allowed only at special situations with the permission of the Consultant. Use of sharp 90 degree bends and tees is prohibited.

Bends shall have enlarged ends to receive the conduit without any reduction in the internal diameter of the PVC pipe.

All accessories e.g. boxes, coupling, bends, solid plugs, bushes, reducers, check nuts etc. shall be equal in quality to the specified conduit.

The drawings do not show conduit routes and all the planning for arranging conduit routes shall be carried out by the Contractor to the satisfaction of the Consultant.

The entire conduit system shall be essentially completed before the wiring pulling is taken in hand. Each conduit run shall be tested for continuity and obstructions. All obstructions shall be cleared in an approved manner. Water and moisture that has entered any section of the conduit installation must be dried with suitable swabs to the satisfaction of the Consultant.

Adequate expansion joints shall be provided in all conduit runs passing across the expansion joints in the concrete slab of the buildings

All the free ends of conduit shall be solidly plugged till such time as final and proper terminations are made

12.3.3 Installation Instructions

All wiring shall be continuous between terminations and use of connectors or joints are not allowed. Spur and tee connections are strictly prohibited.

Manufacturers recommended lubricant shall be allowed to facilitate pulling of wires. Use of any kind of oil and soap is prohibited.

12.4 Wiring Accessories

12.4.1 Switches

Indoor switches controlling lights and fans shall be single pole, 5A, one or two way, suitable for 250V, 50 Hz. The body of the switches shall be made of molded plastic, one; two, three or four gang with integral built in molded plastic faceplate.

Weatherproof switches shall conform to B.S. standard.

12.4.2 Switch Socket Outlet Units

Switch & socket units shall be single, pole, 3 pin rated 5A, 15A or 20A, 250V, 50 Hz. These shall be moulded plastic type with white integral built-in faceplate. Each socket shall have its control switch by the side of it on a common faceplate. Thus the complete unit specified in BOQ shall be as switch and a socket outlet unit.

12.4.3 Fans

All fans shall be capacitor type Deluxe models or equivalent and suitable for operation on 200/220 volts, 50 Hz, A.C Supply. All ceilings fans shall have five speed dimmers. The air displacement shall be 10,000 c.f.m for 48" (1219 mm) Sweep and 12,000 c.f.m. for 56" (1423 mm) Sweep at maximum speed. The fan motor shall be capacitor type and bearings shall be groove type to give noiseless and quiet operation. The noise level relative to a frequency of range 1000 Hz shall be within the limits of +3 dB.

12.4.4 Dimmer

The dimmer shall be recessed type as required and shall be approved by the Consultant.

12.4.5 Fan Hook

The fan hook shall be made of 12 dia mild 5/5 steel rod bent to shape of approved design. It shall be in the form of a loop about 3-1/4" (87.5 mm) long and about 2" (50 mm) wide. The rod shall be bent to have at least 8" (200 mm) extension on both sides for tying to the reinforcement steel of the slab. All ceiling fan shall be of one make only.

The fan hook shall be installed in the RCC slab of the ceiling at the time of pouring concrete.

12.5 General

The description of light fixtures is given in the Bills of Quantities, and stated on the Drawings, and all relevant materials are described in this Section.

The determination of quality is based on certified photometric data covering the coefficient of utilization, light distribution curves, construction material, shape, finish, operation, etc.

The Contractor shall submit samples of each and every lighting fixture specified for approval of the Consultant.

The lighting fixtures shall be manufactured by M/s. Philips, M/s.RZB Lighting, M/s Thorn or equivalent as approved by Consultant.

12.5.5 Incandescent Light Fixture

The glass globes/ shades/ diffusers of the incandescent light fixtures shall be first class quality glass free from any air bubbles or voids. The glass shall generally be of opal white colour unless otherwise specified. The shape of the glass may be spherical, hemispherical, flattened bottom or tablet shaped as required.

Surface mounted fixture shall have stove enameled sheet steel body. It may also be satin brass or aluminium anodized finish as required. The fixing holes shall match the outlet box. Wall bracket light fixtures shall have back plates with matching holes of the outlet box and decorative finish as required.

All the lighting fixtures shall be suitable for local climatic conditions'

12.5.7 Installation Instructions

Light fittings shall be installed according to manufacturers' recommendations or as approved by the Consultant.

Flexible connecting wires from outlet box to the fixture shall be provided by the contractor; connector made of porcelain or thermoplastic material shall be provided and installed in the outlet boxes for connecting flexible wires to the point wires.

Outlet boxes or any openings in the ceilings and walls shall be covered with appropriately fabricated accessories to provide an architectural entity to conceal them.

12.5.8 Distribution Feeder Panel

Single line diagram of the L.T. switch board shall be approved by the consultant and Maldives Electricity Bureau before placing order for the switch board.

12.5.9 Earthing

The switchboard shall be effectively earth by means of a copper strip of 25mm x 3mm (1" x 1/8") cross -section bolted to connections near the bottom of the switchboard.

12.5.10 Accessories

Designations labels, lifting lugs, foundation bolts, interconnecting nuts bolts, and washers, thimbles, lugs, leveling shims cable glands and/or cable end box for all the sizes of incoming and outgoing cable shall be supplied with the switchboard

12.6 Testing

The following tests shall be conducted on each completed switchboard.

Type Tests

- (a) Temperature rise test
- (b) Mechanical endurance test

- (c) Making/Breaking Capacity test
- Routing Test
- (a) High Voltage test

The Switchboard shall be tested to British/Electricity Council Standard 41-5. Preference shall however, be given to Switchboards fabricated from all components manufactured by only one manufacturer.

12.7 Installation Instruction

All labour, equipments, tools and plants required to complete the installation shall be provided by the contractor. The Switchboard shall be fixed firmly on the floor in perfect line, plumb and level position.

All incoming and outgoing cable connections shall be made from the bottom including Earth connections.

12.8 Distribution Board

The distribution boards shall be either free-standing, cubical type or wall mounting type suitable for fully recessed mounting. Each distribution board (d.b.) shall be tropical in design, fully dust and vermin proof and liquid repellent.