



## Scope of Works

### 1. Location of the Works

The site for the works proposed under this contract is in the Island of K. Hulhumale', Maldives.

### 2. Description of the Works

The scope of works for the project includes construction works of boundary fence at inventory site of MWSC in Hulhumale'.

- Scope of works includes mobilization , site clearance and demobilization
- Modification works are mentioned in BOQ
- Assess the suitability of soil for proposed construction.
- Excavation works for the fence foundation.
- Concrete and reinforcement works for the fence foundation and gates
- Installation of the fence

#### NOTE:

1. Test locations should be confirmed by the Contractor based on the actual site condition and planned locations for the structure.
2. The contractor is responsible for any damages to the existing building property during construction. The contractor shall indemnify the respective party against all losses or claims.
3. Contractor shall supply the 'as-built' drawing within 15 days after completion date.
4. All test should be carried out according to geotechnical standards, ASTM or other applicable standards accepted by MWSC. All the testing equipment should be calibrated and arranged by contractor. Perform quality checks on collected data and laboratory testing procedures.
5. Maintain records of all field and laboratory data, including photographs, borehole logs, and test results.
6. Water and electricity are to be arranged by the contractor.
7. All the items on the bills are for supplying and construction unless otherwise specified.
8. All measurements to be checked at site before detail design.
9. The geotechnical report and foundation design must be reviewed and approved by a qualified geotechnical engineer. Provide the final report and design to the client and relevant authorities.
10. Comply with relevant geotechnical testing standards, ASTM or other applicable standards. Follow the project-specific requirements and objectives.

### Summary of evaluation criteria with weights

#### Part - A

#	Criteria	Weighting %
1	Price	70%
2	Duration	30%

#### Part - B

#	Criteria	Capability
3	Resource	Pass/Fail