

BILL OF QUANTITIES
CLASSROOM BLOCK at Adh.Fenfushi School

CLIENT : MINISTRY OF EDUCATION, GOVERNMENT OF MALDIVES

CLASSROOM BLOCK at ADH.FENFUSHI
CLASSROOM BLOCK at Adh.Fenfushi School

DESCRIPTION	AMOUNT	%
Bill №: 01 - PRELIMINARIES		
Bill №: 02 - EXCAVATION AND FILLING		
Bill №: 03 - INSITU CONCRETE WORKS		
Bill №: 04 - MASONRY		
Bill №: 05 - ROOFING		
Bill №: 06 - WINDOWS, SCREENS & LIGHTS		
Bill №: 07 - DOORS, SHUTTERS & HATCHES		
Bill №: 08 - FLOOR, WALL, CEILING, AND ROOF FINISHINGS		
Bill №: 09 - SUSPENDED CEILING		
Bill №: 10 - PAINTING & DECORATIONS		
Bill №: 11 - STAIRS, WALKWAYS AND BALUSTRADES		
Bill №: 12 - MECHANICAL & ELECTRICAL SERVICES		
Bill №: 13 - PLUMBING		
Bill №: 14 - INSULATION, FIRE STOPPING & FIRE PROTECTION		
Bill №: 15- ADDITIONS AND OMMISIONS		
TOTAL AMOUNT		

PREAMBLE NOTES

1.1 Discrepancies

All participants in the Tender exercise are deemed to have read the Specifications and BOQ carefully in conjunction with all the Contract Drawings. Any discrepancies between these documents are to be brought to the attention of the Employer and clarified prior to the closing of the Tender. Should any said discrepancies be discovered at a later date, the decision of the Employer is final and any extra cost due to the contractor as a result of such discrepancies will NOT be entertained whatsoever. The Contractor shall, at all times, exercise with care and professional scrutiny to ensure that there are no discrepancies and/or divergence between Contract Drawings and specifications prior to execution of any portion of the Works on site. The Contractor shall immediately give the Employer a written notice specifying any such discrepancies or divergence should he discovered such issues and the Employer shall issue instructions in regard thereto. The Contractor should exercise due diligence in this matter as a failure and/or negligence in complying with the above stated requirements may result in extra costs. Any extra costs incurred in respect therefore shall be borne solely by the Contractor.

1.2 General Notes

1. The Bill of Quantities shall be read in conjunction with the Instruction to Bidders, General Conditions of Contract, Appendix to bid, Technical Specification and Tender Drawings.
2. The rates and prices tendered in the priced Bill of Quantities shall, except in so far as it is otherwise provided under the Contract, include all constructional plant, labour, supervision, materials, transportation, installation/erection, profit, together with all general risks, liabilities and obligations set out or implied in the Contract.
3. The Tenderer is deemed to have visited the site/s and fully acquainted himself as to the location of each of the items and works to be carried out and to all conditions which may affect the performance of the works, including but not limited to:
 - Access to each of the roads where solid waste transfer process will be carried out, and Access for the dump site.
 - Restrictions applicable to working in proposed area.
 - All safety regulations and employer site safety procedures.
4. A rate or price shall be entered against each item in the Bill of Quantities, whether quantities are stated or not. All quantities given herein shall be deemed to be estimated quantities of the work to be done. Tenderer shall check and verify the quantities before submitting the tender.
5. The whole cost of complying with the provisions of the Contract shall be included in the items provided in the priced Bill of Quantities, and where no items are provided but required for completion of contract works, the cost shall be deemed to be distributed among the rates and prices entered for the related item of work.
6. General directions and descriptions of work and materials are not necessarily repeated or summarized in the Bill of Quantities. The Bidder shall refer to relevant sections of the Contract Document to fully understand the item requirements before entering rates or prices against each item in the Bill of Quantities. No variation is allowed for the given scope of work.
- 7.. Measurement standard applied for calculation of quantities are according to NRM-2, RICS.

CLASSROOM BLOCK at ADH.FENFUSHI
Male, Republic of Maldives

BILL OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
1.0.00	Bill №: 01 - PRELIMINARIES					
1.1.00	GENERAL NOTES <u>Abbreviations</u> m - metre nr - numbers m3 - cubic metres m2 - square metres m - linear metre t - tons inc. - including mm - millimetre SS - stainless steel GI - galvanized iron					
1.2.00	SITE MANAGEMENT COSTS Allow for all on and off site management cost including costs of foreman and assistants, temporary services, telephone, fax, hoardings & similar.	item	1.00			
1.3.00	SIGN BOARD Allow for sign board.	nr	1.00			
1.4.00	CLEAN-UP Allow for clean-up upon completion of works.	item	1.00			
1.5.00	INSURANCE, BONDS, GUARANTEES AND WARRANTIES Insurance as stated in the general conditions.	item	1.00			
1.6.00	SHOP DRAWINGS & AS BUILT DRAWINGS Allow for Shop Drawings during the progress of the project and As-Built Drawings after the completion of the project as stated in the general conditions.	item	1.00			
1.7.00	SAFETY ON SITE Safety on site:- Providing and maintaining adequate safety measures on site for all workers and all authorized visitors on site and protecting adjoining properties and people against falling objects or other with regard to the construction works	item	1.00			
1.6.00	TOTAL OF BILL №: 01 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
2.0.00	Bill №: 02 - EXCAVATION AND FILLING					
2.1.00	GENERAL					
	(a) Rates shall include for: leveling, grading, trimming, compacting to faces of excavation, keep sides plumb, backfilling, consolidating, and disposing surplus soil.					
2.2.00	SITE CLEARING					
2.2.01	Clear the area of site from rubbish and vegetable matters, stumps, roots. Rates shall include for removal of trees and tree stumps	m ²	309.40			
2.3.00	FILLING					
	Rate shall include for: levelling, grading, trimming, compacting and similar					
2.3.01	Compacted earth filling under ground slab	m ²	70.00			
2.4.00	DAMP-PROOF MEMBRANE					
	Rate shall include for: dressing around and sealing to all penetrations,laps and turnups.					
2.4.01	Polythene damp proof membrane (500 gauge)	m ²	70.00			
2.5.00	TOTAL OF BILL №: 02 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
3.0.00	Bill №: 03 - INSITU CONCRETE WORKS					
3.1.00	GENERAL					
	(a) Rates shall include for: placing in position, making good after removal of formwork, mortar touch up to all concrete and casting in all required items; additional concrete required to conform to structural and excavated tolerances					
	(b) Mix ratio for reinforced concrete shall be 1:2:3 and lean concrete shall be 1:2:6.					
	(c) All structural concrete shall be GRADE M25 and lean concrete shall be GRADE M15					
	(d) Rates shall include for: concrete, formwork, reinforcement, cleaning, fabrication, placing, the provision for all necessary temporary fixings and supports including tie wires and chair supports, laps, distribution bars and wastage.					
	(e) Rates shall include for: all necessary boarding, supports, erecting, framing, temporary cambering, cutting, perforations for reinforcing bars, bolts, straps, ties, hangers, pipes and removal of formwork.					
	(f) Rates shall include for: cleaning, fabrication, placing the provision for all necessary temporary fixings and supports including tie wires and chair supports, laps, distribution bars and wastage.					
	(g) All reinforcing bars shall be high strength bars.					
	(h) Slab soffits to be finished fairfaced, use plasteciser and formwork with reducing agent.					
	(i) All exposed & external concrete members shall be casted with masterpel 777 or equivalent water proofing chemical.					
	(j) Rate shall include for applying 2 coats of waterproofing chemical to substructure.(Below ground level).					
3.1.01	Allow for Concrete Testing.	item	1.00			
3.3.00	REINFORCED INSITU CONCRETE					
3.4.00	GROUND FLOOR					
	SLABS					
3.4.01	100 mm thk Concrete Slab on ground	m ³	7.00			
3.4.02	100 mm thk Concrete Slab on ramp	m ³	0.57			
3.5.00	OTHER WORKS					
	Lintel and Sill beams					
3.5.01	150 x 150 mm Beam LT1	item	1.00			
3.5.02	300 x 150 mm Beam LT2	item	1.00			
	FIN					
3.5.03	62 X 150 mm thk Concrete fin GF (Toilet area)	item	1.00			
3.5.04	62 X 150 mm thk Concrete fin 1F (Toilet area and balcony)	item	1.00			
	RC bench					
3.5.05	75 mm thk Concrete Slab for vanity at toilet	item	1.00			
	GROUND WELL					
3.5.06	1000mm Dia Water well as per detailed drawing	item	1.00			
	SEPTIC TANK					
3.5.07	3300x5300x1900mm Septic tank as per detailed rawing	item	1.00			
3.6.00	TOTAL OF BILL №: 03 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
4.0.00	Bill №: 04 - MASONRY					
4.1.00	GENERAL					
	(a) Rates shall include for: cleaning out cavities, forming rebated reveals and pointing and cleaning down to reveals where necessary; fractional size blocks, all necessary machine cutting, cutting or forming chases or edges of floor slabs, cutting or leavingholes and openings as recesses for and building in pipes, conduits, sleeves and similar as required for all trades; leaving surfaces rough or raking out joints for plastering and flashing, bedding frames or plates, building in joists, bearers or similar, temporary supports to openings, templates, reinforcement in walls and for all necessary making good.					
4.2.00	BLOCK WORK					
	Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar. (EXTERNAL WALLS)					
	150 mm thk full height					
4.2.01	GROUND FLOOR	m ²	2.00			
4.2.02	FIRST FLOOR	m ²	2.00			
	150 mm thk full height					
4.2.03	BELOW GROUND LEVEL (RAMP)	m ²	13.50			
	100 mm thk full height					
4.2.04	GROUND FLOOR	m ²	16.14			
4.2.05	FIRST FLOOR	m ²	18.34			
4.3.00	TOTAL OF BILL №: 04 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
5.0.00	Bill №: 05 - ROOFING					
5.1.00	GENERAL					
	(a) Rates shall include for: fair edges, dressing over angel fillets, roof sealant, turning into grooves, all other labours, circular edges, nails, screws and other fixings and laps.					
5.2.00	MAIN ROOF COVERING					
5.2.01	Lysaght roofing sheet to specification	m ²	359.55			
5.2.02	50mm mineral wool insulation with reflective layers on both installed as per suppliers specifications with recommended lap length and air gap tape. Rate shall include for BRC mesh over purlins to support insulation layer.	m ²	359.55			
5.3.00	CAPPING					
5.3.01	Lysaght ridge cap as per roofing sheet suppliers assembly	m	29.40			
5.4.00	GUTTER					
5.4.01	200 x 200 mm Zinc gutter	m	57.00			
5.5.00	DOWN PIPE					
5.5.01	82 mm dia rain water pipes	item	1.00			
5.5.02	82 mm dia rain water outlets	item	1.00			
5.5.03	50 mm dia rain water outlets	item	1.00			
5.6.00	FASCIA					
5.6.01	50 x 200 mm fascia board	m	80.98			
5.7.00	TOTAL OF BILL №: 05 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
6.0.00	Bill №: 06 - WINDOWS, SCREENS & LIGHTS					
6.1.00	GENERAL					
	(a) Rates shall include for locks, latches, closers, push plates, pull handles, bolts, kick plates, hinges and all door & window hardware.					
	(b) Rates shall include for door frames, mullions, transoms, trims, glazing, tinting, timber panels, boardings, framing, lining, fastenings and all fixings.					
	(c) Sizes are given overall outside dimensions of actual doors and windows.					
	(d) Thickness and sizes of glass panels are shown on the Drawings and doors and windows schedule					
	(e) Rates shall include for all painting as specified					
	(f) Rates shall include all items specified in the door schedule and specification.					
	(g) Frames and sashes to be 25-60 micron white powder coated aluminium other wise specified.					
6.2.00	WINDOWS					
	GROUND FLOOR					
6.2.01	1525 x 1300 W1 - Aluminium sliding window with clear glass panel on aluminium frame	nr	6.00			
6.2.02	2450 x 1535 W2 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	6.00			
6.2.03	650 x 785 W3 - Aluminium window with aluminium louvers on aluminium frame	nr	4.00			
6.2.04	3000 x 600 V1 - Aluminium window with aluminium louvers on aluminium frame	nr	7.00			
6.2.05	2975 x 600 V2 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
6.2.06	1875 x 600 V3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00			
6.2.07	2550 x 600 V4 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
	FIRST FLOOR					
6.2.08	1525 x 1300 W1 - Aluminium sliding window with clear glass panel on aluminium frame	nr	6.00			
6.2.09	2450 x 1535 W2 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	6.00			
6.2.10	650 x 785 W3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00			
6.2.11	1200 x 1535 W4 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	1.00			
6.2.12	3000 x 600 V1 - Aluminium window with aluminium louvers on aluminium frame	nr	7.00			
6.2.13	2975 x 600 V2 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
6.2.14	1875 x 600 V3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00			
6.2.15	2550 x 600 V4 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
6.3.00	TOTAL OF BILL №: 06 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
7.0.00	Bill №: 07 - DOORS, SHUTTERS & HATCHES					
7.1.00	GENERAL					
	(a) Rates shall include for locks, latches, closers, push plates, pull handles, bolts, kick plates, hinges and all door & window hardware.					
	(b) Rates shall include for door frames, mullions, transoms, trims, glazing, tinting, timber panels, boardings, framing, lining, fastenings and all fixings.					
	(c) Sizes are given overall outside dimensions of actual doors and windows.					
	(d) Thickness and sizes of glass panels are shown on the Drawings and doors and windows schedule.					
	(e) Rates shall include for all painting as specified					
	(f) Rates shall include all items specified in the door schedule and specification.					
	(g) Frames and sashes to be 25-60 micron white powder coated aluminium other wise specified.					
7.2.00	DOORS					
	GROUND FLOOR					
7.2.01	1000 x 2300 D1 - Aluminium panel door on Aluminium frame with 6mm thk clear glass	nr	5.00			
7.2.02	1000 x 2300 D2 - Aluminium panel door on Aluminium frame with aluminium louvers	nr	3.00			
7.2.03	900 x 2200 D3 - Aluminium panel door on aluminium frame	nr	2.00			
7.2.04	700 x 2000 D4 - Aluminium panel door on aluminium frame	nr	3.00			
7.2.05	1000 x 2300 D5 - Aluminium panel door on Aluminium frame	nr	1.00			
7.2.06	2000 2000 mm G1 Steel Gate	nr	1.00			
	FIRST FLOOR					
7.2.07	1000 x 2300 D1 - Aluminium panel door on Aluminium frame (single swing)	nr	7.00			
7.2.08	1000 x 2300 D2 - Aluminium panel door on Aluminium frame (single swing)	nr	2.00			
7.2.09	900 x 2200 D3 - Aluminium panel door on aluminium frame	nr	2.00			
7.2.10	700 x 2000 D4 - Aluminium panel door on aluminium frame	nr	6.00			
7.3.00	TOTAL OF BILL №: 07 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
8.0.00	Bill №: 08 - FLOOR, WALL, CEILING, AND ROOF FINISHINGS					
8.1.00	GENERAL					
	(a) Rates shall include for: fixing, bedding, grouting, and pointing materials; making good around pipes, sanitary fixtures, and similar; cleaning down and polishing.					
	(b) "Masterseal 588" or equivalent should be applied on top of screeds and walls upto 300mm in all toilets.					
	(c) All external surface of masonry wall should be waterproofed with "Masterseal 588" or equivalent					
8.2.00	PLASTERING					
	20 mm thk cement plaster on external surface as specified on the drawing.					
8.2.01	GROUND FLOOR	m ²	25.00			
8.2.02	FIRST FLOOR	m ²	25.00			
8.3.00	CEMENT SCREED					
	50 mm thk cement screed					
8.3.01	GROUND FLOOR	m ²	207.55			
8.3.02	FIRST FLOOR	m ²	203.04			
	25 mm thk cement screed					
8.3.03	GROUND FLOOR	m ²	78.84			
8.3.04	FIRST FLOOR	m ²	77.14			
8.4.00	FLOOR TILING					
	600 x 600 mm Homogenous Non-slip tiles					
8.4.01	GROUND FLOOR	m ²	214.94			
8.4.02	FIRST FLOOR	m ²	195.93			
	300 x 300 mm Homogenous Non-slip tiles					
8.4.03	GROUND FLOOR	m ²	26.30			
8.4.04	FIRST FLOOR	m ²	31.23			
8.5.00	FLOOR PAINTING					
	Epoxy floor paint					
8.5.01	GROUND FLOOR	m ²	5.82			
8.6.00	WALL TILING					
	300 x 600 mm Homogenous tiles					
8.6.01	GROUND FLOOR	m ²	98.98			
8.6.02	FIRST FLOOR	m ²	132.50			
8.7.00	SKIRTING					
	120-150 mm high Homogeneous tile skirting					
8.7.01	GROUND FLOOR	item	1.00			
8.7.02	FIRST FLOOR	item	1.00			
8.8.00	STEP TILING					
8.8.01	Ground floor to first floor	item	1.00			
8.9.00	SCHOOL NAME AND LOGO					
8.9.01	School Name and Logo in Acrylic board	item	1.00			
8.10.00	TOTAL OF BILL №: 08 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
9.0.00	Bill №: 09 - SUSPENDED CEILING					
9.1.00	GENERAL (a) Rates shall include for: all labour in framing, notching and fitting around projections, pipes, light fittings, hatches, grilles and similar and complete with cleats, packers, wedges and similar and all nails and screws.					
9.2.00	PLASTERBOARD CEILING					
9.2.01	Fixed "Boral" or equivalent plasterboard ceiling system with timber framing FIRST FLOOR	m ²	168.31			
9.2.02	6mm Cement board ceiling on roof eave / gable ceiling / toilet area GROUND FLOOR	m ²	26.30			
9.2.03	FIRST FLOOR	m ²	174.68			
9.3.00	TOTAL OF BILL №: 09 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
10.0.00	Bill №: 10 - PAINTING & DECORATIONS					
10.1.00	GENERAL					
	(a) Rates shall include for: the provision, erection and removal of scaffolding, preparation, wall putty application, rubbing down between coats and similar work, the protection and/or masking floors, fittings and similar work, removing and replacing door & window furniture.					
	(b) All painting work shall be carried in accordance with the Specifications.					
10.2.00	WALL PAINTING					
	Weatherbound paint finish as specified (EXTERNAL SURFACES)					
10.2.01	GROUND FLOOR	m ²	247.03			
10.2.02	FIRST FLOOR	m ²	207.63			
	Emulsion paint finish including putty application on brick walls as specified (INTERNAL SURFACES)					
10.2.03	GROUND FLOOR	m ²	559.75			
10.2.04	FIRST FLOOR	m ²	399.10			
10.3.00	CEILING PAINTING					
	Selected paint finish including putty application on ceiling as specified (CEILING)					
10.3.01	GROUND FLOOR	m ²	234.59			
10.3.02	FIRST FLOOR	m ²	342.99			
10.4.00	TOTAL OF BILL №: 10 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
11.0.00	Bill №: 11 - STAIRS, WALKWAYS AND BALUSTRADES					
11.1.00	GENERAL (a) Rates shall include for: all fabrication work, welding, marking, drilling for bolts incl. those securing timbers, steel plates, bolts, nuts and any type of washer, riveted work, counter sinking and tapping for bolts or machine screws. (b) Rates shall include for fabrication and erection and temporary supports and fixing into position.					
11.2.00	RAMP RAILING 50mm dia (1.5-2mm thk) SS 304 handrail at 900mm height as per drawing					
11.2.01	RAMP	m	9.80			
11.3.00	STAIRCASE RAILING 25 & 50mm dia GI powder coated handrail at 900mm height as per drawing					
11.3.01	GROUND - 1ST FLOOR	m	6.40			
11.4.00	WALKWAY RAILING Rate shall include for removing rusts and applying zinc coating in existing railings					
11.4.01	FIRST FLOOR	item	1.00			
11.5.00	TOTAL OF BILL №: 11 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
12.0.00	Bill №: 12 - MECHANICAL & ELECTRICAL SERVICES					
12.1.00	GENERAL					
	<p>(a) Design, provide and install electrical network for the entire building complete in accordance to standards set by the local governing body STELCO/FENAKA</p> <p>(b) The following items and description and the drawings are given as a guidance as to the nature of the information required to be returned by the contractor. Should they not be appropriate the contractor should provide a similar BOQ using the Additions/Omissions sheets provided at the back of this BOQ.</p> <p>(c) The cost shall include for: screws, nails, bolts, nuts, standard cable fixing or supporting clips, brackets, straps, rivets, plugs and all incidental accessories.</p> <p>(d) Rate shall include for necessary chasings, trenching, conduits, cables, cable trays, fittings and clips, cutting holes and chases in brick work/ block work/ concrete work complete with all necessary accessories such as sockets, connections, cable glands and boxes, hardware clips, soldering and jointing materials etc., for proper installing and laying of cables.</p> <p>(e) Rates for electrical isolators, conduits, fittings, equipment and similar items shall include for: all fixings to various building surfaces.</p> <p>(f) A light fixture is measured as one point; switch end of wire is not included in the quantity.</p> <p>(g) A point wiring for power points is measured (regardless of 1 gang, 2 gang etc) as one point for each socket outlet; other end of wire is not included in the quantity.</p> <p>(h) All under ground cables directly buried in ground/run in trenches to be properly laid and covered with cable tiles/trench covers. Rate for under ground cables shall include for all necessary excavation, sand layers, concrete tiles, warning strips and back filling with approved quality earth properly compacted, hot dipped galvanized brackets for trenches, accessories, etc as applicable.</p> <p>(i) The contractors are requested to refer Conditions of Contract, Special Conditions of Contract, Drawings and Specification and other relevant documents related to this tender prior to pricing of the following items</p> <p>(j) The contractor shall provide a schedule of all builder's work in connection with details of such items as necessary, along with the tender.</p> <p>(k) Rates for materials/ plants/ equipments not approved for duty free facilities to be quoted on duty paid basis.</p> <p>(l) All equipments shall be guaranteed for a period of 12 months from the date of commissioning or date of practical completion of the project which ever later</p> <p>(m) The rate shall include for insurance during handling, rehandling, transport, storage until ready for installation, delivery of equipments up to the point of installation and until handing over.</p> <p>(n) The rates shall include for comprehensive maintenance during defects liability period of 12 months from the date of handing over</p> <p>(o) The tenderer shall submit the following information on the items/equipments quoted for together with the tender.</p> <ol style="list-style-type: none"> a. make b. model No. c. technical data d. country of manufacture e. delivery period f. lead time for manufacturing. g. port of shipping h. CIF value of each item in foreign currency. i. Optional items and their additional cost. (additional cost to be submitted separately) k. Schedule of items to be carried out by others connected to installation of generators/transformers/Electrical panels such as some builders work and electrical connection. l. Details of all special features m. schedule attached to specification. <p>(p) Rate for all electrical panels shall include for supply and installation of all necessary MCCBs, MCBS, EFRs, ELCBs, auxiliary contacts, Voltmeters, ammeters, Digital analyser,kWh meters, indicator lamps, selector switches, copper bus bars, inter locks, aligning and grounding of the panel, inter connectors, internal wiring connections to switch gear,steel channels and necessary hardware fixing insulating materials,all in fully enclosed metal clad panels and distribution boards completed as shown in drawing. They shall comply with the specifications and I.E.E.regulations and be complete to working order to the approval of local authorities.</p> <p>(q) Rate shall include for supply, installation, maintaining, testing and commissioning of the system for power and lighting according to drawings and specifications to working order.</p> <p>(r) All materials, equipment wiring shall conform to local codes, specifications, standards/latest I.E.E. regulations (BS 7671).</p>					
12.2.00	MAIN DISTRIBUTION, SUB DISTRIBUTION AND DISTRIBUTION SYSTEM					
	<u>Main Panel Board and Sub-Distribution Boards (DB)</u>					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
12.2.01	Main Panel Board on Ground floor and sub-Distribution Boards on each floor as shown on the drawing, complete with all incoming and outgoing MCBs, RCCBs, etc any other item required to working order, wall mounted wall mount steel powder coated, IP44 enclouser with neutral link, earth bar and required accessories, all complete as per the specifications & drawings.	nr	1.00			
12.2.02	Main Panel Board	nr	6.00			
12.2.03	Distribution Boards	nr	1.00			
	Internet switch board					
	MAIN / SUB CABLING					
	All under ground cables directly buried in ground/ in the trenches as applicable, to be laid properly and covered with cable tiles, protection tapes, etc for mechanical protection, PVC sleeves may use if required. Rate shall include for all necessary works/accessories such as excavation, sand layers, cable tiles, warning strips and back filling with approved quality earth,properly compacted, to the satisfaction of the Engineer.					
	All above ground cables shall be laid on cable tray/ trucnking /conduits as applicable and covered by tray covers, etc. for mechanical protection. PVC sleeves may use if required. Rate shall include for all necessary works/ accessories such as galvernized brackets, supporting materials, fittings, nails, cable ties, earthing, etc, trays shall be of required sizes, GI powder coated. and shotted. to the satisfaction of Engineer					
	CABLING UP TO MDB/DB					
12.2.04	Feeder cable	item	1.00			
12.2.05	Cabling from main Electrical source to DBs	item	1.00			
12.2.06	Cabling from main internet source to internet switch board	item	1.00			
12.3.00	GENERAL EARTHING					
12.3.01	Allow for the total earthing system inclusive of the necessary cables from all the DBs	item	1.00			
12.4.00	POINT WIRING AND FITTINGS					
	Rate shall include for supply & installation of cable, conduits for point wiring in concealed installations including lights,switches, power outlet,data points,isolators, etc, all as specified in the drawing					
12.4.01	Supply and Installation of 2 x 1C 1.5mm2 PVC/PVC/Cu + 2.5mm2 PVC/Cu earth cable c/w uPVC conduit, junction boxes etc. for lights and switches point wiring	nr	235.00			
12.4.02	Supply and Installation of 2 x 1C 2.5mm2 PVC/PVC/Cu + 2.5mm2 PVC/Cu earth cable c/w uPVC conduit, junction boxes,ethernet cables, RJ45 Connectors, VGA cables etc. for the Socket outlets point wiring	nr	135.00			
12.5.00	LIGHTS,SWITCHES AND SOCKETS					
	Rate shall include supply and installation of following lighting fixtures, socket outlets as specified and detailed, fixed in position including all fixing accessories, supports and connect to power, under following conditions 1. All bathrooms, out door light fixtures shall be IP65 2. All switches & sockets shall be ABB or equivalent brand.					
	LIGHTS AND SWITCHES					
12.5.01	Outdoor wall light 40W (IP65)	nr	33.00			
12.5.02	Mirror light (7W LED light)	nr	7.00			
12.5.03	Recessed Down light 12W LED	nr	18.00			
12.5.04	Ceiling light 18W LED	nr	4.00			
12.5.05	2 x 4' tube light with weather proof opal casing	nr	5.00			
12.5.06	2 x 4' fluorescent light with opal casing	nr	51.00			
12.5.07	Ceiling fan (52" - 54")	nr	24.00			
12.5.08	Light switch (1 G)	nr	19.00			
12.5.09	Light switch (2 G)	nr	19.00			
12.5.10	Light switch (3 G)	nr	1.00			
12.5.11	Light switch (4 G)	nr	18.00			
12.5.12	Light switch (5 G)	nr	3.00			
12.5.13	Exhaust fan	nr	1.00			
12.5.14	Emergency Lights	nr	14.00			
12.5.15	Exit lights	nr	18.00			
	SOCKETS					
12.5.16	13 A twin sockets	nr	62.00			
12.5.17	13 A sockets	nr	26.00			
12.5.18	Flex outlet	nr	5.00			
12.5.19	Twin compute network outlet	nr	6.00			
12.5.20	Data points	nr	6.00			
12.5.21	HDMI,VGA & RAC AV Sockets	nr	6.00			
12.5.22	HDMI,VGA & RAC AV Twin Sockets	nr	6.00			
12.5.23	Speakers with volume controller and paging mic	nr	12.00			
12.5.24	Two gang TV/SAT socket outlet	nr	6.00			
12.6.00	TOTAL OF BILL №: 12 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
13.0.00	Bill №: 13 - PLUMBING					
13.1.00	GENERAL					
	(a) Rates shall include for sockets, running joints, connectors, elbows, junctions, valves, reducers, expansion joints, backnuts and similar, incidental fitting, clips saddles, brackets, straps, hangers, screws, nails and fixing complete, including cutting and forming holes, excavating, laying pipes and backfilling trenches.					
	(b) All pipe work and fittings shall be high pressure PVC.					
	(c) Rates shall include for supply and fixing of all pipes.					
	(d) All sanitary fixtures used shall be of superior quality and approved by the architect/consultant on submission of samples.					
13.2.00	WATER SUPPLY					
	Provide and fix UPVC high pressure pipes including piping, connections, fittings, valves, excavations, ducting, fixing with brackets and leak testing.					
	<u>INTERNAL PLUMBING - FRESH WATER SUPPLY PIPE</u>					
13.2.01	Note: Internal plumbing to all toilets and kitchen including supply and laying of pipes.	item	1.00			
	<u>EXTERNAL PLUMBING</u>					
13.2.02	All pipe works under groundfloor screed/slab to be laid for Waste water, sewage, fresh water and well water connection.	item	1.00			
13.2.03	Waste water and sewage connection from all the toilets including the necessary catch pits and manholes as necessary. Rates shall include for supply and laying of pipes including clean-outs as necessary.	item	1.00			
13.2.04	Water connection to all toilets. Rate shall include for supply and laying of pipes.	item	1.00			
13.3.00	DISCHARGE WORK					
13.3.01	Provide and fix UPVC pipes including vent pipes, vent cowls, cleaning eye, connections, fittings, valves, excavations, ducting, fixing with brackets, connecting to proposed septic tank and leak testing.	item	1.00			
13.4.00	FIXTURES					
	Complete installation, cleaning and testing of:					
13.4.01	Wash basin	nr	11.00			
13.4.02	Wash basin tap	nr	11.00			
13.4.03	Muslim shower with stop valve	nr	9.00			
13.4.04	Soap holder	nr	9.00			
13.4.05	Floor Drain	nr	4.00			
13.4.06	Floor Gully	nr	9.00			
13.4.07	510 x 1110 Face Mirror	nr	7.00			
13.4.08	Water Closet	nr	9.00			
13.4.09	1000 x 600 Counter top with tile finish	nr	1.00			
13.4.10	1875 x 600 Counter top with tile finish	nr	3.00			
13.4.11	Water booster pump	nr	1.00			
13.4.12	Water dispenser	set	2.00			
	<u>DISABLED TOILET</u>					
13.4.13	Wash basin	nr	1.00			
13.4.14	Wash basin tap	nr	1.00			
13.4.15	Muslim shower with stop valve	nr	1.00			
13.4.16	Soap holder	nr	1.00			
13.4.17	510 x 1110 Face Mirror	nr	1.00			
13.4.18	Water Closet	nr	1.00			
13.4.19	SS Grab bars as per detailed drawing	set	1.00			
13.5.00	TOTAL OF BILL №: 15 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
14.0.00	Bill №: 14 - INSULATION, FIRE STOPPING & FIRE PROTECTION					
14.0.00	GENERAL					
	(a) Rates shall include for: cabinet,screws, nails, bolts, nuts, standard cable fixing or supporting clips, brackets, straps, rivets, plugs and all incidental accessories					
	(b) Rates shall include for cable conduits, fittings, equipment and similar items shall include for: all fixings to various building surfaces					
	(c) Rates shall include for all necessary electrical wiring and accessories required for completion					
14.2.00	FIRE EXTINGUISHERS (Confirming to BS EN 3-10)					
14.2.01	Supply and installation of 2Kg CO2 Extinguishers	nr	3.00			
14.2.02	Supply and installation of 9 Lt. water Extinguishers.	nr	3.00			
14.3.00	TOTAL OF BILL №: 14 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
15.0.00	Bill №: 15- ADDITIONS AND OMMISIONS					
15.1.00	<u>ADDITIONS</u>					
15.1.01	Bill №: 01 - PRELIMINARIES					
15.1.02	Bill №: 02 - EXCAVATION AND FILLING					
15.1.03	Bill №: 03 - INSITU CONCRETE WORKS					
15.1.04	Bill №: 04 - MASONRY					
15.1.05	Bill №: 05 - ROOFING					
15.1.06	Bill №: 06 - WINDOWS, SCREENS & LIGHTS					
15.1.07	Bill №: 07 - DOORS, SHUTTERS & HATCHES					
15.1.08	Bill №: 08 - FLOOR, WALL, CEILING, AND ROOF FINISHINGS					
15.1.09	Bill №: 09 - SUSPENDED CEILING					
15.1.10	Bill №: 10 - PAINTING & DECORATIONS					
15.1.11	Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES					
15.1.12	Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES					
15.1.13	Bill №: 14 - PLUMBING					
15.1.14	Bill №: 15 - INSULATION, FIRE STOPPING & FIRE PROTECTION					
	<u>TOTAL</u>					
15.2.00	<u>OMISSIONS</u>					
15.2.01	Bill №: 01 - PRELIMINARIES					
15.2.02	Bill №: 02 - EXCAVATION AND FILLING					
15.2.03	Bill №: 03 - INSITU CONCRETE WORKS					
15.2.04	Bill №: 04 - MASONRY					
15.2.05	Bill №: 05 - STRUCTURAL METAL WORKS					
15.2.06	Bill №: 06 - ROOFING					
15.2.07	Bill №: 07 - WINDOWS, SCREENS & LIGHTS					
15.2.08	Bill №: 08 - DOORS, SHUTTERS & HATCHES					
15.2.09	Bill №: 09 - FLOOR, WALL, CEILING, AND ROOF FINISHINGS					
15.2.10	Bill №: 10 - SUSPENDED CEILING					
15.2.11	Bill №: 11 - PAINTING & DECORATIONS					
15.2.12	Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES					
15.2.13	Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES					
15.2.14	Bill №: 14 - PLUMBING					
15.2.15	Bill №: 15 - INSULATION, FIRE STOPPING & FIRE PROTECTION					
	<u>TOTAL</u>					
16.3.00	TOTAL OF BILL №: 16 - Carried Over To Summary					