

BILL OF QUANTITIES

PROJECT:

Edhuruvehi 3 Flats Renovation 2024

Flats 2-1B, 8-3A, 14-3C

CLIENT:

Ministry of Education / Thauleemee Fund

SUMMARY BILL OF QUANTITIES KITCHEN

#	Bill name	Amount
1	Removal of the existing kitchen sets	MVR 0.00
2	Supply and Installation of Kitchen set	MVR 0.00
3	Supply and installation of Under cabinet ventilation hood	MVR 0.00
4	Supply and installation of Sink Tap and Sink	MVR 0.00
5	Supply and installation of two burner countertop gas stove	MVR 0.00
	TOTAL	MVR 0.00
	GST 8%	MVR 0.00
	AMOUNT	MVR 0.00

SUMMARY BILL OF QUANTITIES

#	Bill name	Amount
1	Hard wood door installation	MVR 0.00
2	Demolition	MVR 0.00
2.1	Demolition of the dry wall partition	MVR 0.00
3	Masonry Works	MVR 0.00
4	Aluminium Toilet door installation	MVR 0.00
5	Replacing Balcony Door	MVR 0.00
6	Painting interior one room apartment	MVR 0.00
7	Painting interior two room apartment	MVR 0.00
8	Painting interior three room apartment	MVR 0.00
9	Fan Installation	MVR 0.00
10	Replacing Wall Tiles	MVR 0.00
11	Replacing Floor Tiles	MVR 0.00
12	Toilet installation	MVR 0.00
13	Muslim shower installation	MVR 0.00
14	Wash basin Installation	MVR 0.00
15	Head shower installation	MVR 0.00
16	Mirror Installation	MVR 0.00
17	Water Leak	MVR 0.00
18	Electrical and others	MVR 0.00
	TOTAL	MVR 0.00
	GST 8%	MVR 0.00
	AMOUNT	MVR 0.00

Total Project Value **MVR 0.00**

BILL OF QUANTITIES 1

#	Bill name	Qty	Unit	Price	Amount
1	Removal of the existing kitchen sets Removal and discarding of the existing kitchen sets. Contractor must see that no damages are done to the property all prevention shall take place on site to protect the property from being damaged while the removal of the existing kitchen set. If any damages are caused it should be rectified by the contractor.	3.00	no.		MVR 0.00
2	Supply and Installation of Kitchen set Installing new kitchen sets with soft-closing hinges, new cabinet knobs, and handles. The surface top will be replaced with granite. Existing electrical sockets will be relocated as needed. All fittings and components will require client approval prior to installation.	3.00	no.		MVR 0.00
3	Supply and installation of Under cabinet ventilation hood Supply and instalation of hood for the kitchen. Needs to be approved from the client before purchase	3.00	no.		MVR 0.00
4	Supply and installation of Sink Tap and Sink Sink tap and a double bowl sink shall be SS coated, sink tap shall be a long neck tap that needs to be approved from the client before purchase and shall be installed and checked for any water leaks. This shall include all needed fittings for the installation.	3.00	no.		MVR 0.00
5	Supply and installation of two burner countertop gas stove Needs to be approved from the client before purchase	3.00	no.		MVR 0.00
TOTAL					MVR 0.00
GST 8%					MVR 0.00
AMONT					MVR 0.00

BILL OF QUANTITIES

#	Bill name	Qty	Unit	Price	Amount
Ministry edhuruvehi flat renovation					
1	<p>Hard wood door installation</p> <p>Existing doors shall be removed by the contractor. Door shall be a solid wood door which has to be hinged on to a solid timber frame with 4 hinge nos. 125 X 30 X 3 stainless steel bearing hinges, providing door stopper, Lever Handle Locks as per samples approved and as per site requirements. Install a door border covering the gap between door frame and the wall. Price shall include the installation of door frame and the door border.</p>	11	no.		MVR 0.00
2	<p>Demolition</p> <p>Demolishing and making a door way into the attached room for access to the toilet from the room. Segregation and disposal of debris in accordance with local regulations and environmental guidelines.</p>	30	sqft		MVR 0.00
2.1	<p>Demolition of the dry wall partition</p> <p>Dismantling and removal of existing dry wall partitions, including all associated framework, fixings, and fastenings. Segregation and disposal of debris in accordance with local regulations and environmental guidelines.</p>	106.25	Sqft		MVR 0.00
3	<p>Masonry Works</p> <p>Closing exiting doorway, by building a brick wall and plastering from both sides. And installation of a sill beam to the new door opening to the room.</p>	30	sqft		MVR 0.00
4	<p>Aluminium Toilet door installation</p> <p>Toilet door shall be made using aluminium cladding and aluminium profiles which has to be hinged 3 hinges nos. 125 X 30 X 3 stainless steel bearing hinges, providing door stopper, door handles and lock. as per samples approved and as per site requirements.</p>	4	no.		MVR 0.00
5	<p>Replacing Balcony Door</p> <p>Existing doors shall be removed by the contractor. Door shall be a solid wood door which has to be hinged on to a solid timber frame with 4 hinge nos. 125 X 30 X 3 stainless steel bearing hinges, providing door stopper, Lever Handle Locks as per samples approved and as per site requirements.</p>	3	no.		MVR 0.00

6	<p>Painting interior one room apartment</p> <p>All loose paint shall be scraped, if needed putty should be applied and sanded for surface preparation. All walls including toilets ceiling and balcony walls also will have to be painted with one code of wall sealer and 2 codes of paint. as per samples approved and as per site requirements.</p>	1	no.		MVR 0.00
7	<p>Painting interior two room apartment</p> <p>All loose paint shall be scraped, if needed putty should be applied and sanded for surface preparation. All walls including toilets ceiling and balcony walls also will have to be painted with one code of wall sealer and 2 codes of paint. as per samples approved and as per site requirements.</p>	1	no.		MVR 0.00
8	<p>Painting interior three room apartment</p> <p>All loose paint shall be scraped, if needed putty should be applied and sanded for surface preparation. All walls including toilets ceiling and balcony walls also will have to be painted with one code of wall sealer and 2 codes of paint. as per samples approved and as per site requirements.</p>	1	no.		MVR 0.00
9	<p>Fan Installation</p> <p>Removal of existing fans and replacing with an Orient Ceiling Fan Quasar Ornamental 1200mm or equivalent fan. Price shall include changing the switch.</p>	11	no.		MVR 0.00
10	<p>Replacing Wall Tiles</p> <p>Replacing wall tiles of the bath and toilet area. Removal of all existing tiles on the wall area of bath and toilet and replacing it with new 1X2 feet tiles which has to be approved by the clint. Tiling will need to be done using a chemical cement equivalent of Dunlop floor and wall adhesive.</p>	564	sqft		MVR 0.00
11	<p>Replacing Floor Tiles</p> <p>Replacing floor tiles of the bath and toilet area. Removal of all existing tiles on the floor area of bath and toilet and replacing it with new 1X1 feet non slip tiles which has to be approved by the clint. Tiling will need to be done using a chemical cement equivalent of Dunlop floor and wall adhesive.</p>	124	sqft		MVR 0.00
12	<p>Toilet installation</p> <p>Removal and discarding of the existing commode toilet and installing of an cotto or equivalent commode toilet. as per samples approved and as per site requirements.</p>	5	no.		MVR 0.00

13	Muslim shower installation Removal and discarding of the existing hand shower and installing of an water tek or equivalent hand shower. as per samples approved and as per site requirements.	5	no.		MVR 0.00
14	Wash basin Installation Removal and discarding of the existing wash basin and installing of an cotto or equivalent wash basin. as per samples approved and as per site requirements.	5	no.		MVR 0.00
15	Head shower installation Removal and discarding of the existing Head shower and installing of an coto or equivalent head shower. As per samples approved and as per site requirements.	5	no.		MVR 0.00
16	Mirror Installation Removal and discarding of the existing mirrors and installing of mirror measuring "19 inches X 26 inches ". As per samples approved and as per site requirements and fixation of the damaged tiles.	5	no.		MVR 0.00
17	Water Leak Identify water leak and fixing of water leak and dampness from walls and ceiling leaks of 2-1B and 14-3C	2	no.		MVR 0.00
18	Electrical and others Removal and discarding of the existing distribution board and installing of new DB. Replacing and fixation of faulty electrical points, sockets and switches.	3	no.		MVR 0.00
TOTAL					MVR 0.00
GST 8%					MVR 0.00
AMOUNT					MVR 0.00