

BILL OF QUANTITIES

PROJECT:

Edhuruvehi Painting & Renovation 2024

CLIENT:

Ministry of Education / Thauleemee Fund

SUMMARY BILL OF QUANTITIES

| # | Bill name | Price | Amount |
|---|------------------------------|-------|----------|
| 1 | Painting Exterior | | MVR 0.00 |
| 2 | Painting Interior | | MVR 0.00 |
| 3 | Crack filling Exterior | | MVR 0.00 |
| 4 | Fixation of damaged railings | | MVR 0.00 |
| | TOTAL | | MVR 0.00 |
| | GST 8% | | MVR 0.00 |
| | AMONT | | MVR 0.00 |

BILL OF QUANTITIES

| # | Bill name | Qty | Unit | Price | Amount |
|---------------|---|-----------|--------|-------|----------|
| 1 | Painting Exterior Painting of exterior walls of edhuruvehi building including the boundary wall. All loose paint should be scraped well before painting the new codes of paint. The price shall be for 1 code of fix primer and 2 codes of exterior paint that which will have to be approved by the client. (Sigma oil base exterior paint or equivalent). | 55,440.00 | Sqr ft | | MVR 0.00 |
| 2 | Painting Interior All loose paint should be scraped well before painting the new codes of paint. The price shall be for 2 codes of Interior paint that which will have to be approved by the client. (Sigma cryl silk paint or equivalent.) Price shall include putty works needed to fill the irregular defects using interior putty. | 16,632.00 | Sqr ft | | MVR 0.00 |
| 3 | Crack filling Exterior All cracks bigger than 2mm has to be grinded before applying the crack fillers. The crack filler has to be approved by the client before purchasing. | 55,440.00 | Sqr ft | | MVR 0.00 |
| 4 | Gutter guard installation PVC snap in guard covers or any other protective guard has to be approved by client and shall be installed on rain gutters on the roofing to help prevent leaves, twigs, and debris from falling into gutters and clogging both gutters and downspouts. | 765.25 | ft | | MVR 0.00 |
| 5 | Relocation of electrical wiring Relocation of main electrical wiring cable of flat 15-1B from stelco panel room the flat's distribution box through the duct. Getting authority from stelco shall be included. | 1.00 | no. | | MVR 0.00 |
| 6 | Fixation of damaged railings The corroded railing posts are to be welded into the ledge with around 2inch welds. This includes removing any existing corrosion. The existing paint on the railings shall be thoroughly scraped off, followed by the application of a coat of red oxide primer. A top layer of paint will be applied to ensure a durable finish. | 45.00 | no. | | MVR 0.00 |
| TOTAL | | | | | MVR 0.00 |
| GST 8% | | | | | MVR 0.00 |
| AMONT | | | | | MVR 0.00 |