



الجمهورية العربية السورية الوزارة العامة للتربية والتعليم

الجمهورية العربية السورية: وزارة التربية والتعليم
الوزارة العامة للتربية والتعليم
دمشق، سورية

الجمهورية العربية السورية: PC-23/SIN/2026/11

الجمهورية العربية السورية: (IUL)23-PD(PMS)/23/2026/79

الجمهورية العربية السورية: 26 أيار 2026

Information Sheet

Project: Fungus / Mould Treatment

Works

Location: Orange Hiya – Third Floor

Total Floor Area (Ceiling): 19,825.34 Sq.ft

Item No	Description	Unit	Qty	Material Rate (MVR)	Labor Rate (MVR)	Total Unit Rate (MVR)	Amount (MVR)
A1	Site inspection, assessment, and method statement submission	Item	1.00			-	-
A2	Provision of scaffolding / mobile tower / lift for 18ft height access	Item	1.00			-	-
A3	Protection of existing floors, partitions, fittings	Item	1.00			-	-
A4	PPE, safety measures, and debris disposal	Item	1.00			-	-
B1	Scraping and removal of mould from steel ceiling surfaces	Sq.ft	19,825.34			-	-
B2	Scraping and cleaning of mould from partition walls (both sides)	Sq.ft	20,160.00			-	-
B3	Mechanical cleaning / wire brushing of steel members	Item	1.00			-	-
B4	Disposal of contaminated materials	Item	1.00			-	-
C1	Application of anti-fungal treatment on ceiling	Sq.ft	19,825.34			-	-
C2	Application of anti-fungal treatment on partition walls	Sq.ft	20,160.00			-	-
D1	Application of anti-condensation coating on steel ceiling	Sq.ft	19,825.34			-	-
D2	Application of anti-fungal paint to partition walls	Sq.ft	20,160.00			-	-
E1	Connection of drain piping for 12 dehumidifiers from third floor to ground floor, including all fittings, supports, and routing	Item	12.00	-	-	-	-
E2	Connection and arrangement of electrical supply points for 12 dehumidifiers using existing sockets (including cable management, extensions if required)	Item	12.00			-	-
Note; A floor plan of Orange Hiya third floor is attached.						Subtotal (MVR)	-
						GST 8%	-
						Total (MVR):	-

