



Ministry of Islamic Affairs and Endowments

Republic of Maldives

Scope of work

700 Pax Islamic Centre

Issued on: June 2026

Issued By:

Infrastructure Development Section

Ministry of Islamic Affairs & Endowments



Quantity Surveying & Specifications

- Bill of Materials (BOM): A detailed inventory of raw materials, manufacturing standards, and components.
- Bill of Quantities (BOQ): A structured BOQ for tendering, commercial evaluation, and construction billing.
- Technical Specifications: Comprehensive material datasheets and execution methodologies for civil, structural, finishes, and MEP works.

Visualizations & Renderings

- High-fidelity exterior 3D renderings showcasing all building elevations.
- Interior 3D visualizations highlighting the Main Prayer Hall, Multipurpose Hall, and entrance lobbies.

Regulatory Compliance & Certifications

- Complete architectural drawing sets verified and stamped by an Accredited Architectural Checker registered in the Maldives.
- Complete structural drawing sets and calculation sheets verified and stamped by an Accredited Structural Engineer.
- All the required Approvals from regulatory authorities as necessary

Project Considerations & Constraints

Cultural Heritage & Context

The architectural design of the Islamic Centre must harmoniously blend traditional Maldivian craftsmanship and cultural heritage with contemporary Islamic architecture.

Site Planning & Infrastructure

- Qibla Orientation: Main Prayer Hall must be aligned precisely with the Qibla.
- Access & Security: Provision of safe, separate pedestrian and vehicular access.
- Inclusivity: A dedicated, secure, and private entrance path must be provided for female worshippers.
- Parking Infrastructure: Adequate parking spaces sized appropriately for daily staff and

peak Friday congregation loads if applicable.

- Circulation: Optimized site layout ensuring efficient, unbottle necked movement during high-volume periods (Friday prayers and Eid congregations).
- Landscaping: Incorporation of local flora, green spaces, and functional outdoor shaded structures.

Space Allocation & Capacity Planning

- Total Congregation Capacity: Accommodations for up to 700 worshippers simultaneously.
- Demographic Allocation: A minimum of 25% of the total capacity must be dedicated to female worshippers, ensuring complete privacy and security.
- Spatial Density: Spatial allocation shall be calculated at an industry standard of 6 sq. ft. per person (1.5' x 4' per prayer mat space).

Functional Space	Capacity / Allocation Target	Access Requirements
Main Prayer Hall	700 Worshippers Total	Structural columns minimized to prevent row obstruction; full universal access
Multipurpose Hall	300 Persons	Accessible from the public zone; dual interior/exterior storage access
Classrooms (4x)	15 Students per room	Accessible from the educational/general zone
Library	25 Students	Quiet zone integrated with digital infrastructure
Hifz Test Room	3 Panel Examiners + 1 Student	Sound-isolated administrative area
Admin Office	1 Executive + 5 Staff Members	Secure zone with integrated network/IT backbone

Structural Roofing & Geometries

- Roof Engineering: Roof structures must be engineered to sustain dead loads, wind loads, and dead loads introduced by the Solar PV array installation. Ramps or ladders must provide safe roof maintenance access.
- Central Dome: The central dome must have a minimum diameter of 8.5 meters and be visually prominent across all exterior structural elevations.

Minaret Engineering

- Proportions: The minaret height must be proportional to the main building mass, standing no less than 1.3 times the height of the main mosque roofline.
- Acoustics & Lighting: Horn speakers must be omnidirectionally arrayed to optimize Adhan coverage. The minaret shell must feature prominent structural uplighting for nighttime visibility.
- Safety: Integrated internal or structural cat-ladder with safety cages to facilitate high-level access.

Submission Deliverables

The selected consultant is contractually obligated to submit the following deliverables at specific milestones:

Phase 1: Concept Stage

- Design statement
- Site layout plan
- Concept floor plans and elevation
- Preliminary 3D visualization

Phase 2: Detailed design stage

- Fully coordinated architectural, structural & MEP drawings
- Engineering calculations (Structural, BTU, Lumens)
- Complete Tender Package (BOM, BOQ, Technical Specifications)

Phase 3: Final approved submissions

- Regulatory approved & Stamped sets (Architectural & Structural)
- Final Photo – Realistic 3D Renderings (interior & Exterior)
- Digital Handover (Editable CAD/BIM/Word files + Master Vector PDFs)

General & Legal Framework

1. **Statutory Compliance:** All designs, engineering assumptions, and construction methodologies shall comply strictly with the applicable laws, building codes, and structural regulations of the Republic of Maldives.
2. **Ministry Coordination:** The consultant shall maintain regular communication with the Infrastructure Development Section of the Ministry throughout the design life cycle.
3. **Change Management:** Any significant deviations from the approved SOW or concept brief are strictly subject to formal approval by the Ministry.
4. **Iterative Refinements:** The consultant shall incorporate all corrective review comments, structural adjustments, and layout revisions requested by the Ministry during the design development stage at no additional cost.
5. **Interdisciplinary Coordination:** The consultant bears sole responsibility for performing rigorous clash-detection across architectural, structural, and MEP fields prior to the final submission of tender documents.
6. **Intellectual Property:** All calculations, drawings, blueprints, digital models (BIM/CAD), specifications, and visualizations developed during this contract shall become the sole property of the Ministry of Islamic Affairs and Endowments upon project completion.

