



ಕರ್ನಾಟಕ ಸರ್ಕಾರ
ಸರ್ಕಾರಿ ಕೆಲಸ

Project: Maduvvaree Welcome Gate

Bill of Quantities

NO		DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	FOUNDATION					
1.1	LEAN CONCRETE					
		OPC CEMENT 50KG BAG	4.00	bags		
		COARSE SAND (50KG BAGS)	12.00	bags		
		COARSE AGGREGATE (50KG BAGS)	24.00	bags		
1.2	FOOTING					
		OPC CEMENT 50KG BAG	23.00	bags		
		COARSE SAND (50KG BAGS)	46.00	bags		
		COARSE AGGREGATE (50KG BAGS)	69.00	bags		
		PLYWOOD 12MM X 4FT X 8FT	4.00	nos		
		TIMBER 2INCH X 2INCH X 20FT	6.00	nos		
		DEFORMED STEEL BAR 12MM X 6MTR	20.00	nos		
		BINDING WIRE 18G	1.00	kg		
1.3	TIE BEAM					
		OPC CEMENT 50KG BAG	11.00	bags		
		COARSE SAND (50KG BAGS)	22.00	bags		
		COARSE AGGREGATE (50KG BAGS)	33.00	bags		
		PLYWOOD 12MM X 4FT X 8FT	4.00	nos		
		TIMBER 2INCH X 2INCH X 20FT	6.00	nos		
		DEFORMED STEEL BAR 12MM X 6MTR	11.00	nos		
		DEFORMED STEEL BAR 6MM X 6MTR	17.00	nos		
		BINDING WIRE 18G	1.00	kg		
2	COLUMN					
		OPC CEMENT 50KG BAG	29.00	bags		
		COARSE SAND (50KG BAGS)	58.00	bags		

		COARSE AGGREGATE (50KG BAGS)	87.00	bags		
		PLYWOOD 12MM X 4FT X 8FT	17.00	nos		
		TIMBER 2INCH X 2INCH X 20FT	26.00	nos		
		DEFORMED STEEL BAR 16MM X 6MTR	35.00	nos		
		DEFORMED STEEL BAR 12MM X 6MTR	35.00	nos		
		DEFORMED STEEL BAR 6MM X 6MTR	47.00	nos		
		BINDING WIRE 18G	6.00	kg		
3	BEAMS					
		OPC CEMENT 50KG BAG	13.00	bags		
		COARSE SAND (50KG BAGS)	26.00	bags		
		COARSE AGGREGATE (50KG BAGS)	39.00	bags		
		PLYWOOD 12MM X 4FT X 8FT	5.00	nos		
		TIMBER 2INCH X 2INCH X 20FT	8.00	nos		
		DEFORMED STEEL BAR 12MM X 6MTR	15.00	nos		
		DEFORMED STEEL BAR 6MM X 6MTR	21.00	nos		
		BINDING WIRE 18G	2.00	kg		
4	TRUSS					
		50 X 50 X 2.2MM GI RHS	13.00	nos		
		50 X 100 X 2.5MM GI RHS	2.00	nos		
		50 X 50 X 2MM GI RHS	16.00	nos		
		50 X 100 X 2MM GI RHS	16.00	nos		
		50 X 100 X 4.5MM GI RHS	7.00	nos		
		75 x 75 x 4.5MM Angle	3.00	nos		
		M12 ANCHOR BOLT	48.00	nos		
5	CLADDING					
		ALUMINUM CLADDING 4MM	54.00	sqm		
6	CONTROL ROOMS					
		SOLID BLOCK 6" (12" X 6" X 6")	1741.00	nos		
		OPC CEMENT 50KG BAG	18.00	bags		
		COARSE SAND (50KG BAGS)	72.00	bags		
		OPC CEMENT 50KG BAG	32.00	bags		
		FINE SAND 192.00	70.00	bags		

		PUTTY - SHEETROCK ALL PURPOSE JOINT COMPOUND	79.00	kg		
		WALL SEALER - NIPPON OIL BASED	32.00	ltrs		
		PAINT - NIPPON WEATHERPROOF	32.00	ltrs		
		GYPSUM BOARD 9MM	3.00	nos		
		DOOR 750 X 2100 FIBRE BOARD + PANEL	2.00	nos		
7	ELECTRICAL WORKS					
		CEILING LIGHT	10.00	nos		
		WEATHERPROOF WALL LIGHT	2.00	nos		
		ONE WAY SWITCH	8.00	nos		
		D BOARD	1.00	nos		
		STRIP LIGHT	34.00	m		
		OUTDOOR LED PANEL SCREEN	115.00	sqft		
Labour Cost						
		Labouor Cost				
		Total Amount, Including GST				