

BILL OF QUANTITIES

PROJECT: Monument at H.Dh. Nalhivaran

Duration: 60 days

No.	Description	Qty	Unit
GROUND WORKS			
1	Excavation, price to include compaction and backfilling upon completion	5.12	m ³
CONCRETE WORKS			
Foundation level			
2	Lean concrete @1:3:6	1.12	m ³
	Cement	5	Bag
	Sand	15	Bag
	Aggregate	30	Bag
3	TB	5.13	m ³
	Cement	42	Bag
	Sand	84	Bag
	Aggregate	126	Bag
	12mm deformed bar	52	Bars
	6mm mild steel bar	72	Bars
	12mm plywood	18	no.s
	50mm x 50mm timber runner	1270	ft
	Binding wire	60	Kg
	Wire nail	10	Kg
	4" wood screw	420	no.s
4	Footing pad (5 no.s) (Light posts / flag post)	0.2	m ³
	Cement	2	Bag
	Sand	4	Bag
	Aggregate	6	Bag
	10mm deformed bar	2	Bars
	12mm plywood	2	no.s
	50mm x 50mm timber runner	20	ft
	Binding wire	10	Kg
	Wire nail	1	Kg
	4" wood screw	30	no.s
5	Footing pad (4 no.s) (bench shade)	0.97	m ³
	Cement	8	Bag
	Sand	16	Bag
	Aggregate	24	Bag
	10mm deformed bar	8	Bars
	12mm plywood	2	no.s
	50mm x 50mm timber runner	120	ft

	Binding wire	20	Kg
	Wire nail	2	Kg
	4" wood screw	30	no.s
No.	Description	Qty	Unit
6	Island concept ground slab	7.74	m ³
	Cement	62	Bag
	Sand	124	Bag
	Aggregate	186	Bag
	6mm mild steel bar	115	Bars
	12mm plywood	4	no.s
	50mm x 50mm timber runner	30	ft
	Binding wire	30	Kg
	Wire nail	5	Kg
7	Letter base	1.69	m ³
	Cement	14	Bag
	Sand	28	Bag
	Aggregate	42	Bag
	10mm deformed bar	96	Bars
	12mm plywood	8	no.s
	50mm x 50mm timber runner	480	ft
	Binding wire	30	Kg
	Wire nail	5	Kg
MASONRY AND PLASTERING			
8	Masonry work	57.65	m ²
	Blocks as per design	645	no.s
	Cement	8	Bag
	Sand	40	Bag
FLOORING			
9	Paving blocks	835	no.s
10	Outdoor carpet	115	m ²
WOODWORKS / FIBREGLASS WORKS			
11	Fibre coated letters, inclusive of timber frame, plywood covering, proper anchorage to concrete base and fibreglass coating	1	Ls
METAL WORKS			
12	Flagpost	1	LS

13	Bench shade as proposed, inclusive of GI frame and canvas covering	4	No.s
PAINTING WORKS			
14	Boundary wall	57.6	m ²
	Wall sealer	30	Ltrs
	Paint	60	Ltrs
No.	Description	Qty	Unit
15	Painting work on fibreglass letters	12.72	m ²
	Primer	20	Ltrs
	Texture	60	Ltrs
	Enamel paint	40	Ltrs
ELECTRICAL WORKS			
Ground floor			
16	Main connection to service provider	1	no.s
	Distribution Board	1	no.s
	Earth rod	1	no.s
	Outdoor light post	4	no.s
	Weatherproof LED spotlight	14	no.s

SUMMARY	
GROUND WORKS	-
CONCRETE WORKS	-
MASONRY AND PLASTERING	-
FLOORING	-
WOOD WORKS	-
METAL WORKS	-
PAINTING WORKS	-
ELECTRICAL WORKS	-
TOTAL	-