MWSC

ދާދި ވޮޅަށް ފަސްވެ ކަނޑައެޅުނު ގުދަނެއް ހިންގުމަށް

Construction of Foam Pouring Pump System Building at Hdh. Kulhudhuffushi

Qualification of Bidders:

The bid document shall comprise the following information in the given format and order, which MWSC shall use to determine whether the Bidder possesses relevant experience, technical capacity to undertake the project works and to complete successfully in accordance to the bid. Any bid did not accompanied by the following in the given **format and order** shall be rejected by the Employer as non-responsive.

- Bid form. Must be filled stamped and signed. Amount stated in the bid document should be exclusive of GST and should tally with the amount stated in the BOQ.
- Form – Non-Collusion & Related Party Declaration
- Bid Security
- MIRA tax clearance (within 06 months). Must be clear.
- MNPHI Contractors Registration Certificate
- Business Registration Certificate at Economic Ministry
- Company Business Information Sheet (Economic Ministry), Generated within 1 month prior to the Bid submission deadline
- GST Registration
- Priced BOQ. Must be filled and complete. BOQ should not be altered. Bidder's rates should not be more than two decimals.
- Work schedule. Should tally with the duration stated in Bid form
- Site Organization chart
- Resource allocation proposed for the project in the given format "Resource allocation plan" under Section II - Sample Tendering Forms
    - Bidders shall have the following key minimum key personnel's.
        - Project Manager with minimum Diploma qualification.
        - Draftsmen – Diploma or 2 Years' Experience in AutoCAD Drafting
        - Site supervisor with Diploma in building technology related program having one-year experience or Site Supervisor having field experience of minimum 2 years
- Experience – Part 1 list of Similar Projects completed over last five years in the given format "Form of Experience" under Section II - Sample Tendering Forms
- Experience – Part 2 list of Ongoing MWSC Projects in the given format "Form of Experience" under Section II - Sample Tendering Forms. (Applicable for bidders with ongoing contract commitments with MWSC)

Scope of Works

1. Location of the Works

The site for the works proposed under this contract is in the Island of **Kulhudhuffushi City.**

2. Description of the Works

The contract work constitutes the following:

1. **Preliminaries**
   - Mobilization and demobilization
   - Site management, safety arrangements, and temporary facilities
   - General site cleaning throughout the project
2. **Groundworks**
   - Site clearing and disposal of surplus materials
   - Excavation for tie beams, including shoring, leveling, backfilling, and compaction
3. **Concrete Works**
   - Lean concrete, reinforced concrete works for tie beams, columns, and ground slab
   - Formwork, reinforcement, concrete placing, curing, and testing
4. **Masonry & Plastering**
   - Construction of 100mm block masonry boundary wall with concrete columns
   - 20mm plastering to both sides of walls and exposed concrete surfaces
5. **Metal Works**
   - Fabrication and installation of GI CHS columns, roof framing, and wall framing
   - Painting and protective coatings as specified
6. **Doors & Windows**
   - Supply and installation of door (D01) and windows/louvres (W01) with all necessary hardware
7. **Painting & Finishes**
   - Surface preparation and two coats of emulsion paint to interior/exterior walls and fiber board
8. **Roofing & Cladding**
   - Supply and installation of Colorbond roofing sheets, gutters, fascia, and downpipe
   - Exterior Colorbond cladding with GI supports and interior cement fiber board cladding
9. **Electrical Works**
   - Main cable installation from facility panel room
   - Distribution board, lighting points, high-bay LED lights, switches, and sockets

- Wiring, conduits, accessories, and testing

10. Plumbing Works

- Installation of uPVC water supply lines, pump connection, and tap point
- Testing and connection to existing water line

11. Handover

- Testing and commissioning of all systems
- Final cleaning and submission of as-built documents

NOTE:

1. The contractor is responsible for any damage to the existing building property during construction. The contractor shall indemnify the respective party against all losses or claims. All measures required to prevent damages to panels should be taken.
2. Water and electricity should be arranged by the contractor at their own cost.
3. All tests should be carried out according to specification if any. All the testing equipment should be arranged by the contractor.
4. All measurements are to be checked at the site before detail design and fabrication.
5. Approval for all the materials shall be taken from MWSC before commencing any work
6. Upon completion, provide as-built drawings and documentation to the project engineer within 14 days.

Summary of evaluation criteria with weights

Part - A

#	Criteria	Weighting %
1	Price	70%
2	Duration	30%

Part - B

#	Criteria	Capability
3	Resource	Pass/Fail
4	Experience	Pass/Fail