Report: 141/001

## 100 Football pitch Project



Football Ground Thaa. Madifushi
Site visit report – supporting information

Date of visit	6 <sup>th</sup> March 2021					
Site address	Madifushi Football Ground (Sports Arena)					
Weather Condition during site visit	Hot dry and sunny					
Officials present during site visit	Council President, Sports councilor					
Local Contact details	Island:	Thaa. Madifushi				
	Contact name:	Iznadh				
	Designation	Council Director				
	Address:					
	Tel:					
	e-mail					
	Fax:					

Scope of the Project	Design and construction of full-size football Artificial turf pitch							
	Category of pitch requiremen	t	FIFA Recommend	ed				
	Level of competition and active requirement	vities &	National Level					
Proposed usage	Level of play		National Level	l .				
	Intensity of play per week / ye	ear	36 hrs /week					
Field orientation	North / South							
Proposed filed dimensions	EW + EE		1					
		Length		Width	Width			
	Field size	105m		68m				
	Run – off area	North	South	West	East			
		3m	3m	2.5m	2.5m			
	Total Green area (synthetic) 111m x 73m		73m					
Spectator Area	No Existing facility	1						
Fencing	No Existing facility/ Structure	No Existing facility/ Structure (new reclaimed land)						

<del>-</del>	South / East of the island; 5 trail holes were made. Noticed +/- 300 mm of reclaim with coral and up layer needs removing of the grass patches and scrap. Backfilling need sieving and use the small
Groundwater evidence	Location is the heart of the island, according to the represents on site water is likely more than 3 feet deep
Topography	Old surface with patches of grass and uneven terrain.
Drain Outlet	No public sewerage pipe or system in place, drainage must be designed with enough soak pits to flush excess water.
Existing Service & sports lighting	No existing service area
Disposal of Spoil	All removed spoil sand needs to be removed in accordance with council instruction.

Trial Holes



## Site Photo



Construction Detail							
Site access	Proposed site is accessible from all 4 sides, however distance from harbor could create some degree of difficulty for transportation of materials						
Site Compound	It is located on south west side on newly reclaimed area, no infrastructure beside a waste land on the west of the plot, transporting materials may course some degree of difficulty						
Best time of the year to construct	No significant time of the year						
Working restriction	No						
Drainage	Subbase will be designed with gutter and soak pit to drain the excess water.						
Provision for new functional extension	Sufficiently large area for the development of Football ground and other sports courts						
Maintenance equipment requirement	TBC						
Sports equipment	TBC						

								leration						

- No benchmark identified, for the groundbreaking and defining footprint of the football pitch, a thorough survey is important.
- Waste management area next to the football pitch plot.
- Power supply or electrical and water outlet available

## PROPOSED INDICATIVE LAYOUT

wide strip of land from the allocated for other purpose on the East side of the football pitch area.

