

Network Cabling & Installation with Power points:

1. Network Installation
2. Since Faceplates for termination should be used, PATCH CORDS long enough to reach the workstation shall be included in the quotation.
3. All cables are required to travel through casings & floor casing is required for floor paths.
4. Dual-gang and Single-gang power sockets with socket box are required along with the proper electrical wiring to workstations.
5. A 48-Port Network Switch and a 24-Port Network Switch that supports PoE shall be supplied by the vendor.
6. A 12U rack or Server Rack compatible to accommodate the network equipment shall be included in the Bid.
7. Cable accessories, PVC Casings, RJ45 Jacks, Power terminations must be included in the Bid.
8. Wireless Access Point with 2.4Ghz & 5Ghz suitable for Office Environment
9. Install NAS with UPS and create file servers as to the need of BCM.
10. Install Firewall as to the need of BCM.
11. Suggested Floor casings 20 mm x 8 mm or supplier to quote after inspection.
12. Suggested PVC Casing 24 mm x 13 mm (6.6ft) or supplier to quote after inspection.