

BILL OF QUANTITIES
MFMC OFFICE PARTITIONS AND INTERIOR WORKS AT, H. SUEZ 2ND FLOOR

No	Particulars	Unit	Qty	Rate (MVR)	Amount (MVR)
1	Removing of existing partitions	LS			0
2	PARTITION 'A' Supplying and installation of ceiling height aluminium framed, 8mm thick clear glass (partly frosted) with swing doors as shown the drawings. All complete as per clients approval.	No	1		0
3	PARTITION 'B' Supplying and installation of ceiling height aluminium framed, 8mm thick clear glass (partly frosted) with sliding door and swing door as shown the drawings. All complete as per clients approval.	No	1		0
4	PARTITION 'C' Supplying and installation of door height aluminium framed, 8mm thick clear glass (partly frosted) with swing door as shown the drawings. All complete as per clients approval.	No	1		0
5	PRAYER ROOM PARTITIONS Supplying and installation of door height aluminium framed, 8mm thick clear glass (partly frosted) with sliding door as shown the drawings. All complete as per clients approval.	No	1		0
6	TYPICAL PARTITIONS Supplying and installation of ceiling height aluminium framed, 8mm thick clear glass (partly frosted) partition as shown the drawings. All complete as per clients approval.				
	6a. Partition P1, length 3875mm	No	1		0
	6b. Partition P2, length 3175mm	No	1		0
	6c. Partition P3, length 3900mm	No	1		0
	6d. Partition P4, length 5625mm	No	2		0
7	PANTRY CABINET Providing and fixing of pantry cabinet with SS sink as shown in the drawings, include connecting to fresh water and drainage. The work is to be complete with all labour and material as per drawing and including all the hardware required.	No	1		0
8	FLOORING Supplying and installation of complete laminate flooring with matching skirting (oak light grey) of approved make in the areas shown in the drawings .	m ²	172		0
9	PAINTING				

	Supply and apply 2 coats of Nippon or equivalent emulsion paint on all interior walls (including all column surfaces)	LS			0
10	RO SYSTEM Supplying and installation of full cover RO system (7 stage) inside the pantry cabinet (under the sink compartment).	No	1		0
SUB TOTAL					0
GST 6%					0
TOTAL					0