


1. STEFANY CHANNESIAN, CLERK OF THE TOWN
OF MEDWAY, RECEIVED AND RECORDED FROM
THE PLANNING BOARD COVENANT APPROVAL
OF THIS PLAN ON July 7, 2021 AND NO
APPEAL WAS TAKEN FOR TWENTY DAYS NEXT
AFTER RECEIPT AND RECORDING OF SAME.

Stefany Channe
TOWN CLERK

10/12/2021
DATE



MEDWAY PLANNING BOARD

afkod.
But J. H. K.
Richard J. Dittler

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

LEGAL NOTES

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED AS A GUIDE TO EXCAVATION. THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY BE ENCOUNTERED BY CONTRACTORS (IN ACCORDANCE WITH THE MANUAL, CHAPTER 82, SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT (1888)DIG-SAFE(7233).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY
EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS,
RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY
BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT

NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA. 02053

**SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS**

COVER SHEET

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT
	AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS



SHEET 1 OF 14	JOB NO. F3519
------------------	---------------

-
- VICINITY MAP**
- SCALE: 1" = 500'

WAIVERS GRANTED


ON JUNE 22, 2021 THE BOARD VOTED TO APPROVE WAIVERS FROM THE FOLLOWING PROVISIONS OF THE RULES AND REGULATIONS FOR THE SUBMISSION AND APPROVAL OF SITE PLANS, AS AMENDED OCTOBER 8, 2019.

1. SECTION 204-5 B SITE CONTEXT SHEET
2. SECTION 204-3 F WRITTEN DEVELOPMENT IMPACT STATEMENT.
3. SECTION 204-5 D.7 UTILITIES PLAN
4. SECTION 204-5 D.8 LANDSCAPE PLAN
5. SECTION 207-9 A.7 PEDESTRIAN AND BICYCLE ACCESS AND SIDEWALKS
6. SECTION 207-17 SOLID WASTE REMOVAL
7. SECTION 207-19 LANDSCAPING. B. LANDSCAPE BUFFERS (2)
8. SECTION 207-19 LANDSCAPING. C. PARKING AREAS (1a)
9. SECTION 207-19 LANDSCAPING. H.


INDEX

1. COVER SHEET
2. ABUTTERS FOR 300FT.
3. EXISTING CONDITIONS
4. GENERAL NOTES
5. PROPOSED LAYOUT
6. LIMIT OF CLEARING/EROSION CONTROL
7. PROPOSED GRADING AND UTILITIES
8. PROPOSED BRIDGE DETAILS
9. PROPOSED BRIDGE DESIGN--INTENTIONALLY
LEFT BLANK-- SEE PLAN SET BY COLLINS
ENGINEERS, INC**
10. PHOTOMETRIC PLAN
11. LANDSCAPING PLAN
12. REMEDIATION PLAN
- 13-14 CONSTRUCTION DETAILS

**ADDITIONAL PLAN SETS BY COLLINS ENGINEERS, INC.
BRIDGE DESIGN PLANS ENTITLED
'MEDWAY MILL BRIDGE WIDENING PROJECT'
SHEETS 01-08



- ABUTTERS**
- 0 COTTAGE ST. EVERGREEN CEMETERY ASSOC. MAP 48 PARCEL 68
1 CHOATE PARK RD. TOWN OF MEDWAY MAP 39 PARCEL 74
- 32 LINCOLN ST. RICHARD BRIGGS MAP 48 PARCEL 85
34 LINCOLN ST. LAURIE MARCINKIEWICZ MAP 48 PARCEL 89
35 LINCOLN ST. MICHAEL & ELIZABETH HEIDEN MAP 48 PARCEL 109
36 LINCOLN ST. JOHN & STACEY CLOUTIER MAP 48 PARCEL 90
37 LINCOLN ST. STEPHEN & KERI PATTERSON MAP 48 PARCEL 108
39 LINCOLN ST. MICHAEL MARRAFFINO TRUSTEE MAP 48 PARCEL 107
40 LINCOLN ST. JAMES COAKLEY MAP 48 PARCEL 91
41 LINCOLN ST. JENNIFER & HANS MORRISON MAP 48 PARCEL 106
42 LINCOLN ST. CALVIN & KAREN WHITLA MAP 48 PARCEL 93
43 LINCOLN ST. KRISTY HARGREAVES & MICHAEL CAMPAGNA MAP 48 PARCEL 105
44 LINCOLN ST. CATHERINE SANDOZ MAP 48 PARCEL 94
45 LINCOLN ST. FEDERICO VASQUEZ MAP 48 PARCEL 104
- 148 MAIN ST. UNIT A TAREK CHEBAKLO MAP 48 PARCEL C-A
148 MAIN ST. UNIT B ARTHUR PRUTSALIS MAP 48 PARCEL 9 C-B
145 MAIN ST. EARLY CAPITAL LLC MAP 48 PARCEL 22
149 MAIN ST. EARLY CAPITAL LLC MAP 48 PARCEL 21
151 MAIN ST. JOHN & CHRISTINE EARLY MAP 48 PARCEL 20
153 MAIN ST. JOHN & CHRISTINE EARLY MAP 48 PARCEL 19
155 MAIN ST- DAVID AND TARA WERLICH MAP 48 PARCEL 99
157 MAIN ST- 157 MAIN ST. REALTY TRUST MAP 48 PARCEL 98
158 MAIN ST- WOMACK FAMILY FUNDING MAP 48 PARCEL 2
159 MAIN ST- PAUL & KATHLEEN YORKIS MAP 48 PARCEL 97
160 MAIN ST- SHIRLEY MCDANIEL MAP 48 PARCEL 1
164 MAIN ST. FASLAND LLC MAP 48 PARCEL 114
167 MAIN ST. JOHN & CHARLENE KAIRIT MAP 48 PARCEL 96
168 MAIN ST. RICHARD & KRYSTIN FRASER MAP 48 PARCEL 115
169 MAIN ST. I O O F TRUST MAP 48 PARCEL 95
170 MAIN ST. UNIT A ARTHUR COWAN MAP 48 PARCEL 116- CA
170 MAIN ST. UNIT B RICHARD HUFFAM & MARK DENOMMEE MAP 48 PARCEL 116- CB
171 MAIN ST. JOSE & DAMARYS CAICEDO MAP 48 PARCEL 103
172 MAIN ST. FRANCIS & MARGARET YERED MAP 48 PARCEL 117
173 MAIN ST. STEVEN LINNELL MAP 48 PARCEL 102
174-A MAIN ST. PAUL CHELMAN & ROSE COTE MAP 47 PARCEL 35-A
174-B MAIN ST. MICHAEL OLIVAL MAP 47 PARCEL 35-B
175 MAIN ST. CHERYL ROSENBERG TRUSTEE 1 MAP 48 PARCEL 101
177 MAIN ST. ERIC & TANYA BOUWMAN MAP 48 PARCEL 100
179 MAIN ST. VLADIMIR & SUZANNE ATEYZEK MAP 47 PARCEL 43
- 14 MECHANIC ST. WILLIAM & BETTYE REARDON MAP 48 PARCEL 112
- 26 NORFOLK AVE. CHRISTOPHER & KRISTIN BRODEUR MAP 48 PARCEL 80
29 NORFOLK AVE. PETER & BRENDA LEE CHAPIN MAP 48 PARCEL 84
30 NORFOLK AVE. JENNIFER & JOHN DIGIACOMO MAP 48 PARCEL 82
31 NORFOLK AVE. THOMAS & CLAUDETTE BANNON MAP 48 PARCEL 83
- 0 OAK ST. TOWN OF MEDWAY MAP 39 PARCEL 74-1
- 1 WINTHROP ST. LINDA S. RUSSO REVOCABLE TRUST MAP 48 PARCEL 3



APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD
[Signature]
Richard J. Distefano

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

LEGAL NOTES

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED APPROXIMATE. DURING EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY, COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT 1(888)DIG-SAFE(7233).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA
DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT

NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA 02053

**SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS**


ABUTTERS FOR 300FT.

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS

Guerriere & Halnon, Inc.
ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com

THE EXISTING CONDITIONS TOPOGRAPHICAL SURVEY AND BOUNDARY SHOWN HEREIN WAS OBTAINED FROM REED LAND SURVEYING, INC. 109 RHODE ISLAND ROAD, SUITE 4A, LAKEVILLE, MA 02347. MINOR FIELD SURVEY WAS DONE BY GUERRIERE & HALNON, INC. TO UPDATE THE PARKING STRIPING AND OTHER MINOR FEATURES. GUERRIERE & HALNON, INC. WITH ELECTRONIC FILES PROVIDED BY REED LAND SURVEYING, CONVERTED THE DRAWING FROM THE PREVIOUS DATUM TO NAD83/NAVDB88.




EXISTING PARKING NOTE

79 EXISTING PARKING SPACES
+4 HANDICAP PARKING SPACES
TOTAL EXISTING PARKING SPACES = 83 SPACES

**AGRICULTURAL RESIDENTIAL II
MAIN STREET AUOD DISTRICT
MEDWAY MILL CONVERSION SUBDISTRICT**

	REQUIRED	EXISTING
MINIMUM LOT AREA	22,500 SF	317,260±SF. (7.28 ACRES)
MINIMUM LOT FRONTAGE	150'	286.79 MAIN STREET 38.45 LINCOLN STREET
MINIMUM YARDS		
FRONT	35'	8' ENCROACHING ON MAIN
SIDE	15'	.06' ENCROACHING ON YORKIS PROP
REAR	15'	163'±
MAXIMUM BUILDING HEIGHT	35'	
% OF LOT UPLAND COVERED BY:		
STRUCTURES	30	42,777±SF (13.5%)
STRUCTURES+PAVING	40	106,303±SF. (33.50%)



APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

[Signature]
Paul Yorkis
10-12-2021

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

LEGAL NOTES

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES. IT SHOULD BE CONSIDERED APPROXIMATE. DURING EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY DETERMINED. COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT 1(888)DIG-SAFE(7233).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT


NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA 02053

**SITE PLAN
MEDWAY MILL
161-165 MAIN STREET
MEDWAY
MASSACHUSETTS**

EXISTING CONDITIONS

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS



Guerriere & Halnon, Inc.
ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com

3:\GIS\Franklin\F3519\DWG\F3519-SITE-rev 5 parking sketch 4.dwg, 9/28/2021 11:20:09 AM, DAB

STORM DRAINAGE NOTES

SPECIAL CONSIDERATION FOR INLET CONTROLS FOR EROSION COLLECTION BEFORE ENTERING DRAINAGE SYSTEM:

- 1. INSTALL SILT SACKS.
- 2. BARRIER AROUND CATCH BASIN, MULCH SOCK OR EQUAL
- 3. INSTALL FILTER FABRIC ON ALL DRAIN MANHOLE OUTLETS DISCHARGING TO INFILTRATION SYSTEM.
- 4. INSPECTIONS BEFORE AND AFTER STORM EVENTS ARE REQUIRED TO INSURE ADEQUACY OF EROSION CONTROL MEASURES.
- 5. CONTRACTOR & ARCHITECT ARE TO VERIFY SITE UTILITIES PRIOR TO DESIGN & CONSTRUCTION.
- 6. ALL DRAINAGE PIPES ARE TO BE 12" CLASS V RCP.
- 7. ALL PIPE GASKETS SHALL BE PRE-MOLDED NEOPRENE O-RING TYPE (300-11 B.(2)(A)).

EXCESS MATERIALS WILL BE MAINTAINED AND REMOVED OFF SITE DUE TO LIMITED SPACE.

UTILITY NOTE

ALL UTILITIES SHALL BE CONSTRUCTED ACCORDING TO STATE AND LOCAL REGULATIONS.

TESTING INFORMATION

TESTING DATE: MARCH 25, 2010 SOIL EVALUATOR: DONALD NIELSEN, SE #1744

192.00	TP 1		186.10	TP 2		176.80	TP 3	
191.25	LOAM 10YR2/2	9"	185.60	LOAM 10YR3/2	6"	175.80	LOAM 10YR3/2	12"
189.25	SUBSOIL 10YR5/8	24"	184.60	SUBSOIL 10YR5/6	12"	173.80	FILL 10YR5/6	24"
	SAND W/ SILT TRACES 3"-6" COBBLES BONEY ANGULAR BOF OF HOLE	63"		SAND W/ 3"-6" COBBLES	51"	173.05	NATURAL LOAM	9"
184.00	REFUSAL @ 8" NO GW @ 8"		180.35	10Y5/4		171.80	SUBSOIL	15"
						170.55	COARSE SAND 3"-8" COBBLES	15"
							RUST & GW @ 60"	
181.20	TP 4		176.65	TP 5		176.10	TP 6	
180.20	LOAM	12"	176.15	FILL	6"	173.10	SANDY LOAM FILL	36"
178.20	SUBSOIL	24"	175.15	LOAM	12"	170.10	NATURAL LOAM 10YR2/	36"
	SANDY LOAM 3"-6" COBBLES SOME SILT	54"	173.15	GRAVELLY SUBSOIL	24"		MED TO COARSE SAND	12"
173.70			172.15	FINE SILTY SAND	12"	169.10	10Y5/6	
	GW @ 88"			GW @ 3'-6"			GW @ 4'-6"	
174.50	TP 7							
174.34	MULCH	2"						
168.84	CLEAN SAND FILL	66"						
166.84	LOAM 10YR5/6	24"						
165.84	COARSE GRAVEL	12"						
	10Y5/3							
	GW @ 80"							

AGRICULTURAL RESIDENTIAL II
MAIN STREET AUOD DISTRICT
MEDWAY MILL CONVERSION SUBDISTRICT

MINIMUM LOT AREA	REQUIRED 22,500 SF	EXISTING 317,260±SF. (7.28 ACRES)	PROPOSED 317,260±SF. (7.28 ACRES)
MINIMUM LOT FRONTAGE	150'	286.79 MAIN STREET	286.79 MAIN STREET
MINIMUM YARDS		38.45 LINCOLN STREET	38.45 LINCOLN STREET
FRONT	35'	8' ENCROACHING ON MAIN	8' ENCROACHING ON MAIN
SIDE	15'	.06' ENCROACHING ON YORKIS PROP	.06' ENCROACHING ON YORKIS PROP
REAR	15'	163'±	163'±
MAXIMUM BUILDING HEIGHT	35'	--	--
% OF LOT UPLAND COVERED BY:			
STRUCTURES	30	42,777±SF (13.5%)	42,777±SF (13.5%)
STRUCTURES+PAVING	40	106,303±SF. (33.50%)	125,029±SF. (39.40%)
PARKING	134	83 PARKING SPACES	135 TOTAL PARKING SPACES

EXISTING BUILDING AREAS:

	OFFICE SPACE	RETAIL	STORAGE
MAIN MILL			
FIRST FLOOR	10,790±SF.	4325±SF.	
SECOND FLOOR	8826±SF.	1505±SF.	258±SF.
THIRD FLOOR	1875±SF.		
REAR BUILDING			
FIRST FLOOR	4449±SF.		
TENANT BAY BUILDINGS			
FIRST FLOOR	1075±SF.	4537±SF.	8327±SF.
TOTAL AREAS	27,015±SF.	10,367±SF.	8585±SF.

REQUIRED PARKING FOR EXISTING USES:

PARKING SPACES REQUIRED	90 SPACES	35 SPACES	9 SPACES
TOTAL PARKING REQUIRED=	134 PARKING SPACES		

PARKING NOTES

- 1. EXISTING PARKING SPACES ON SITE = 83 PARKING SPACES.
- 2. 15 PARKING SPACES PROPOSED TO THE EAST SIDE OF SITE.
- 3. 42 NEW PARKING SPACES PROPOSED ON THE WEST SIDE OF SITE.
- 4. 5 PARKING SPACES REMOVED DUE TO THE BRIDGE EXPANSION.
- 5. ONE SPACE REMOVED FOR HANDICAP PARKING
- 6. ONE SPACE ADDED ON WEST SIDE OF SITE
- 7. A TOTAL OF PARKING SPACES FOR THIS SITE = 135 PARKING SPACES

LEGEND

⊞	CATCH BASIN	☆	PROPOSED LIGHT POLE
⊙	DRAIN MANHOLE	⊙	UTILITY POLE
⊙	ELECTRIC MANHOLE	⊙	GUY WIRE
⊙	SEWER MANHOLE	⊙	SIGN
⊙	GAS VALVE	—S—	SEWER LINE
⊙	GAS SHUT OFF VALVE	—D—	DRAIN LINE
⊙	WATERGATE	—W—	WATER LINE
⊙	WATER SHUT OFF VALVE	—G—	GAS LINE
VCC	FIRE HYDRANT	—ETC—	ELEC., TEL. CABLE
RW	VERTICAL CONC CURB	—OHW—	OVERHEAD WIRES
A.F.G.	RETAINING WALL	—25'B—	25' WETLAND BUFFER
⊙	ABOVE FINISH GRADE	EP	EDGE OF PAVEMENT
⊙	ARBORVITAE	X 000.0	SPOT ELEVATION
⊙	SHRUB	• C.O.	CLEAN OUT
⊙	TREE	⊙	ELECTRIC METER

TEMPORARY RETENTION AREA NOTES:

- 1. CONSTRUCT TEMPORARY RETENTION AREA TO COLLECT RUNOFF.
- 2. THE TEMPORARY RETENTION AREA IS TO BE UTILIZED AS A TEMPORARY SEDIMENTATION TRAP DURING CONSTRUCTION.
- 3. ALL CONSTRUCTION GRADES IN THE INTERIM SHALL BE SLOPED TO FLOW INTO THE TEMPORARY RETENTION AREA, WHERE POSSIBLE.
- 4. CLEAN ALL SEDIMENT OUT OF TEMPORARY RETENTION AREA PRIOR TO FINAL GRADING AND SURFACE STABILIZATION.
- 5. ONCE SITE IS STABILIZED REMOVE ALL REMAINING ACCUMULATED SEDIMENT AT THE BOTTOM OF THE SEDIMENT TRAP.
- 6. SEDIMENT CONTROL SHALL REMAIN IN PLACE UNTIL THE SITE IS STABILIZED.
- 7. CLEAN ALL ON SITE CATCH BASINS, MANHOLES, PIPING, TEMPORARY SEDIMENT TRAP, AND INFILTRATION CHAMBERS. INSTALL SILT BAGS AT EACH CATCH BASIN.
- 8. FOR FURTHER EROSION CONTROL NOTES REFER TO THE FOLLOWING SECTIONS ON THE DETAIL SHEETS:
"INTERIM EROSION CONTROL AND CONSTRUCTION SEQUENCE"
"GENERAL EROSION CONTROL AND CONSTRUCTION NOTES"



F3519

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD
BEING A MAJORITY
ENDORSEMENT DATE 10-12-2021

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO REVEAL A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED APPROXIMATE. DURING EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY BE MET BY CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT 1(888)DIG-SAFE[7233].

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT


NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA

SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS

GENERAL NOTES

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT
	AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS




Guerriere &
Halnon, Inc.

ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com

SHEET
4 OF 14

JOB NO. F3519



F3519

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD
[Signature]
[Signature]
[Signature]

BEING A MAJORITY
ENDORSEMENT DATE 10-12-2021

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS. MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED APPROXIMATE. EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE A COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT 1(888)DIG-SAFE(72333).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT


NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA. 02053

**SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS**


SITE LAYOUT

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT
	AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS




Guerriere & Halnon, Inc.
ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com



NOTE:

EVERY EFFORT TO PRESERVE THE 36" MAPLE WILL BE TAKEN.

1. PLACE CONSTRUCTION FENCING 5' AROUND BASE OF TREE
2. PLACE A "KEEP OUT" PLACARD ON FENCE.
3. IMPROVE SOIL CONDITIONS WITH 5% ORGANIC MATTER, 50% MINERAL PARTICLES (40% SAND, 40% SILT, 20% CLAY) AND 45% PORE SPACE WITHIN FENCED AREA.
4. PLACE 4-6" OF MULCH ON TOP OF NEW SOIL MIXTURE.
5. WATER TREE DURING DROUGHTS.



NOTES

1. THE CONTRACTOR SHALL VERIFY ALL UTILITIES PRIOR TO CONSTRUCTION.
2. PROTECT ALL TREES, SHRUBS, CURBS, PAVING, AND OTHER SITE FEATURES THAT ARE NOT DESIGNATED FOR REMOVAL.
3. PLACE EROSION CONTROL IN DESIGNATED AREAS ACCORDING TO PLAN. DESIGN ENGINEER SHALL INSPECT EROSION AFTER PLACEMENT.
4. INSTALL CONSTRUCTION ENTRANCE ACCORDING TO DETAIL.
5. TEMPORARY FENCING WITH CONSTRUCTION SIGNAGE SHALL BE INSTALLED AROUND PROPOSED PARKING AND DETENTION AREAS.
6. INSTALL SILT SACKS IN ALL CATCH BASINS WITHIN THE LIMIT OF WORK.

Cut/Fill Summary

Name	Cut Factor	Fill Factor	2d Area	Cut	Fill	Net
Cut-Fill Surface	1.000	1.000	30459 Sq. Ft.	217 Cu. Yd.	1819 Cu. Yd.	1602 Cu. Yd.<Fill>
Totals			30459 Sq. Ft.	217 Cu. Yd.	1819 Cu. Yd.	1602 Cu. Yd.<Fill>

A. Names of Persons or Entities Responsible for Plan Compliance

John Greene
NRG Concepts, Inc.
165 Main Street
Suite 307
Medway, MA 02053
Tel: 508-367-8745

B. Construction Period Pollution Prevention Measures

1. Inventory materials to be present on site during construction.
2. Train employees and subcontractors in prevention and clean up procedures.
3. All materials stored on site will be stored in their appropriate containers and if possible under a roof or covered.
4. Follow manufacturer's recommendation for disposal of used containers.
5. Store only enough products on site to do the job.
6. On site equipment, fueling and maintenance measures:
 - a. Inspect owned vehicles and equipment daily for leaks.
 - b. Conduct all vehicle and equipment maintenance and refueling in front of building, away from storm drains.
 - c. Perform major repairs and maintenance off site.
 - d. Use drip pans, drip cloths or absorbent pads when replacing spent fuels.
 - e. Collect spent fuels and remove from site, per Local and State regulations.
 - f. Maintain a clean construction entrance; install a crushed stone apron where truck traffic is frequent to reduce soil compaction constant sweeping is required and limit tracking of

C. Site Development Plans

1. See Site Plan set "Site Plan Medway Mill 163-165 Main Street Medway Massachusetts" dated February 14, 2020, revised to 6/22/21, prepared by Guerriere & Halnon, Inc.

D. Construction Erosion and Sedimentation Control Plan

1. See Site Plan set "Site Plan Medway Mill 163-165 Main Street Medway Massachusetts" dated February 14, 2020, revised to 6/22/21, prepared by Guerriere & Halnon, Inc.

E. Plans

1. Construction Sequencing Plan
 - a. A NPDES NOI shall be filed with the EPA.
 - b. Record Order of Conditions - The site superintendent shall be aware of all the Conditions contained within the Order, including inspection schedules.
 - c. Install DEP File # Sign.
 - d. Prior to any work on the site including tree/fresh clearing, the approved limit of clearing as well as the location of the proposed erosion control devices (such as silt fence/straw bales, etc.) must be staked on the ground under the direction of a Massachusetts registered Professional Land Surveyor.
 - e. Install erosion control barrier at locations depicted on the plans.
 - f. Erosion control to be inspected by either the design engineer (or agent) or an erosion control monitor appointed by the Town of Medway.
 - g. Extra erosion control devices shall be stored on the site to be used in case of an emergency (large storm).
 - h. Perform tree/brush removal.
 - i. Strip off top and subsoil. Stockpile material to be reused away from any drainage inlet or protected wetland areas, remove excess material from the site. Install and maintain erosion control barrier around stockpile.
 - j. Rough grade site, maintaining temporary low areas/sediment traps for sediment accumulation and away from the wetlands and prevent sedimentation from migrating from the site.
 - k. Construct forebay/basin, and outlet/outfalls. Install pipes, manholes and catch basins. Stabilize side slopes with loam, seed and mulch.
 - l. Install underground utilities; protect all open drainage structures with erosion/sedimentation control devices, and rope off any areas susceptible to heavy vehicle damage.
 - m. Prepare compacted prevent base.
 - n. Loam and seed (mulch as required) disturbed areas of site other than immediately adjacent to work area.
 - o. Upon all catchment structures and mitigation features becoming operational, install pavement up to final finish grade. Straw bales backed by crushed stone to be provided on down gradient side of catch basins to direct water to temporary basin.

- a. Install curbing and catch basin curb inlets.
- a. Install final pavement wearing course.
- r. Construct pervious sidewalk.
- s. Finish grade - loam and seed (mulch as required) adjacent to parking lot.
- t. Maintain all erosion control devices until site is stabilized and final inspections are performed.

The Contractor shall be responsible to schedule any required inspections of his/her work.

2. Construction Waste Management Plan
 - a. Dumpster for trash and bulk waste collection shall be provided separately for construction.
 - b. Recycle materials whenever possible (paper, plaster cardboard, metal cans). Separate containers for materials are recommended.
 - c. Segregate and provide containers for disposal options for waste as needed. Recycling products will also be removed off site weekly.
 - d. Do not bury waste and debris on site.
 - e. Certified haulers will be hired to remove the dumpster container waste as needed. Recycling products will also be removed off site weekly.
 - f. The sewer system is only for disposal of human waste, and substances permitted for disposal by the Charles River Pollution Control District (CRPCD).

F. Operation and Maintenance of Erosion and Sedimentation Controls

The operation and maintenance of sedimentation control shall be the responsibility of the contractor. The inspection and maintenance of the storm water component shall be performed as noted below. The contractor shall, at all times have erosion control in place. The contractor, based on future weather reports shall prepare and inspect all erosion control devices: cleaning, repairing and upgrading is a priority so that the devices perform as per design. Inspect the site during rain events. Don't stay away from the site. At a minimum, there should be inspection to assure the devices are not clogged or plugged, or that devices have not been destroyed or damaged during the rain event. After a storm event inspection is required to clean and repair any damage components. Immediate repair is required.

G. Inspection and Maintenance Schedules

1. Inspection must be conducted at least once every 7 days and within 24 hours prior to and after the end of a storm event 0.5 inches or greater.
2. Inspection frequency can be reduced to once a month if:
 - a. The site is temporarily stabilized.
 - b. Runoff is unlikely due to winter conditions, when site is covered with snow or ice.
3. Inspections must be conducted by qualified personnel, "qualified personnel" means a person knowledgeable in the principles and practice of erosion and sediment controls and who possesses the skills to assess the conditions and take measures to maintain and ensure proper operation, also to conclude if the erosion control methods selected are effective.
4. For each inspection, the inspection report must include:
 - a. The inspection date.
 - b. Names, titles of personnel making the inspection.
 - c. Weather information for the period since the last inspection.
 - d. Weather information at the time of the inspection.
 - e. Locations of discharges of sediment from the site, if any.
 - f. Locations of BMP's that need to be maintained.
 - g. Locations where additional BMP's may be required.
 - h. Corrective action required or any changes to the SWPPP that may be necessary.
5. Qualified personnel shall inspect the following in-place work:

Inspection Schedule:
Erosion Control Weekly
Catch Basins Weekly
Temporary Sedimentation Weekly
Traps/Basins Weekly
Pavement Sweeping Weekly

Please Note: Special inspections shall also be made after a significant rainfall event.

Maintenance Schedule
Erosion Control Devices Failure Immediately
Temporary Sedimentation As needed
Traps/Basins As needed
Pavement Sweeping 14 days minimum and prior to any significant rain event.

Please Note: Special maintenance shall also be made after a significant rainfall event.

H. Inspection and Maintenance Log Form.
1. See Construction Phase Inspection and Maintenance Form attached

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

[Signature]
[Signature]
[Signature]

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED APPROXIMATE. DURING EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT (888)DIG-SAFE(7233).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT

NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA 02053

SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS


EROSION CONTROL
LIMIT OF CLEARING

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS



Guerriere & Halnon, Inc.
ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com



F3519

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

[Signature]
[Signature]
[Signature]

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED APPROXIMATE. LACKING EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY, COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82, SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT 1(888)DIGSAFE(7233).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT

NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA 02053

**SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS**

GRADING AND DRAINAGE

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS




Guerriere & Halton, Inc.
ENGINEERING & LAND SURVEYING

55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com



SHEET 7 OF 14

JOB NO. F3519





NOTES

1. REMOVE ALL SAND AND SEDIMENT FROM SHALLOW CATCH BASINS.
2. ADD CONCRETE BOTTOM TO CATCHBASINS.
3. ADD HOODS, THE ELIMINATOR, TO EXISTING CATCH BASINS.



EXISTING CONDITIONS FOR THE AREA OF PROPOSED BRIDGE

SCALE: 1"=10'



PROPOSED BRIDGE LOCATION

SCALE: 1"=10'



F3519

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

[Signature]
[Signature]
[Signature]

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED APPROXIMATE. DURING EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT 1(888)DIG-SAFE(7233).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT


NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA. 02053

SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS

BRIDGE DETAIL

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT
	AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS




Guerriere & Halnon, Inc.
ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com

SHEET
8 OF 14

JOB NO.
F3519

SEE PLAN ENTITLED ' MEDWAY MILL BRIDGE WIDENING PROJECT, MEDWAY
MILL BRIDGE OVER CHICKEN BROOK, TOWN OF MEDWAY, NORFOLK COUNTY'
BY COLLINS ENGINEERS, INC.
FOR BRIDGE DETAILS
SHEET 01-SHEET 08



APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

[Signature]

[Signature]

[Signature]

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED APPROXIMATE. PRIOR TO ANY EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY, COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT 1(888)DIG-SAFE(72333).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT


NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA. 02053

SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS

BRIDGE DETAIL

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT
	AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS




**Guerriere &
Halnon, Inc.**


ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com

SHEET 9 OF 14



JOB NO. F3519



 AREA TO BE MOWED ONCE A YEAR- BOTTOM, SIDE SLOPES OF BASIN, ACCESS PATH

 AREAS FOR PLANTING NEW ENGLAND CONSERVATION SEED MIX

NOTE: GREEN GIANT ARBORVITAE 50' HIGH AND 12'-20' SPREAD AT MATURITY



REMEDATION LEGEND			
SYMBOL	NAME	SIZE	QUANTITY
	RIVER BIRCH BETULA NIGRA	4" MIN. 2.5" CAL.	7
	MOUNTAIN PEPPERBUSH CLETHRA ACUMINATA	3 GAL.	43
	WITCHHAZEL HAMAMELIS VIRGINIANA	5 GAL.	16
	WINTERBERRY ILEX VERTICILLATA	3 GAL.	23
	JUNIPER PLUMROSA COMPACTA	3 GAL.	16
	CINNAMON FERN OSMUNDA CINNAMOMEA	2 GAL.	113
	RED MAPLE ACER RUBRUM	4" MIN. 2.5" CAL.	7

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

BEING A MAJORITY
ENDORSEMENT DATE 10-12-2021

UTILITIES ARE PLOTTED AS A COMPILATION OF
RECORD DOCUMENTS, MARKINGS AND OTHER
OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE
UNDERGROUND UTILITIES AND SHOULD BE
CONSIDERED APPROXIMATE. PRIOR TO EXCAVATION,
THE EXACT LOCATION OF UNDERGROUND FEATURES
CANNOT BE 100% COMPLETELY AND
RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT
EVIDENCED BY RECORD DOCUMENTS OR OBSERVED
PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN
ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION
40 AS AMENDED) MUST CONTACT ALL UTILITY
COMPANIES BEFORE EXCAVATING AND DRILLING AND
CALL DIGSAFE AT 1(888)DIG-SAFE(72333).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY
EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS,
RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY
BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER
165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA
DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092





















APPLICANT
NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA. 02053


SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS

REMEDATION
FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT
	AND CONSULTANT
6/22/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS

Guerriere & Halnon, Inc.
ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com





10-6-21

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

10-12-2021

BEING A MAJORITY

ENDORSEMENT DATE

UTILITIES ARE PLOTTED AS A COMPILATION OF RECORD DOCUMENTS, MARKINGS AND OTHER OBSERVED EVIDENCE TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES AND SHOULD BE CONSIDERED APPROXIMATE. EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY COMPLETELY AND RELIABLY DEPICTED. ADDITIONAL UTILITIES, NOT EVIDENCED BY RECORD DOCUMENTS OR OBSERVED PHYSICAL EVIDENCE, MAY EXIST. CONTRACTORS (IN ACCORDANCE WITH MASS.G.L. CHAPTER 82 SECTION 40 AS AMENDED) MUST CONTACT ALL UTILITY COMPANIES BEFORE EXCAVATING AND DRILLING AND CALL DIGSAFE AT (1866)DIG-SAFE(7233).

CONSTRUCTION ON THIS LAND IS SUBJECT TO ANY EASEMENTS, RIGHTS-OF-WAY, RESTRICTIONS, RESERVATIONS, OR OTHER LIMITATIONS WHICH MAY BE REVEALED BY AN EXAMINATION OF THE TITLE.

OWNER

165 MAIN STREET REALTY TRUST
JOHN J. GREENE TRUSTEE
165 MAIN STREET
SUITE 307
MEDWAY, MA

DEED BOOK 24499 PAGE 10
A.M. 48 LOT 092

APPLICANT


NRG CONCEPTS, INC.
165 MAIN STREET
SUITE 307
MEDWAY, MA 02053

SITE PLAN
MEDWAY MILL
163-165 MAIN STREET
MEDWAY
MASSACHUSETTS


CONSTRUCTION
DETAILS

FEBRUARY 14, 2020

DATE	REVISION DESCRIPTION
10/13/2020	REVISED PARKING CONFIGURATION
12/23/2020	PER TOWN COMMENTS
4/21/21	PER CONVERSATION WITH CLIENT
6/22/21	AND CONSULTANT
7/30/21	PER PLANNING DECISION
7/30/21	PER TOWN COMMENTS



0 15 30 FEET 60 90
0 2.5 5 10 METERS 20



Guerriere & Halnon, Inc.
ENGINEERING & LAND SURVEYING
55 WEST CENTRAL ST. PH. (508) 528-3221
FRANKLIN, MA 02038 FX. (508) 528-7921
www.gandhengineering.com

SHEET 13 OF 14

JOB NO. F3519

Aeris™

NEW

Intended Use

For streets, walkways, parking lots and surrounding areas.

Features

Housing - Die-cast single piece aluminum with nominal 1/2" wall thickness. Integral arm provides easy installation to pole or wall. Housing completely sealed against moisture or environmental contaminants.

Door Assembly - Die-cast door frame, impact-resistant, tempered, glass lens, 1/2" thick, fully sealed with one-piece tubular silicone gasket. Tool-less entry and closure via spring loaded die-cast latches.

Optics - Anodized segmented reflectors for superior uniformity and control. Reflectors attach with tool-less fasteners and are rotatable and interchangeable.

Installation - Heavy duty easy mount block attaches to pole or wall to provide ease of installation as well as ensured alignment and leveling.

Electrical - 150W and below utilize a high reactance, high power factor, 175W and above use a constant-wattage autotransformer ballast. 42W uses an electronic high frequency ballast. Ballasts mounted on removable power tray with tool-less latch and have positive locking disconnect plugs. Ballasts are copper wound and 100% factory tested.

Finish - Standard finish is dark bronze (DDB) polyester powder finish. Other architectural colors available.

Socket - Porcelain, medium-base socket for AS1, mogul-base socket for AS2, with copper alloy nickel-plated screw shell and center contact. UL listed.


Listings - UL Listed (standard), CSA Certified or NOM certified (see options). U.S. and Canada patents pending. UL listed for wet locations. IP65 certified. Meets IES-NA full cutoff criteria.

For product details and performance data, see the OUTDOOR Lighting or the on-line catalog at www.lithonia.com.

Ordering Information

Example: AS1 150S SR2 120 SF LPI

Designation	Distribution	Voltage	Included	Mounting*	Options/Accessories
High Pressure Sodium					
AS1 35S	SR2 Segmented Type II roadway	120, 208, 240, 277, 347, 480, TB ¹	SPA Square pole mounting block		SF Single fuse, 120, 277, 347V (n/a TB) ²
AS1 50S					DF Double fuse, 208, 240, 480V (n/a TB) ²
AS1 70S	SR3 Segmented Type III asymmetric		RPA Round pole mounting block		PER NEMA twist-lock receptacle only (no photocontrol)
AS1 100S					QRS Quartz restra system (100W max. AS1, 250W max. AS2, lamp not included) ³
AS1 150S	SR4SC Segmented Type IV forward throw, sharp cutoff		WBA wall bracket (up or down)		CR Corrosion-resistant finish
AS2 200S					HS House-side shield
AS2 250S	SR4W Segmented Type IV wide, forward throw (size 2 only)				EC Emergency circuit ⁷
AS2 400S					TP Tamperproof
Metal Halide					SCWA Super CWA Pulse Start Ballast (not available with HPS or TH)
AS1 50M					LPI Lamp included (standard)
AS1 70M					CSA CSA Certified
AS1 100M					NOM ⁷ NOM Certified
AS1 150M	SR5S Segmented Type V square				For optional architectural colors, see page 348.
AS1 175M					Shipped separately
AS2 200M ¹					PE1 NEMA twist-lock PE (120, 208, 240V)
AS2 250M ¹					PE3 NEMA twist-lock PE (347V)
AS2 320M ¹					PE4 NEMA twist-lock PE (480V)
AS2 350M ¹					PE7 NEMA twist-lock PE (277V)
AS2 400M ²					SC Shoring cap
Compact Fluorescent					AS1VG Vandal guard
AS1 42TRT (128, 27, 347V only)					AS2VG Vandal guard



Dimensions are shown in inches (centimeters) unless otherwise noted.


	AS1	AS2
Length	21.38"	26"
Width	12.25"	16.25"
Height	6.28"	8.25"

LITHONIA LIGHTING

MODEL NO. AS1-150S-SR3-HS

PARKING LIGHTING DETAIL AND SPECIFICATIONS

NOT TO SCALE
PROPOSED HEIGHT OF POLES = 12FT.




- WHERE SECTION ENDS MEET, THERE SHALL BE AN OVERLAP OF 6" OR GREATER. BOTH SIDES SHALL BE ANCHORED (OAK STAKES, TREES, ETC.) TO STABILIZE THE UNION.
- NO ADDITIONAL ANCHORS ARE REQUIRED ON SLOPES LESS THAN 2:1.
- ADDITIONAL ANCHORS ARE REQUIRED AT 5' INTERVALS (MAX.) ON THE DOWNSLOPE OR PROTECTED SIDE ON SLOPES GREATER THAN 2:1 TO PREVENT MOVEMENT.


EROSION CONTROL BARRIER

NOT TO SCALE

- SPEED BUMPS SHALL BE BITUMINOUS CONCRETE.
- CLEAN EXISTING PAVEMENT.
- SCAFFOLD EXISTING PAVEMENT ALONG THE OUTER LINES.
- REPLACE BITUMINOUS CONCRETE.
- COMPACT AND JOINT AND SURFACE SEALING USING TACK COAT




SPEED BUMP DETAIL



TYPICAL LIGHT POLE BASE


NOT TO SCALE
LIGHT POLES BY ELECTRIC CONTRACTOR



BOLLARD DETAIL


NOT TO SCALE

LED BOLLARD LIGHT (XBVRD)



U.S. and International patents pending.
LEDs - An array of 24 select high brightness LEDs in Cool White (5000K), Warm White (3000K) or Natural White (4000K) color temperatures. 60° beam.
REFLECTOR DISTRIBUTION - Indirect. Photometric data is tested in accordance to EISA Procedures.
HOUSING - Crown: Virtually tamper-proof, corrosion resistant, clear polycarbonate in the cast aluminum crown assembly.
Lower Housing: One-piece, 322 inch stainless, extruded aluminum. Vandal heights are available in 6" increments starting at a minimum of 30" (maximum height is 60"). Lower housing affixes to cast aluminum base plate with four stainless steel set screws.
OPTIONAL HARDWARE REINFORCEMENT - .315" thick steel plate, steel base plate with welded 1/4" diameter reinforcement. .315" diameter 302 stainless steel set screws with 10,000 lb. shear load.
LENS/GASKET - One-piece, clear acrylic lens enclosure fully gasketed at top and bottom edges.
ANCHOR BOLTS - Requires four heavy-duty 3/8" x 10" galvanized steel anchor bolts.
ELECTRICAL - Universal voltage, power supply (120-277 VAC, 600 Hz), 347-480V also available. -400mA is standard. Surge protector meets IEEE C62.41.2-2002, Category I Location Class II.
DRIVER - State-of-the-art, direct technology designed specifically for LED light sources provides unsurpassed system efficiency. Driver complies with FCC and EMC standards.
OPERATING TEMPERATURE - -40°F to 150°F (-40°F to 122°F).
FINISH - Polished or finished with LSI's DuraGrip™ polyester powder coat finishing process. The DuraGrip finish withstands extreme weather changes without cracking or peeling.
DECAL STRIPPING - Color-coordinated decal is available in 5 standard decal colors or by custom order from a selection of hundreds. Decal is guaranteed for five years against peeling, cracking, or fading.
WARRANTY - LSI Lighting carries a limited 5-year warranty.
PHOTOMETRICS - Please visit our website at www.lsi-lighting.com for detailed photometric data.
LISTINGS - Listed in U.S. and Canadian safety standards. Suitable for wet locations. DULC - not all product specifications are UL approved. Please refer to UL or UL's website for specific listings. For a list of the specific products in this series that are UL listed, please consult the LSI Lighting website or our website at the Design Lights website at www.designlights.com.
This product, or selected variants of this product, meet the standards listed below. Please consult factory for specific requirements.
AARA
Also available in traditional light sources
LSI LIGHTING

WALKWAY LIGHTING DETAIL AND SPECIFICATIONS



A. Names of Persons or Entities Responsible for Plan Compliance

John Greene
NRG Concepts, Inc.
165 Main Street
Suite 307
Medway, MA 02053
Tel: 508-367-8745

B. Construction Period Pollution Prevention Measures

- Inventory materials to be present on site during construction.
- Train employees and subcontractors in prevention and clean up procedures.
- All materials stored on site will be stored in their appropriate containers and if possible under a roof or covered.
- Follow manufacturer's recommendation for disposal of used containers.
- Store only enough products on site to do the job.
- On site equipment, fueling and maintenance measures:
 - Inspect on-site vehicles and equipment daily for leaks.
 - Conduct all vehicle and equipment maintenance and refueling in front of building, away from storm drains.
 - Perform major repairs and maintenance off site.
 - Use drip pans, drip cloths or absorbent pads when replacing spent fluids.
 - Collect spent fuels and remove from site, per Local and State regulations.
 - Maintain a clean construction entrance; install a crushed stone apron where truck traffic is frequent to reduce soil compaction constant sweeping is required and limit tracking of sediment into streets, sweeping street when silt is observed on street.
 - A temporary concrete washout station and equipment wash station shall be located on the site. Areas shall be surrounded with silt fence and or Filter Mitt to contain materials and provide ease of cleanup.
 - Stock pile materials, and maintain Erosion Control around the materials where it can easily be accessed. Maintain easy access to clean up materials to include brooms, mops,

rags, gloves, goggles, sand, sawdust, plastic and metal trash containers.

- Never hose down "dirty" pavement or impermeable surfaces where fluids have spilled. Use dry cleanup methods (sawdust, cat litter and/or rags and absorbent pads).
- Sweep up dry materials immediately.
- Never wash them away or bury them.
- Clean up spills on dirt areas by digging up and properly disposing of contaminated soil in a certified container and notify a certified hauler for removal.
- Report significant spills to the Fire Department.

- It is the responsibility of the site superintendent or employees designated by the Applicant to inspect erosion control and repair as needed, also to inspect all on site vehicles for leaks and check all containers on site that may contain hazardous materials daily.

C. Site Development Plans


- See Site Plan set "Site Plan Medway Mill 163-165 Main Street Medway Massachusetts" dated February 14, 2020, Revised June 22, 2021 prepared by Guerriere & Halnon, Inc.

D. Construction Erosion and Sedimentation Control Plan

- See Site Plan set "Site Plan Medway Mill 163-165 Main Street Medway Massachusetts" dated February 14, 2020, Revised June 22, 2021 prepared by Guerriere & Halnon, Inc.


E. Plans

- Construction Sequencing Plan:
 - A NPDES NOI shall be filed with the EPA.
 - Revised Order of Conditions - The site superintendent shall be aware of all the Conditions contained within the Order including inspection schedules.
 - Install DEP File # Sign.
 - Prior to any work on the site including



Surface Mount Bike Rack

NOTE: BIKE RACK TO PROVIDE SPACE FOR 4 BIKES



- SEE DRIVEWAY STANDARD PLANS CDR.21 FOR JOINTING AND LAYOUT.
- PERMEABLE PAVERS SHALL CONFORM TO ALL REQUIREMENTS BELOW:
 - 3-1/8" THICK PAVERS FOR VEHICULAR APPLICATIONS
 - 3-1/8" THICK PAVERS FOR PEDESTRIAN AREAS
 - SURFACE AREA AND ASPECT RATIO REQUIREMENTS OF ASTM C936
- AGGREGATE FOR BASE COURSE SHALL BE CLEAN, ANGULAR ROCK 1-1/4", CONFORMING TO PERMEABLE BALLAST WSDOT 9-03.02.
- PERMEABLE PAVERS TO BE INSTALLED AFTER CONSTRUCTION OF HOUSE. AFTER INSTALLATION, PROTECT PERMEABLE PAVEMENT FROM LANDSCAPE AND OTHER CONSTRUCTION ACTIVITIES.
- SUBGRADE IS TO BE COMPACTED TO THE MINIMUM NECESSARY FOR STRUCTURAL STABILITY, USING DUAL WHEEL SMALL MECHANICAL ROLLERS IN STAIRWISE. HEAVY EQUIPMENT OR TRUCK TRAFFIC IS NOT ALLOWED ON SUBGRADE.
- TO PRESENT COMPACTION, INSTALL THE AGGREGATE BASE IN THE FOLLOWING MANNER (BACK DUMPING):
 - DUMP AGGREGATE BASE ONTO SUBGRADE FROM THE EDGE OF THE INSTALLATION, THEN PUSH IT OUT ONTO THE SUBGRADE.
 - DUMP SUBSEQUENT LAYERS FROM TOP OF THE AGGREGATE BASE AS THE INSTALLATION PROGRESSES.
- PERVIOUS CONCRETE SIDEWALK SHALL BE TESTED PRIOR TO ACCEPTANCE. ONE TEST PER 5000 SF AREA MINIMUM. TESTING SHALL MEET ASTM C1091 AND SHALL MEET A MINIMUM OF 100 PSI.
- INTERFERENCE CHECK DAMS IN THE BASE COURSE ARE REQUIRED FOR SLOPES BETWEEN 5% AND 10%. SLOPE SHALL NOT EXCEED 10%.
- NO HORIZONTAL GEOTEXTILE FABRIC UNLESS RECOMMENDED BY GEOTECHNICAL PROFESSIONAL DUE TO POOR SOIL STRENGTH. VERTICAL SEPARATION WITH GEOTEXTILE FABRIC MAY BE REQUIRED PER ENGINEER, DEPENDENT ON ADJACENT STRUCTURES.

tree/brush clearing, the approved limit of clearing as well as the location of the proposed erosion control devices (such as silt fence/stake bales, etc.) must be staked on the ground under the direction of a Massachusetts registered Professional Land Surveyor.

- Install erosion control barrier at locations depicted on the plans.
- Erosion control to be inspected by either the design engineer (or agent) or an erosion control monitor appointed by the Town of Medway.
- Extra erosion control devices shall be stored on the site to be used in case of an emergency (large storm).
- Perform tree/brush removal.
- Strip off top and subsoil. Stockpile material to be reused away from any drainage inlet or protected wetland areas, remove excess material from the site. Install and maintain erosion control barrier around stockpile.
- Rough grade site, maintaining temporary low areas/sediment traps for sediment accumulation and away from the wetlands and prevent sedimentation from migrating from the site.
- Construct forebay/basin, and outlets/outfalls. Install pipes, manholes and catch basins. Stabilize side slopes with loam, seed and mulch.
- Install underground utilities; protect all open drainage structures with erosion/sediment control devices, and rope off any areas susceptible to heavy vehicle damage.
- Prepare compacted pavement base.
- Loam and seed (mulch as required) disturbed areas of site other than down gradient side of catch basins to direct water to temporary basin.
- Install initial pavement wearing course.
- Finish grade - loam and seed (mulch as required) adjacent to parking lot.
- Maintain all erosion control devices until site is stabilized and final inspections are performed.

The Contractor shall be responsible to schedule any required inspections of his/her work.

- Construction Waste Management Plan:
 - Dumpster for trash and bulk waste collection shall be provided separately for construction.
 - Recycle materials whenever possible (paper, plastic, cardboard, metal cans). Separate containers for material are recommended.
 - Segregate and provide containers for disposal options for waste.
 - Do not bury waste and debris on site.
 - Certified haulers will be hired to remove the dumpster container waste as needed. Recycling products will also be removed off site weekly.
 - The sewer system is only for disposal of human waste, and substances permitted for disposal by the Charles River Pollution Control District (CRPCD).

Please Note: Special inspections shall also be made after a significant rainfall event.

- Inspection Schedule:

Erosion Control	Weekly
Catch Basins	Weekly
Temporary Sedimentation Traps/Basins	Weekly
Pavement Sweeping	Weekly

Please Note: Special inspections shall also be made after a significant rainfall event.

- Inspection and Maintenance Log Form:
 - See Construction Phase Inspection and Maintenance Form attached

The operation and maintenance of sedimentation control shall be the responsibility of the contractor. The inspection and maintenance of

the storm water component shall be performed as noted below. The contractor shall, at all times, have erosion control in place. The contractor, based on future weather reports shall prepare and inspect all erosion control devices; cleaning, repairing and upgrading is a priority so that the devices perform as per design. Inspect the site during rain events. Don't stay away from the site. At a minimum, there should be inspection to assure the devices are not clogged or plugged, or that devices have not been destroyed or damaged during the rain event. After a storm event inspection is required to clean and repair any damage components. Immediate repair is required.

G. Inspection and Maintenance Schedules

- Inspection must be conducted at least once every 7 days and within 24 hours prior to and after the end of a storm event 0.5 inches or greater.
- Inspection frequency can be reduced to once a month if:
 - The site is temporarily stabilized.
 - Rainfall is unlikely due to winter conditions, when site is covered with snow or ice.
- Inspections must be conducted by qualified personnel, "qualified personnel" means a person knowledgeable in the principles and practice of erosion and sediment controls and who possess the skills to assess the conditions and take measures to maintain and ensure proper operation, also to conclude if the erosion control methods selected are effective.
- For each inspection, the inspection report must include:
 - The inspection date.
 - Names, titles of personnel making the inspection.
 - Weather information for the period since the last inspection.
 - Weather information at the time of the inspection.
 - Locations of discharges of sediment from the site, if any.
 - Locations of BMPs that need to be maintained.
 - Locations where additional BMPs may be required.
 - Corrective action required or any changes to the SWPPP that may be necessary.
- Qualified personnel shall inspect the following in-place work:

Inspection Schedule:	Weekly
Erosion Control	Weekly
Catch Basins	Weekly
Temporary Sedimentation Traps/Basins	Weekly
Pavement Sweeping	Weekly

Please Note: Special inspections shall also be made after a significant rainfall event.

- Inspection and Maintenance Log Form:
 - See Construction Phase Inspection and Maintenance Form attached

The operation and maintenance of sedimentation control shall be the responsibility of the contractor. The inspection and maintenance of

the storm water component shall be performed as noted below. The contractor shall, at all times, have erosion control in place. The contractor, based on future weather reports shall prepare and inspect all erosion control devices; cleaning, repairing and upgrading is a priority so that the devices perform as per design. Inspect the site during rain events. Don't stay away from the site. At a minimum, there should be inspection to assure the devices are not clogged or plugged, or that devices have not been destroyed or damaged during the rain event. After a storm event inspection is required to clean and repair any damage components. Immediate repair is required.

G. Inspection and Maintenance Schedules

- Inspection must be conducted at least once every 7 days and within 24 hours prior to and after the end of a storm event 0.5 inches or greater.
- Inspection frequency can be reduced to once a month if:
 - The site is temporarily stabilized.
 - Rainfall is unlikely due to winter conditions, when site is covered with snow or ice.
- Inspections must be conducted by qualified personnel, "qualified personnel" means a person knowledgeable in the principles and practice of erosion and sediment controls and who possess the skills to assess the conditions and take measures to maintain and ensure proper operation, also to conclude if the erosion control methods selected are effective.
- For each inspection, the inspection report must include:
 - The inspection date.
 - Names, titles of personnel making the inspection.
 - Weather information for the period since the last inspection.
 - Weather information at the time of the inspection.
 - Locations of discharges of sediment from the site, if any.
 - Locations of BMPs that need to be maintained.
 - Locations where additional BMPs may be required.
 - Corrective action required or any changes to the SWPPP that may be necessary.
- Qualified personnel shall inspect the following in-place work:

Inspection Schedule:	Weekly
Erosion Control	Weekly
Catch Basins	Weekly
Temporary Sedimentation Traps/Basins	Weekly
Pavement Sweeping	Weekly

Please Note: Special inspections shall also be made after a significant rainfall event.

- Inspection and Maintenance Log Form:
 - See Construction Phase Inspection and Maintenance Form attached

The operation and maintenance of sedimentation control shall be the responsibility of the contractor. The inspection and maintenance of

the storm water component shall be performed as noted below. The contractor shall, at all times, have erosion control in place. The contractor, based on future weather reports shall prepare and inspect all erosion control devices; cleaning, repairing and upgrading is a priority so that the devices perform as per design. Inspect the site during rain events. Don't stay away from the site. At a minimum, there should be inspection to assure the devices are not clogged or plugged, or that devices have not been destroyed or damaged during the rain event. After a storm event inspection is required to clean and repair any damage components. Immediate repair is required.

G. Inspection and Maintenance Schedules

- Inspection must be conducted at least once every 7 days and within 24 hours prior to and after the end of a storm event 0.5 inches or greater.
- Inspection frequency can be reduced to once a month if:
 - The site is temporarily stabilized.
 - Rainfall is unlikely due to winter conditions, when site is covered with snow or ice.
- Inspections must be conducted by qualified personnel, "qualified personnel" means a person knowledgeable in the principles and practice of erosion and sediment controls and who possess the skills to assess the conditions and take measures to maintain and ensure proper operation, also to conclude if the erosion control methods selected are effective.
- For each inspection, the inspection report must include:
 - The inspection date.
 - Names, titles of personnel making the inspection.
 - Weather information for the period since the last inspection.
 - Weather information at the time of the inspection.
 - Locations of discharges of sediment from the site, if any.
 - Locations of BMPs that need to be maintained.
 - Locations where additional BMPs may be required.
 - Corrective action required or any changes to the SWPPP that may be necessary.
- Qualified personnel shall inspect the following in-place work:

Inspection Schedule:	Weekly
Erosion Control	Weekly
Catch Basins	Weekly
Temporary Sedimentation Traps/Basins	Weekly
Pavement Sweeping	Weekly

tree/brush clearing, the approved limit of clearing as well as the location of the proposed erosion control devices (such as silt fence/stake bales, etc.) must be staked on the ground under the direction of a Massachusetts registered Professional Land Surveyor.

- Install erosion control barrier at locations depicted on the plans.
- Erosion control to be inspected by either the design engineer (or agent) or an erosion control monitor appointed by the Town of Medway.
- Extra erosion control devices shall be stored on the site to be used in case of an emergency (large storm).
- Perform tree/brush removal.
- Strip off top and subsoil. Stockpile material to be reused away from any drainage inlet or protected wetland areas, remove excess material from the site. Install and maintain erosion control barrier around stockpile.
- Rough grade site, maintaining temporary low areas/sediment traps for sediment accumulation and away from the wetlands and prevent sedimentation from migrating from the site.
- Construct forebay/basin, and outlets/outfalls. Install pipes, manholes and catch basins. Stabilize side slopes with loam, seed and mulch.
- Install underground utilities; protect all open drainage structures with erosion/sediment control devices, and rope off any areas susceptible to heavy vehicle damage.
- Prepare compacted pavement base.
- Loam and seed (mulch as required) disturbed areas of site other than down gradient side of catch basins to direct water to temporary basin.
- Install initial pavement wearing course.
- Finish grade - loam and seed (mulch as required) adjacent to parking lot.
- Maintain all erosion control devices until site is stabilized and final inspections are performed.

The Contractor shall be responsible to schedule any required inspections of his/her work.

- Construction Waste Management Plan:
 - Dumpster for trash and bulk waste collection shall be provided separately for construction.
 - Recycle materials whenever possible (paper, plastic, cardboard, metal cans). Separate containers for material are recommended.
 - Segregate and provide containers for disposal options for waste.
 - Do not bury waste and debris on site.
 - Certified haulers will be hired to remove the dumpster container waste as needed. Recycling products will also be removed off site weekly.
 - The sewer system is only for disposal of human waste, and substances permitted for disposal by the Charles River Pollution Control District (CRPCD).

Please Note: Special inspections shall also be made after a significant rainfall event.

- Inspection Schedule:

Erosion Control	Weekly
Catch Basins	Weekly
Temporary Sedimentation Traps/Basins	Weekly
Pavement Sweeping	Weekly

Please Note: Special inspections shall also be made after a significant rainfall event.

- Inspection and Maintenance Log Form:
 - See Construction Phase Inspection and Maintenance Form attached

The operation and maintenance of sedimentation control shall be the responsibility of the contractor. The inspection and maintenance of

the storm water component shall be performed as noted below. The contractor shall, at all times, have erosion control in place. The contractor, based on future weather reports shall prepare and inspect all erosion control devices; cleaning, repairing and upgrading is a priority so that the devices perform as per design. Inspect the site during rain events. Don't stay away from the site. At a minimum, there should be inspection to assure the devices are not clogged or plugged, or that devices have not been destroyed or damaged during the rain event. After a storm event inspection is required to clean and repair any damage components. Immediate repair is required.

G. Inspection and Maintenance Schedules

- Inspection must be conducted at least once every 7 days and within 24 hours prior to and after the end of a storm event 0.5 inches or greater.
- Inspection frequency can be reduced to once a month if:
 - The site is temporarily stabilized.
 - Rainfall is unlikely due to winter conditions, when site is covered with snow or ice.
- Inspections must be conducted by qualified personnel, "qualified personnel" means a person knowledgeable in the principles and practice of erosion and sediment controls and who possess the skills to assess the conditions and take measures to maintain and ensure proper operation, also to conclude if the erosion control methods selected are effective.
- For each inspection, the inspection report must include:
 - The inspection date.
 - Names, titles of personnel making the inspection.
 - Weather information for the period since the last inspection.
 - Weather information at the time of the inspection.
 - Locations of discharges of sediment from the site, if any.
 - Locations of BMPs that need to be maintained.
 - Locations where additional BMPs may be required.
 - Corrective action required or any changes to the SWPPP that may be necessary.
- Qualified personnel shall inspect the following in-place work:

Inspection Schedule:	Weekly
Erosion Control	Weekly
Catch Basins	Weekly
Temporary Sedimentation Traps/Basins	Weekly
Pavement Sweeping	Weekly

Please Note: Special inspections shall also be made after a significant rainfall event.

- Inspection and Maintenance Log Form:
 - See Construction Phase Inspection and Maintenance Form attached

The operation and maintenance of sedimentation control shall be the responsibility of the contractor. The inspection and maintenance of

the storm water component shall be performed as noted below. The contractor shall, at all times, have erosion control in place. The contractor, based on future weather reports shall prepare and inspect all erosion control devices; cleaning, repairing and upgrading is a priority so that the devices perform as per design. Inspect the site during rain events. Don't stay away from the site. At a minimum, there should be inspection to assure the devices are not clogged or plugged, or that devices have not been destroyed or damaged during the rain event. After a storm event inspection is required to clean and repair any damage components. Immediate repair is required.

G. Inspection and Maintenance Schedules

- Inspection must be conducted at least once every 7 days and within 24 hours prior to and after the end of a storm event 0.5 inches or greater.
- Inspection frequency can be reduced to once a month if:
 - The site is temporarily stabilized.
 - Rainfall is unlikely due to winter conditions, when site is covered with snow or ice.
- Inspections must be conducted by qualified personnel, "qualified personnel" means a person knowledgeable in the principles and practice of erosion and sediment controls and who possess the skills to assess the conditions and take measures to maintain and ensure proper operation, also to conclude if the erosion control methods selected are effective.
- For each inspection, the inspection report must include:
 - The inspection date.
 - Names, titles of personnel making the inspection.
 - Weather information for the period since the last inspection.
 - Weather information at the time of the inspection.
 - Locations of discharges of sediment from the site, if any.
 - Locations of BMPs that need to be maintained.
 - Locations where additional BMPs may be required.
 - Corrective action required or any changes to the SWPPP that may be necessary.
- Qualified personnel shall inspect the following in-place work:

Inspection Schedule:	Weekly
Erosion Control	Weekly
Catch Basins	Weekly
Temporary Sedimentation Traps/Basins	Weekly
Pavement Sweeping	Weekly

Please Note: Special inspections shall also be made after a significant rainfall event.

- Inspection and Maintenance Log Form:
 - See Construction Phase Inspection and Maintenance Form attached

The operation and maintenance of sedimentation control shall be the responsibility of the contractor. The inspection and maintenance of

the storm water component shall be performed as noted below. The contractor shall, at all times, have erosion control in place. The contractor, based on future weather reports shall prepare and inspect all erosion control devices; cleaning, repairing and upgrading is a priority so that the devices perform as per design. Inspect the site during rain events. Don't stay away from the site. At a minimum, there should be inspection to assure the devices are not clogged or plugged, or that devices have not been destroyed or damaged during the rain event. After a storm event inspection is required to clean and repair any damage components. Immediate repair is required.

G. Inspection and Maintenance Schedules

- Inspection must be conducted at least once every 7 days and within

MEDWAY MILL BRIDGE WIDENING PROJECT

MEDWAY MILL BRIDGE OVER CHICKEN BROOK

(42.146529, -71.426606)

TOWN OF MEDWAY
NORFOLK COUNTY

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

**COLLINS
ENGINEERS**
333 Elm Street, Suite 110
Dedham, MA 02026
Phone: 781-251-0630
Fax: 781-251-0633

NRG CONCEPTS, INC.
MEDWAY MILL
165 MAIN STREET,
SUITE 307
MEDWAY, MA 02053

INDEX, KEY PLAN, LOCUS MAP,
AND GENERAL NOTES

INDEX	
SHEET NO.	DESCRIPTION
1	INDEX, KEY PLAN, LOCUS MAP, AND GENERAL NOTES
2	NOTES
3	PLAN AND ELEVATION
4	ABUTMENT PLAN, ELEVATION, AND SECTIONS
5	GRAVITY WALLS AND APPROACH SLAB DETAILS
6	FRAMING PLAN AND BEAM DETAILS
7	TYPICAL SECTION, SAFETY CURB, DECK SLAB, AND BEARING DETAILS
8	THREE-BEAM PANEL DETAILS AND SAFETY CURB TAPER PLAN


DESIGN CRITERIA:

DESIGN:	AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 8TH EDITION, NOVEMBER 2017
	MASSDOT LRFD BRIDGE MANUAL 2013 EDITION
	MASSACHUSETTS STATE BUILDING CODE - 780 CMR
	AMERICAN CONCRETE INSTITUTE (ACI 318-19)
	ASCE/SEI 7-16
LIVE LOAD:	E-ONE (75,000 LBS.) (PER OWNER AND MEDWAY FIRE DEPT.) (AERIAL BODY, CYCLONE II X CHASSIS, HP100 AERIAL LADDER)
DEAD LOAD:	INCLUDES 40.8 PSF WEARING SURFACE
SEISMIC PARAMETERS:	$A_g = 0.08$ $S_{ps} = 0.17$ $S_{p1} = 0.07$ SITE CLASS "C" SEISMIC ZONE 1 SEISMIC DESIGN CATEGORY A
REINFORCING STEEL:	SEE SHEET NO. 2
PRESTRESSED CONCRETE:	SEE SHEET NO. 6
CONCRETE:	SEE SHEET NO. 2


SPECIFICATIONS AND REFERENCES

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF TRANSPORTATION
STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES
2021 EDITION

GEOTECHNICAL ENGINEERING ASSESSMENT, GEOINSIGHT, 31 JULY 2020 (GEA)



KEY PLAN
N.T.S.



LOCUS MAP
N.T.S.

SCOPE OF WORK:

CONSTRUCTION DRAWINGS FOR A NEW BRIDGE MEASURING APPROXIMATELY 15 FEET WIDE WITH AN APPROXIMATE SPAN OF 30 FEET, THE NEW STRUCTURE WILL ABUT THE EXISTING STRUCTURE.

GENERAL NOTES:


- EXISTING INFORMATION AND PROPOSED CONSTRUCTION IS BASED ON A LIMITED SITE SURVEY PLAN PROVIDED BY THE OWNER AND LIMITED FIELD MEASUREMENTS AND OBSERVATIONS CONDUCTED BY COLLINS ON JULY 8, 2020. CONTRACTOR MUST CONDUCT AN INDEPENDENT SITE SURVEY TO ESTABLISH VERTICAL AND HORIZONTAL CONTROL AND TO VERIFY EXISTING CONDITIONS. NOTIFY THE OWNER WHERE EXISTING CONDITIONS ARE DIFFERENT FROM THOSE SHOWN.
- "ENGINEER" AS USED IN THESE DRAWINGS REFERS TO THE OWNER OR THE OWNER'S REPRESENTATIVE.
- METHODS, PROCEDURES AND SEQUENCES OF CONSTRUCTION ARE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING AND IMPLEMENTING THE NECESSARY PRECAUTIONS TO MAINTAIN AND ENSURE THE INTEGRITY OF THE STRUCTURE DURING CONSTRUCTION.
- TEMPORARY BRACING, SHEETING, SHORING, ETC. REQUIRED TO ENSURE THE STRUCTURAL INTEGRITY/STABILITY OF THE EXISTING BUILDINGS, SIDEWALKS, UTILITIES, ETC. DURING CONSTRUCTION IS THE RESPONSIBILITY OF THE CONTRACTOR.
- IMPLEMENTATION OF JOB SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

GENERAL NOTES (CONTINUED):

- IN CASE OF CONFLICT BETWEEN THE GENERAL NOTES, SPECIFICATIONS, AND DRAWINGS, THE MOST RIGID REQUIREMENTS WILL GOVERN.
- WORK NOT INDICATED ON A PART OF THE DRAWINGS, BUT REASONABLY IMPLIED TO BE SIMILAR TO THAT SHOWN AT CORRESPONDING LOCATIONS, IS TO BE REPEATED.
- THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE OVER SHOP DRAWINGS UNLESS SPECIFICALLY NOTED OTHERWISE.
- INSPECTION, TESTING, CONSTRUCTION, WORKMANSHIP AND MATERIALS, SPECIFICATIONS, SHALL CONFORM TO THE REQUIREMENTS OF THE GOVERNING BUILDING CODES AND REFERENCED STANDARDS.
- COORDINATE ANY CONSTRUCTION SITUATION NOT COVERED BY THESE PLANS, GENERAL NOTES, OR SPECIFICATIONS WITH THE OWNER.
- THE PROJECT SHALL BE SECURED AT ALL TIMES DURING CONSTRUCTION.
- CONTRACTOR SHALL CONFINE ALL WORK TO THE LIMITS ESTABLISHED BY THE OWNER.
- COLLINS ENGINEERS, INC. ASSUMES NO RESPONSIBILITY FOR DAMAGES, LIABILITY, OR COSTS FROM CHANGES OR ALTERATIONS MADE TO THESE DESIGN DRAWINGS WITHOUT COLLINS WRITTEN PERMISSION.

SCALES:

PLAN SHEETS ARE TO BE PRINTED ON 22"x34" SHEETS AT 100% SCALE. IF HALF SIZES (11"x17") ARE WARRANTED, PRINT PLANS AT 50% SCALE. NOTE: AT 50% SCALE, THE SCALES INDICATED ON EACH SHEET SHALL BE HALVED.



DESIGN		DESCRIPTION	
NO.	DATE	BY	
DESIGN BY:		RCB	
DRAWN BY:		RCB	
CHECKED BY:		AD	
DATE:		09/24/2021	
SHEET NO:		01	

NOTES

EXISTING PLAN:

PLAN FOR THE EXISTING BRIDGE ARE AVAILABLE FROM GUERRIERE & HALNON, INC., DATED JUNE 24, 2020.

EXISTING CONDITIONS:

1. THE CONTRACTOR SHALL DETERMINE AND ESTABLISH ALL DIMENSIONS AND EXISTING DETAILS NECESSARY FOR THE COMPLETION OF WORK BY FIELD MEASUREMENTS AND SURVEY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADEQUACY AND ACCURACY THEREOF AND SHALL NOT ORDER ANY MATERIALS OR COMMENCE ANY FABRICATION UNTIL THE REQUIRED MEASUREMENTS HAVE BEEN MADE ON THE ACTUAL STRUCTURE AND THE EXTENT OF PROPOSED WORK HAS BEEN APPROVED BY THE OWNER.
2. WHERE EXISTING CONDITIONS DIFFER FROM THOSE SHOWN, NOTIFY THE OWNER PRIOR TO FABRICATION OF ANY STRUCTURAL COMPONENT.
3. DETAILS DESIGNATED AS "TYPICAL DETAILS", APPLY GENERALLY TO THE DRAWINGS IN AREAS WHERE CONDITIONS ARE SIMILAR TO THOSE DESCRIBED IN THE DETAILS.

UTILITIES:

1. ALL UTILITIES LOCATIONS ARE APPROXIMATE AND SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
2. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL UTILITIES LOCATED AND MARKED PRIOR TO START OF CONSTRUCTION. ANY FOUND UTILITIES NOT STATED ABOVE SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER FOR DIRECTION, PRIOR TO PROCEEDING WITH CONSTRUCTION IN THE AREA OF SAID UTILITIES. THE VERIFIED LOCATIONS OF ALL UTILITIES SHALL BE DEPICTED ON THE WORKING RECORD DRAWINGS AND AS-BUILT DRAWINGS.
3. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES AND PROTECT FROM DAMAGE.
4. THE CONTRACTOR MUST COORDINATE ALL WORK WITH THE TOWN OF MEDWAY, ALL UTILITY COMPANIES, AND ANY ABUTTERS AS DIRECTED BY THE OWNER.

TRAFFIC:

1. BRIDGE SHALL BE CLOSED TO TRAFFIC DURING CONSTRUCTION.
2. ROAD WILL BE CLOSED TO ALL TRAFFIC DURING PERIOD OF PERFORMANCE. CONTRACTOR TO PROVIDE ROAD CLOSURE SIGNAGE.
3. THE CONTRACTOR SHALL NOT OBSTRUCT THE RIGHT-OF-WAY OF ADJACENT PROPERTIES DURING THE WORK.

STORMWATER POLLUTION PREVENTION PLAN (SWPPP):

THE CONTRACTOR SHALL ENSURE THAT BEST MANAGEMENT PRACTICES (BMPS) ARE IN PLACE PRIOR TO AND DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT EROSION AND SEDIMENT CONTROL MEASURES COMPLY WITH FEDERAL, STATE, AND LOCAL REGULATIONS.

SEDIMENT CONTROL:

CONTRACTOR SHALL PROVIDE AND MAINTAIN SEDIMENT CONTROL SERVICES IN ACCORDANCE WITH FEDERAL, STATE, AND LOCAL REGULATIONS THROUGHOUT THE TERM OF THE WORK COVERED BY THIS CONTRACT.

DRAINAGE:

1. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ADEQUATE DRAINAGE AT ALL TIMES DURING CONSTRUCTION OF PROPOSED BRIDGE.
2. CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE AT ALL TIMES DURING THE INSTALLATION OF THE STRUCTURES AND DRAINAGE IMPROVEMENTS.

CLEARING AND GRUBBING / DEMOLITION:

1. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL STRUCTURES, DEBRIS, VEGETATION, TREES, AND OTHER WASTE MATERIAL AT AN APPROPRIATE OFF-SITE LOCATION. OTHER WASTE MATERIALS INCLUDING ROOTS, CONCRETE, SLURRY, AND DRAINAGE DEBRIS COLLECTED SHALL BE DISPOSED OF OFF-SITE BY THE CONTRACTOR.
2. THE CONTRACTOR SHALL PRESERVE AND PROTECT OR REMOVE (WITH PRIOR WRITTEN APPROVAL OF AFFECTED PROPERTY OWNERS) ALL TREES, SHRUBS, HEDGES, RETAINING WALLS, LANDSCAPING, BUILDINGS, WALKS, ETC., IN OR NEAR CONSTRUCTION AREA.
3. CONTRACTOR SHALL DISPOSE OF ALL DEMOLITION DEBRIS, CONSTRUCTION DEBRIS, WOOD WASTES, CONTAMINATED SOILS, HAZARDOUS MATERIALS, AND OTHER SPECIAL WASTES IN STRICT ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS.
4. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY NOT TO DAMAGE THOSE PORTIONS OF THE EXISTING THAT ARE TO REMAIN. SITE, BRIDGE AND SUBSTRUCTURE DAMAGE RESULTING FROM THE CONTRACTOR'S OPERATIONS, SHALL BE REPAIRED TO THE SATISFACTION OF THE OWNER AND AT THE CONTRACTOR'S EXPENSE.
5. STOCKPILING OF MATERIAL IS NOT ALLOWED INSIDE THE FLOODPLAIN.
6. CONTRACTOR IS ADVISED THAT ADDITIONAL DEMOLITION OF ELEMENTS NOT OTHERWISE UNCOVERED OR OBSERVED MAY BE REQUIRED TO COMPLETE THE WORK.

EXCAVATION:

1. ALL EXCAVATED MATERIAL MUST BE DISPOSED OF AT AN APPROVED DISPOSAL LOCATION, UNLESS OTHERWISE NOTED OR APPROVED FOR USE AS BACKFILL MATERIAL.
2. TRUCKS SHALL BE LOADED IN A MANNER SO AS TO AVOID LOSS OF LOADED MATERIAL OR ANY PORTION THEREOF DURING TRANSPORT IN ACCORDANCE WITH STATE LAW.

FOUNDATIONS:

1. COMPLETE SUBGRADE PREPARATION IN ACCORDANCE WITH THE GEA.
2. FOUNDATIONS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE GEA; MAXIMUM DESIGN FOUNDATION BEARING PRESSURE IS 2.9 KSF.
3. SUBSTRUCTURE CONCRETE MUST BE PLACED IN THE DRY.
4. OPERABLE EQUIPMENT SHALL NOT OPERATE WITHIN 7 FEET FROM THE BACK FACE OF THE FOOTINGS WITHOUT APPROVAL FROM A GEOTECHNICAL ENGINEER.

CONCRETE:

1. 4000 PSI, 3/4 IN, 585 HP CEMENT CONCRETE SHALL BE USED FOR DECK SLAB. 5000 PSI, 3/4 IN, 685 HP CEMENT CONCRETE SHALL BE USED FOR SAFETY CURBS. 4000 PSI, 3/8 IN, 660 CEMENT CONCRETE SHALL BE USED FOR SUBSTRUCTURE REPAIRS.
2. ALL EXPOSED EDGES SHALL BE CAST WITH 3/4 INCH CHAMFERS. UNLESS OTHERWISE NOTED.

REINFORCEMENT:

REINFORCING STEEL SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M 31 GRADE 60. UNLESS OTHERWISE NOTED ON THE CONSTRUCTION DRAWINGS, ALL BARS SHALL BE LAPPED AS FOLLOWS:

<u>MODIFICATION CONDITION</u>	<u>#4 BARS</u>	<u>#5 BARS</u>	<u>#6 BARS</u>
1. NONE	16"	19"	23"
2. 12" OF CONCRETE BELOW BAR	20"	25"	30"
3. EPOXY COATED BARS, COVER $<3d_b$, OR CLEAR SPACING $<6d_b$	23"	29"	34"
4. COATED BARS, ALL OTHER CASES	18"	23"	27"
5. CONDITION 2. AND 3.	26"	32"	39"
6. CONDITION 2. AND 4.	24"	30"	36"

ALL OTHER BARS SHALL BE LAPPED AS SHOWN ON THE CONSTRUCTION DRAWINGS.

SUBMITTALS:

1. PROVIDE THE FOLLOWING SUBMITTALS TO THE OWNER A MINIMUM OF 15 DAYS BEFORE ADVANCING THE WORK:
- A. SEQUENCE OF DEMOLITION, CONSTRUCTION AND PROPOSED EQUIPMENT
 - B. SCHEDULE OF VALUES BROKEN OUT BY PERCENT OF TOTAL FOR:
 - 1. DEMOLITION
 - 2. SUBGRADE PREPARATION
 - 3. CAST-IN-PLACE CONCRETE CONSTRUCTION
 - 4. SUPERSTRUCTURE CONSTRUCTION
 - 5. PAVING AND GUARDRAIL INSTALLATION
 - 6. SITE RESTORATION
 - C. LIST OF SUBCONTRACTORS
 - D. NAME AND LOCATION OF DISPOSAL FACILITIES, AND PROOF OF MATERIALS ACCEPTED AT THE FACILITY(S)
 - E. LIST OF PRODUCERS/SUPPLIERS/FABRICATORS FOR FOR AGGREGATES, SOILS, CONCRETE, PAVEMENT AND GUARDRAIL
 - F. WRITTEN SWPP PLAN
 - G. WRITTEN PLAN FOR PREVENTING DEBRIS AND CONSTRUCTION MATERIALS FROM ENTERING CHICKEN BROOK
 - H. SITE RESTORATION PLAN

APPROVED DATE: 6-22-2021
MIDWAY PLANNING BOARD
[Signature]
[Signature]
[Signature]

BEING A MAJORITY

ENDORSEMENT DATE 10-12-202

CONTRACTOR RESPONSIBILITIES AND COORDINATION:

1. THE CONTRACTOR SHALL FURNISH ALL LABOR AND MATERIALS FOR SUCCESSFUL COMPLETION OF THIS PROJECT.
2. THE SPECIFICATIONS AND DESIGN DRAWINGS REPRESENT THE FINISHED STRUCTURE AND DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE MEANS, METHODS, TECHNIQUES, SEQUENCES, AND OPERATION OF CONSTRUCTION AND SAFETY PRECAUTIONS AND PROGRAMS INCIDENTAL THERETO.
3. THE SPECIFICATIONS ARE AN INTEGRAL PART OF THE CONTRACT DOCUMENTS AND SHALL BE USED IN CONJUNCTION WITH THE DRAWINGS. IN CASES, IF ANY, WHERE REQUIREMENTS INDICATED ON THE DRAWINGS DIFFER FROM THE SPECIFICATIONS, NOTIFY THE OWNER.
4. THE CONTRACTOR IS RESPONSIBLE FOR THE STABILITY OF THE STRUCTURE UNTIL THE CONSTRUCTION OF THE STRUCTURE REACHES ITS FINISHED STATE.
5. TEMPORARY EARTH SUPPORT IS NOT SHOWN ON DESIGN DRAWINGS AND IS REQUIRED FOR THIS PROJECT. CONTRACTOR SHALL DESIGN, DETAIL, AND PROVIDE TEMPORARY EARTH SUPPORTS AS REQUIRED ACCORDING TO HIS MEANS, METHODS, AND TECHNIQUES. CONTRACTOR ACCEPTS FULL RESPONSIBILITY TO COMPLY WITH CURRENT CODES, SPECIFICATIONS, AND STATE AND TOWN REQUIREMENTS.
6. THE CONTRACTOR IS RESPONSIBLE FOR DAMAGE DONE TO ADJACENT STRUCTURES AND LANDSCAPING NOT WITHIN THE SCOPE OF THIS PROJECT AS A RESULT OF PERFORMING THIS WORK. CONTRACTOR SHALL PROVIDE COMPLETE REPAIR OR REPLACEMENT OF SUCH DAMAGES TO THE SATISFACTION OF THE OWNER.
7. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE THE WORK WITH THE OTHER APPLICABLE TRADES.
8. MATERIALS AND EQUIPMENT SHALL BE STORED AND TRANSPORTED IN A MANNER APPROVED OF BY THE OWNER.
9. THE CONTRACTOR SHALL MAKE NO DEVIATION FROM THE DESIGN DRAWINGS WITHOUT WRITTEN APPROVAL FROM THE OWNER.
10. THE CONTRACTOR SHALL NOTIFY THE OWNER OF ANY DISCREPANCIES BETWEEN THE STRUCTURAL DOCUMENTS, DRAWINGS, DETAILS, SPECIFICATIONS, AND ANY OTHER DOCUMENTS OR EXISTING CONDITIONS FOR RESOLUTION PRIOR TO PROCEEDING WITH THE WORK. DO NOT ASSUME THAT EITHER THE DRAWINGS OR SPECIFICATIONS TAKE PRECEDENCE.
11. THE CONTRACTOR SHALL NOTIFY THE OWNER OF ANY DISCREPANCIES BETWEEN THE STRUCTURAL DOCUMENTS, DRAWINGS, SPECIFICATIONS, AND ANY OTHER DOCUMENTS OR EXISTING CONDITIONS, FOR RESOLUTION PRIOR TO PROCEEDING WITH THE WORK.
12. THE CONTRACTOR IS RESPONSIBLE FOR THE STABILITY OF THE EXISTING AND PROPOSED STRUCTURES UNTIL THE COMPLETION AND ACCEPTANCE OF THE WORK.
13. THE CONTRACTOR SHALL STOP WORK AND IMMEDIATELY NOTIFY THE OWNER IF CRACKS OR MOVEMENT ARE OBSERVED AT EXISTING STRUCTURES.

SPECIFICATIONS, MATERIALS AND SUPPLIERS:

1. WORK MUST BE COMPLETED IN ACCORDANCE WITH THE SPECIFICATIONS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1.1. SECTION 140 AND THE GEA
 - 1.2. SECTION 150 AND THE GEA
 - 1.3. SECTION 170 AND THE GEA
 - 1.4. SECTION 400 AND THE GEA
 - 1.5. SECTION 850
 - 1.6. SECTION 901, 965, 970, 975
2. MATERIALS MUST CONFORM TO DIVISION III SECTION M.
3. MATERIALS AND SUPPLIERS SHALL BE THOSE LISTED ON THE QUALIFIED CONSTRUCTION MATERIALS LIST.

**COLLINS
ENGINEERS^{INC}**
333 Elm Street, Suite 110
Dedham, MA 02026
Phone: 781-251-0630
Fax: 781-251-0633

ENRG CONCEPTS, INC.
MEDWAY MILL
165 MAIN STREET,
SUITE 307
MEDWAY, MA 02053

NOTES

NO.	DATE	DESIGN BY	DESCRIPTION



DESIGN BY: RCB

DRAWN BY: RCB



CHECKED BY: AD

DATE:
09/24/2021

SHEET NO:
02



- NOTES:**
1. PROTECTIVE COURSE TO BE CLASS I DENSE BINDER COURSE FOR BRIDGES, PLACED IN 2" LAYERS AND COMPACTED WITH A MECHANICAL HAND-GUIDED TAMPER WITHIN 12 HOURS AFTER PLACING MEMBRANE WATERPROOFING.
 2. ALL REINFORCING SHOWN IN THESE DETAILS SHALL BE COATED BARS, EXCEPT FOR APPROACH SLAB REINFORCEMENT.
 3. ATTACH CLOSED CELL FOAM TO BACK OF PRECAST BEAM WITH ADHESIVE.
 4. BACKWALL CONCRETE SHALL BE PLACED AFTER ALL BEAMS HAVE BEEN ERECTED.
 5. 4000 PSI, 3/4 IN, 610 CEMENT CONCRETE SHALL BE USED FOR THE BACKWALL.
 6. DRAPE MEMBRANE WATERPROOFING OVER CLOSED CELL FOAM BACKER ROD.
 7. THE FACTORED BEARING PRESSURE = 2.9 KSF AS PER AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS STRENGTH I LOAD COMBINATION.
 8. FACTORED BEARING RESISTANCE = 4.5 KSF. FACTORED BEARING RESISTANCE IS THE PRODUCT OF THE NOMINAL BEARING RESISTANCE AND A RESISTANCE FACTOR OF 0.45.
 9. PORTIONS OF THE ABUTMENTS, EXPOSED ABOVE GRADE, SHALL BE MADE TO APPEAR IN A FASHION THAT REINFORCES THE INDIGENOUS APPEARANCE OF THE MILL AREA.
 10. ABUTMENTS ARE TO BE BACKFILLED IN FRONT AND BACK BEFORE SUPERSTRUCTURE PLACEMENT BEGINS.
 11. THE ELEVATION OF THE BOTTOM OF FOOTING SHALL MATCH THE ELEVATION OF THE BOTTOM OF THE EXISTING RETAINING WALLS.
 12. THE ELEVATION OF THE ABUTMENT SEAT SHALL BE 21 1/2" BELOW THE PROPOSED ELEVATION OF THE PROPOSED WEARING SURFACE OF THE PROPOSED BRIDGE.
 13. THE ABUTMENT STEM HEIGHT SHOWN IS BASED ON AVAILABLE INFORMATION AND MAY BE ADJUSTED TO ACCOMMODATE ELEVATION DIFFERENCED IDENTIFIED AS A RESULT OF CONTRACTORS SURVEY.







**COLLINS
ENGINEERS^{INC.}**
333 Elm Street, Suite 110
Dedham, MA 02026
Phone: 781-251-0630
Fax: 781-251-0633

NRG CONCEPTS, INC.
MEDWAY MILL
165 MAIN STREET,
SUITE 307
MEDWAY, MA 02053

ABUTMENT PLAN, ELEVATION,
AND SECTIONS


NO.	DATE	DESIGN BY	DESCRIPTION
DESIGN BY:	RCB		
DRAWN BY:	RCB		
CHECKED BY:	AD		
DATE: 09/24/2021			
SHEET NO: 04			



1. ALL REINFORCING SHOWN IN THESE DETAILS SHALL BE COATED BARS, EXCEPT FOR APPROACH SLAB REINFORCEMENT.
2. PLACE LONGITUDINAL REINFORCEMENT PARALLEL TO ϕ CONSTRUCTION PLACE TRANSVERSE REINFORCEMENT PARALLEL TO ABUTMENT.
3. ATTACH CLOSED CELL FOAM TO BACKWALL WITH ADHESIVE.
4. THE ELEVATION OF THE BOTTOM OF FOOTING SHALL MATCH THE ELEVATION OF THE BOTTOM OF THE EXISTING RETAINING WALLS.
5. THE GRAVITY WALL STEM HEIGHT SHOWN IS BASED ON AVAILABLE INFORMATION AND MAY BE ADJUSTED TO ACCOMMODATE ELEVATION DIFFERENCED IDENTIFIED AS A RESULT OF CONTRACTORS SURVEY.
6. THE GRAVITY WALL LENGTH SHALL BE DETERMINED BY THE CONTRACTOR BASED ON THE CONDITION AND SLOPE OF THE EXISTING BANKS.



05

GRAVITY WALLS AND APPROACH SLAB DETAILS



FRAMING PLAN
SCALE: $\frac{1}{8}$ " = 1'-0"

NOTE:
SEE STANDARD SPECIFICATIONS FOR
BEAMS ERECTION AND LAYOUT.






DETAIL 1 NOTES:




1. MORTAR FOR EXTERIOR POCKETS SHALL CONFORM TO M4.02.15 AND SHALL BE THE SAME COLOR AND TEXTURE AS THE BEAM CONCRETE.
2. OTHER ANCHORAGE SYSTEMS MAY BE SUBSTITUTED WITH THE APPROVAL OF THE OWNER. ALTERNATE ANCHORAGE SYSTEMS SHALL BE WATERTIGHT AND CORROSION PROOF.
3. TRANSVERSE TIES SHALL BE COVERED BY A SEAMLESS POLYPROPYLENE SHEATH (WITH CORROSION INHIBITING GREASE BETWEEN THE STRAND AND SHEATH) FOR THE FULL LENGTH OF THE STRAND, EXCEPT AT THE ANCHORAGE LOCATION.

PRESTRESS NOTES:



1. ALL PRETENSIONING ELEMENTS SHALL BE 0.6" ϕ , UNCOATED, SEVEN-WIRE, LOW RELAXATION STEEL STRANDS AND SHALL CONFORM TO AASHTO M 203.
2. THE TENSILE STRENGTH OF THE PRETENSIONING STRANDS SHALL BE 270 KSI.
3. THE INITIAL TENSION PER 0.6" ϕ STRAND SHALL BE 44 KIPS.
4. THE MINIMUM 28 DAY COMPRESSIVE STRENGTH SHALL BE 6500 PSI.
5. NO PRESTRESS SHALL BE TRANSFERRED TO THE CONCRETE UNTIL IT HAS ATTAINED A COMPRESSIVE STRENGTH, AS SHOWN BY CYLINDER TEST, OF AT LEAST 4500 PSI.
6. THE TOP OF ALL BEAMS SHALL BE GIVEN A RAKE FINISH ($\frac{1}{4}$ " AMPLITUDE) ACROSS THE WIDTH (PERPENDICULAR TO THE BEAM'S AXIS).
7. THE FABRICATOR IS FULLY RESPONSIBLE FOR THE DESIGN OF THE LIFTING DEVICES WHICH SHALL BE ADEQUATE FOR THE SAFETY FACTORS REQUIRED BY THE ERECTION PROCEDURE.
8. + DENOTES STRAIGHT STRANDS.
9. SEE BEAM ELEVATION FOR STIRRUP SPACING.



NOTE: C.G. = CENTER OF GRAVITY OF BEAM



* SEE SAFETY CHAIR DETAIL ON NEXT SHEET FOR ADDITIONAL BEAM #5 REINFORCEMENT.



CONSTRUCTION SEQUENCE NOTES:

1. AFTER ALL BEAMS HAVE BEEN ERECTED, TENSION EACH TRANSVERSE TIE TO 5 KIPS.
2. FILL ALL KEYWAYS WITH MORTAR (M4.04.0). IF THE KEYWAYS ARE NOT FILLED WITHIN FIVE (5) DAYS AFTER THE BEAMS ARE ERECTED, THE CONTRACTOR SHALL COVER AND PROTECT THE KEYWAYS FROM WEATHER AND DEBRIS UNTIL THEY ARE FILLED.
3. AFTER THE MORTAR HAS CURED (24 HOURS MINIMUM), TENSION EACH TRANSVERSE TIE TO 44 KIPS.
4. CONCRETE FOR DECK SLAB SHALL BE 4000 PSI, $\frac{3}{4}$ IN, 585 HP CEMENT CONCRETE AND SHALL BE PLACED AFTER THE TRANSVERSE TIES HAVE BEEN FULLY TENSIONED.
5. NO TRAFFIC OR HEAVY EQUIPMENT WILL BE PERMITTED ON THE BRIDGE UNTIL ALL TRANSVERSE TIES HAVE BEEN PROPERLY TENSIONED AND THE DECK HAS BEEN CAST AND CURED PER THE STANDARD SPECIFICATIONS.

APPROVED DATE: 6-22-2021

MEDWAY PLANNING BOARD

DESIGN BY: [Signature]
DATE: [Signature]
NO. [Signature]

BEING A MAJORITY

ENDORSEMENT DATE: 10-12-2021



COLLINS ENGINEERS
333 Elm Street, Suite 110
Dedham, MA 02026
Phone: 781-251-0630
Fax: 781-251-0633

NRG CONCEPTS, INC.
MEDWAY MILL
165 MAIN STREET,
SUITE 307
MEDWAY, MA 02053



**FRAMING PLAN AND
BEAM DETAILS**

DESIGN NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		

DESIGN BY: RCB
DRAWN BY: RCB
CHECKED BY: WMM
DATE: 09/24/2021
SHEET NO: 06



NOTE:
1. PROVIDE $\frac{1}{8}$ "/FT SLOPE BETWEEN BEARINGS.



APPROVED DATE: 6-22-2021

MIDWAY PLANNING BOARD

[Signature]

[Signature]

[Signature]

BEING A MAJORITY

ENDORSEMENT DATE 10-12-2021

**COLLINS
ENGINEERS^{PC}**
333 Elm Street, Suite 110
Dedham, MA 02026
Phone: 781-251-0630
Fax: 781-251-0633

NRG CONCEPTS, INC.
MEDWAY MILL
165 MAIN STREET,
SUITE 307
MEDWAY, MA 02053

TYPICAL SECTION,
SAFETY CURB, DECK SLAB,
AND BEARING DETAILS

NO.	DATE	DESIGN BY	DESCRIPTION






DESIGN BY: RCB

DRAWN BY: RCB


CHECKED BY: WMM

DATE:
09/24/2021

SHEET NO:
07



- MATERIALS:**
1. POSTS, BASE PLATES, AND ANCHOR PLATES SHALL BE AASHTO M 270 GRADE 50 GALVANIZED.
 2. THRIE-BEAM BRIDGE PANEL SHALL BE AASHTO M 180, CLASS B (10 GAUGE), AND GALVANIZED.
 3. NUTS, BOLTS, AND WASHERS SHALL BE GALVANIZED.
- GENERAL NOTES:**
1. SET POSTS PERPENDICULAR TO BRIDGE DECK.
 2. ANCHOR BOLTS SHALL BE SET WITH TEMPLATES. THE NUT SECURING THE POST BASE PLATE TO THE CONCRETE SHALL BE TIGHTENED TO A SNUG FIT AND GIVEN AN ADDITIONAL 1/2 TURN AFTER STEEL IS IN PLACE.
 3. WELDING SHALL CONFORM TO THE REQUIREMENTS OF AWS D1.5 - BRIDGE WELDING CODE.
 4. PLACE A REFLECTORIZED WASHER IN THE UPPER VALLEY OF EVERY THRIE-BEAM POST.
 5. THE MINIMUM EMBEDMENT OF THE 10"x10" TIMBER POSTS SHALL BE 4'-3 1/4".



COLLINS ENGINEERS
333 Elm Street, Suite 110
Dedham, MA 02026
Phone: 781-251-0630
Fax: 781-251-0633

NRG CONCEPTS, INC.
MEDWAY MILL
165 MAIN STREET,
SUITE 307
MEDWAY, MA 02053

**THRIE-BEAM PANEL DETAILS
AND
SAFETY CURB TAPER PLAN**

NO.	DATE	DESIGN BY	DESCRIPTION
1	09/24/2021	RCB	DESIGN BY: RCB
2		RCB	DRAWN BY: RCB
3		WMM	CHECKED BY: WMM
4			DATE: 09/24/2021
5			SHEET NO: 08