



COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC WORKS

45B Holliston Street
Medway, MA 02053
Phone (508) 533-3275
dps@townofmedway.org

DPW Director
Peter Pelletier

Deputy Director
Nolan Lynch

Town of Medway Street Standards

Standards to be Employed when restoring any roadway and public right of way.

Section:

1. Purpose and Scope
2. Definitions
3. Permit Requirements
4. Work Standards
5. Safety
6. Protection of Adjoining Facilities
7. Excavations
8. Backfill and Compaction
9. Pavement Restoration
10. Sidewalks and Driveways

1. Purpose and Scope

- 1.1 The purpose of these Standards is to ensure that a Contractor, after excavating in any Town street, lane, or highway ("public ways"), restores such street, lane or highway to the same condition in which they were found before the excavation. Such standards apply to both paved and unpaved areas of the public way.
- 1.2 Nothing in these Standards is intended to be inconsistent with any ordinance or bylaw and the constitution and laws of the Commonwealth.
 - (a). The Contractor is responsible for insuring compliance, for itself and its subcontractors, with these Standards. However, work may be inspected by the Town to assure that proper procedures are being followed. In the event a Contractor fails to comply with these Standards, he shall, at his own expense, correct such failures.

1. Definitions

AASHTO means The American Association of State Highway and Transportation Officials.

Applicant means any person(s) or organization requesting a Permit to perform Street Opening Work in a public way.

Clay means very finely textured soil which, when moist, forms a cast which can be handled freely without crumbling/breaking; that exhibits plasticity; and when dried, breaks into very hard lumps i.e., high dry strength) and is difficult to pulverize into a soft, flour-like powder.

Cold Patch means a bituminous concrete made with slow curing asphalts and used primarily as a temporary patching material when hot mix plants are closed. Compaction means compressing of suitable material and gravel that has been used to backfill an excavation by means of mechanical tamping to within 95% of maximum dry density as determined by the modified Proctor test in accordance with AASHTO T180.

Medway Street Standards

Contractor means, for the purpose of these Standards, any person or entity engaged by or on behalf of an Applicant to perform Street Opening Work in the Town of Medway.

Controlled Density Fill ("CDF"), meeting MHD Specification M4.08.0 Type 2E (flowable, excavatable), also called flowable fill means a mixture of portland cement, fly ash, sand and water. High air (25% plus) may be used instead of fly ash with an adjustment in sand content. CDF is hand-tool excavatable.

DTE means the Department of Telecommunications and Energy.

Emergency Repair Work means street opening work which must be commenced immediately to correct a hazardous condition whose continuation would unreasonably risk injury, loss of life or property damage.

Gravel means coarse to very coarse-grained soil ranging from approximately 0.1 inch to 3.0 inches. Gravel exhibits no plasticity.

Infrared Process means a recycling procedure whereby an infrared heater plasticizes the surface of an asphalt pavement, preparatory to the introduction of additional compatible paving materials uniformly reworked and compacted to achieve a density and profile consistent and thoroughly integrated with the adjacent pavement.

MHD means the Massachusetts Highway Department.

Mass. Highway Standards means the "Commonwealth of Massachusetts Department of Public Works Standard Specifications for Highways and Bridges, 1988 edition."

Newly Paved Road means a road whose re-paving is less than five years old.

Organic Soil means soil high in organic content, usually dark (brown or black) in color. When considerable fibrous material is the principal constituent, it is generally classified as "peat." Plant remains or a woody structure may be recognized and the soil usually has a distinct odor. Organic soil may exhibit little (or a trace of) plasticity.

Permanent Patch means a final repair of street opening work to be performed in accordance with these Standards and intended to permanently return the opened portion of the roadway to as good a condition as it was prior to the performance of the street opening work.

Permit means a permit granted by the Town to an Applicant for permission to do street opening work in a public way.

Plasticity means that property of soil that allows it to be deformed or molded without crumbling (e.g., like dough or soft rubber). This property reflects the capacity of soil to absorb moisture.

Poorly Graded Soil means soil that contains a large percentage of its constituent particles within a relatively narrow range; also referred to as "uniform" soil.

Sand means coarse grained soil in which the individual grains can be visually detected. When moist it forms a cast which will crumble when lightly touched; when dry, it will not form a cast and will fall apart when confining pressure is released. Sand exhibits no plasticity.

Silt means finely-textured soil. When moist, it forms a cast which can be freely handled; when wet, it readily puddles; when dry, it may be cloddy and readily pulverizes into powder with a soft flour-like feel (i.e., low dry strength). Silt exhibits little or no plasticity.

Street Opening Work means any cutting, excavating, compacting, construction, repair or other disturbance in or under a public way, paved or unpaved, together with restoration of the public way in accordance with these Standards, Town ordinances and any other applicable law following such disturbance.

Temporary Patch means the application of either cold patch or Type I bituminous concrete compacted to achieve a density equal to that of the surrounding pavement.

Town means the Town of Medway.

Medway Street Standards

Well Graded Soil means soil having its constituent particles within a wide range, also referred to as "nonuniform" soil.

3.0 Permit Requirements

A Right of Way license and permit is required for a Contractor to perform work in the public way. A Permit is issued with the stipulation that it may be modified or revoked with just cause at any time at the discretion of the Town without rendering the Town liable in any way. The Town has the authority to inspect work in progress and the Contractor shall correct any deficiencies identified during said inspections. The following are required of a Contractor prior to the issuance of a Permit.

- 3.1 The work shall be performed in accordance with plans on file with the Town.
- 3.2 The Contractor shall notify the Town two (2) days prior to the start of work. No work shall be authorized or proceed without said notification.
- 3.3 The Contractor shall notify Dig Safe, in accordance with G.L. c. 82 § 40, at least seventy-two (72) hours prior to the start of work for the purpose of identifying the location of underground utilities.
- 3.4 The Contractor shall be responsible to contact the Town regarding the field location of any underground traffic control devices on this project.
- 3.5 A copy of the Permit must be on the job site at all times for inspection (except for emergency repair work). Failure to have the permit available could result in suspension of the rights granted by the Permit.
- 3.6 Work, day, and time constraints shall be conditions of the Permit.
- 3.7 If it becomes necessary to open the roadway surface in a larger area than specified in the Permit, the Contractor shall apply for an additional Permit to cover the project.
- 3.8 The Contractor shall notify the Town within three (3) days after completion of the physical work.
- 3.9 Contractor shall protect all storm drain inlets in the work area, use appropriate erosion and sediment controls, and minimize off-site sediment tracking

4.0 Work Standards

- 4.1 All work shall be in compliance with the Mass. Highway Standards as it pertains to utility street excavations and repairs unless modified by these Standards.
- 4.2 The Contractor shall be responsible for any settlement that may occur as a result of the work done in accordance with the Permit.
- 4.3 The Contractor shall be responsible for the ponding of water that may develop within the roadway which was caused by this work.
- 4.4 In the event a street opening failure presents a nuisance or a public safety problem, the Contractor shall respond to all trench restoration requests by the Town within twenty-four (24) hours. Non-response within the specified time will result in the required restoration work being done by the Town, with all expenses to be paid by the Contractor. The Contractor shall reimburse the Town for the invoiced amount within thirty (30) days.
- 4.5 Failure to respond to trench restoration requests may result in denial of future Permit requests.

5.0 Safety

Medway Street Standards

- 5.1 Provisions shall be made for the safety and protection of pedestrian traffic during the construction period.
- 5.2 The Contractor shall be responsible to furnish and erect all required signs and traffic safety devices.
- 5.3 Cones and non-reflecting warning devices shall not be left in operating position on the roadway when the daytime operations have ceased. If it becomes necessary for the Town to remove any construction warning devices or the appurtenances from the project due to negligence by the Contractor, all cost for this work will be charged to the Contractor.
- 5.4 Flashing arrow boards may be required in some instances by the Town. In such cases, they must be used as directed when operations occupy the roadway and shall be available for use at all times.
- 5.5 All signs and devices shall conform to the most recent edition, of the Manual on Uniform Traffic Control Devices (MUTCD).
- 5.6 Efforts shall be made to maintain normal traffic flow, but interruptions or obstructions to traffic shall be defined by conditions of the Permit.
- 5.7 When, in the opinion of the Town, the work constitutes a hazard to traffic in any area the Contractor may be required to suspend operations during certain hours and to remove any equipment from the roadway.
- 5.8 When a snow or ice condition exists during the progress of this work, the Contractor shall keep the area affected by the work safe for travel. The Town may restrict work during snow, sleet, or ice storms and subsequent snow removal operations.
- 5.9 The roadway surface shall be kept clean of debris at all times and shall be thoroughly cleaned at the completion of the work.
- 5.10 At the completion of the work done in accordance with the Permit, all disturbed areas shall be restored to a condition equal in kind to that which existed prior to the work.
- 5.11 Blasting, if necessary, shall be done in accordance with State law and Town By-law.
- 5.12 The Contractor shall supply copies of all log data and analyses collected from groundwater monitoring wells as required by State law and Town By-law.
- 5.13 The Town utilizes the Massachusetts Highway Department Standards for Line Clearance, in conformity with the National Electric Safety Code Standard Clearance for Highway Crossings.

6.0 Protection of Adjoining Facilities

- 6.1 If directed by the Town, photographs shall be taken prior to the start of work to insure restoration of designated areas to their former conditions within the limits of the work areas. Copies of the photographs shall be delivered to a place designated by the Town.
- 6.2 Care must be taken to not interfere with underground structures that exist in the area.
- 6.3 Care shall be exercised not to disturb any existing traffic duct systems. Any such system, if disturbed, shall be restored immediately to its original condition.
- 6.4 The Contractor shall be responsible to replace all pavement markings in kind which have been disturbed as a result of work done in accordance with the Permit. These pavement markings shall be restored within ten (10) days after this work is performed or as deemed necessary by the Town.
- 6.5 Existing guardrail that may be removed or damaged shall be reset or replaced to existing Mass. Highway Standards.
- 6.6 The Contractor will be responsible for any damage caused by its operation to curbing, structures, roadway, etc.

Medway Street Standards

- 6.7 No trees shall be cut or removed under this Permit.
- 6.8 Hand digging shall be required around roots of trees.
- 6.9 Tree Removal:
 - 6.9.1 The Contractor shall obtain written permission from the Tree Warden of the Town if it becomes necessary to remove any tree. Replacement trees must be obtained from an established nursery in accordance with "USA Standard for Nursery Stock". The trees will be replaced in size and specie as directed by said Tree Warden.
 - 6.9.2 The tree stump shall be removed a minimum of six (6) inches below the surrounding surface and all debris shall be disposed of outside the right-of-way line.
 - 6.9.3 The tree shall be removed under the supervision of a qualified tree surgeon.
- 6.10 Every effort shall be made to protect bound markers. However, if it becomes necessary to remove and reset any bound marker, the Contractor shall hire a registered professional land surveyor to perform this work. It shall be the responsibility of this land surveyor to submit to the Town a statement in writing and a plan containing his stamp and signature showing that said work has been performed.
- 6.11 These standards do not cover the installation of any utility poles.

7.0 Excavations

- 7.1 The surface of a roadway to be excavated for utility work shall be cut in reasonably straight and parallel lines using a jack hammer, saw or other accepted method to insure the least amount of damage to the roadway surface. The pavement, including reinforcing steel on concrete roadways, shall be cut the full depth of surfacing. The excavation shall only be between these lines. The cutting operation shall not be done with a backhoe, grade-all or any type of ripping equipment.
- 7.2 Steel plates used by a Contractor to protect an excavation shall be of sufficient thickness to resist bending, vibration, etc., under traffic loads and shall be anchored securely to prevent movement. If these conditions are not met, the Contractor will be required to back fill and pave the excavations daily. No open trench shall be left unattended overnight.
- 7.3 Steel sheeting, shoring or bracing shall be driven or placed for all depths over five (5) feet. At the discretion of the Town, said sheeting shall be left in place and cut off two (2) feet below the surface.
- 7.4 When a Contractor installs a service lateral to a customer, an opening may be made over the common supply line to make the proper connection, but the service should be bored or driven the remainder of the way wherever possible.
- 7.5 Water jetting of the trench area is prohibited. The Contractor may request a waiver of this requirement if it can provide verification of sufficient drainage in the trench for water jetting to be effective and proper compaction through the provisions of Section 8.14 witnessed and approved by the Town or its representative.

1. Backfill And Compaction

- 8.1 In restoring municipal roadways and right of ways, Contractors may utilize approved backfill material compacted to achieve soil density values of 95% modified Proctor density (as described in AASHTO T180), which may include, as the conditions warrant, the use of Controlled Density Fill ("CDF").

CDF is required on all trenches in the travelway on all roads paved within the past 5 years and on the following roadways. See Street Moratorium & Flowable Fill Listing for the most up to date information. The Contractor may request a waiver of this requirement if it can provide verification of adequate compaction through the provisions of Section 8.13 witnessed and approved by the Town or its representative.

- 8.2 If CDF is required or the selected option of the Contractor when backfilling excavations, the Contractor shall backfill with sand or stone as approved by the Town and compact to a level twelve (12) inches over utilities before adding CDF to the trench.

Medway Street Standards

- 8.3 CDF shall be utilized for those excavations where compaction cannot be readily accomplished with normal compaction methods.
- 8.4 If CDF is used around utilities, CDF shall flow under and around the pipe, conduit, or bedding material providing uniform support without leaving voids. CDF shall be discharged from the mixer by a reasonable means into the trench area to be filled. Filling operations shall proceed simultaneously on both sides of the pipe or conduit so that the two (2) fills are kept at approximately the same elevation at all times. An external load shall be applied to the pipe or conduit, sufficient to hold it in place before filling.
- 8.5 The trench in all cases shall be filled to the bottom of the existing pavement to provide room for the pavement restoration.
- 8.6 The following subsections provide general guidelines and criteria to determine whether a soil is suitable as backfill for Contractor excavations in roadways. They prescribe proper procedures for backfilling and compaction to achieve soil density values of 95% modified Proctor density. The ultimate objective is to obtain a finished road surface repair which will undergo settlements only within acceptable performance limits as defined within these standards for the functional life of the existing road. The guidelines are based on good engineering practice and testing of both materials and equipment.
- 8.7 Compliance with these Standards will insure satisfactory compaction. These Standards are to be used in the field when there is an absence of sieve analysis of materials, Proctor values of the soils and the corresponding inability to utilize a nuclear density gauge or sand cone field density test. The Contractor shall not be required to use other accepted testing methods. However, the Town reserves the right, at its own expense, to utilize other accepted testing methods to verify compaction. In the event of test failure, the Contractor shall be responsible for re-compacting the excavation to meet the required standards.
- 8.8 Suitability of Backfill Material.
- 8.8.1 This section addresses suitability of materials to obtain an adequate level of compaction.
- 8.8.2 Suitable backfill material is free of stones larger than half the size of the compacted lift as provided for in Mass. Highway Standards, construction debris, trash, frozen soil and other foreign material. It consists of the following:
- a. Well-graded gravel and sand;
 - b. Poorly graded gravel and sand;
 - c. Gravel-sand mixtures with a small amount of silt;
 - d. Gravel-sand mixtures with a small amount of silt and trace amounts of clay.
- 8.8.3 Unsuitable backfill materials consist of the following:
- a. Inorganic silts and clays;
 - b. Organic silts;
 - c. Organic soils including peat, humus, topsoil, swamp soils, mulch, and soils containing leaves, grass, branches, and other fibrous vegetable matter.
- 8.9 Evaluation of Excavated Soil.
- 8.9.1 The soil excavated from a trench shall be evaluated by trained personnel to determine whether or not it is suitable as a backfill in accordance with Subsection 8.7.

Medway Street Standards

- 8.9.2 An excavated soil that has been evaluated as suitable for backfill shall be reused provided its moisture content has been determined to be "suitable" in accordance with Subsection 8.8.
- 8.9.3 An excavated soil that has been evaluated as unsuitable for backfill shall be removed from the site and disposed of properly.
- 8.9.4 New material, which meets the requirements of Subsection 8.7, shall be brought in to replace excavated soil found to be unsuitable.

8.10 Proper Moisture Content for Backfill Material.

Proper moisture content i.e., ratio of moisture to mineral solid by weight in a soil) in a backfill is essential for effective compaction. Soils with too much moisture (wet) or too little moisture (dry) would not yield an adequate level of compaction. All material used as backfill, shall be examined by testing a sample prior to backfilling. This requirement applies to excavated soil to be reused as backfill and to new replacement material.

8.11 Field Determination of Moisture Content.

- 8.11.1 Trained personnel will conduct the following field test of moisture content, also referred to as a "soil ball" test.
- 8.11.2 The personnel conducting the soil ball test must do the following:
 - a. first take a handful of the particular soil from beneath the surface of a stockpile (excavated from trench or obtained from a borrow area) and then;
 - b. squeeze the sample firmly making a closed fist;
 - c. open the hand and observe, the condition of the soil ball;
 - d. if the soil ball is loose and crumbly, the soil is too dry for compaction;
 - e. if the soil ball drips water, the soil is too wet for compaction;
 - f. if the soil ball holds together firmly or breaks into large chunks, the soil has suitable moisture content for compaction.

8.12 Corrective Treatment When Moisture Content is Not Suitable:

- a. if the soil is too dry, small amounts of water may be added by sprinkling;
- b. if the soil is too wet, the soil may be dried out by spreading it out and exposing it to the atmosphere;
- c. after the remedial treatment, the soil shall be tested again (Subsection 8.11.2);
- d. if the corrective treatment is not effective, the soil shall be removed from the site and disposed of properly.

8.13 Backfill And Compaction Of Excavations.

- 8.13.1 Backfill and compaction shall be performed in accordance with Subsections 8.13.2 through 8.13.6, or Subsections 8.13.7 and 8.13.8. All utility lines shall be properly bedded with materials and in depths as specified by the appropriate utility prior to backfilling to obtain compaction values of 95% modified Proctor density.
- 8.13.2 Compaction equipment which may be used is specified in Table A. Compactors shall be operated in approximately the vertical position.
- 8.13.3 Care should be exercised when compacting near a buried facility to avoid damage to the facility.
- 8.13.4 The bottom of the excavation shall be level, free of stones and compacted in accordance with Subsection 8.13.5 prior to commencement of backfilling.
- 8.13.5 Compaction shall be performed by making a minimum of four (4) passes per lift with the compactor. The passes shall start around the perimeter of the excavation and move toward the center in an inward spiral.

Medway Street Standards

- 8.13.6 Backfill material shall be placed in lifts with the loose thickness (i.e., prior to compaction) as specified in Table A.
- 8.13.7 The effectiveness of any compaction method used other than that specified in this Section, including Table A, shall be determined by testing to establish the pre-compacted or loose thickness of lifts, the number of passes with the compactor required to obtain the desired results, the type of compacting tool used and the soil type.
- 8.13.8 All maintenance work shall be compacted in 6" lifts. Construction work shall, based on the specific compaction equipment used, utilize Table A to determine appropriate lifts. Construction work shall be defined as the installation of new or replacement facilities.

Table A

| Tool | Thickness of Lifts |
|---|--------------------|
| Pneumatic Air Tamper | 6" |
| Percussive Wacker Rammer | 6" - 12" |
| Vibratory Compactor (7,000lb) | 6" - 12" |
| Pavement Breaker Tampering Foot (60-90 lb) | 6" |

- 8.13.9 Well-graded gravel that may exist immediately under the paved surface shall be replaced in like-compacted depth.
- 8.13 Compaction Verification.
- 8.13.1 Compaction verification shall be performed in accordance with the following to assure that 95% modified Proctor density has been achieved:
- The compaction of each lift shall be verified using a Dynamic Cone Penetrometer (DCP), or equivalent as approved by the Town. For standard maintenance excavations, each lift shall be verified at one location. For longer excavations (e.g. trenches), a DCP test shall be made approximately every twenty-five (25) feet for each lift.
 - A DCP test shall be considered acceptable if, after fifteen (15) drops, the pass/fail reference line on the DCP is above the soil surface.
 - An unacceptable DCP test shall require that corrective measures be taken until an acceptable DCP test is achieved. This may include making additional passes with the compactor or, in some cases, removing the backfill material and starting over.

- 8.14 CDF, when used, shall not be applied to depths exceeding four (4) feet. For trenches beyond this depth, compacted material applied per the requirements of Section 8.13 and 8.14 shall be used first to reduce the depth of CDF required to four (4) feet.

8.15 Training.

Field personnel performing backfill and compaction operations shall be trained in the implementation of this procedure. Personnel shall receive retraining every two (2) years. The Contractor shall certify with the submission of a Permit application that all personnel are properly trained.

9.0 Pavement Restoration

- 9.1 The Contractor shall be responsible to replace all pavement disturbed by work under the Permit with homogeneous and in-kind pavement, unless otherwise stipulated, to the original strength and condition.

Medway Street Standards

- 9.2 Single gradation (Type I, surface course) bituminous concrete patches may be used when the existing pavement depth is less than three (3) inches, provided that the new patch is installed to a depth one (1) inch greater than the surrounding pavement.
- 9.3 Single gradation (Type I, binder course) bituminous concrete may be used where post grind and inlay method is a condition of the Permit. Minimum allowable depth of pavement shall be four (4) inches when utilizing the grind and inlay method. When the grind and inlay method is performed, the surface of the pavement shall be uniformly ground and removed to a minimum depth of one and one-half (1.5) inches for subsequent pavement replacement. The grinding procedure shall provide a cutback into existing undisturbed pavement and shall encompass all disturbed pavement areas of the excavation. Grinding shall be done in reasonably straight lines.
- 9.4 All non-emergency pavement excavations shall be repaired with same day permanent patches unless specifically exempted in the permit.
- 9.5 Same day patches installed in conformance with these Standards will not require re-excavation and may utilize the infrared method or the grind and inlay method to correct subsequent settlements. However, the restoration of single patches up to five (5) feet by seven (7) feet in area shall be by the infrared method, unless another method is agreed to by the Town.
- 9.6 Immediately following the procedures outlined in the section for Backfill and Compaction, the adjacent pavement shall be cut back, full depth, to encompass all disturbed pavement areas and underlying cavities associated with the excavation. All cutbacks shall be done in reasonably straight and parallel lines.
- 9.7 All existing pavement surfaces shall be swept clean of dirt, dust, and debris prior to patching. The existing vertical pavement surfaces shall be tack coated with an appropriate asphalt tacking material prior to patching and subsequent to cleaning.
- 9.8 Pavement repair depths shall equal or exceed adjoining pavement depths. When existing pavement depths are greater than two (2) inches, pavement repairs shall be made utilizing Type I, binder course in the underlying patch courses. The wearing surface shall be a minimum one and one-half (1.5) inches of Type I, surface course. Pavement courses shall not exceed two (2) inches. All pavement courses shall be thoroughly compacted prior to placement of subsequent courses.
- 9.9 When the pavement remaining between an excavation and the edge of the roadway is less than two (2) feet, the remaining area shall be removed and replaced in conjunction with the permanent pavement repair.
- 9.10 All leak detection holes (i.e. bar holes) shall be filled to refusal with an appropriate asphalt filler to a depth equal to the surrounding pavement depth.
- 9.11 Temporary pavement repairs shall be permitted under the following conditions:
- a. Emergency Repair Work completed outside normal Monday through Friday working hours.
 - b. Emergency repair work performed between November 15 and March 31 when bituminous concrete is not available on a daily basis.
 - c. Excavations which shall be reopened within three (3) working days.
- 9.12 The Contractor shall make every effort to limit excavations conducted under the aforementioned conditions.
- 9.13 All excavation, back fill, and compaction work associated with temporary patches shall be performed in accordance with these Standards.
- 9.14 Temporary patches shall be made with high-performance cold patch or Type I, bituminous concrete to a minimum depth of four (4) inches. Temporary patches made between November 15 and March 31 shall be removed and replaced with a permanent patch as outlined above within five (5) working days. Temporary patches made between April 1 and November 14 shall be removed and replaced with a permanent patch as outlined above within two (2) working days.

Medway Street Standards

- 9.15 The Contractor shall be responsible to maintain temporary patches in a safe condition for all types of travel until a permanent pavement repair has been made.
- 9.16 The Town shall have jurisdiction to determine the pavement repair method to be utilized on all pavements which have been installed for less than five (5) years.
- 9.17 Completed pavement repairs shall not deviate more than 0.25 inches from the existing street surface.
- 9.18 No less than thirty (30) days and no more than sixty (60) days from the completion of the permanent pavement repair, the Contractor shall inspect the excavation for settlements, cracking and other pavement defects. Any such excavation which has required repair shall then be reinspected no less than thirty (30) days and no more than sixty (60) days from the completion of the subsequent repair. The Contractor shall further warranty all excavations for a one (1) year time period. Pavements that deviate more than 0.25 inches from the existing street surface shall be repaired by the infrared or grind and inlay methods. Surface or joint cracking 0.25 inches wide or greater shall be repaired utilizing a modified asphalt pavement sealant.
- 9.19 The Contractor shall prepare, document and maintain records of these inspections and make them available to the Town upon request.
- 9.20 All excavations made within concrete roadway/sidewalk areas shall be repaired with concrete in depths equal to the existing concrete.
- 9.21 Concrete used for repairs shall conform to the requirements of Mass. Highway Standards for concrete roadway construction.

10.0 Sidewalks and Driveways

- 10.1 All work shall be performed in accordance with 521 CMR Rules and Regulations of the Architectural Access Board (AAB) and Americans with Disabilities Act (ADA).
- 10.2 A sidewalk area that is disturbed shall be restored, full width, in kind a minimum of one (1) foot beyond the disturbed area for bituminous concrete and to the next joint line for concrete.
- 10.3 After the subgrade has been prepared, a foundation of gravel shall be placed upon it. After thorough mechanical compaction, the foundation shall be at least eight (8) inches thick and parallel to the proposed surface of the walk.
- 10.4 If applicable, the bituminous concrete sidewalk surface shall be laid in two (2) courses to a depth after rolling of three (3) inches. The bottom course shall be one and one-half (1-½) inches thick and its surface after rolling shall be one and one-half (1-½) inches below the parallel to the proposed grade of the finished surface. The top course shall be one and one-half (1-½) inches thick after rolling.
- 10.5 If applicable, the concrete sidewalk shall be placed in alternate slabs thirty (30) feet in length. Provide dowel bars at each transverse joint including connection to existing concrete. Thoroughly clean the drilled holes of contaminants and set the dowels into the hardened concrete face of the existing pavement with a Type VIII epoxy bonding compound. The slabs shall be separated by transverse preformed expansion joint filler one-half (½) inch thick (shall conform to AASHTO-M153). Preformed expansion joint filler shall also be placed adjacent to or around existing structures. Sawed transverse contraction joints shall be installed every five (5) feet in length. Clean and seal all joints. All concrete shall be broom finished.
- 10.6 On the foundation as specified above, the concrete (Air-Entrained 4000 psi, 3/4" 610) shall be placed in such quantity that after being thoroughly consolidated in place it shall be four (4) inches in depth. At driveways, the sidewalk shall be six (6) inches in depth.
- 10.7 Driveways shall be surfaced with Bituminous Concrete, Type I and shall be laid in two (2) courses to a depth of three (3) inches, after rolling, with a foundation of at least six (6) inches of compacted gravel. The finished surface shall butt into and not overlap the existing highway grade at the road edge.

Medway Street Standards

10.8 Driveways shall be so graded that no water shall enter the layout, pond or collect thereon, including the roadway.

10.9 Department of Public Works can restrict installation of landscape plantings, trees, walls, curbs, cobbles, bricks, pavers (etc.) within the Public Right of Way.

10.10 No private drainage utilities such as catch basins, leaching structures, area drains (etc.) are permitted in the Public Right of way.

11.0 Mailboxes

(a). Installation of Mailboxes

1. Follow USPS guidelines for installation and placement of mailboxes.
<https://www.usps.com/manage/mailboxes.htm>
2. Position your mailbox 41" to 45" from the road surface to the bottom of the mailbox or point of mail entry
3. Place your mailbox 6" to 8" back from the curb. If you do not have a raised curb, contact your local postmaster for guidance.
4. The best mailbox supports are stable but bend or fall away if a car or snow hits them. The Federal Highway Administration recommends:
 - (a) A 4" x 4" wooden support or a 2"-diameter standard steel or aluminum pipe. Avoid unyielding and potentially dangerous supports, like heavy metal pipes, concrete posts, and farm equipment (e.g., milk cans filled with concrete). Bury your post no more than 24" deep.

(b). Installation of mailbox on sidewalk

1. In addition, if the mailbox is to be installed in an area with sidewalks, it is important to recognize that the sidewalks must continue to comply with ADA requirements: minimum unobstructed 3' path of travel, excluding curb must be maintained.
2. American Disabilities Act (ADA). The most current version of the ADA Standards for Accessible Design set forth the minimum requirements to ensure facilities are readily accessible to and usable by individuals with disabilities. <http://www.ada.gov/regs2010/2010ADAStandards/2010ADASTandards.htm#c4>

UPON REQUEST, UTILITIES AND THEIR CONTRACTORS SHALL PROVIDE TO THE TOWN COPIES OF ALL REPORTS FILED WITH DTE REGARDING FAILED RESTORATIONS.