

MEDWAY MUNICIPAL COMPLEX

Alternate No. 4: Partial Berm, No Basement, No Firing Range

FIRE STATION

T&D- Building Soil Excavations to Offsite Disposal "<RCS-1"- (2,251cy x 1.7 tons/cy)	3,827.00	TN
T&D- Excess Foundation Soil Excavations to Offsite Disposal "<RCS-1"- (1,728cy x 1.7 tons/cy)	2,938.00	TN

POLICE STATION

T&D- Building Soil Excavations to Offsite Disposal "<RCS-1"- (1,854cy x 1.7 tons/cy)	3,152.00	TN
T&D- Excess Foundation Soil Excavations to Offsite Disposal "<RCS-1"- (2,397cy x 1.7 tons/cy)	4,075.00	TN

TOWN HALL

T&D- Building Soil Excavations to Offsite Disposal "<RCS-1"- (1,662cy x 1.7 tons/cy)	2,825.00	TN
T&D- Excess Foundation Soil Excavations to Offsite Disposal "<RCS-1"- (887cy x 1.7 tons/cy)	1,508.00	TN

MAINTENANCE BUILDING

T&D- Building Soil Excavations to Offsite Disposal "<RCS-1"- (767cy x 1.7 tons/cy)	1,304.00	TN
T&D- Excess Foundation Soil Excavations to Offsite Disposal "<RCS-1"- (1,617cy x 1.7 tons/cy)	2,749.00	TN

SITework

T&D- Excess Site Soil to Offsite Disposal "<RCS-1"- (28,655cy x 1.7 tons/cy)	48,714.00	TN
T&D- Excess Infiltration System Soil to Offsite Disposal "<RCS-1"- (1,269cy x 1.7 tons/cy)	2,157.00	TN

Water Utilities

T&D- Excess Trench Soil to Offsite Disposal "<RCS-1"- (288cy x 1.7 tons/cy)	490	TN
---	-----	----

Geothermal Wells

T&D- Trench Spoils to Offsite Disposal "<RCS-1"- (571cy x 1.7 tons/cy)	971	TN
T&D- Structure Spoils to Offsite Disposal "<RCS-1"- (54cy x 1.7 tons/cy)	92	TN

Sanitary Sewerage Utilities

T&D- Excess Trench Soil to Offsite Disposal "<RCS-1"- (794cy x 1.7 tons/cy)	1,350.00	TN
T&D- Excess Structure Soil to Offsite Disposal "<RCS-1"- (123cy x 1.7 tons/cy)	209	TN

Storm Drainage Utilities

T&D- Excess Trench Soil to Offsite Disposal "<RCS-1"- (878cy x 1.7 tons/cy)	1,493.00	TN
T&D- Excess Structure Soil to Offsite Disposal "<RCS-1"- (413cy x 1.7 tons/cy)	702	TN
T&D- Excess Subsurface Detention System Soil to Offsite Disposal "<RCS-1"- (1,269cy x 1.7 tons/cy)	2,157.00	TN

Electrical Utilities

T&D- Excess Trench Soil from Electrical Duct Banks to Offsite Disposal "<RCS-1"- (53cy x 1.7 tons/cy)	90	TN
T&D- Excess Trench Soil from Telecom Duct Banks to Offsite Disposal "<RCS-1"- (74cy x 1.7 tons/cy)	126	TN
T&D- Excess Trench Soil from Generator Duct Banks to Offsite Disposal "<RCS-1"- (95cy x 1.7 tons/cy)	161	TN
T&D- Excess Trench Soil from Fire Pump Duct Banks to Offsite Disposal "<RCS-1"- (24cy x 1.7 tons/cy)	41	TN
T&D- Excess Trench Soil from Site Light Raceways to Offsite Disposal "<RCS-1"- (663 cy x 1.7 tons/cy)	1,127.00	TN

Site Clearing

T&D- Stripped "Japanese Knotweed Soils" (36") to Offsite Disposal "<RCS-1"- (1,970cy x 1.3 tons/cy)	2,561.00	TN
T&D- Stripped Forest Mat/ Topsoil (24") to Offsite Disposal "<RCS-1"- (2,864cy x 1.3 tons/cy)	3,723.00	TN

Total: Soil / Topsoil to Export Offsite=

88,542.00 TONS