



# TOWN OF CLARKTON - SEWER ASSET MANAGEMENT PLAN

October 2025

*Prepared for:*



Town of Clarkton  
81 N Elm St  
Clarkton, NC, 28433  
Phone: (910) 647-5961

*Prepared by:*



**WithersRavenel**

*Our People. Your Success.*

WithersRavenel, Inc.  
115 MacKenan Drive  
Cary, NC 27511  
Phone: (919) 469-3340  
License #: F-1479

NC DEQ Project No. AIA-W-ARP-0065

WR Project No. 02200415.02

# TABLE OF CONTENTS

<b>1</b>	<b>Executive Summary.....</b>	<b>5</b>
1.1	Introduction.....	5
1.2	Project Purpose .....	5
1.3	Key Components.....	5
1.3.1	Inventory of Assets.....	5
1.3.2	Condition Assessment Summary .....	6
1.3.3	10-Year Capital Improvement Plan.....	7
1.3.4	Operation and Maintenance (O&M) Plan .....	8
<b>2</b>	<b>Background and System Overview .....</b>	<b>10</b>
2.1	Background.....	10
2.2	System Overview .....	10
2.2.1	Sewer System .....	10
<b>3</b>	<b>Level of Service .....</b>	<b>11</b>
3.1	Sewer System.....	11
<b>4</b>	<b>Sewer System Inventory .....</b>	<b>13</b>
4.1	Gravity Mains.....	13
4.2	Force Mains .....	15
4.3	Manholes.....	15
4.4	Pump Stations .....	16
<b>5</b>	<b>Risk Assessment .....</b>	<b>17</b>
5.1	Likelihood of Failure (LoF) .....	17
5.1.1	Additional Recommended Assessments .....	21
5.2	Consequence of Failure (CoF) .....	22
5.2.1	Additional Analysis Recommendations .....	24
5.3	Risk Score Analysis.....	25
<b>6</b>	<b>Collection System Operation and Maintenance (O&amp;M) Plan .....</b>	<b>27</b>
6.1	Pump Station Maintenance .....	27
6.2	Collection System Maintenance.....	28
<b>7</b>	<b>Capital Improvement Plan .....</b>	<b>31</b>



7.1 Capital Costs.....	31
7.2 Capital Improvement Projects .....	31
<b>8 Total CIP Estimates .....</b>	<b>32</b>
<b>9 Lifecycle Model Results .....</b>	<b>33</b>
9.1 Sewer System.....	33
9.1.1 Gravity Mains.....	33
9.1.2 Force Mains.....	33
9.1.3 Manholes .....	33

## LIST OF TABLES

Table 1 - Town's Core Sewer Infrastructure Assets .....	5
Table 2 - Sewer System Inventory .....	5
Table 3 - 10-Year Capital Improvement Plan .....	7
Table 4 - Operations and Maintenance Plan .....	8
Table 5 - Clarkton, NC Level of Service Criteria.....	11
Table 6 - Sewer System Design Standards per NCAC .....	11
Table 7 - Collection System Inventory in Linear Feet .....	13
Table 8 - Force Mains by Diameter and Material (summarized by length in feet) .....	15
Table 9 - Manholes by Depth.....	15
Table 10 - Pump Station Inventory Information.....	16
Table 11 - Pipe Life Expectancy by Material Types.....	18
Table 12 - Condition Criteria for Gravity and Force Mains.....	18
Table 13 - Condition Criteria for Manholes.....	19
Table 14 - Summary of Overall Condition of Collection System Assets .....	19
Table 15 - Consequence of Failure Criteria for Gravity and Force Mains .....	22
Table 16 - Summary of Sewer Criticality.....	23
Table 17 - Sewer Collection System Risk Matrix.....	25
Table 18 - Summary of Operation and Maintenance Recommendations .....	29
Table 19 - List of Proposed Projects for the Next 10 Years .....	32

# LIST OF FIGURES

Figure 1 - Condition of Gravity Mains .....	6
Figure 2 - Condition of Force Mains .....	6
Figure 3 - Condition of Manholes.....	6
Figure 4 - Distribution of Sewer Mains by Diameter and Material .....	14
Figure 5 - Summary of Sewer Main by Material Types.....	14
Figure 6 - Percentage of Gravity Main According to Assessed Condition.....	20
Figure 7 - Percentage of Force Mains According to Assessed Condition .....	20
Figure 8 - Percentage of Manholes According to Assessed Condition.....	21
Figure 9 - Percentage of Gravity Mains According to Assessed Criticality .....	24
Figure 10 - Risk Matrix .....	25
Figure 11 - Percentage of Gravity Mains According to Assessed Risk.....	26

# APPENDICES

Appendix I – GIS Maps
Appendix II – Condition Assessment Results
Appendix III – Lifecycle Model Documentation Report
Appendix IV – Lifecycle Model Results Narrative
Appendix V – Rate Study
Appendix VI – References

# LIST OF ABBREVIATIONS

AMP	-	Asset Management Plan
CAS	-	Cast Iron Pipe
CIP	-	Capital Improvement Plan
DIP	-	Ductile Iron Pipe
EPA	-	Environmental Protection Agency
FY	-	Fiscal Year
GIS	-	Geographic Information System
GPM	-	Gallons per Minute
ISO	-	Insurance Services Office
LF	-	Linear Feet
LOS	-	Level of Service
LWSP	-	Local Water Supply Plan
MG	-	Million Gallons
MGD	-	Million Gallons per Day
NCAC	-	North Carolina Administrative Code
NCDEQ	-	North Carolina Department of Environmental Quality
O&M	-	Operation and Maintenance
PCCP	-	Prestressed Concrete Cylinder Pipe
PSI	-	Pounds per Square Inch
PVC	-	Polyvinyl Chloride Pipe
RPT	-	Reinforced Plastic Truss
SCADA	-	Supervisory Control and Data Acquisition
SSO	-	Sanitary Sewer Overflow
UGPJ	-	Underground Pipe Junction
VC	-	Vitrified Clay Pipe
WTP	-	Water Treatment Plant
WWTP	-	Wastewater Treatment Plant

# 1 Executive Summary

## 1.1 Introduction

The Town of Clarkton, with the assistance of WithersRavenel, developed a comprehensive Asset Management Plan (AMP) for its sewer collection system assets. The AMP for the collection system is funded through the North Carolina Division of Environmental Quality (NCDEQ) Asset Inventory and Assessment (AIA) Grant Program.

The scope of the Asset Management Plan is shown in Table 1 below, which outlines the Town's core collection system assets assessed and included in this AMP.

**Table 1 - Town's Core Sewer Infrastructure Assets**

Asset Category	Asset Type
Collection System	Gravity Mains, Manholes, Force Mains, Pump Stations (Inventory only)

## 1.2 Project Purpose

The purpose of this AMP is to deliver a near- and long-term roadmap for proactive management of the Town's sewer assets. The AMP will also provide data driven insights for the Town to make informed decisions for capital planning while maximizing value of existing infrastructure in the most cost-effective manner, all while ensuring enhanced levels of service for its residents.

The AMP is a compilation of four (4) key components:

1. Inventory of Assets
2. Condition of Assets
3. Capital Improvements Plan (CIP) with projected cost estimates
4. Operation and Maintenance (O&M) Plan

## 1.3 Key Components

### 1.3.1 Inventory of Assets

Table 2 below summarizes inventory of the Town's Sewer system assets and their replacement values.




**Table 2 - Sewer System Inventory**

Sewer System Inventory		
Asset Type	Quantity	Total Replacement Value
Gravity Mains	13.5 miles	\$14,900,000
Force Mains	0.5 miles	\$410,000
Manholes	239	\$447,000
Pump Stations <sup>1</sup>	2	-

<sup>1</sup> Pump stations were not assessed for their replacement values

### 1.3.2 Condition Assessment Summary

Figures 1-3 below illustrate the condition across each asset type.



1.3.3 10-Year Capital Improvement Plan

Table 3 below represents the CIP by year over a 10-year span with cost estimates adjusted for inflation.

Table 3 – 10-Year Capital Improvement Plan

Town of Clarkton Capital Improvements Plan												
Project Location	Current Cost	Year 1 2027	Year 2 2028	Year 3 2029	Year 4 2030	Year 5 2031	Year 6 2032	Year 7 2033	Year 8 2034	Year 9 2035	Year 10 2036	Year 11+ 2037
<a href="#">Sewer Collection System and Pump Station Improvements</a>												
1. 10" Gravity Line Repair or Replacement North Railroad St	\$256,000	\$282,240										
2. 8" Gravity Line Repair or Replacement N Gooden St	\$372,000	\$410,130										
3. 8" Gravity Line Repair or Replacement N Elm St/Mid Aly	\$321,000	\$353,903										
4. 8" Gravity Line Repair or Replacement Page Rd	\$248,000	\$273,420										
5. Gravity Line Repair or Replacement Elm St, W Currie St, N Mitchell Ford Rd	\$568,000	\$626,220										
6. Gravity Line Repair or Replacement S Mid Aly and Misc.	\$318,000						\$447,458					
7. 8" Gravity Line Hwy221 From Pump Station	\$315,000						\$443,237					
8. 8" Gravity Line Misc Offshoots	\$175,000						\$246,243					
9. Repair 15 Manholes	\$36,000	\$3,308	\$3,473	\$3,647	\$3,829	\$4,020	\$4,221	\$4,432	\$4,654	\$4,887	\$5,131	\$5,388
10. Raise 5 Manholes and Replace Covers (Influent to Hwy211 Pump Station)	\$30,000		\$34,729									
11. Plant Pump Station Pump Replacements	\$300,000	\$330,750										
<a href="#">WWTP and Pump Station Improvements</a>												
1. UV System Rehabilitation - FUNDED	\$298,000	\$328,545										
2. Hwy 211 Floodwall and Flood Gate Installation - FUNDED	\$298,000	\$328,545										
3. Grating and Piping System Replacement	\$714,000	\$787,185										
4. Blowers Replacement	\$714,000						\$1,004,670					
5. Solar Panel Installation	\$595,000						\$837,225					
6. HWY 211 Lift Station Pumps Replacement	\$143,000											\$256,807
7. Generator Replacement	\$714,000											\$1,282,241
8. UV System Replacement	\$714,000											\$1,282,241
9. Screw Screen Replacement	\$714,000											\$1,282,241
<a href="#">Maintenance Improvements</a>												
1. Annual Clearing of ROW	\$10,000	\$11,025	\$11,576	\$12,155	\$12,763	\$13,401	\$14,071	\$14,775	\$15,513	\$16,289	\$17,103	\$17,959
<a href="#">Other Costs</a>												
SRF Loan Fee	\$64,639	\$64,639										
<b>TOTAL</b>	\$7,917,639	\$3,799,910	\$49,778	\$15,802	\$16,592	\$17,421	\$2,997,125	\$19,207	\$20,167	\$21,176	\$22,234	\$4,126,877

### 1.3.4 Operation and Maintenance (O&M) Plan

Table 4 provides an O&M list prepared as a part of the project

**Table 4 - Operations and Maintenance Plan**

Collection System Maintenance		
Asset	Maintenance	Frequency
Collection System	Clean and video inspect at least 10% of the collection system. Record the date, location of cleaning, type of cleaning, and other general observations during cleaning (type of debris, quantities, etc.).	Annually
	Document all Sanitary Sewer Overflow (SSOs) using the State form or other similar form. All spills, reportable or not, must be documented. Spills that are reported to the State should be on the required form.	As Needed
	Incorporate information from new construction and rehabilitation projects, including line diameter, material, and scoring for other Key Performance Indicators (KPIs), into the collection system GIS within one (1) year of construction completion.	As Needed
	All high priority lines (including aerals, sub-waterway crossings, lines contacting surface waters, lines positioned parallel to stream banks and subject to eroding in such a manner that may threaten the line, and any other segment of the system that is designated as high priority) must be inspected every six (6) months. A log must document the area inspected, the date, method of inspection, and any corrective actions performed or initiated.	Semi-Annually
Pump Station System Maintenance		
Pump Station Maintenance	Inspecting, cleaning, and removing debris from the pump station structure, outside perimeter, and wet well.	Annually
	Inspecting and exercising all valves.	Annually
	Inspecting and lubricating pumps and other mechanical equipment.	Annually
	Verifying the proper operation of the alarms, telemetry system, and auxiliary equipment.	Annually
	Other testing procedures as recommended by the manufacturer.	Annually
	Annual flow meter calibration (at a minimum).	Annually
	NOTE: Pump stations not connected to telemetry systems must be inspected at least daily. Pump stations with telemetry must be inspected at least once per week.	Daily/Weekly
	Record hours of running time from elapsed time meters.	Weekly
	Check for equal run times on each pump.	Weekly
	Inspect control panel switches for proper positioning.	Annually
	Test alarms.	Annually

Check valves for proper positioning (valves functioning, normally open valves are open, normally closed valves are closed).	Annually
Confirm valve lever arms and weights are okay.	Annually
Check for unusual pump noise or vibration.	Annually
Check amp readings. Note discrepancies.	Annually
Confirm pumps appear to be seated properly.	Annually
Confirm that no leakage is observed.	Annually
Confirm guide rails and brackets are aligned and fastened.	Annually
Note any rust or loose parts.	Annually
Confirm that piping and valves are not leaking, and that bolts and nuts are properly torqued.	Annually
Confirm that any corroded or worn parts have been replaced, cleaned, painted, or restored.	Annually
Record flow rate observed during site visit.	Annually
Check and record pressure gauge readings during observed flow rate. Note any changes from normal readings.	Annually
At least once per week, manually pump down the wet well to check for and remove debris.	Weekly
Inspect floats, transducer, and cables. Remove all debris to ensure proper operation.	Annually
Ensure all automatic cycle operation cables and appurtenances are free and clear of debris or obstructions and functioning as designed.	Annually
Check control settings.	Annually
If a pump is removed, place the lead pump selector switch on the number of the pump remaining in operation.	Annually
Inspect the pump hand/off/automatic selector switch. Turn to off. Fill up wet well with water until high water is activated. Turn to auto and check if both pumps operate automatically with slight delay between each. Pump until pump shuts off. Fill water until the lead pump starts. When the lead pump starts, shut off water. Allow pump to lower the wet well until the pump shuts off.	Annually
Check pumps for blockage and any abnormalities in operation.	Annually
Confirm generator is automatically exercising on schedule at start-up. Manually throw main disconnect to check the Automatic Transfer Switch (ATS) and generator operation.	Annually
Cut grass, pick up trash, remove debris, walk around perimeter, inspect fencing, landscaping, look for vandalism or evidence of trespassing or other security concerns.	Annually



## 2 Background and System Overview

### 2.1 Background

Town of Clarkton is in Eastern North Carolina in Bladen County, approximately 48 miles southeast of Fayetteville. The population of the Town is approximately 600 and accounts for approximately 2% of the total population in Bladen County.

The Town received an AIA grant award of \$240,000 to study its sewer collection system in the Spring 2022 funding cycle. The Town, with the help of WithersRavenel, reviewed their sewer system assets by performing a Geographic Information System (GIS) data review and populating manhole attribute information. Data collected from this review was used to classify critical assets, perform a risk assessment, identify critical projects to include in the Town's Capital Improvements Plan (CIP), and determine operation and maintenance strategies to mitigate future risk of failure. This study resulted in the development of this AMP. The elements of the AMP framework include:

- Level of Service (LOS) Statement
- Asset Inventory
- Risk Analysis using Likelihood of Failure (LoF) and Consequences of Failure (CoF)
- 10-Year Capital Improvements Plan (CIP)
- Operation and Maintenance (O&M) Plan

This AMP is intended to be a living document that is updated regularly. It is recommended that the data stored within the Town's GIS database be continually validated and updated to ensure that the most relevant and accurate representations of the current system are captured.

### 2.2 System Overview

#### 2.2.1 Sewer System

The sewer collection system collects wastewater from 508 residential, commercial, industrial, and institutional customers and conveys it to the Town's Wastewater Treatment Plant (WWTP) where it is treated and discharged into Brown Marsh Swamp in the Waccamaw River Basin. The WWTP operates under permit number NC0021610. The sewer system assets include approximately:

- 13.5 miles Gravity Mains
- 0.5 miles Force Mains
- 239 Manholes
- 2 Pump Stations

The sewer collection system inventories are stored and maintained in the Town's GIS database. The following sections break down the current state of the inventory. Maps of sewer system assets can be found in Appendix I.

### 3 Level of Service

Level of Service (LOS) criteria define the goals and standards the Town will strive to attain. LOS criteria reflect the mission of the Town and are expressed in terms of quality, quantity, reliability, responsiveness, cost, and environmental impact. Taking all these considerations into account, the Town is adopting the following LOS criteria:

**Table 5 - Clarkton, NC Level of Service Criteria**

Category	Level of Service	Performance Measure	Target
	<b>1. Residential Back-ups and SSOs</b> No adverse events will cause residential sewer back-ups and sanitary sewer overflows (SSOs)	Number of violations per year	0 events/year
	<b>2. Sewer System Performance</b>	Main break frequency per year	≤ 15/100 miles
		Full leak detection survey - water	Every 5 years
		CCTV inspection	10% every year
<b>Customer Service</b>	<b>3. Response Time</b> Respond to customer complaints/requests in a timely manner	Emergency (breaks)	1-2 hours
		Leaks	1-2 hours
		Meter repair	1-5 days
	<b>4. Communication</b> Notification of planned shutdown will be provided	Number of days	≥ 7 days
<b>Financial</b>	<b>5. Financial Capability</b> Rates are reviewed on an annual basis and revised as needed to ensure full cost recovery	Revise, review rates	Once/year

With the LOS criteria developed, the Town must establish sustainable business processes to ensure information required for measuring LOS is readily available and cost effective. The processes for collecting the information must be integrated into existing workflows.

#### 3.1 Sewer System

The prevention of residential sewer back-ups and sanitary sewer overflows were designated as important metrics for the sewer system analysis, and Table 6 summarizes the sewer system design standards per NCAC. These standards were used to identify assets within the collection system that require updates to become compliant.

**Table 6 - Sewer System Design Standards per NCAC**

System Parameter	Evaluation Criterion	Value	Design Standard/Guideline
Design Capacity	Daily Flow	Various <sup>1</sup>	15A NCAC 02T.0114
Minimum Separation	Storm Sewer	18 inches	15A NCAC 02T.0305
	Water Mains - Vertical	18 inches	
	Water Mains - Horizontal	10 feet	

	Reclaimed Water Lines - Vertical	18 inches	
	Reclaimed Water Lines - Horizontal	2 feet	
	Drinking Water Source	100 feet	
	Classified Waters <sup>2</sup> or Wetlands <sup>3</sup>	50 feet	
	Stream, Lake, Impoundment, Wetlands <sup>4</sup> , Waters <sup>5</sup>	10 feet	
	Building Foundation	5 feet	
	Basement	10 feet	
	Top slope <sup>6</sup>	10 feet	
	Drainage System	5 feet	
	Swimming Pool	10 feet	
	Final Earth Grade	36 inches	
Minimum Nominal Diameter	Public Gravity	8-inch	15A NCAC 02T.0305
	Private Gravity	6-inch	
Minimum Slope, in feet/100 feet, by Diameter of Gravity Pipe <sup>7</sup>	6-inch	0.6	15A NCAC 02T.0305
	8-inch	0.4	
	10-inch	0.28	
	12-inch	0.22	
	14-inch	0.17	
	16-inch	0.15	
	18-inch	0.14	
	21-inch	0.1	
	24-inch	0.08	
	27-inch	0.07	
	30-inch	0.06	
	36-inch	0.05	
Manholes	Maximum Distance	425 feet	15A NCAC 02T.0305
	Minimum Diameter	4 feet	
	Minimum Bench Slope	4%	
Force Mains	Minimum Nominal Diameter	4-inch	15A NCAC 02T.0305
	Air Release Valves for Vertical Distance	> 10 feet	

1. Refer to NCAC Standard for detailed list of values.

2. Classified WS-II, WS-III, WS-IV, B, SA, ORW, HQW, SB from normal high water or tide elevation.

3. Classified as UWL or SWL or directly abutting the waters classified above.

4. Classified as WL.

5. Classified as C, SC, or WS-V, or ground water lowering and surface drainage ditches.

6. Embankment or cuts of 2 feet or more vertical height.

7. Based upon a mean velocity of 2.0 feet per second and Manning's "n" of 0.0013.

## 4 Sewer System Inventory

### 4.1 Gravity Mains

The Town's sewer collection system consists of thirteen and a half (13.5) miles of gravity mains, serving approximately 508 customers which includes residential, commercial, industrial, and institutional classifications.

Gravity main diameters range from 6 to 12 inches and materials include asbestos cement (AC), cast iron (CIP), ductile iron (DIP), high density polyethene (HDPE), polyvinyl chloride (PVC), reinforced concrete (RCP), and vitrified clay pipe (VCP).

Table 7 provides a summary of the diameter and materials of the gravity main pipes in the system in linear feet (LF).

**Table 7 - Collection System Inventory in Linear Feet**

Material / Diameter	AC	CIP	DIP	HDPE	PVC	RCP	VCP	Unknown /Other	Total	Percent of Total
6-inch	378	-	38	-	43	-	124	-	583	0.82%
8-inch	19,076	-	2,481	9,518	26,841	83	998	507 <sup>1</sup>	59,504	83.66%
10-inch	2,374	118	789	121	2,449	-	-	195 <sup>2</sup>	6,046	8.50%
12-inch	4,419	-	68	220	-	-	-	-	4,706	6.62%
Unknown	-	-	-	-	-	-	-	290	290	0.41%
<b>Total</b>	<b>26,246</b>	<b>118</b>	<b>3,376</b>	<b>9,859</b>	<b>29,333</b>	<b>83</b>	<b>1,122</b>	<b>992</b>	<b>71,129</b>	
<b>Percent of Total</b>	<b>36.90%</b>	<b>0.17%</b>	<b>4.75%</b>	<b>13.86%</b>	<b>41.24%</b>	<b>0.12%</b>	<b>1.58%</b>	<b>1.39%</b>		


Notes:

1 Represents pipe materials transitioned from: AC to DIP.


2 Two lines representing pipe materials transitioned from VCP to DIP and DIP to PVC.

Over 98% of the system has known material and diameter. The most commonly used pipe material within the system is PVC, which accounts for approximately 41%, followed by AC pipe, which makes up 37% of the system. In terms of pipe size, the most prevalent diameter is 8 inches, representing approximately 84% of the entire network.

Figure 4 illustrates gravity mains by materials and sizes summarized by length in feet, and Figure 5 illustrates gravity mains by material types presented in percentages.



**Figure 4 - Distribution of Sewer Mains by Diameter and Material**



**Figure 5 - Summary of Sewer Main by Material Types**

## 4.2 Force Mains

The Town's collection system consists of approximately one-half (0.5) mile of force mains, all constructed of six (6)-inch diameter PVC pipe.

Table 8 - provides a summary of the diameter and materials of the force main pipes in the system.

**Table 8 - Force Mains by Diameter and Material (summarized by length in feet)**

Material / Diameter	PVC	Unknown	Total	Percent of Total
6-inch	2,488	-	2,488	91%
Unknown	-	238	238	9%
<b>Total</b>	2,488	238	2,727	

## 4.3 Manholes

The collection system contains 239 manholes, ranging in approximate depth from 1.45 to 11.5 feet and materials including brick, concrete, concrete reinforced, and precast concrete.

Table 9 provides a summary of the depth and material of the manholes in the system. Approximately, 15% of manholes have unknown depth or material.

**Table 9 - Manholes by Depth**

Depth	Count
<5'	56
5-10'	140
10'+	8
Unknown	35
<b>Total</b>	239

## 4.4 Pump Stations

The collection system contains two (2) pump stations that are an integral part of the conveyance of wastewater to the WWTP. Pump station assessments were not performed as part of this project; however, the Town performed an independent drawdown test on the Plant Pump Station. Table 10 - gives a summary of year built, design flow, known pump data, and drawdown testing results.

**Table 10 - Pump Station Inventory Information**

Name	No. of Pumps	Pump Design Capacity	Model	Manufacturer	Pump Type	Year Built	Year of Last Upgrade	Force Main Size	Discharge Location	Drawdown Capacity Results
Hwy 211 PS	2	Unknown	Unknown	Unknown	Unknown	1984	Pump and Control Panel Replacement 2022	Unknown	Unknown	Not performed
WWTP Influent PS	2	400 GPM (each)	Unknown	Cornell	Submersible	1963	Pump Replacement 2012, Wet Well lined 2012, Influent screw screen 2020	Unknown	WWTP	Pump 1: 200 GPM Pump 2: 185 GPM

## 5 Risk Assessment

As infrastructure ages, it becomes increasingly more challenging to assign limited capital expenditures to the repair, rehabilitation, or replacement of the assets. This section describes how the Town's risk model was used in decision making and preparing the Town's capital improvement programs for the prioritization for sewer infrastructure.

The intent of the risk model is to answer questions such as "which sewer mains will have the greatest impact if a failure is to occur?" This allows staff to focus resources and effort on these assets before they fail.

The risk associated with a given asset failing can be determined by multiplying Likelihood of Failure (LoF), based on asset's condition, and the Consequence of Failure (CoF), based on its criticality.

$$\text{Risk} = \text{LoF} \times \text{CoF}$$

The following summarizes the LoF and CoF criteria and methodologies used to calculate risk for project prioritization for capital planning.

### 5.1 Likelihood of Failure (LoF)

The Likelihood of Failure (LoF) is a numerical metric used to represent the probability of an asset's failure, based on quantifiable factors such as asset age, condition assessments, historical break data, and input from operations staff.

For this project, the condition of gravity mains was primarily determined using asset age or available condition inspections such as closed-circuit television (CCTV) and Town conducted smoke testing results. The condition of force mains was assessed based on pipe age and industry-standard life expectancies for force main materials. Each gravity and force main segment were assigned a condition rating according to its CCTV and/or smoke testing results or estimated remaining useful life, as outlined in Table 12. The age-related estimates were developed using asset age and material information in accordance with NCDEQ-recommended lifespans presented in Table 11. The CCTV and Town provided Smoke Testing results are included in Appendix II.

Manhole condition ratings were derived from visual inspections conducted by WithersRavenel survey staff, with the rating criteria detailed in Table 13.

Although pump stations were not directly assessed as part of this project, Town staff input and Town conducted drawdown testing results were used to support future recommendations for condition and capacity evaluations, as well as operations and maintenance (O&M) planning.



**Table 11 - Pipe Life Expectancy by Material Types**

Material	Life Expectancy (years)
Asbestos Cement	60
Cast Iron	60
Ductile Iron	100
High density Polyethylene	80
Polyvinyl Chloride	80
Reinforce Concrete	100
Vitrified Clay	50
Unknown	50

Reference: Recommended Life Spans, sourced from 2022 AMP DWI Guidance Document

**Table 12 - Condition Criteria for Gravity and Force Mains**

Likelihood of Failure (LoF) based on Pipe Age		
Asset Category	Condition Rating	Description
Pipe Condition (% of Estimated Useful Life)	5	>3 Category 5 NASSCO/PACP Defects, Smoke Observed. Or for lines without CCTV <5% Remaining Useful Life. End of Life. Requires complete rehabilitation.
	4	1-3 Category 5 NASSCO/PACP Defects. Or for lines without CCTV >=5, <15% Remaining Useful Life. Poor, unable to meet level of service.
	3	Category 3 or 4 NASSCO/PACP Defects, Localized smoke observed at isolated defects. Or for lines without CCTV >=15, <50% Remaining Useful Life. Fair, major wear, impacting level of service.
	2	Category 1 or Category 2 NASSCO/PACP. Or for lines without CCTV >=50, <95% Remaining Useful Life. Good, minor wear.
	1	No Structural Defects, No Smoke Observed. Or for lines without CCTV >=95%. Excellent, New or Nearly New.

**Table 13 - Condition Criteria for Manholes.**


Likelihood of Failure (LoF) based on Manhole Visual Assessment		
Asset Category	Condition Rating	Description
Manhole Condition	5	End of Life. Severe defects, failure imminent
	4	-
	3	Fair. Moderate defects, maintenance necessary soon. (Cracking, aggregate and reinforcement exposure, minor root intrusions)
	2	-
	1	Excellent. Like New

Table 12 and Table 13 summarize the condition criteria for each asset category on a scale of 1 through 5 with 1 being the lowest LoF and 5 being the highest.


Using these categories, each sewer main, force main, and manhole in the system were assigned a condition score. A summary of the overall condition of each asset category by percentage is listed in Table 14 below and stored in the Town's GIS database. Collection mains were listed in linear feet and manholes and pump stations were summarized by asset count.

**Table 14 - Summary of Overall Condition of Collection System Assets**


Asset / LoF	1 - Excellent	2 - Good	3 - Fair	4 - Poor	5 - End of Life
Gravity Mains	16,735	21,289	20,202	2,731	10,172
Force Mains	-	-	2,727	-	-
Manholes	124	-	100	-	15



**Figure 6 - Percentage of Gravity Main According to Assessed Condition**



**Figure 7 - Percentage of Force Mains According to Assessed Condition**



**Figure 8 - Percentage of Manholes According to Assessed Condition**

Table 14 shows approximately 14% of gravity mains and 6% of manholes were given a rating of 5 “Very Poor” indicating that the assets have or nearly have surpassed their useful life and are likely to fail in the immediate future. These respective assets were considered for rehabilitation/ replacement projects on the CIP, discussed in Section 7.

### 5.1.1 Additional Recommended Assessments

The forecasted state of the sewer asset condition assessment is focused on increasing the known condition information of the collection system assets.

#### *Closed-Circuit Television (CCTV) inspection*

Performing additional CCTV inspections on the collection system would provide condition information used to prioritize rehabilitation and replacement needs. Regular CCTV inspections to gather updated condition information would help the Town prevent residential back-ups and sanitary sewer overflows (SSOs) by rehabilitating or replacing assets before they fail.

#### *Manhole Inspection*

Manhole inspections are typically performed along with CCTV inspection initiatives. Regular manhole inspections would help the Town identify corrosion, inflow and infiltration, fat and grease build up, and other issues that could cause residential back-ups, SSOs, or clogs in the collection system.

#### *Pump Station Assessment*

For the purposes of this project, pump station information was gathered from the Town. Pump drawdown testing would provide the existing capacity for each pump to compare to the design capacity, allowing the Town to determine the remaining efficiency of the pump. Complete pump

station assessment would also provide condition information for the pumps and pump accessories within the pump stations, and help the Town identify maintenance, rehabilitation, and replacement needs.

## 5.2 Consequence of Failure (CoF)

CoF is a numerical representation of the impact of an asset's failure to the community. Assets with higher CoF scores have been determined to be the most critical components of the Town's sewer system in terms of maintaining the performance and integrity of the entire system.

The CoF scores were determined using economic, environmental, and social impacts as described in Table 15 below. Various CoF criteria were presented to the Town and the selected ones are listed below based on their applicability to the Town's system. The weighting for each category was equally distributed among the five (5) criteria selected.

**Table 15 - Consequence of Failure Criteria for Gravity and Force Mains**

Consequence of Failure Criteria for Sewer Mains		
Asset Category	Criticality Rating	Description
Cost of Repair (Pipe Size)	5	12"+ pipe diameter
	4	10" pipe diameter
	3	8" pipe diameter
	2	6" pipe diameter
	1	<6" pipe diameter
Cost of Repair (Pipe Depth)	5	>20 ft depth
	4	15 ft-20 ft depth
	3	10 ft-15 ft depth
	2	5 ft-10 ft depth
	1	<5 ft depth
Proximity to Critical Infrastructure <sup>1</sup>	5	<50 ft of railroad or NCDOT state road, significant impact on traffic flow and access issue
	4	50-100 ft railroad or NCDOT state road, major impact on traffic flow and access issue
	3	100-150 ft railroad or NCDOT state road, moderate impact on traffic flow, some access issue
	2	150-200 ft railroad or NCDOT state road, minimal impact on traffic flow, easy access for repair
	1	>200 ft railroad or NCDOT state road, no/minimal impact on traffic flow, easy access for repair
Critical Users <sup>2</sup>	5	Health and Safety, Public Utilities (Hospitals, Schools, Treatment Plant, etc.) and all Force Mains
	4	Public Services / Administration (Town Office)
	3	Industrial / Commercial
	2	Businesses
	1	Residential

Proximity to a Water Body	5	<25 ft of a water body or crossing
	4	25-50 ft of a water body or crossing
	3	50-100 ft of a water body or crossing
	2	100-150 ft of a water body or crossing
	1	>150 ft of a water body or crossing

**Notes:**


1. *Critical Infrastructure selected for analysis includes:*
  - E Green Street (NC-211)
  - US-701
  - Business 701 (College Street)
  - North Railroad Street
  - South Railroad Street
  - Housing Authority Outfall
  - Wood Street Outfall
2. *Critical Users selected for analysis includes:*
  - Sewer Treatment Plant
  - Fire Department
  - Bladen Medical Associates
  - Clarkton Health Center - Church Street
  - Peach Street / S Smith Street Nursing Home
  - Booker T. Washington Primary School
  - Clarkton School of Discovery
  - Town Hall
  - Gildan Yarns
  - Harriet and Henderson Yarns, Inc.
  - E. J. Cox Peanut Factory
  - El Torito Restaurant
  - Subway
  - Burger Shack
  - IGA
  - Dollar General
  - Clarkton Drug

Using these categories, each sewer asset was assigned a CoF rating, which is stored in the GIS geodatabase. These categories were summarized by linear foot for gravity and force mains and by asset count for manholes.

Manholes were prioritized for replacement by the risk value of their connected mains. Pump station criticality was not assessed as a part of this project.

**Table 16 - Summary of Sewer Criticality**

Asset / Criticality	5 - Very high	4 - High	3 - Moderate	2 - Low	1 - Very Low
Gravity Mains	344	14,388	29,037	27,316	43
Force Mains	2,727	-	-	-	-



**Figure 9 - Percentage of Gravity Mains According to Assessed Criticality**

As shown in Table 16, approximately 20% of gravity mains were assigned a criticality rating of 4, or “High,” and above, indicating that failure of these assets would have a significant impact on Town operations. All force mains were assigned a criticality rating of 5, or “Very High,” as the failure of any force main is expected to result in equally severe operational consequences. These criticality ratings were used in conjunction with condition ratings to help prioritize rehabilitation and replacement projects included in the Capital Improvement Plan (CIP), discussed in Section 7.

### 5.2.1 Additional Analysis Recommendations

#### *Regulatory Considerations*


NCDEQ adopted the Minimum Design Criteria for the permitting of Gravity Sewers in February 1996 and updated the design criteria to the 15A NCAC 2T Regulations in March 2008. NCDEQ adopted the Minimum Design Criteria for the permitting of pump stations and force mains in June 2000. The purpose of the standards described in these regulations is to protect the health and safety of the community and environment. Table 7 contains a summary of these NCAC sewer system design standards. Using these standards, the collection system assets could be evaluated to determine the assets that are not in compliance with these NCAC design standards. As the collection system assets are upgraded, rehabilitated, or replaced, the new assets are required to comply with these standards.

## 5.3 Risk Score Analysis

The quantification of risk using LoF and CoF scores was used to identify priority projects for preparation of the Town's Capital Improvements Plan (CIP).

$$\text{Risk} = \text{LoF} \times \text{CoF}$$

The results of multiplying the LoF and CoF scores for each asset were jointly analyzed on the risk matrix shown in Table 13 below.



**Figure 10 - Risk Matrix**

Assets with a high likelihood of failure, as indicated by their poor condition, and high consequences of failure, as indicated by their criticality, score in the extreme risk category and have been prioritized for replacement on the Town's CIP. Assets with very low to significant risk could contribute to replacement at a later year and/or operation and maintenance activities, etc.

The risk scores for each asset are stored in the GIS database. Mains are summarized in linear feet while manholes are summarized in asset count. Pump stations were not assessed as a part of this project.


**Table 17 - Sewer Collection System Risk Matrix**

Asset / Risk	Extreme	High	Significant	Low	Very Low
Gravity Mains	-	9,535	11,300	29,750	20,543
Force Mains	-	2,727	-	-	-

As shown in Table 17, approximately 13% of gravity mains and 100% of force mains were assigned a high-risk rating, indicating that failure of these assets would have a significant impact on Town operations. These high-risk assets were used to prioritize rehabilitation and replacement projects included in the CIP, as discussed in Section 7.

Manholes were prioritized for replacement based on the risk ratings of the gravity mains to which they are connected.





**Figure 11 - Percentage of Gravity Mains According to Assessed Risk**

## 6 Collection System Operation and Maintenance (O&M) Plan

Operation and Maintenance (O&M) for the wastewater system focuses on upkeep of the gravity mains, force mains, manholes, and pump stations. Maintenance consists of “Emergency Maintenance,” which is corrective action needed quickly to keep the system operational, and “Preventative Maintenance,” which is routine, scheduled tasks to prevent problems before they arise. The items below represent routine maintenance items performed throughout the collection system.

### 6.1 Pump Station Maintenance

The routine Pump Station Operation and Maintenance Program will include the following items:

- Inspecting, cleaning, and removing debris from the pump station structure, outside perimeter, and wet well.
- Inspecting and exercising all valves.
- Inspecting and lubricating pumps and other mechanical equipment.
- Verifying the proper operation of the alarms, telemetry system, and auxiliary equipment.
- Other testing procedures as recommended by the manufacturer.
- Annual flow meter calibration (at a minimum).
- NOTE: Pump stations not connected to telemetry systems must be inspected at least daily. Pump stations with telemetry must be inspected at least once per week.

In addition, a Pump Station Check List Form should be created and utilized for each inspection. The inspection form should cover the following items:

- Check wet well level periodically, more frequently when high flows are expected or have occurred.
- Record hours of running time from elapsed time meters at least once per week and check for equal running times on each pump.
- Inspect control panel switches for proper positioning.
- Test alarms.
- Check valves for proper positioning (valves functioning, normally open valves are open, normally closed valves are closed).
- Confirm valve lever arms and weights are okay.
- Check for unusual pump noise or vibration.
- Check amp readings. Note discrepancies.
- Confirm pumps appear to be seated properly.
- Confirm that no leakage is observed.
- Confirm guide rails and brackets are aligned and fastened.
- Note any rust or loose parts.
- Confirm that piping and valves are not leaking, and that bolts and nuts are properly torqued.

- Confirm that any corroded or worn parts have been replaced, cleaned, painted, or restored.
- Record flow rate observed during site visit.
- Check and record pressure gauge readings during observed flow rate. Note any changes from normal readings.
- At least once per week, manually pump down the wet well to check for and remove debris.
- Inspect floats, transducer, and cables. Remove all debris to ensure proper operation.
- Ensure all automatic cycle operation cables and appurtenances are free and clear of debris or obstructions and functioning as designed.
- Check control settings.
- If a pump is removed, place the lead pump selector switch on the number of the pump remaining in operation.
- Inspect the pump hand/off/automatic selector switch. Turn to off. Fill up wet well with water until high water is activated. Turn to auto and check if both pumps operate automatically with slight delay between each. Pump until pump shuts off. Fill water until the lead pump starts. When the lead pump starts, shut off water. Allow pump to lower the wet well until the pump shuts off.
- Check pumps for blockage and any abnormalities in operation.
- Confirm generator is automatically exercising on schedule at start-up. Periodically manually throw main disconnect to check the Automatic Transfer Switch (ATS) and generator operation.
- Cut grass, pick up trash, remove debris, walk around perimeter, inspect fencing, landscaping, look for vandalism or evidence of trespassing or other security concerns.

## 6.2 Collection System Maintenance

The routine Collection System Operation and Maintenance Program will include the following items:

- Clean and video inspect at least 10% of the collection system each year. At the time of cleaning, record the date, location of cleaning, type of cleaning, and other general observations during cleaning (type of debris, quantities, etc.).
- Document all Sanitary Sewer Overflow (SSOs) using the State form or other similar form. All spills, reportable or not, must be documented. Spills that are reported to the State should be on the required form.
- Incorporate information from new construction and rehabilitation projects, including line diameter, material, and scoring for other KPIs, into the collection system GIS within one (1) year of construction completion.
- All high priority lines (including arials, sub-waterway crossings, lines contacting surface waters, lines positioned parallel to stream banks and subject to eroding in such a manner that may threaten the line, and any other segment of the system that is designated as high priority) must be inspected every six (6) months. A log must document the area inspected, the date, method of inspection, and any corrective actions performed or initiated.

**Table 18 - Summary of Operation and Maintenance Recommendations**

Collection System Maintenance		
Asset	Maintenance	Frequency
Collection System	Clean and video inspect at least 10% of the collection system. Record the date, location of cleaning, type of cleaning, and other general observations during cleaning (type of debris, quantities, etc.).	Annually
	Document all Sanitary Sewer Overflow (SSOs) using the State form or other similar form. All spills, reportable or not, must be documented. Spills that are reported to the State should be on the required form.	As Needed
	Incorporate information from new construction and rehabilitation projects, including line diameter, material, and scoring for other Key Performance Indicators (KPIs), into the collection system GIS within one (1) year of construction completion.	As Needed
	All high priority lines (including aerals, sub-waterway crossings, lines contacting surface waters, lines positioned parallel to stream banks and subject to eroding in such a manner that may threaten the line, and any other segment of the system that is designated as high priority) must be inspected every six (6) months. A log must document the area inspected, the date, method of inspection, and any corrective actions performed or initiated.	Semi-Annually
Pump Station System Maintenance		
Pump Station Maintenance	Inspecting, cleaning, and removing debris from the pump station structure, outside perimeter, and wet well.	Annually
	Inspecting and exercising all valves.	Annually
	Inspecting and lubricating pumps and other mechanical equipment.	Annually
	Verifying the proper operation of the alarms, telemetry system, and auxiliary equipment.	Annually
	Other testing procedures as recommended by the manufacturer.	Annually
	Annual flow meter calibration (at a minimum).	Annually
	NOTE: Pump stations not connected to telemetry systems must be inspected at least daily. Pump stations with telemetry must be inspected at least once per week.	Daily/Weekly
	Record hours of running time from elapsed time meters.	Weekly
	Check for equal run times on each pump.	Weekly
	Inspect control panel switches for proper positioning.	Annually
	Test alarms.	Annually
	Check valves for proper positioning (valves functioning, normally open valves are open, normally closed valves are closed).	Annually

Confirm valve lever arms and weights are okay.	Annually
Check for unusual pump noise or vibration.	Annually
Check amp readings. Note discrepancies.	Annually
Confirm pumps appear to be seated properly.	Annually
Confirm that no leakage is observed.	Annually
Confirm guide rails and brackets are aligned and fastened.	Annually
Note any rust or loose parts.	Annually
Confirm that piping and valves are not leaking, and that bolts and nuts are properly torqued.	Annually
Confirm that any corroded or worn parts have been replaced, cleaned, painted, or restored.	Annually
Record flow rate observed during site visit.	Annually
Check and record pressure gauge readings during observed flow rate. Note any changes from normal readings.	Annually
At least once per week, manually pump down the wet well to check for and remove debris.	Weekly
Inspect floats, transducer, and cables. Remove all debris to ensure proper operation.	Annually
Ensure all automatic cycle operation cables and appurtenances are free and clear of debris or obstructions and functioning as designed.	Annually
Check control settings.	Annually
If a pump is removed, place the lead pump selector switch on the number of the pump remaining in operation.	Annually
Inspect the pump hand/off/automatic selector switch. Turn to off. Fill up wet well with water until high water is activated. Turn to auto and check if both pumps operate automatically with slight delay between each. Pump until pump shuts off. Fill water until the lead pump starts. When the lead pump starts, shut off water. Allow pump to lower the wet well until the pump shuts off.	Annually
Check pumps for blockage and any abnormalities in operation.	Annually
Confirm generator is automatically exercising on schedule at start-up. Periodically manually throw main disconnect to check the Automatic Transfer Switch (ATS) and generator operation.	Annually
Cut grass, pick up trash, remove debris, walk around perimeter, inspect fencing, landscaping, look for vandalism or evidence of trespassing or other security concerns.	Annually

## **7 Capital Improvement Plan**

### **7.1 Capital Costs**

The capital improvement cost includes the material cost and labor cost for the rehabilitation, replacement, or installation of a new or existing sewer system asset. This cost can be determined for an asset with direct price quotes provided by a supplier or general cost estimates based on an evaluation of recent construction bids across North Carolina and the RSMeans Catalog.

### **7.2 Capital Improvement Projects**

Based on input from Town staff and results of the risk analysis, the projects listed in Table 19 below are recommended for inclusion in the CIP budget for the sewer system over the next ten (10) years.

8 Total CIP Estimates

Table 19 - List of Proposed Projects for the Next 10 Years

Town of Clarkton Capital Improvements Plan												
Project Location	Current Cost	Year 1 2027	Year 2 2028	Year 3 2029	Year 4 2030	Year 5 2031	Year 6 2032	Year 7 2033	Year 8 2034	Year 9 2035	Year 10 2036	Year 11+ 2037
Sewer Collection System and Pump Station Improvements												
1. 10" Gravity Line Repair or Replacement North Railroad St	\$256,000	\$282,240										
2. 8" Gravity Line Repair or Replacement N Gooden St	\$372,000	\$410,130										
3. 8" Gravity Line Repair or Replacement N Elm St/Mid Aly	\$321,000	\$353,903										
4. 8" Gravity Line Repair or Replacement Page Rd	\$248,000	\$273,420										
5. Gravity Line Repair or Replacement Elm St, W Currie St, N Mitchell Ford Rd	\$568,000	\$626,220										
6. Gravity Line Repair or Replacement S Mid Aly and Misc.	\$318,000						\$447,458					
7. 8" Gravity Line Hwy221 From Pump Station	\$315,000						\$443,237					
8. 8" Gravity Line Misc Offshoots	\$175,000						\$246,243					
9. Repair 15 Manholes	\$36,000	\$3,308	\$3,473	\$3,647	\$3,829	\$4,020	\$4,221	\$4,432	\$4,654	\$4,887	\$5,131	\$5,388
10. Raise 5 Manholes and Replace Covers (Influent to Hwy211 Pump Station)	\$30,000		\$34,729									
11. Plant Pump Station Pump Replacements	\$300,000	\$330,750										
WWTP and Pump Station Improvements												
1. UV System Rehabilitation - FUNDED	\$298,000	\$328,545										
2. Hwy 211 Floodwall and Flood Gate Installation - FUNDED	\$298,000	\$328,545										
3. Grating and Piping System Replacement	\$714,000	\$787,185										
4. Blowers Replacement	\$714,000						\$1,004,670					
5. Solar Panel Installation	\$595,000						\$837,225					
6. HWY 211 Lift Station Pumps Replacement	\$143,000											\$256,807
7. Generator Replacement	\$714,000											\$1,282,241
8. UV System Replacement	\$714,000											\$1,282,241
9. Screw Screen Replacement	\$714,000											\$1,282,241
Maintenance Improvements												
1. Annual Clearing of ROW	\$10,000	\$11,025	\$11,576	\$12,155	\$12,763	\$13,401	\$14,071	\$14,775	\$15,513	\$16,289	\$17,103	\$17,959
Other Costs												
SRF Loan Fee	\$64,639	\$64,639										
TOTAL	\$7,917,639	\$3,799,910	\$49,778	\$15,802	\$16,592	\$17,421	\$2,997,125	\$19,207	\$20,167	\$21,176	\$22,234	\$4,126,877

## 9 Lifecycle Model Results

The Lifecycle Model created for Clarkton's Sewer Systems utilized the Town's data which contains installation date, material, diameter, and condition. Appendix III, the Lifecycle Model Documentation Report, provides a technical explanation of how the data was used to develop the model. Appendix IV, the Lifecycle Model Results Narrative, provides a detailed explanation of the scenarios explored, treatment costs, future investigations, and next steps. This section summarizes the recommended funding scenario for each asset type.

### 9.1 Sewer System

Within the sewer collection system, the gravity mains, force mains, and manholes were included in the lifecycle model analysis.

#### 9.1.1 Gravity Mains

The condition categories determined in Section 5 were used as the input for the model simulations for the gravity mains. The treatment scenario recommended for the gravity mains is annual funding of \$175,000, including annual inflation, to maintain a service state equivalent to a fair condition throughout the system. This treatment scenario will result in the rehabilitation or replacement of approximately 875 linear feet of pipe each year.

#### 9.1.2 Force Mains

The condition categories determined in Section 5 were used as the input for the model simulations for the force mains. The data received for Clarkton's two (2) force mains indicates no immediate need for replacement in the first 25 years to maintain a service state equivalent to a good condition throughout the system.

#### 9.1.3 Manholes

The condition categories determined in Section 5 were used as the input for the model simulations for the manholes. The treatment scenario recommended for the manholes is an annual funding of \$10,000, including annual inflation, to maintain a service state equivalent to a fair condition throughout the system. This treatment scenario will result in the rehabilitation or replacement of approximately three (3) manholes each year.



# APPENDIX I – GIS Maps

# Sewer System Overall Map

Town of Clarkton, NC



**WithersRavenel**

Our People. Your Success.  
115 MacKenan Dr | Cary NC, 27511  
t: 919.469.3340  
license #: F-1479  
[www.withersravenel.com](http://www.withersravenel.com)


This map is for informational purposes only. All feature locations displayed are approximate based on available data sources.


Data features are not based on professional field survey unless stated otherwise.

## Legend

- Manholes
- Lift Station
- Sewer Treatment Plant
- Unknown Production Well
- Sewer Gravity Main
- Sewer Force Main

## Treatment Plant Detail View





# Sewer System Materials Map

Town of Clarkton, NC



WithersRavenel

Our People. Your Success.  
115 MacKenan Dr | Cary NC, 27511  
t: 919.469.3340  
license #: F-1479  
[www.withersravenel.com](http://www.withersravenel.com)

This map is for informational purposes only.  
All feature locations displayed are approximate  
based on available data sources.

Data features are not based on professional  
field survey unless stated otherwise.

## Legend

### Sewer Gravity Main

#### Material


- Polyvinyl Chloride
- Asbestos Cement
- High Density Polyethylene
- Ductile Iron
- Vitrified Clay
- Other
- Reinforced Concrete
- Cast Iron
- Unknown

### Sewer Force Main

#### Material

- PVC
- UNK





# Sewer System Diameter Map

Town of Clarkton, NC



**WithersRavenel**

Our People. Your Success.  
115 MacKenan Dr | Cary NC, 27511  
t: 919.469.3340  
license #: F-1479  
[www.withersravenel.com](http://www.withersravenel.com)

This map is for informational purposes only.  
All feature locations displayed are approximate  
based on available data sources.

Data features are not based on professional  
field survey unless stated otherwise.

## Legend


### Sewer Gravity Main

- 6"
- 8"
- 10"
- 12"
- Unknown

### Sewer Force Main

- 6"
- Unknown





# Sewer System Condition Map

Town of Clarkton, NC



**WithersRavenel**

Our People. Your Success.  
 115 MacKenan Dr | Cary NC, 27511  
 t: 919.469.3340  
 license #: F-1479  
[www.withersravenel.com](http://www.withersravenel.com)

This map is for informational purposes only.  
 All feature locations displayed are approximate  
 based on available data sources.

Data features are not based on professional  
 field survey unless stated otherwise.

## Legend


### Sewer Gravity Main

- Excellent
- Good
- Fair
- Poor
- End of Life

### Sewer Force Main

- - - Fair





# Sewer System CCTV Condition Map

Town of Clarkton, NC



**WithersRavenel**

Our People. Your Success.

115 MacKenan Dr | Cary NC, 27511

t: 919.469.3340

license #: F-1479

[www.withersravenel.com](http://www.withersravenel.com)

This map is for informational purposes only.  
All feature locations displayed are approximate  
based on available data sources.

Data features are not based on professional  
field survey unless stated otherwise.

## Legend

Sewer Gravity Main

— Excellent

— Good

— Fair


— Poor

— End of Life

— No Score

0 500 1,000  
Feet





# Sewer System Manhole Condition Map

Town of Clarkton, NC



Our People. Your Success.  
115 MacKenan Dr | Cary NC, 27511  
t: 919.469.3340  
license #: F-1479  
[www.withersravenel.com](http://www.withersravenel.com)

This map is for informational purposes only.  
All feature locations displayed are approximate  
based on available data sources.


Data features are not based on professional  
field survey unless stated otherwise.

## Legend

### Manholes - Condition

- Good
- Fair
- Poor
- No Condition Data
- Sewer Mains
- Sewer Force Main

0 750 1,500  
Feet



# Sewer System Criticality Map

Town of Clarkton, NC



**WithersRavenel**

Our People. Your Success.  
 115 MacKenan Dr | Cary NC, 27511  
 t: 919.469.3340  
 license #: F-1479  
[www.withersravenel.com](http://www.withersravenel.com)

This map is for informational purposes only. All feature locations displayed are approximate based on available data sources.

Data features are not based on professional field survey unless stated otherwise.

## Legend

### Sewer Gravity Main


- Very Low
- Low
- Moderate
- High
- Very High

### Sewer Force Main

- - - Very Low
- - - Low
- - - Moderate
- - - High
- - - Very High







# Sewer System Risk Map

Town of Clarkton, NC



**WithersRavenel**

Our People. Your Success.  
 115 MacKenan Dr | Cary NC, 27511  
 t: 919.469.3340  
 license #: F-1479  
[www.withersravenel.com](http://www.withersravenel.com)

This map is for informational purposes only. All feature locations displayed are approximate based on available data sources.

Data features are not based on professional field survey unless stated otherwise.

## Legend

### Sewer Gravity Main

- Very Low
- Low
- Significant
- High
- Extreme

### Sewer Force Main

- - - Very Low
- - - Low
- - - Significant
- - - High
- - - Extreme



# Sewer System CIP Projects Map

Town of Clarkton, NC



**WithersRavenel**

Our People. Your Success.

115 MacKenan Dr | Cary NC, 27511


t: 919.469.3340

license #: F-1479

[www.withersravenel.com](http://www.withersravenel.com)

This map is for informational purposes only.  
All feature locations displayed are approximate  
based on available data sources.

Data features are not based on professional  
field survey unless stated otherwise.



# Sewer System CIP Projects Map

Town of Clarkton, NC



**WithersRavenel**

Our People. Your Success.

115 MacKenan Dr | Cary NC, 27511

t: 919.469.3340

license #: F-1479

[www.withersravenel.com](http://www.withersravenel.com)


This map is for informational purposes only.  
All feature locations displayed are approximate  
based on available data sources.

Data features are not based on professional  
field survey unless stated otherwise.

## Legend

### CIP Point Projects

- 9. Repair 15 Manholes
- 10. Raise and Replace Covers (Influent to Hwy211 Pump Station)
- 11. Plant Pump Station Pump Replacement
- Gravity Mains



# **APPENDIX II – Condition Assessment Results**



### Smoke Testing Results (Provided by Town)

ID #	Test Date	Street Location	Smoke Quantity	Defect Type	Corrected
1	4/2/2024 10:52	School	Medium	Unknown	No
2	4/2/2024 10:53	School	Medium	Unknown	No
3	4/2/2024 10:56	School	Low	Inside building	No
4	4/2/2024 11:03	School	Medium	Inside building	No
5	4/2/2024 11:48	North College Street	High	Cleanout - Broken	No
6	4/2/2024 11:51	North College Street	High	Manhole/below surface	No
7	4/2/2024 11:53	North College Street	Medium	Cleanout - Broken	No
8	4/2/2024 11:55	North College Street	Medium	Cleanout - Missing Cap	No
10	4/2/2024 13:29	Highway 211 West	Low	Unknown	No
11	4/2/2024 13:35	Tina's Lane	Low	Cleanout - Missing Cap	Yes
12	4/2/2024 13:36	Tina's Lane	Low	Cleanout - Missing Cap	Yes
13	4/2/2024 13:39	Tina's Lane	Low	Cleanout - Broken	Yes
14	4/2/2024 13:47	Highway 211 West	High	Cleanout - Broken	Yes
15	4/2/2024 13:49	Highway 211 West	High	Cleanout - Broken	Yes
16	4/2/2024 13:51	Highway 211 West	Medium	Cleanout - Broken	Yes
17	4/2/2024 13:52	Highway 211 West	Medium	Cleanout - Broken	Yes
18	4/2/2024 14:03	Ella Bell Rd	High	Cleanout - Missing Cap	No
19	4/2/2024 14:08	Highway 211 West	Medium	Manhole/needs repair	No
20	4/2/2024 14:09	Little John Rd / Hwy 211	High	Cleanout - Broken	No
21	4/2/2024 14:12	Highway 211 West	Medium	Cleanout - Broken	Yes



## Project Summary - CLARKTON SEWER CCTV TV6 04 08 24

Project Name:		CLARKTON SEWER CCTV TV6 04 08 24						
US MH	DS MH	Pipe ID	Date	Street	Material	Size	Total	Inspected
1251	1250	1251_1250	04/09/2024	N CLARK ST	Reinforced Concrete Pipe	6		162

Diameter: 6

Total Ln.: 0.0

Inspected Ln.: 162.0

US MH	DS MH	Pipe ID	Date	Street	Material	Size	Total	Inspected
103057	103059	103057_103059	04/08/2024	COLLEGE ST	Reinforced Concrete Pipe	8		49.9
103057A	103057	103057A_103057	04/08/2024	COLLEGE ST	Vitrified Clay Pipe	8		90.5
103057B	103057	103057B_103057	04/08/2024	COLLEGE ST	Reinforced Concrete Pipe	8		98.5
103060	103062	103060_103062	04/08/2024	COLLEGE ST	Reinforced Concrete Pipe	8		406.7
103062	103217	103062_103217	04/09/2024	E ROBERTS ST	Reinforced Concrete Pipe	8		56.6
103062	103217	103062_103217	04/09/2024	E ROBERTS ST	Reinforced Concrete Pipe	8		227.2
103062A	103062	103062A_103062	04/08/2024	E ROBERTS ST	Reinforced Concrete Pipe	8		368.1
103137	1261	103137_1261	04/09/2024	S GROVE ST	Reinforced Concrete Pipe	8		280.4
103138	103137	103138_103137	04/09/2024	S GROVE ST	Reinforced Concrete Pipe	8		211.3
103139	3140	103139_3140	04/09/2024	S GROVE ST	PolyVinyl Chloride	8		56.9
103192	1243	103192_1243	04/09/2024	N CLARK ST	Reinforced Concrete Pipe	8		122.4
103204	1330	103204_1330	04/11/2024	PAGE ST	Reinforced Concrete Pipe	8		243.8
103216	1366	103216_1366	04/11/2024	OFF N COLLEGE ST	Ductile Iron Pipe	8		258.8



## Project Summary - CLARKTON SEWER CCTV TV6 04 08 24

103219	103220	103219_103220	04/08/2024	N MITCHELL FORD RD	Reinforced Concrete Pipe	8		172.8
103220	103025	103220_103025	04/08/2024	N MITCHELL FORD RD	Reinforced Concrete Pipe	8		158.3
1238	1344	1238_1344	04/10/2024	N ELMHURST ST	Asbestos Cement	8		286.6
1239	1238	1239_1238	04/10/2024	N ELMHURST ST	Asbestos Cement	8		389.6
1243	1250	1243_1250	04/09/2024	N CLARK ST	Reinforced Concrete Pipe	8		159.5
1250	1252	1250_1252	04/09/2024	N GROVE ST	Reinforced Concrete Pipe	8		181.7
1260	1259	1260_1259	04/09/2024	N GROVE ST	Reinforced Concrete Pipe	8		253.3
1261	1260	1261_1260	04/09/2024	N GROVE ST	Reinforced Concrete Pipe	8		283.2
1347	103137	1347_103137	04/11/2024	E GREENE ST	Reinforced Concrete Pipe	8		244.3
1364	1365	1364_1365	04/10/2024	OFF W GRAHAM ST	Reinforced Concrete Pipe	8		273.2
3140	103138	3140_103138	04/09/2024	S GROVE ST	Reinforced Concrete Pipe	8		213.9

Diameter: 8

Total Ln.: 0.0

Inspected Ln.: 5087.5

US MH	DS MH	Pipe ID	Date	Street	Material	Size	Total	Inspected
103163	1345	103163_1345	04/10/2024	OFF SIXTH ST	Reinforced Concrete Pipe	12		232.4
1345	1344	1345_1344	04/10/2024	OFF SIXTH ST	Reinforced Concrete Pipe	12		404

Diameter: 12

Total Ln.: 0.0

Inspected Ln.: 636.4

Project Total Ln.: 0.0

Project Inspected Ln.: 5885.9




## 4 Image Report

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103219_103220	CLARKTON	N MITCHELL FORD RD	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 0.0 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 103220



Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 4.0 ft. Grade: 4  
 Condition: RBL-Roots Ball Lateral  
 Remarks: N/A




Distance: 4.0 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103219_103220	CLARKTON	N MITCHELL FORD RD	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 8.0 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 10.3 ft. Grade: 0  
 Condition: MGO-Miscellaneous General Observation  
 Remarks: CLEANED ROOT BEST AS POSSIBLE  
 WITHOUT BEING ABLE TO CLEAN FROM



Distance: 17.6 ft. Grade: 3  
 Condition: RMJ-Roots Medium Joint  
 Remarks: N/A



Distance: 20.6 ft. Grade: 2  
 Condition: FC-Fracture Circumferential  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103219_103220	City CLARKTON	Street N MITCHELL FORD RD	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 20.6 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 25.0 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 33.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 37.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103219_103220	City CLARKTON	Street N MITCHELL FORD RD	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 49.1 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 53.4 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 57.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 57.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A






## 4 Image Report

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103219_103220	CLARKTON	N MITCHELL FORD RD	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 61.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 65.4 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 73.4 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 77.2 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A





## 4 Image Report


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103219_103220	CLARKTON	N MITCHELL FORD RD	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 85.5 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 97.5 ft. Grade: 3  
 Condition: JOM-Joint Offset Medium  
 Remarks: N/A



Distance: 100.7 ft. Grade: 0  
 Condition: TFC-Tap Factory Made Capped  
 Remarks: N/A



Distance: 149.7 ft. Grade: 3  
 Condition: JOM-Joint Offset Medium  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103219_103220	City CLARKTON	Street N MITCHELL FORD RD	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 161.0 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 161.0 ft. Grade: 3  
 Condition: RML-Roots Medium Lateral  
 Remarks: N/A



Distance: 165.6 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A




Distance: 169.2 ft. Grade: 0  
 Condition: TFC-Tap Factory Made Capped  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103219_103220	City CLARKTON	Street N MITCHELL FORD RD	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 172.8 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 172.8 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103219




Distance: 172.8 ft. Grade: 0  
Condition: MGO-Miscellaneous General Observation  
Remarks: LAMPHOLE MH



## Defect Listing Plot

Pipe Segment Reference 103219_103220	City CLARKTON	Street N MITCHELL FORD RD	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 8	MPR 25	PO Number		Customer		
SPRI 2.7	MPRI 8.3	Work Order Number		Purpose		
QSR 3221	QMR 4132					
OPR 33	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/08/2024		Media label	
OPRI 5.5	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 12:32		Weather Dry	
Date Cleaned 04/08/2024			End Time 12:55		Additional Info	







## Defect Listing Plot

Pipe Segment Reference 103219_103220	City CLARKTON	Street N MITCHELL FORD RD	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length	

20.6 ft. FC-Fracture Circumferential




2

20.6 ft. RFJ-Roots Fine Joint



1

25 ft. RFJ-Roots Fine Joint




1

33.3 ft. RFJ-Roots Fine Joint



1

37.3 ft. RFJ-Roots Fine Joint



1

49.1 ft. RFJ-Roots Fine Joint



1

53.4 ft. RFJ-Roots Fine Joint



1

57.3 ft. RFJ-Roots Fine Joint



1

57.3 ft. RFJ-Roots Fine Joint



1



## Defect Listing Plot


Pipe Segment Reference	City	Street	Material		Location Code	Pipe Use
103219_103220	CLARKTON	N MITCHELL FORD RD	Reinforced Concrete Pipe			Sanitary Sewage Pipe
Upstream MH 103219	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103220	Length surveyed 172.8	Year Renewed	Height 8	Width	Pipe Joint Length	

61.3 ft. RFJ-Roots Fine Joint




1

65.4 ft. RFJ-Roots Fine Joint



1

73.4 ft. RFJ-Roots Fine Joint



1

77.2 ft. RFJ-Roots Fine Joint




1

85.5 ft. RFJ-Roots Fine Joint




1


97.5 ft. JOM-Joint Offset Medium



3

100.7 ft. TFC-Tap Factory Made  
Capped

149.7 ft. JOM-Joint Offset Medium



3

161 ft. TF-Tap Factory Made





## Defect Listing Plot

Pipe Segment Reference	City	Street	Material		Location Code	Pipe Use
103219_103220	CLARKTON	N MITCHELL FORD RD	Reinforced Concrete Pipe			Sanitary Sewage Pipe
Upstream MH	Total Length	Year Constructed	Shape		Location Details	
103219			Circular			
Downstream MH	Length surveyed	Year Renewed	Height	Width	Pipe Joint Length	
103220	172.8		8			

161 ft. RML-Roots Medium Lateral




3

165.6 ft. RFJ-Roots Fine Joint




1


169.2 ft. TFC-Tap Factory Made Capped



172.8 ft. TF-Tap Factory Made




172.8 ft. AMH-Access Point Manhole



103219

172.8 ft. MGO-Miscellaneous General Observation



LAMPHOLE MH




103219




## 4 Image Report


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103220_103025	CLARKTON	N MITCHELL FORD RD	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH	Total Length	Year Constructed	Shape	Location Details	
103220			Circular		
Downstream MH	Length surveyed	Year Renewed	Height	Width	Pipe Joint Length
103025	158.3		8		



Distance: 0.0 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 103220



Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 23.2 ft. Grade: 3  
 Condition: LFB-Lining Feature Blistered  
 Remarks: N/A



Distance: 74.4 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103220_103025	City CLARKTON	Street N MITCHELL FORD RD	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103220	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103025	Length surveyed 158.3	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 74.4 ft. Grade: 4  
Condition: IRL-Infiltration Runner Lateral  
Remarks: N/A




Distance: 158.3 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103025



## Defect Listing Plot


Pipe Segment Reference 103220_103025	City CLARKTON	Street N MITCHELL FORD RD	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103220	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103025	Length surveyed 158.3	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 3	MPR 4	PO Number		Customer		
SPRI 3	MPRI 4	Work Order Number		Purpose		
QSR 3100	QMR 4100					
OPR 7	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/08/2024		Media label	
OPRI 3.5	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 13:06		Weather Dry	
Date Cleaned 04/08/2024			End Time 13:18		Additional Info	





## 4 Image Report

Pipe Segment Reference 103057A_103057	City CLARKTON	Street COLLEGE ST	Material Vitrified Clay Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057A	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103057	Length surveyed 90.5	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 15.7 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 64.6 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 84.7 ft. Grade: 5  
 Condition: HVV-Hole Void Visible  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103057A_103057	City CLARKTON	Street COLLEGE ST	Material Vitrified Clay Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057A	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103057	Length surveyed 90.5	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 89.3 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 90.5 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103057A



Distance: 90.5 ft. Grade: 0  
Condition: MGO-Miscellaneous General Observation  
Remarks: LAMPHOLE MH



Distance: 90.5 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103057A_103057	City CLARKTON	Street COLLEGE ST	Material Vitrified Clay Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057A	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103057	Length surveyed 90.5	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 90.5 ft. Grade: 0  
Condition: MSC-Miscellaneous Shape/Size Change  
Remarks: N/A



## Defect Listing Plot

Pipe Segment Reference 103057A_103057	City CLARKTON	Street COLLEGE ST	Material Vitrified Clay Pipe	Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057A	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103057	Length surveyed 90.5	Year Renewed	Height 8	Width	Pipe Joint Length
SPR 5	MPR 0	PO Number		Customer	
SPRI 5	MPRI 0	Work Order Number		Purpose	
QSR 5100	QMR 0000				
OPR 5	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/08/2024	Media label	
OPRI 5	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 15:21	Weather Dry	
Date Cleaned 04/08/2024			End Time 15:33	Additional Info	





## Defect Listing Plot

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103057A_103057	CLARKTON	COLLEGE ST	Vitrified Clay Pipe		Sanitary Sewage Pipe
Upstream MH 103057A	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103057	Length surveyed 90.5	Year Renewed	Height 8	Width	Pipe Joint Length

90.5 ft.

MGO-Miscellaneous General  
Observation

LAMPHOLE MH

90.5 ft.

TF-Tap Factory Made



90.5 ft.

MSC-Miscellaneous  
Shape/Size Change

103057A



## 4 Image Report


Pipe Segment Reference 103057B_103057	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057B	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103057	Length surveyed 98.5	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 103057



Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 20.3 ft. Grade: 0  
 Condition: TFC-Tap Factory Made Capped  
 Remarks: N/A




Distance: 35.9 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A





## 4 Image Report


Pipe Segment Reference 103057B_103057	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057B	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103057	Length surveyed 98.5	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 81.8 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 94.7 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 95.4 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 98.5 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103057B_103057	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057B	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103057	Length surveyed 98.5	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 98.5 ft. Grade: 5  
 Condition: RBB-Roots Ball Barrell  
 Remarks: RB AT END OF LINE



Distance: 98.5 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A




Distance: 98.5 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 103057B



## Defect Listing Plot

Pipe Segment Reference 103057B_103057	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057B	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103057	Length surveyed 98.5	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 26	MPR 7	PO Number		Customer		
SPRI 2	MPRI 7	Work Order Number		Purpose		
QSR 2A00	QMR 5100					
OPR 33	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/08/2024		Media label	
OPRI 2.4	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 15:39		Weather Dry	
Date Cleaned 04/08/2024			End Time 16:28		Additional Info	







## Defect Listing Plot

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103057B_103057	CLARKTON	COLLEGE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103057B	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103057	Length surveyed 98.5	Year Renewed	Height 8	Width	Pipe Joint Length

98.5 ft. TF-Tap Factory Made




98.5 ft. RBB-Roots Ball Barrell



RB AT END OF LINE


98.5 ft. SAV-Surface Damage Aggregate Visible - F01



98.5 ft. AMH-Access Point Manhole



103057B



103057B



## 4 Image Report

Pipe Segment Reference 103057_103059	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103059	Length surveyed 49.9	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A




Distance: 49.9 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103059



## Defect Listing Plot

Pipe Segment Reference 103057_103059	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103057	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103059	Length surveyed 49.9	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 0	MPR 0	PO Number		Customer		
SPRI 0	MPRI 0	Work Order Number		Purpose		
QSR 0000	QMR 0000					
OPR 0	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/08/2024		Media label	
OPRI 0	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 17:01		Weather Dry	
Date Cleaned 04/08/2024			End Time 12:03		Additional Info	







## 4 Image Report

Pipe Segment Reference 103060_103062	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103062



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 8.0 ft. Grade: 3  
Condition: JOM-Joint Offset Medium  
Remarks: N/A




Distance: 96.6 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A





## 4 Image Report

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103060_103062	CLARKTON	COLLEGE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 153.5 ft. Grade: 0  
 Condition: TFC-Tap Factory Made Capped  
 Remarks: N/A



Distance: 185.3 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 194.9 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A




Distance: 211.4 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A






## 4 Image Report


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103060_103062	CLARKTON	COLLEGE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 222.0 ft. Grade: 2  
Condition: FC-Fracture Circumferential  
Remarks: N/A



Distance: 232.2 ft. Grade: 1  
Condition: RFJ-Roots Fine Joint  
Remarks: N/A



Distance: 232.2 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A




Distance: 240.0 ft. Grade: 1  
Condition: RFJ-Roots Fine Joint  
Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103060_103062	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 240.2 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 247.5 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 247.5 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A




Distance: 252.1 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A





## 4 Image Report


Pipe Segment Reference 103060_103062	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 255.6 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 255.6 ft. Grade: 1  
 Condition: RFL-Roots Fine Lateral  
 Remarks: N/A



Distance: 259.8 ft. Grade: 0  
 Condition: MGO-Miscellaneous General Observation  
 Remarks: BURIED MH




Distance: 288.4 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103060_103062	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 304.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 308.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 308.3 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



Distance: 312.2 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A





## 4 Image Report


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103060_103062	CLARKTON	COLLEGE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length




Distance: 317.7 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 325.8 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 388.0 ft. Grade: 0  
 Condition: TFC-Tap Factory Made Capped  
 Remarks: N/A



Distance: 389.9 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



## 4 Image Report

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103060_103062	CLARKTON	COLLEGE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 404.5 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 406.7 ft. Grade: 0  
 Condition: MSA-Miscellaneous Survey Abandoned  
 Remarks: CAPPED AT END OF LINE.



## Defect Listing Plot

Pipe Segment Reference 103060_103062	City CLARKTON	Street COLLEGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 51	MPR 14	PO Number		Customer		
SPRI 2	MPRI 0	Work Order Number		Purpose		
QSR 312C	QMR 0000					
OPR 65	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/08/2024		Media label	
OPRI 2.6	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 17:50		Weather Dry	
Date Cleaned 04/08/2024			End Time 18:13		Additional Info	








## Defect Listing Plot


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103060_103062	CLARKTON	COLLEGE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length

211.4 ft. RFJ-Roots Fine Joint




1

222 ft. FC-Fracture Circumferential




2

232.2 ft. RFJ-Roots Fine Joint




1

232.2 ft. MWL-Miscellaneous Water Level




240 ft. RFJ-Roots Fine Joint



1

240.2 ft. RFJ-Roots Fine Joint




1

247.5 ft. RFJ-Roots Fine Joint



1

247.5 ft. RFJ-Roots Fine Joint



1

252.1 ft. RFJ-Roots Fine Joint




1




## Defect Listing Plot

Pipe Segment Reference	City	Street	Material		Location Code	Pipe Use
103060_103062	CLARKTON	COLLEGE ST	Reinforced Concrete Pipe			Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length	

255.6 ft. TF-Tap Factory Made




255.6 ft. RFL-Roots Fine Lateral




1

259.8 ft. MGO-Miscellaneous General Observation




BURIED MH

288.4 ft. RFJ-Roots Fine Joint



1

304.3 ft. RFJ-Roots Fine Joint



1

308.3 ft. RFJ-Roots Fine Joint




1

308.3 ft. SAV-Surface Damage Aggregate Visible - F01



2

312.2 ft. RFJ-Roots Fine Joint



1

317.7 ft. RFJ-Roots Fine Joint



1



## Defect Listing Plot


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103060_103062	CLARKTON	COLLEGE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103060	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103062	Length surveyed 406.7	Year Renewed	Height 8	Width	Pipe Joint Length

325.8 ft. RFJ-Roots Fine Joint




1


388 ft. TFC-Tap Factory Made Capped



389.9 ft. TF-Tap Factory Made



404.5 ft. TF-Tap Factory Made



406.7 ft. MSA-Miscellaneous Survey Abandoned



CAPPED AT END OF LINE.



## 4 Image Report

Pipe Segment Reference 103062A_103062	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062A	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 368.1	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 118.8 ft. Grade: 4  
Condition: H-Hole  
Remarks: N/A



Distance: 118.8 ft. Grade: 5  
Condition: HSV-Hole Soil Visible  
Remarks: N/A




Distance: 237.5 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103062A_103062	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062A	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 368.1	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 322.6 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A




Distance: 368.1 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103062A



## Defect Listing Plot

Pipe Segment Reference 103062A_103062	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062A	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 368.1	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 9	MPR 0	PO Number		Customer		
SPRI 4.5	MPRI 0	Work Order Number		Purpose		
QSR 5141	QMR 0000					
OPR 9	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/08/2024		Media label	
OPRI 4.5	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 18:28		Weather Dry	
Date Cleaned 04/08/2024			End Time 18:42		Additional Info	






## Defect Listing Plot

Pipe Segment Reference 103062A_103062	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062A	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103062	Length surveyed 368.1	Year Renewed	Height 8	Width	Pipe Joint Length	

368.1 ft.

AMH-Access Point Manhole



103062A



103062A




## 4 Image Report

Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 56.6	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 3.0 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 16.2 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A



Distance: 43.1 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A






## 4 Image Report


Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 56.6	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 43.1 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: DIP



Distance: 53.7 ft. Grade: 0  
 Condition: RPP-Point Repair Patch  
 Remarks: CIPP PATCH




Distance: 56.6 ft. Grade: 0  
 Condition: MSA-Miscellaneous Survey Abandoned  
 Remarks: CANNOT PASS RPP. NEEDS REVERSAL UP TO PATCH



## Defect Listing Plot

Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 56.6	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 10	MPR 0	PO Number		Customer		
SPRI 2	MPRI 0	Work Order Number		Purpose		
QSR 2500	QMR 0000					
OPR 10	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 2	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 09:00		Weather Dry	
Date Cleaned 04/09/2024			End Time 09:07		Additional Info	





## Defect Listing Plot

Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 56.6	Year Renewed	Height 8	Width	Pipe Joint Length	

56.6 ft.


MSA-Miscellaneous Survey  
AbandonedCANNOT PASS RPP. NEEDS REVERSAL  
UP TO PATCH





## 4 Image Report

Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 227.2	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 0.0 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 0.0 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 9.0 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 227.2	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 13.5 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 16.2 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



Distance: 21.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A




Distance: 25.1 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A





## 4 Image Report


Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 227.2	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 25.1 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 30.9 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 30.9 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A




Distance: 34.3 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 227.2	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 146.8 ft. Grade: 0  
Condition: TFC-Tap Factory Made Capped  
Remarks: N/A



Distance: 221.9 ft. Grade: 0  
Condition: MMC-Miscellaneous Material Change  
Remarks: PVC



Distance: 222.1 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A



Distance: 227.2 ft. Grade: 0  
Condition: MSA-Miscellaneous Survey Abandoned  
Remarks: MADE TO PREVIOUS RPP



## Defect Listing Plot

Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 227.2	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 82	MPR 10	PO Number		Customer		
SPRI 2	MPRI 0	Work Order Number		Purpose		
QSR 2G00	QMR 0000					
OPR 92	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/09/2024		Media label	
OPRI 2.2	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 09:30		Weather	
Date Cleaned 04/09/2024			End Time 09:43		Additional Info	







## Defect Listing Plot

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103062_103217	CLARKTON	E ROBERTS ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103217	Length surveyed 227.2	Year Renewed	Height 8	Width	Pipe Joint Length

21.3 ft. RFJ-Roots Fine Joint




1

25.1 ft. RFJ-Roots Fine Joint



1

25.1 ft. RFJ-Roots Fine Joint




1

30.9 ft. RFJ-Roots Fine Joint




1

30.9 ft. RFJ-Roots Fine Joint




1

34.3 ft. RFJ-Roots Fine Joint



1

146.8 ft. TFC-Tap Factory Made Capped



221.9 ft. MMC-Miscellaneous Material Change



PVC

222.1 ft. SAV-Surface Damage Aggregate Visible - F01



2



## Defect Listing Plot

Pipe Segment Reference 103062_103217	City CLARKTON	Street E ROBERTS ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103062	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103217	Length surveyed 227.2	Year Renewed	Height 8	Width	Pipe Joint Length	

227.2 ft.

MSA-Miscellaneous Survey  
Abandoned


MADE TO PREVIOUS RPP






## 4 Image Report


Pipe Segment Reference 103139_3140	City CLARKTON	Street S GROVE ST	Material PolyVinyl Chloride		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103139	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 3140	Length surveyed 56.9	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103139



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 1.0 ft. Grade: 0  
Condition: MMC-Miscellaneous Material Change  
Remarks: RCP




Distance: 56.9 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 3140



## 4 Image Report

Pipe Segment Reference 103139_3140	City CLARKTON	Street S GROVE ST	Material PolyVinyl Chloride		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103139	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 3140	Length surveyed 56.9	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 56.9 ft. Grade: 0  
Condition: MGO-Miscellaneous General Observation  
Remarks: LAMPHOLE MH





## Defect Listing Plot


Pipe Segment Reference 103139_3140	City CLARKTON	Street S GROVE ST	Material PolyVinyl Chloride		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103139	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 3140	Length surveyed 56.9	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 0	MPR 0	PO Number		Customer		
SPRI 0	MPRI 0	Work Order Number		Purpose		
QSR 0000	QMR 0000					
OPR 0	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 0	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 10:27		Weather Dry	
Date Cleaned 04/09/2024			End Time 10:32		Additional Info	





## 4 Image Report


Pipe Segment Reference 3140_103138	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 3140	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103138	Length surveyed 213.9	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 9.9 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 9.9 ft. Grade: 2  
 Condition: FC-Fracture Circumferential  
 Remarks: N/A




Distance: 24.0 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A





## 4 Image Report

Pipe Segment Reference 3140_103138	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 3140	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103138	Length surveyed 213.9	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 52.0 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 71.2 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: PVC



Distance: 75.9 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: RCP




Distance: 80.0 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



## 4 Image Report


Pipe Segment Reference 3140_103138	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 3140	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103138	Length surveyed 213.9	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 120.5 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



Distance: 123.2 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: PVC



Distance: 129.2 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: RCP



Distance: 130.8 ft. Grade: 5  
 Condition: TFI-Tap Factory Made Intruding  
 Remarks: N/A






## 4 Image Report


Pipe Segment Reference 3140_103138	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 3140	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103138	Length surveyed 213.9	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 166.2 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: PVC



Distance: 170.7 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: RCP



Distance: 196.2 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 196.2 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A




## 4 Image Report

Pipe Segment Reference 3140_103138	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 3140	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103138	Length surveyed 213.9	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 209.9 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A




Distance: 213.9 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103138



## Defect Listing Plot

Pipe Segment Reference 3140_103138	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 3140	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103138	Length surveyed 213.9	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 18	MPR 7	PO Number		Customer		
SPRI 2	MPRI 7	Work Order Number		Purpose		
QSR 2900	QMR 5100					
OPR 25	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 2.5	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 10:33		Weather Dry	
Date Cleaned 04/09/2024			End Time 10:49		Additional Info	
















## Defect Listing Plot

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
3140_103138	CLARKTON	S GROVE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 3140	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103138	Length surveyed 213.9	Year Renewed	Height 8	Width	Pipe Joint Length

75.9 ft.	MMC-Miscellaneous Material Change				RCP
80 ft.	SAV-Surface Damage Aggregate Visible - S01		2		
120.5 ft.	SAV-Surface Damage Aggregate Visible - F01		2		
123.2 ft.	MMC-Miscellaneous Material Change				PVC
129.2 ft.	MMC-Miscellaneous Material Change				RCP
130.8 ft.	TFI-Tap Factory Made Intruding		5		
166.2 ft.	MMC-Miscellaneous Material Change				PVC
170.7 ft.	MMC-Miscellaneous Material Change				RCP
196.2 ft.	RFJ-Roots Fine Joint		1		





## Defect Listing Plot

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
3140_103138	CLARKTON	S GROVE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 3140	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103138	Length surveyed 213.9	Year Renewed	Height 8	Width	Pipe Joint Length


196.2 ft. RFJ-Roots Fine Joint



209.9 ft. TF-Tap Factory Made



213.9 ft. AMH-Access Point Manhole



103138




103138



## 4 Image Report

Pipe Segment Reference 103138_103137	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103138	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103137	Length surveyed 211.3	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103138



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 11.4 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A




Distance: 62.8 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



## 4 Image Report


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
103138_103137	CLARKTON	S GROVE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 103138	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 103137	Length surveyed 211.3	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 67.9 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 101.1 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A




Distance: 211.3 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 103137





## Defect Listing Plot

Pipe Segment Reference 103138_103137	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103138	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103137	Length surveyed 211.3	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 0	MPR 0	PO Number		Customer		
SPRI 0	MPRI 0	Work Order Number		Purpose		
QSR 0000	QMR 0000					
OPR 0	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 0	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 11:26		Weather Dry	
Date Cleaned 04/09/2024			End Time 12:13		Additional Info	








## Defect Listing Plot

Pipe Segment Reference 103138_103137	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103138	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103137	Length surveyed 211.3	Year Renewed	Height 8	Width	Pipe Joint Length	

211.3 ft.

AMH-Access Point Manhole



103137

103137



## 4 Image Report

Pipe Segment Reference 103137_1261	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103137	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1261	Length surveyed 280.4	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103137



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 74.2 ft. Grade: 3  
Condition: LFW-Lining Feature Wrinkled  
Remarks: N/A



Distance: 100.4 ft. Grade: 3  
Condition: LFW-Lining Feature Wrinkled  
Remarks: N/A






## 4 Image Report


Pipe Segment Reference 103137_1261	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103137	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1261	Length surveyed 280.4	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 106.1 ft. Grade: 3  
 Condition: LFW-Lining Feature Wrinkled  
 Remarks: N/A



Distance: 135.5 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 175.5 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 280.4 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 1261



## Defect Listing Plot

Pipe Segment Reference 103137_1261	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103137	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1261	Length surveyed 280.4	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 6	MPR 0	PO Number		Customer		
SPRI 3	MPRI 0	Work Order Number		Purpose		
QSR 3200	QMR 0000					
OPR 6	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 3	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 12:18		Weather Dry	
Date Cleaned 04/09/2024			End Time 12:58		Additional Info	








## Defect Listing Plot

Pipe Segment Reference 103137_1261	City CLARKTON	Street S GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103137	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1261	Length surveyed 280.4	Year Renewed	Height 8	Width	Pipe Joint Length	

280.4 ft.

AMH-Access Point Manhole



1261

1261




## 4 Image Report

Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1261



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 0.1 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A



Distance: 35.2 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A





## 4 Image Report


Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 35.6 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: PVC



Distance: 35.6 ft. Grade: 3  
 Condition: JOM-Joint Offset Medium  
 Remarks: N/A



Distance: 38.1 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A




Distance: 39.2 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A




## 4 Image Report


Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 46.0 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 47.4 ft. Grade: 0  
Condition: MMC-Miscellaneous Material Change  
Remarks: RCP



Distance: 47.4 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A




Distance: 47.9 ft. Grade: 3  
Condition: FL-Fracture Longitudinal  
Remarks: N/A





## 4 Image Report


Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 73.6 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



Distance: 73.6 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: PVC



Distance: 88.1 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: RCP




Distance: 88.1 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A






## 4 Image Report

Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 131.5 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 163.3 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 175.4 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A




Distance: 177.9 ft. Grade: 2  
Condition: FC-Fracture Circumferential  
Remarks: N/A






## 4 Image Report


Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 201.8 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 207.1 ft. Grade: 5  
 Condition: HSV-Hole Soil Visible  
 Remarks: N/A



Distance: 209.7 ft. Grade: 5  
 Condition: HSV-Hole Soil Visible  
 Remarks: N/A




Distance: 210.1 ft. Grade: 3  
 Condition: FL-Fracture Longitudinal  
 Remarks: N/A






## 4 Image Report


Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 227.2 ft. Grade: 0  
Condition: TFC-Tap Factory Made Capped  
Remarks: N/A



Distance: 233.4 ft. Grade: 2  
Condition: FC-Fracture Circumferential  
Remarks: N/A



Distance: 233.4 ft. Grade: 5  
Condition: HSV-Hole Soil Visible  
Remarks: N/A




Distance: 252.2 ft. Grade: 3  
Condition: FL-Fracture Longitudinal  
Remarks: N/A






## 4 Image Report

Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 260.7 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 275.7 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 283.2 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



Distance: 283.2 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 1260



## Defect Listing Plot

Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 135	MPR 2	PO Number		Customer		
SPRI 2.2	MPRI 0	Work Order Number		Purpose		
QSR 5334	QMR 0000					
OPR 137	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 2.2	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 15:08		Weather Dry	
Date Cleaned 04/09/2024			End Time 15:25		Additional Info	








## Defect Listing Plot

Pipe Segment Reference	City	Street	Material		Location Code	Pipe Use
1261_1260	CLARKTON	N GROVE ST	Reinforced Concrete Pipe			Sanitary Sewage Pipe
Upstream MH	Total Length	Year Constructed	Shape		Location Details	
1261			Circular			
Downstream MH	Length surveyed	Year Renewed	Height	Width	Pipe Joint Length	
1260	283.2		8			


39.2 ft.

SAV-Surface Damage  
Aggregate Visible - F01


2

46 ft.

TF-Tap Factory Made




47.4 ft.

MMC-Miscellaneous Material  
Change

RCP


47.4 ft.

SAV-Surface Damage  
Aggregate Visible - S02

2


47.9 ft.

FL-Fracture Longitudinal




3

73.6 ft.

SAV-Surface Damage  
Aggregate Visible - F02


2

73.6 ft.

MMC-Miscellaneous Material  
Change


PVC

88.1 ft.

MMC-Miscellaneous Material  
Change

RCP

88.1 ft.

SAV-Surface Damage  
Aggregate Visible - S03


2




## Defect Listing Plot

Pipe Segment Reference	City	Street	Material		Location Code	Pipe Use
1261_1260	CLARKTON	N GROVE ST	Reinforced Concrete Pipe			Sanitary Sewage Pipe
Upstream MH	Total Length	Year Constructed	Shape		Location Details	
1261			Circular			
Downstream MH	Length surveyed	Year Renewed	Height	Width	Pipe Joint Length	
1260	283.2		8			

131.5 ft. TF-Tap Factory Made




163.3 ft. TF-Tap Factory Made



175.4 ft. TF-Tap Factory Made




177.9 ft. FC-Fracture Circumferential




2

201.8 ft. RFJ-Roots Fine Joint




1

207.1 ft. HSV-Hole Soil Visible




5

209.7 ft. HSV-Hole Soil Visible




5

210.1 ft. FL-Fracture Longitudinal



3

227.2 ft. TFC-Tap Factory Made Capped






## Defect Listing Plot


Pipe Segment Reference 1261_1260	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1261	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1260	Length surveyed 283.2	Year Renewed	Height 8	Width	Pipe Joint Length	

233.4 ft. FC-Fracture Circumferential




2

233.4 ft. HSV-Hole Soil Visible



5

252.2 ft. FL-Fracture Longitudinal




3

260.7 ft. RFJ-Roots Fine Joint



1

275.7 ft. TF-Tap Factory Made



283.2 ft. SAV-Surface Damage Aggregate Visible - F03



2

283.2 ft. AMH-Access Point Manhole



1260




1260





## 4 Image Report

Pipe Segment Reference 1260_1259	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1260	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1259	Length surveyed 253.3	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1260



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 19.8 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A




Distance: 23.3 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A





## 4 Image Report


Pipe Segment Reference 1260_1259	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1260	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1259	Length surveyed 253.3	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 84.1 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 93.7 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 103.4 ft. Grade: 3  
 Condition: LFB-Lining Feature Blistered  
 Remarks: N/A



Distance: 251.4 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: DROP



## 4 Image Report

Pipe Segment Reference 1260_1259	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1260	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1259	Length surveyed 253.3	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 253.3 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1259





## Defect Listing Plot

Pipe Segment Reference 1260_1259	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1260	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1259	Length surveyed 253.3	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 3	MPR 0	PO Number		Customer		
SPRI 3	MPRI 0	Work Order Number		Purpose		
QSR 3100	QMR 0000					
OPR 3	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 3	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 15:44		Weather Dry	
Date Cleaned 04/09/2024			End Time 15:57		Additional Info	






## Defect Listing Plot

Pipe Segment Reference 1260_1259	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1260	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1259	Length surveyed 253.3	Year Renewed	Height 8	Width	Pipe Joint Length	

251.4 ft.

TF-Tap Factory Made



DROP

253.3 ft.

AMH-Access Point Manhole



1259





## 4 Image Report


Pipe Segment Reference 103192_1243	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103192	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1243	Length surveyed 122.4	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1243



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 110.2 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A




Distance: 118.4 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A





## 4 Image Report

Pipe Segment Reference 103192_1243	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103192	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1243	Length surveyed 122.4	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 122.4 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 103192



Distance: 122.4 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: LAMPHOLE MH. COULD NOT LOCATE




Distance: 122.4 ft. Grade: 0  
 Condition: MGO-Miscellaneous General Observation  
 Remarks: COULD NOT LOCATE



## Defect Listing Plot

Pipe Segment Reference 103192_1243	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103192	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1243	Length surveyed 122.4	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 0	MPR 0	PO Number		Customer		
SPRI 0	MPRI 0	Work Order Number		Purpose		
QSR 0000	QMR 0000					
OPR 0	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/09/2024		Media label	
OPRI 0	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 16:38		Weather Dry	
Date Cleaned 04/09/2024			End Time 16:44		Additional Info	






## Defect Listing Plot

Pipe Segment Reference 103192_1243	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103192	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1243	Length surveyed 122.4	Year Renewed	Height 8	Width	Pipe Joint Length	

122.4 ft.

MGO-Miscellaneous General  
Observation

103192

COULD NOT LOCATE





## 4 Image Report

Pipe Segment Reference 1243_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1243	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 159.5	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 0.0 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A



Distance: 62.0 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A



Distance: 62.0 ft. Grade: 0  
Condition: MMC-Miscellaneous Material Change  
Remarks: PVC



## 4 Image Report


Pipe Segment Reference 1243_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1243	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 159.5	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 65.8 ft. Grade: 0  
Condition: MMC-Miscellaneous Material Change  
Remarks: RCP



Distance: 65.8 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A



Distance: 77.5 ft. Grade: 4  
Condition: FM-Fracture Multiple  
Remarks: N/A




Distance: 144.4 ft. Grade: 1  
Condition: RFJ-Roots Fine Joint  
Remarks: N/A






## 4 Image Report


Pipe Segment Reference 1243_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1243	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 159.5	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 153.6 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 153.6 ft. Grade: 5  
 Condition: IGL-Infiltration Gusher Lateral  
 Remarks: N/A



Distance: 159.5 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 1250




Distance: 159.5 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A





## Defect Listing Plot

Pipe Segment Reference 1243_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1243	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 159.5	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 66	MPR 6	PO Number		Customer		
SPRI 2.1	MPRI 6	Work Order Number		Purpose		
QSR 412E	QMR 5100					
OPR 72	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 2.2	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 16:48		Weather Dry	
Date Cleaned 04/09/2024			End Time 16:59		Additional Info	






## Defect Listing Plot


Pipe Segment Reference 1243_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1243	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 159.5	Year Renewed	Height 8	Width	Pipe Joint Length	

77.5 ft. FM-Fracture Multiple




4

144.4 ft. RFJ-Roots Fine Joint




1

153.6 ft. TF-Tap Factory Made




153.6 ft. IGL-Infiltration Gusher Lateral



5

159.5 ft. AMH-Access Point Manhole



1250

159.5 ft. SAV-Surface Damage Aggregate Visible - F02



2



1250



## 4 Image Report


Pipe Segment Reference 1251_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1251	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 162	Year Renewed	Height 6	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 0.0 ft. Grade: 0  
 Condition: MGO-Miscellaneous General Observation  
 Remarks: COULD NOT ACCESS US MH. CUT ROOTS BEST AS POSSIBLE WITH



Distance: 44.5 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A




Distance: 65.6 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A





## 4 Image Report


Pipe Segment Reference 1251_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1251	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 162	Year Renewed	Height 6	Width	Pipe Joint Length	




Distance: 94.6 ft. Grade: 1  
Condition: RFJ-Roots Fine Joint  
Remarks: N/A



Distance: 97.9 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 98.7 ft. Grade: 1  
Condition: RFJ-Roots Fine Joint  
Remarks: N/A




Distance: 102.8 ft. Grade: 1  
Condition: RFJ-Roots Fine Joint  
Remarks: N/A






## 4 Image Report


Pipe Segment Reference 1251_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1251	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 162	Year Renewed	Height 6	Width	Pipe Joint Length	




Distance: 106.9 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 110.7 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 114.8 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A




Distance: 155.0 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A




## 4 Image Report


Pipe Segment Reference 1251_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1251	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 162	Year Renewed	Height 6	Width	Pipe Joint Length	



Distance: 158.1 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 162.0 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: LAMPHOLE MH




Distance: 162.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1251





## Defect Listing Plot

Pipe Segment Reference 1251_1250	City CLARKTON	Street N CLARK ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1251	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1250	Length surveyed 162	Year Renewed	Height 6	Width	Pipe Joint Length	
SPR 0	MPR 7	PO Number		Customer		
SPRI 0	MPRI 0	Work Order Number		Purpose		
QSR 0000	QMR 0000					
OPR 7	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/09/2024		Media label	
OPRI 0	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 17:43		Weather Dry	
Date Cleaned 04/09/2024			End Time 17:58		Additional Info	






## Defect Listing Plot


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
1251_1250	CLARKTON	N CLARK ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 1251	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 1250	Length surveyed 162	Year Renewed	Height 6	Width	Pipe Joint Length

98.7 ft. RFJ-Roots Fine Joint




1

102.8 ft. RFJ-Roots Fine Joint




1

106.9 ft. RFJ-Roots Fine Joint



1

110.7 ft. RFJ-Roots Fine Joint



1

114.8 ft. RFJ-Roots Fine Joint




1

155 ft. RFJ-Roots Fine Joint




1

158.1 ft. TF-Tap Factory Made




162 ft. TF-Tap Factory Made



LAMPHOLE MH

162 ft. AMH-Access Point Manhole



1251




1251




## 4 Image Report


Pipe Segment Reference 1250_1252	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 2.4 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



Distance: 38.1 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A




Distance: 44.0 ft. Grade: 4  
 Condition: H-Hole  
 Remarks: N/A





## 4 Image Report


Pipe Segment Reference 1250_1252	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 52.9 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 56.8 ft. Grade: 1  
 Condition: RFJ-Roots Fine Joint  
 Remarks: N/A



Distance: 61.1 ft. Grade: 2  
 Condition: FC-Fracture Circumferential  
 Remarks: N/A




Distance: 61.1 ft. Grade: 2  
 Condition: RFB-Roots Fine Barrel  
 Remarks: N/A






## 4 Image Report

Pipe Segment Reference 1250_1252	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 65.1 ft. Grade: 2  
 Condition: RTJ-Roots Tap Joint  
 Remarks: CANNOT CHAIN CUT DUE TO PR FURTHER DOWN LINE



Distance: 70.1 ft. Grade: 5  
 Condition: HSV-Hole Soil Visible  
 Remarks: N/A



Distance: 73.0 ft. Grade: 2  
 Condition: RTJ-Roots Tap Joint  
 Remarks: N/A




Distance: 76.5 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: PVC






## 4 Image Report


Pipe Segment Reference 1250_1252	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 76.5 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



Distance: 80.0 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 82.6 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: RCP




Distance: 82.6 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A






## 4 Image Report


Pipe Segment Reference 1250_1252	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 86.5 ft. Grade: 5  
Condition: HSV-Hole Soil Visible  
Remarks: N/A



Distance: 87.5 ft. Grade: 5  
Condition: HSV-Hole Soil Visible  
Remarks: N/A



Distance: 114.4 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 181.7 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1252



## 4 Image Report

Pipe Segment Reference 1250_1252	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 181.7 ft. Grade: 2  
Condition: SAV-Surface Damage Aggregate Visible  
Remarks: N/A



## Defect Listing Plot

Pipe Segment Reference 1250_1252	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 91	MPR 8	PO Number		Customer		
SPRI 2.3	MPRI 2.7	Work Order Number		Purpose		
QSR 5341	QMR 2300					
OPR 99	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/09/2024		Media label	
OPRI 2.3	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 18:11		Weather Dry	
Date Cleaned 04/09/2024			End Time 18:52		Additional Info	








## Defect Listing Plot


Pipe Segment Reference 1250_1252	City CLARKTON	Street N GROVE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length	

61.1 ft. FC-Fracture Circumferential



2

61.1 ft. RFB-Roots Fine Barrel



2


65.1 ft. RTJ-Roots Tap Joint



2


CANNOT CHAIN CUT DUE TO PR  
FURTHER DOWN LINE

70.1 ft. HSV-Hole Soil Visible




5


73 ft. RTJ-Roots Tap Joint



2


76.5 ft. MMC-Miscellaneous Material  
Change

PVC

76.5 ft. SAV-Surface Damage  
Aggregate Visible - F01

2

80 ft. TF-Tap Factory Made

82.6 ft. MMC-Miscellaneous Material  
Change


RCP



## Defect Listing Plot


Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
1250_1252	CLARKTON	N GROVE ST	Reinforced Concrete Pipe		Sanitary Sewage Pipe
Upstream MH 1250	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 1252	Length surveyed 181.7	Year Renewed	Height 8	Width	Pipe Joint Length

82.6 ft. SAV-Surface Damage  
Aggregate Visible - S02




2

86.5 ft. HSV-Hole Soil Visible




5

87.5 ft. HSV-Hole Soil Visible



5

114.4 ft. TF-Tap Factory Made



181.7 ft. AMH-Access Point Manhole



1252

181.7 ft. SAV-Surface Damage  
Aggregate Visible - F02



2



1252



## 4 Image Report

Pipe Segment Reference 1239_1238	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1239	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1238	Length surveyed 389.6	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 1238



Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 93.8 ft. Grade: 5  
 Condition: HSV-Hole Soil Visible  
 Remarks: N/A



Distance: 93.8 ft. Grade: 5  
 Condition: HSV-Hole Soil Visible  
 Remarks: N/A






## 4 Image Report


Pipe Segment Reference 1239_1238	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1239	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1238	Length surveyed 389.6	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 108.2 ft. Grade: 0  
Condition: TFA-Tap Factory Activity  
Remarks: N/A



Distance: 120.3 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 134.8 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A




Distance: 135.4 ft. Grade: 5  
Condition: HSV-Hole Soil Visible  
Remarks: N/A



## 4 Image Report


Pipe Segment Reference 1239_1238	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1239	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1238	Length surveyed 389.6	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 178.2 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 266.1 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 346.2 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 381.8 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A





## 4 Image Report

Pipe Segment Reference 1239_1238	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement	Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1239	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 1238	Length surveyed 389.6	Year Renewed	Height 8	Width	Pipe Joint Length



Distance: 385.1 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: PVC



Distance: 388.7 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: ASBESTES



Distance: 389.6 ft. Grade: 0  
 Condition: MSA-Miscellaneous Survey Abandoned  
 Remarks: CAMERA WILL NOT PULL ANY FURTHER.  
 NO USMH ACCESS TO DO VIDEO FROM.





## Defect Listing Plot

Pipe Segment Reference 1239_1238	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1239	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1238	Length surveyed 389.6	Year Renewed	Height 8	Width	Pipe Joint Length	

SPR 15	MPR 0	PO Number		Customer		
SPRI 5	MPRI 0	Work Order Number		Purpose		
QSR 5300	QMR 0000					
OPR 15	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/10/2024		Media label	
OPRI 5	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 11:02		Weather Dry	
Date Cleaned 04/10/2024			End Time 11:48		Additional Info	






## Defect Listing Plot

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
1239_1238	CLARKTON	N ELMHURST ST	Asbestos Cement		Sanitary Sewage Pipe
Upstream MH 1239	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 1238	Length surveyed 389.6	Year Renewed	Height 8	Width	Pipe Joint Length

135.4 ft. HSV-Hole Soil Visible




5


178.2 ft. TF-Tap Factory Made




266.1 ft. TF-Tap Factory Made




346.2 ft. TF-Tap Factory Made



381.8 ft. TF-Tap Factory Made



385.1 ft. MMC-Miscellaneous Material Change



PVC

388.7 ft. MMC-Miscellaneous Material Change



ASBESTES

389.6 ft. MSA-Miscellaneous Survey Abandoned



CAMERA WILL NOT PULL ANY FURTHER. NO USMH ACCESS TO DO VIDEO FROM.



## 4 Image Report


Pipe Segment Reference 1238_1344	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1238	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1344	Length surveyed 286.6	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1238



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 69.4 ft. Grade: 4  
Condition: H-Hole  
Remarks: N/A




Distance: 69.5 ft. Grade: 4  
Condition: H-Hole  
Remarks: N/A






## 4 Image Report

Pipe Segment Reference 1238_1344	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1238	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1344	Length surveyed 286.6	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 71.9 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 79.7 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 161.1 ft. Grade: 0  
Condition: MMC-Miscellaneous Material Change  
Remarks: DIP



Distance: 172.2 ft. Grade: 1  
Condition: SRI-Surface Damage Roughness Increased  
Remarks: N/A




## 4 Image Report

Pipe Segment Reference 1238_1344	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1238	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1344	Length surveyed 286.6	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 178.2 ft. Grade: 2  
 Condition: SSS-Surface Damage Surface Spalling  
 Remarks: N/A



Distance: 197.4 ft. Grade: 2  
 Condition: SSS-Surface Damage Surface Spalling  
 Remarks: N/A



Distance: 214.3 ft. Grade: 0  
 Condition: MMC-Miscellaneous Material Change  
 Remarks: ASBESTES




Distance: 216.5 ft. Grade: 1  
 Condition: SRI-Surface Damage Roughness Increased  
 Remarks: N/A






## 4 Image Report

Pipe Segment Reference 1238_1344	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1238	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1344	Length surveyed 286.6	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 249.1 ft. Grade: 3  
 Condition: MWLS-Miscellaneous Water Level Sag  
 Remarks: N/A




Distance: 286.6 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 1344





## Defect Listing Plot

Pipe Segment Reference 1238_1344	City CLARKTON	Street N ELMHURST ST	Material Asbestos Cement		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1238	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1344	Length surveyed 286.6	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 21	MPR 3	PO Number		Customer		
SPRI 5.2	MPRI 3	Work Order Number		Purpose		
QSR 4222	QMR 3100					
OPR 24	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/10/2024		Media label	
OPRI 4.8	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 13:14		Weather Dry	
Date Cleaned 04/10/2024			End Time 13:29		Additional Info	






## Defect Listing Plot

Pipe Segment Reference	City	Street	Material	Location Code	Pipe Use
1238_1344	CLARKTON	N ELMHURST ST	Asbestos Cement		Sanitary Sewage Pipe
Upstream MH 1238	Total Length	Year Constructed	Shape Circular	Location Details	
Downstream MH 1344	Length surveyed 286.6	Year Renewed	Height 8	Width	Pipe Joint Length

172.2 ft. SRI-Surface Damage  
Roughness Increased - S01




1

178.2 ft. SSS-Surface Damage Surface  
Spalling



2

197.4 ft. SSS-Surface Damage Surface  
Spalling



2

214.3 ft. MMC-Miscellaneous Material  
Change




ASBESTES

216.5 ft. SRI-Surface Damage  
Roughness Increased - F01




1

249.1 ft. MWLS-Miscellaneous Water  
Level Sag



3

286.6 ft. AMH-Access Point Manhole



1344




1344




## 4 Image Report

Pipe Segment Reference 103163_1345	City CLARKTON	Street OFF SIXTH ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Combined Pipe
Upstream MH 103163	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1345	Length surveyed 232.4	Year Renewed	Height 12	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103163



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 232.4 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1345




Distance: 232.4 ft. Grade: 0  
Condition: MGO-Miscellaneous General Observation  
Remarks: CANNOT LOCATE MH.





## Defect Listing Plot

Pipe Segment Reference 103163_1345	City CLARKTON	Street OFF SIXTH ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Combined Pipe
Upstream MH 103163	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1345	Length surveyed 232.4	Year Renewed	Height 12	Width	Pipe Joint Length	
SPR 0	MPR 0	PO Number		Customer		
SPRI 0	MPRI 0	Work Order Number		Purpose		
QSR 0000	QMR 0000					
OPR 0	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/10/2024		Media label	
OPRI 0	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 14:28		Weather Dry	
Date Cleaned 04/10/2024			End Time 14:54		Additional Info	





## 4 Image Report


Pipe Segment Reference 1345_1344	City CLARKTON	Street OFF SIXTH ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1345	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1344	Length surveyed 404	Year Renewed	Height 12	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1345



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 27.7 ft. Grade: 0  
Condition: MGO-Miscellaneous General Observation  
Remarks: UNMARKED MH/CLEANOUT




Distance: 27.7 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



## 4 Image Report

Pipe Segment Reference 1345_1344	City CLARKTON	Street OFF SIXTH ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1345	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1344	Length surveyed 404	Year Renewed	Height 12	Width	Pipe Joint Length	



Distance: 389.9 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A




Distance: 404.0 ft. Grade: 0  
 Condition: AMH-Access Point Manhole  
 Remarks: 1344





## Defect Listing Plot


Pipe Segment Reference 1345_1344	City CLARKTON	Street OFF SIXTH ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1345	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1344	Length surveyed 404	Year Renewed	Height 12	Width	Pipe Joint Length	
SPR 0	MPR 0	PO Number		Customer		
SPRI 0	MPRI 0	Work Order Number		Purpose		
QSR 0000	QMR 0000					
OPR 0	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/10/2024		Media label	
OPRI 0	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 14:55		Weather Dry	
Date Cleaned 04/10/2024			End Time 15:22		Additional Info	






## 4 Image Report

Pipe Segment Reference 1364_1365	City CLARKTON	Street OFF W GRAHAM ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1364	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1365	Length surveyed 273.2	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1364



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A




Distance: 273.2 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1365



## Defect Listing Plot

Pipe Segment Reference 1364_1365	City CLARKTON	Street OFF W GRAHAM ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1364	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1365	Length surveyed 273.2	Year Renewed	Height 8	Width	Pipe Joint Length	

SPR 0	MPR 0	PO Number		Customer	
SPRI 0	MPRI 0	Work Order Number		Purpose	
QSR 0000	QMR 0000				
OPR 0	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/10/2024	Media label	
OPRI 0	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 16:43	Weather	
Date Cleaned 04/10/2024			End Time 18:26	Additional Info	








## 4 Image Report

Pipe Segment Reference 1347_103137	City CLARKTON	Street E GREENE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1347	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103137	Length surveyed 244.3	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 22.9 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A



Distance: 242.2 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 244.0 ft. Grade: 2  
 Condition: SAV-Surface Damage Aggregate Visible  
 Remarks: N/A




## 4 Image Report

Pipe Segment Reference 1347_103137	City CLARKTON	Street E GREENE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1347	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103137	Length surveyed 244.3	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 244.3 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 244.3 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1347



Distance: 244.3 ft. Grade: 0  
Condition: MGO-Miscellaneous General Observation  
Remarks: LAMPHOLE MH





## Defect Listing Plot

Pipe Segment Reference 1347_103137	City CLARKTON	Street E GREENE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1347	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103137	Length surveyed 244.3	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 88	MPR 0	PO Number		Customer		
SPRI 2	MPRI 0	Work Order Number		Purpose		
QSR 2G00	QMR 0000					
OPR 88	Surveyed By CHRISTIAN CHURCH	Direction Upstream	Date 04/11/2024		Media label	
OPRI 2	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 08:45		Weather Light Rain	
Date Cleaned 04/11/2024			End Time 08:57		Additional Info	







## Defect Listing Plot

Pipe Segment Reference 1347_103137	City CLARKTON	Street E GREENE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 1347	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 103137	Length surveyed 244.3	Year Renewed	Height 8	Width	Pipe Joint Length	

244.3 ft.

MGO-Miscellaneous General  
Observation

LAMPHOLE MH



1347



## 4 Image Report

Pipe Segment Reference 103216_1366	City CLARKTON	Street OFF N COLLEGE ST	Material Ductile Iron Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103216	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1366	Length surveyed 258.8	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 103216



Distance: 0.0 ft. Grade: 0  
Condition: MWL-Miscellaneous Water Level  
Remarks: N/A



Distance: 10.0 ft. Grade: 1  
Condition: SRI-Surface Damage Roughness Increased  
Remarks: N/A




Distance: 167.4 ft. Grade: 2  
Condition: DAZ-Deposits Attached Other  
Remarks: OTHER





## 4 Image Report


Pipe Segment Reference 103216_1366	City CLARKTON	Street OFF N COLLEGE ST	Material Ductile Iron Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103216	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1366	Length surveyed 258.8	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 167.4 ft. Grade: 2  
Condition: SSS-Surface Damage Surface Spalling  
Remarks: N/A



Distance: 243.3 ft. Grade: 0  
Condition: TF-Tap Factory Made  
Remarks: N/A



Distance: 258.8 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1366



Distance: 258.8 ft. Grade: 1  
Condition: SRI-Surface Damage Roughness Increased  
Remarks: N/A





## Defect Listing Plot

Pipe Segment Reference 103216_1366	City CLARKTON	Street OFF N COLLEGE ST	Material Ductile Iron Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103216	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1366	Length surveyed 258.8	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 52	MPR 2	PO Number		Customer		
SPRI 52	MPRI 2	Work Order Number		Purpose		
QSR 2100	QMR 2100					
OPR 54	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/11/2024		Media label	
OPRI 27	Certificate Number P0036843-042022	Pre-Cleaning Heavy Cleaning	Time 10:22		Weather Light Rain	
Date Cleaned 04/11/2024			End Time 10:37		Additional Info	







## Defect Listing Plot

Pipe Segment Reference 103216_1366	City CLARKTON	Street OFF N COLLEGE ST	Material Ductile Iron Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103216	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1366	Length surveyed 258.8	Year Renewed	Height 8	Width	Pipe Joint Length	

258.8 ft.

SRI-Surface Damage  
 Roughness Increased - F01






## 4 Image Report

Pipe Segment Reference 103204_1330	City CLARKTON	Street PAGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103204	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1330	Length surveyed 243.8	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 0.0 ft. Grade: 0  
 Condition: MWL-Miscellaneous Water Level  
 Remarks: N/A



Distance: 75.9 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: .



Distance: 75.9 ft. Grade: 4  
 Condition: IRL-Infiltration Runner Lateral  
 Remarks: N/A




Distance: 149.8 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A






## 4 Image Report


Pipe Segment Reference 103204_1330	City CLARKTON	Street PAGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103204	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1330	Length surveyed 243.8	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 149.8 ft. Grade: 4  
 Condition: IRL-Infiltration Runner Lateral  
 Remarks: N/A



Distance: 176.4 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A



Distance: 176.4 ft. Grade: 4  
 Condition: IRL-Infiltration Runner Lateral  
 Remarks: N/A




Distance: 188.8 ft. Grade: 0  
 Condition: TF-Tap Factory Made  
 Remarks: N/A






## 4 Image Report


Pipe Segment Reference 103204_1330	City CLARKTON	Street PAGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103204	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1330	Length surveyed 243.8	Year Renewed	Height 8	Width	Pipe Joint Length	




Distance: 188.8 ft. Grade: 4  
 Condition: IRL-Infiltration Runner Lateral  
 Remarks: N/A



Distance: 195.1 ft. Grade: 1  
 Condition: IS-Infiltration Stain  
 Remarks: N/A



Distance: 219.2 ft. Grade: 1  
 Condition: ISJ-Infiltration Stain Joint  
 Remarks: N/A



Distance: 220.6 ft. Grade: 1  
 Condition: ISB-Infiltration Stain Barrel  
 Remarks: N/A




## 4 Image Report

Pipe Segment Reference 103204_1330	City CLARKTON	Street PAGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103204	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1330	Length surveyed 243.8	Year Renewed	Height 8	Width	Pipe Joint Length	



Distance: 232.4 ft. Grade: 1  
Condition: ISB-Infiltration Stain Barrel  
Remarks: N/A



Distance: 243.8 ft. Grade: 0  
Condition: AMH-Access Point Manhole  
Remarks: 1330





## Defect Listing Plot

Pipe Segment Reference 103204_1330	City CLARKTON	Street PAGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103204	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1330	Length surveyed 243.8	Year Renewed	Height 8	Width	Pipe Joint Length	
SPR 0	MPR 20	PO Number		Customer		
SPRI 0	MPRI 5	Work Order Number		Purpose		
QSR 0000	QMR 4400					
OPR 20	Surveyed By CHRISTIAN CHURCH	Direction Downstream	Date 04/11/2024		Media label	
OPRI 5	Certificate Number P0036843-042022	Pre-Cleaning Light Cleaning	Time 11:17		Weather Light Rain	
Date Cleaned 04/11/2024			End Time 11:31		Additional Info	






## Defect Listing Plot


Pipe Segment Reference 103204_1330	City CLARKTON	Street PAGE ST	Material Reinforced Concrete Pipe		Location Code	Pipe Use Sanitary Sewage Pipe
Upstream MH 103204	Total Length	Year Constructed	Shape Circular		Location Details	
Downstream MH 1330	Length surveyed 243.8	Year Renewed	Height 8	Width	Pipe Joint Length	

176.4 ft. IRL-Infiltration Runner Lateral




4

188.8 ft. TF-Tap Factory Made




188.8 ft. IRL-Infiltration Runner Lateral




4

195.1 ft. IS-Infiltration Stain



1

219.2 ft. ISJ-Infiltration Stain Joint




1

220.6 ft. ISB-Infiltration Stain Barrel



1

232.4 ft. ISB-Infiltration Stain Barrel



1

243.8 ft. AMH-Access Point Manhole



1330



1330

# **APPENDIX III – Lifecycle Model Documentation Report**





**WithersRavenel**  
Our People. Your Success.

**Model Documentation Report**  
**Summary of process used to structure data for**  
**Town of Clarkton, North Carolina**  
**Sewer Lifecycle Models**

March 2025



## INTRODUCTION

This document lists the tasks performed to prepare the Town of Clarkton's Sewer Lifecycle Model in Capital Predictor software using the Town's GIS data and WithersRavenel's subject matter experts involved in Clarkton's AIA project. Separate lifecycle models were built for the different components of the Town's sewer system which include sewer gravity mains, force mains, and manholes as their GIS datasets are separate as well as the treatment that's applied to each.

## PREPARING YOUR DATA

We utilized Clarkton's GIS data to model the assets within the Town's sewer system. WithersRavenel requested that additional data be added to the Town's GIS that was required to develop an accurate model within Capital Predictor. Those new data fields are listed below.

### Gravity Mains

- Condition – Represents the condition of each gravity main and the remaining useful life for that stage:
  - Service State 5 equals "Very Poor" with <15% remaining useful life
  - Service State 4 equals "Poor" with 16-30% remaining useful life
  - Service State 3 equals "Fair" with 31-50% remaining useful life
  - Service State 2 equals "Good" with 51-75% remaining useful life
  - Service State 1 equals "Good, New, or Nearly New" with 76-95% remaining useful life
- Rehab - To be updated as lines are rehabbed to ensure they are recommended for replacement after the initial rehab is completed.
- Unit Cost Variation - For this field we used the diameter of the main, included to calculate rehab and replacement costs. One gravity main had the diameter of "Unknown" and was assumed to be 8".

### Force Mains

- Life Stage – Represents the present state of each force main based on a 1-5 scale:
  - Life Stage 5 equals "Very Poor" with <5% remaining useful life
  - Life Stage 4 equals "Poor" with 5-15% remaining useful life
  - Life Stage 3 equals "Fair" with 15-50% remaining useful life
  - Life Stage 2 equals "Good" with 50-95% remaining useful life
  - Life Stage 1 equals "Good, New, or Nearly New" with >95% remaining useful life
- Unit Cost Variation – For this field we used the diameter of the force main, included to calculate replacement costs. One force main had the diameter of "Unknown" and was assumed to be 6".

### Manholes

- Condition – Represents the condition of each Manhole and the remaining useful life for that stage:
  - Service State 1 is used for a "Good" condition hydrant with 95% remaining life
  - Service State 3 is used for a "Fair" condition hydrant with 50% remaining life
  - Service State 5 is used for a "Poor" condition hydrant with 30% remaining life
- Unit Cost Variation – For this field we used the depth of the manhole, included to calculate rehab costs.



## ESTABLISH THE UNIT OF MEASURE

As part of the calculation of the value of assets, the Unit of Measure is used as a foundational metric. For Clarkton's gravity mains and force mains models, the line's calculated "Shape\_Leng", which is the pipe's length, is multiplied by the diameter in inches when applying costs. "Shape\_Leng" is used as the unit of measure as these treatment costs are based on length and diameter of the pipe.

A value of 1 is added as the manhole unit of measure as the rehab cost for each manhole is a flat rate of \$300 plus \$250/per depth foot. To accommodate these fees a unique price was added to Capital Predictor for each depth foot possibility.

## ESTABLISH EXPECTED LIVES

Life Stage and Condition are factors of deterioration rates and thereby a key element in a life cycle model as it influences when assets will be replaced. For Clarkton's model, using Life Stage or Condition was determined by the data available. Manholes and sewer gravity mains use Condition, whereas sewer force mains use Life Stage.

Life expectancies for the gravity mains and force mains were based on pipe material. The following life expectancies were given to the following materials:

### Gravity Mains:

Main Material	Expected Life
Asbestos Cement	60 years
Cast Iron	60 years
Ductile Iron	100 years
Polyvinyl Chloride	80 years
High Density Polyethylene	80 years
Vitrified Clay	50 years
Reinforced Concrete	100 years
Other	50 years

### Force Mains:

Main Material	Expected Life
Polyvinyl Chloride	80 years
Unknown	80 years

## TREATMENT

We implemented a “run to failure” model which predicts the end of life for each asset and then calculates the replacement costs of all assets due for replacement each year. Each model was uniquely configured and the treatments for each model are highlighted below.

The Gravity Mains model has two treatments, one for Rehab Line and one for Replace which is based on the Condition of the main. The cost to Rehab Line is estimated to be \$21 per inch\*foot and the cost to Replace is estimated to be \$25 per inch\*foot.

The Force Main model has one treatment for Replace Line which is based on the Life Stage of the main. The estimated cost to replace a Force Main is \$25 per inch\*foot.


The Manhole model has one treatment for Rehab Manhole which is based on the Condition of the manhole. The estimated cost to rehab a manhole is \$300 plus \$250 per depth foot.



## TREATMENT CRITERIA

The established Treatment Criteria is what triggers the asset for treatment in the model. The Treatment Criteria set up for Clarkton's sewer model is based on the asset's Life Stage or Condition.

For the Gravity Mains model, the model will trigger a Rehab when the Condition of the main is a 4 or worse and rehab has not yet been performed on the main. A replacement will occur when the Condition of the main is a 4 or worse and has already been rehabbed.




**Rehab - Rehab**

Triggers for Service Criteria

Service State Native Scale

Service Name	N/A	State 0	State 1 (1)	State 2 (2)	State 3 (3)	State 4 (4)	State 5 (5)	End of Life	
Condition	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>

Figure 1 Treatment Criteria for Rehabbing a Gravity Main based on Life Stage



**Replace Line - Replace Line**


Triggers for Service Criteria

Service State Native Scale

Service Name	N/A	State 0	State 1 (1)	State 2 (2)	State 3 (3)	State 4 (4)	State 5 (5)	End of Life	
Condition	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>

Figure 2 Treatment Criteria for Replacing a Gravity Main based on Life Stage and previous Treatment

For Force Mains, a Replacement is triggered when the Force Main has reached a 4 or worse Life Stage.



**Replace Line - Replace Line**

Triggers for Service Criteria

Service State Native Scale

Service Name	N/A	State 0	State 1 (1)	State 2 (2)	State 3 (3)	State 4 (4)	State 5 (5)	End of Life	
Life Stage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>

Figure 3 Treatment Criteria for Replacing a Force Main based on Life Stage

The Manhole model is setup to trigger a Rehab when the manhole reaches the Condition of a State 5 (Poor) or worse.

Rehab Manhole - Rehab Manhole

Triggers for Service Criteria

Service State Native Scale

Service Name	N/A (Unknown)	State 0	State 1 (Good)	State 2	State 3 (Fair)	State 4	State 5 (Poor)	End of Life	
Condition	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>

*Figure 4 Treatment Criteria for Rehabbing a Manhole based on Condition*

## SERVICE STATE BASED ON AGE AND CONDITION

Another key factor in a Life Cycle Model is the Service State of the asset, often expressed in terms of Condition. Capital Predictor utilizes a standardized 0 to 6 Service State to assign where assets are on their lifecycle degradation curve. Two degradation curves were selected, one to represent Condition, and one to represent Life Stage.

A custom degradation profile was created for Clarkton's condition scale. An asset with a Good condition rating will be considered Service State 1 with 95% remaining life, Fair assets are Service State 3 with 50% remaining life, and Poor assets are Service State 5 with 15% remaining life.




Figure 5 Condition to Service State Assignment Table and Degradation Profile


Another custom degradation profile was created for Clarkton's Life Stage scale. An asset with a Life Stage 1 rating will be considered Service State 1 with 99% remaining life, Life Stage 2 assets are Service State 2 with 95% remaining life, Life Stage 3 assets are Service State 3 with 50% remaining life, Life Stage 4 assets are Service State 4 with 15% remaining life, and Life Stage 5 assets are Service State 5 with 5% remaining life.

**Profile Details**

Service State	Remaining Life (%)	Service Potential (%)	Native Scale
State 0	100%	100%	0
State 1	99%	99%	1
State 2	95%	95%	2
State 3	50%	50%	3
State 4	15%	15%	4
State 5	5%	5%	5
End of Life	0%	0%	6



*Figure 6 Life Stage to Service State Assignment Table and Degradation Profile*





## CONCLUSION

The Town of Clarkton's sewer lifecycle model in Capital Predictor provides a structured and data-driven approach to managing sewer system assets. By integrating GIS data, defining treatment criteria, and establishing expected life spans, the model ensures a proactive strategy for asset maintenance and replacement. The implementation of a "run to failure" methodology allows for accurate forecasting of future costs and infrastructure needs. Moving forward, continued data updates will enhance model accuracy, supporting informed decision-making for long-term infrastructure sustainability.

## NEXT STEPS

To further refine the Town of Clarkton's sewer lifecycle model, the next steps include additional refinements to treatment triggers and cost assumptions based on real-world rehabilitation and replacement data. The model should be periodically reviewed and updated with the latest rehabilitation and replacement activities to maintain accuracy, helping to optimize long-term capital planning. Additionally, budget allocations and funding strategies should be reassessed to ensure alignment with long-term infrastructure needs. Finally, continued coordination between GIS specialists, your WithersRavenel Managed Services Team, and decision-makers will enhance data integrity and support proactive sewer system management.



# **APPENDIX IV – Lifecycle Model Results Narrative**

# Model Results Narrative

## Town of Clarkton, NC Sewer Lifecycle Model

March 2025

### A. Introduction

The Lifecycle Model created for Town of Clarkton's sewer system utilized the Town's GIS data which contains estimated life expectancy and condition data. A technical explanation of how this data was used to develop the model may be found in the accompanying Model Documentation Report.

Separate models were built for each component of the sewer system and the following Model Scenarios (aka Simulations) were created:

#### Gravity Mains

1. Current Budget - \$50k/\$90k/\$50k
2. Current Budget - \$50k/\$90k/\$90k
3. Current Budget - \$50k/\$90k/\$90k w/ inflation
4. Current Budget - \$50k/\$90k/\$175k
5. Calibration
6. No Budget

#### Force Mains

1. Calibration
2. No Budget

#### Manholes

1. \$5,000
2. \$7,500
3. \$10,000
4. \$10,000 w/inflation
5. Calibration
6. No Budget

These budget scenarios are preliminary and may be subject to change. All scenarios were analyzed over a 100-year period. Scenarios that include inflation add 3% inflation year-over-year to the costs of rehabilitation and replacement. The *Calibration* budget is used for the purposes of measurement and shows the model results as if there were no caps on available funding. The *No Budget* model shows the model results as if there was no funding for the entirety of the 100-year timeframe.

## B. Overview of Results

### Gravity Mains

With the proposed budgets of approximately \$50k in FY25 and \$90k in FY26, four separate current budget scenarios were conducted:

- The first simulation of \$50k/\$90k/\$50k (yellow) represents the suggested budgets with a continued budget of \$50k in FY27 through the remainder of the 100-year model. The model maintains a service state of “Good” until Year 18, where it begins to decline into the service state of “Fair”. In Year 40, the model declines into a service state of “Poor” that continues throughout the remainder of the 100-year model.
- The second current budget simulation of \$50k/\$90k/90k (purple) represents the suggested budgets with a continued budget of \$90k in FY27 through the remainder of the 100-year model. This model maintained a service state of “Good” until Year 27 and then a service state of “Fair” until Year 56 that continued throughout the remainder of the 100-year model.
- The third scenario, \$50k/\$90k/\$90k w/ inflation (teal), demonstrates the impact of the second proposed budget with a 3% inflation on rehabilitation and replacement costs. Service state is impacted in Year 20 dropping to “Fair”, “Poor” by Year 39, and ultimately declining to “Very Poor” by Year 61 through the end of the model.
- The fourth scenario, \$50k/\$90k/\$175k (cyan), demonstrates the suggested budget with a continued budget of \$175k in FY27 through the remainder of the model. This budget maintained a service state of “Good” until Year 48 and remains in a consistent state of “Fair” through the final 52 years of the model




Figure 1 Simulation Comparison comparing the Gravity Mains overall service state over 100 years given each current budget scenario.



For baseline purposes *No Budget* (yellow) and *Calibration* (light blue) models were conducted. The *No Budget* (yellow) model reflects a steady decline in service state from “Good” to “Fair” by Year 15 and continues to decline before reaching EOL at Year 93. Our *Calibration* model (light blue) indicates a Year 1 backlog of approximately \$2.16 million as shown in further detail in *Figure 6*, below.




Figure 2 Simulation Comparison comparing the Gravity Mains overall service state over 100 years given each baseline budget scenario.

## Force Mains

The data received for Clarkton’s two force mains indicates no immediate need for replacement in the first 25 years of our 100-year model. The *Calibration* (light blue) model demonstrates the first replacement of the shorter main in Year 27 for approximately \$35k. Replacement for the larger main would take place shortly after in Year 29 for a cost of approximately \$373k. Another replacement of the small main occurring in Year 94. The *No Budget* (green) simulation reflects EOL of both mains by Year 41.




Figure 3 Simulation Comparison comparing the Force Mains overall service state over 100 years given each budget scenario.

## Manholes

The simulation of \$10k (purple) was determined to be an effective model as it maintains a consistent service state over the next 100 years, finishing in a service state of “Good” by Year 100. When considering inflation, the \$10k *with inflation* (yellow) model begins a slight decline in service state around Year 18, due to the increases in rehabilitation costs, that continue through Year 100 where it nears EOL. The \$7.5k (teal) model also maintains a similar service state to the \$10k model through the first 40 years, then a consistent service state a “Fair” through the final 60 years of the model. The \$5k (light blue) budget demonstrates a slight decline in asset condition compared to the other models beginning in Year 18, when an increase in forecasted rehabilitations are expected, and ends the 100-year model in “Poor” condition.




Figure 4 Simulation Comparison comparing the Manholes overall service state over 100 years given each budget scenario.

In the *No Budget* (light blue) simulation, assets degrade from “Good” to “EOL” by Year 49. The *Calibration* (yellow) model demonstrates a Year 1 backlog of approximately \$27.5k as reflected below in Figure 8.




Figure 5 Simulation Comparison comparing the Manholes overall service state over 100 years given each baseline scenario.

## C. Calibration

Calibration of the model was conducted to validate that the model triggers the expected treatments without any budget caps in place. All models were validated with the “Calibration” model and then additional budget scenarios were run.

## D. Treatment Costs

Predictor utilizes an optimization engine that selects the treatment of each asset based on the estimated life expectancy and/or treatment counter data provided. The charts below show the recommended treatment costs required over the 40-year period for each model with no budget restraints in place.




Figure 6 The treatment costs for the Gravity Mains model selected over a 40-year period





Figure 7 The treatment costs for the Force Mains model selected over a 40-year period





*Figure 8 The treatment costs for the Manholes model selected over a 40-year period*

## E. Further investigations & Next Steps

It is encouraged to continue to evaluate your asset data and to continue to keep it updated in Capital Predictor. We also encourage the Town to explore additional budget scenarios to determine the optimal amount to maintain the water and sewer systems at the desired service state.

We encouraged you to continue to work with the lifecycle model, continue to collect asset data, and to consult with WithersRavenel Consultants to further refine your models, create additional scenarios, enhance reporting and similar activity. The goal is to integrate the lifecycle model into the Town's capital planning process.

## **APPENDIX V – Rate Study**

# TABLE OF CONTENTS

Introduction.....	1
Rate Study Findings.....	2
Outcomes .....	5
Conclusions .....	8



# TABLES AND CHARTS

Table 1 FY 2026 Water and Sewer Rates.....	2
Table 2 Tentative Future Water and Sewer Rates.....	6
Table 3 Tentative Sample Monthly Residential Charges .....	7

## Introduction

The following rate study references and builds upon the financial analysis that was completed in the Town's Merger and Regionalization Feasibility study Option A, (Project #MRF-W-ARP-0010). The financial analysis proposed 6% annual rate increases from FY 2027 through FY 2036 to fund capital needs and increasing operating and maintenance costs while establishing a healthy fund balance. The rate study considers the revenue needs and proposes changes, based on best practices, to the rates to accomplish the objectives.

## Rate Study Findings

The following characteristics stand out when analyzing the Town's FY 2026 water and sewer rates, as shown in Table 1.

- They are comprised of fixed/minimum and volumetric charges
- Minimum charges include 1500 gallons of monthly usage
- Outside users pay rates that are double inside rates.
- Fund needs annual revenue increases due to inflation and capital needs
- There are 407 water and 303 sewer customers, actively billed
- 86% of water and sewer users are residential
- 69% of water and 89% of sewer users are located inside Town limits
- Average monthly residential usage is 2,800 gallons

**TABLE 1**  
**FY 2026 Water and Sewer Rates**

<b>WATER - IN TOWN</b>	
Minimum (includes 1,500 gal)	\$ 11.75
Volume, per 1,000	\$ 5.50
<b>SEWER - IN TOWN</b>	
Minimum (includes 1,500 gal)	\$ 14.75
Volume, per 1,000	\$ 6.25
<b>WATER - OUT OF TOWN</b>	
Minimum (includes 1,500 gal)	\$ 23.50
Volume, per 1,000	\$ 11.00
<b>SEWER - OUT OF TOWN</b>	
Minimum (includes 1,500 gal)	\$ 29.50
Volume, per 1,000	\$ 12.50



To analyze the present water and sewer rates and the impact of any changes, a financial model was created to show the impact of various rate modifications. In proposing changes to rates, the objectives are to maintain positive revenue generation for the fund, while promoting user equity and best practices. Below are the structural changes discussed for the Town's future consideration:

**OPTION 1 – Vary minimum charge by meter size max flow rate**

- Greatest impact on the non-residential & large users
- Minimum charges increase by factor of maximum meter flow.

METER SIZE	AMOUNT GREATER FLOW VS ¾-IN
○ 1-in meter	1.6x
○ 2-in meter	5.3x

**Pros:**

- **Reflects system capacity need:** Larger meters can deliver more water, so charges based on size reflect a customer's potential burden on the system.
- **Encourages correct meter sizing:** Customers may opt for smaller meters if they don't need high capacity, which promotes system efficiency.
- **Slightly more stable revenue:** Greater fixed charges help stabilize overall revenue and cover fixed charges if conservation reduces usage.

**Cons:**

- **Disincentivizes conservation:** High fixed charges may reduce the bill's sensitivity to usage, offering less motivation to reduce consumption.
- **May not reflect actual use:** A large meter doesn't always mean high usage, especially for infrequent users or those with sprinklers.

**OPTION 2 – Add second residential rate tier at 5,000 gallons**

- This does not affect small residential customers
- Best practice to charge a significantly higher rate, such as \$0.30 inside and \$0.60 outside

**Pros:**

- **Promotes conservation:** Higher per-unit prices at higher usage levels send a strong price signal to discourage excessive use.
- **Aligns with cost-of-service at high usage:** Reflects the increasing marginal cost of treatment and supply.
- **Supports equity:** Basic water needs prices are unaffected, which benefits low-use customers.

**Cons:**

- **Revenue instability:** Income becomes more sensitive to usage fluctuations from weather, economic changes. etc.
- **May penalize large but efficient households:** Households with more members may unintentionally move into higher blocks.

**OPTION 3 - REDUCE 1500 GALLON ALLOCATION IN FIXED CHARGE**

- Could be implemented over time, for example, over 3 years (500 gallons per year) or 5 years (300 gallons per year), reducing the price shock all at once

**Pros:**

- **Improves pricing transparency:** Customers see a clear separation between fixed infrastructure costs and variable usage costs.
- **Strengthens conservation signal:** All water use is charged volumetrically, eliminating the included usage that can encourage overuse.
- **Aligns with AWWA cost-of-service principles:** Fixed charges reflect customer and demand costs, while usage charges reflect consumption/commodity costs.

**Cons:**

- **Revenue instability:** Income becomes more sensitive to usage fluctuations (weather, economic changes).
- **Bill increases for low-income or fixed-use households:** Those who previously stayed within the included volume will see higher bills despite modest usage.

Each of these rate structure options is provided to help facilitate discussion between Town staff and Town leaders about ways to provide simple, fair, equitable and defensible methods to recover water and sewer program costs from its customers. The implementation of any one or more options will help generate needed future revenues. New revenue is necessary for the program to address growing operation costs and planned capital costs, as depicted in the next section.

## Outcomes

As a result of WithersRavenel's feasibility study, 6% annual water and sewer revenue increases are needed to plan for inflation and capital needs over the next ten years. The water and sewer increases would affect fixed and volume charges but not tap or other miscellaneous charges. These increases, as shown below, utilize structure changes to generate initial revenue needs then across the board increases thereafter.

The increases will help strengthen unrestricted net position, fund large capital needs and operating costs, while considering limited growth in water usage. It is worth mentioning that an increase in water revenue requires a greater increase in rates due to the price elasticity of demand. When rates increase, customers' usage slightly decreases. However, the revenue loss from the lower water and sewer usage is less than the revenue gained from higher rates. Consequently, rate increases generate more revenue for the program but the percentage increases in rates must exceed the percentage increases in required revenues. The proposed differential is 1% more than the revenue increases. Tentative rates for the next five years are shown in the following tables for each option.



**TABLE 2**  
**Tentative Future Water and Sewer Rates**

	<b>CURRENT</b>	<b>YEAR 1</b>	<b>YEAR 2</b>	<b>YEAR 3</b>	<b>YEAR 4</b>	<b>YEAR 5</b>
	<b>2026</b>	<b>2027</b>	<b>2028</b>	<b>2029</b>	<b>2030</b>	<b>2031</b>
<b>WATER - IN TOWN</b>						
Minimum (includes 1,500 gal)	\$ 11.75					
3/4 IN METER		\$ 12.60	\$ 13.50	\$ 14.45	\$ 15.50	\$ 16.60
1 IN METER		\$ 21.05	\$ 22.55	\$ 24.15	\$ 25.85	\$ 27.70
2 IN METER		\$ 67.20	\$ 71.95	\$ 77.00	\$ 82.40	\$ 88.20
1,501 -5,000	\$ 5.50	\$ 5.50	\$ 5.90	\$ 6.35	\$ 6.80	\$ 7.30
5,001 +		\$ 5.80	\$ 6.25	\$ 6.70	\$ 7.20	\$ 7.75
<b>SEWER - IN TOWN</b>						
Minimum (includes 1,500 gal)	\$ 14.75					
3/4 IN METER		\$ 15.80	\$ 16.95	\$ 18.15	\$ 19.45	\$ 20.85
1 IN METER		\$ 26.40	\$ 28.25	\$ 30.25	\$ 32.40	\$ 34.70
2 IN METER		\$ 84.21	\$ 90.15	\$ 96.50	\$ 103.30	\$ 110.55
1,501 -5,000	\$ 6.25	\$ 6.25	\$ 6.70	\$ 7.20	\$ 7.75	\$ 8.30
5,001 +		\$ 6.55	\$ 7.05	\$ 7.55	\$ 8.10	\$ 8.70
<b>WATER - OUT OF TOWN</b>						
Minimum (includes 1,500 gal)	\$ 23.50					
3/4 IN METER		\$ 25.20	\$ 27.00	\$ 28.90	\$ 31.00	\$ 33.20
1 IN METER		\$ 42.10	\$ 45.10	\$ 48.30	\$ 51.70	\$ 55.40
2 IN METER		\$ 134.40	\$ 143.90	\$ 154.00	\$ 164.80	\$ 176.40
1,501 -5,000	\$ 11.00	\$ 11.00	\$ 11.80	\$ 12.70	\$ 13.60	\$ 14.60
5,001 +		\$ 11.60	\$ 12.50	\$ 13.40	\$ 14.40	\$ 15.50
<b>SEWER - OUT OF TOWN</b>						
Minimum (includes 1,500 gal)	\$ 29.50					
3/4 IN METER		\$ 31.60	\$ 33.90	\$ 36.30	\$ 38.90	\$ 41.70
1 IN METER		\$ 52.80	\$ 56.50	\$ 60.50	\$ 64.80	\$ 69.40
2 IN METER		\$ 168.43	\$ 180.30	\$ 193.00	\$ 206.60	\$ 221.10
1,501 -5,000	\$ 12.50	\$ 12.50	\$ 13.40	\$ 14.40	\$ 15.50	\$ 16.60
5,001 +		\$ 13.10	\$ 14.10	\$ 15.10	\$ 16.20	\$ 17.40

**TABLE 3**  
**Tentative Sample Monthly Residential Charges**

	<b>CURRENT</b>	<b>YEAR 1</b>	<b>YEAR 2</b>	<b>YEAR 3</b>	<b>YEAR 4</b>	<b>YEAR 5</b>
	<b>2026</b>	<b>2027</b>	<b>2028</b>	<b>2029</b>	<b>2030</b>	<b>2031</b>
<b>SAMPLE CHARGES</b>						
INSIDE 0.75-IN 2000 GALLONS	\$ 32.38	\$ 34.28	\$ 36.75	\$ 39.38	\$ 42.23	\$ 45.25
INSIDE 0.75-IN 10,000 GALLONS	\$ 126.38	\$ 131.28	\$ 141.05	\$ 151.28	\$ 162.38	\$ 174.30
INSIDE 2-IN 20,000 GALLONS	\$ 243.88	\$ 377.79	\$ 405.70	\$ 434.68	\$ 466.13	\$ 500.10
INSIDE 2-IN 50,000 GALLONS	\$ 596.38	\$ 748.29	\$ 804.70	\$ 862.18	\$ 925.13	\$ 993.60

## Conclusions

Based upon the analysis, the water and sewer fund recovers its system costs through current revenues and has strong unrestricted net position and cash levels. However, due to inflation and capital needs, the current water and sewer rates will not be enough to support future increases in operating costs and planned capital projects. The estimated annual revenue increases will prepare for the phase-in of additional debt service payments, operating, and capital costs associated with the CIP. The Town should consider the issuance of debt for the long-term financing of capital improvements. This would allow debt service payments to be spread over a longer period to avoid rate shock for current customers. Additionally, it allows future customers, who will benefit from the improvements, to pay a fair share of the costs. Furthermore, it should consider the implementation of structural changes to rates to ensure they continue to be fair, equitable, and easy to understand and implement.

The increases are estimated from the current fiscal year's data and projections of future events. If net income declines due to several risks, rates may need to increase further to replace the lost revenue. The risks include, but are not limited to, the following:

- Water usage and sewer flow decline due to higher fees or reduced commercial business.
- Operating costs increasing at unsustainable levels, exceeding those projected.
- Higher than projected CIP cost estimates.
- Rising interest rates or unobtainable funding.

Due to the multiple risks facing the Town, it is recommended that the Town continues to review the assumptions and calculations regularly using updated information to determine if adjustments are required at that time to meet established financial objectives.



## APPENDIX VI – References

1. NCDEQ Asset Assessment Guidance Document September 2020
2. NCDEQ DWR Clarkton Local Water Supply Planning Document 2024