

Bid Entity _____ Contact Name & Phone _____

BID SCHEDULE

Sherman Rd Hot Mix Asphalt

2600 ft x 22 ft. From Slinger Rd to Bonnie Lane & Bonnie Lane west, 1760 ft. x 20.5 ft.

	<u>Tonnage</u>	<u>Unit Price</u>	<u>Item Cost</u>
1. ¾" Hot Mix Asphalt Wedge (2600 x 22)	____ 300 ____ ton	\$_____/ton	\$_____
2. 1.5" Compacted, (5LT-58-28s) Asphaltic Surface Course	____ 535 ____ ton	\$_____/ton	\$_____
3. ¾" Hot Mix Asphalt Wedge (1760 x 20.5 ft.)	____ 180 ____ ton	\$_____/ton	\$_____
4. 1.5" Compacted (5LT-58-28s) Asphaltic Surface Course	____ 340 ____ ton	\$_____/ton	\$_____
5. Traffic Control			\$_____
<u>TOTAL</u>			\$_____

Notes:

- 1.) Milling of butt joints, cleaning of pavement, application of tack coat, match driveways, is incidental to 1.5" asphalt surface item.
- 2.) Asphalt Pavement overlay (5LT-58-28s) to be placed at a depth of 1.5" at locations indicated
- 3.) 125 foot of asphalt curb installed on North side from Bonnie Lane ,west
- 4.) Final Tonnage not to exceed 5% of bid estimate.
- 5.) Milestone Markers need must be preserved or replacement will be charged to contractor
- 6.) Project needs to be completed by September 1, 2025