

Bid Entity _____

LRIP BID SCHEDULE

Sherman Rd Hot Mix Asphalt

Start @ Hwy 175, Eastbound 1100 feet

	<u>Tonnage</u>	<u>Unit Price</u>	<u>Item Cost</u>
1. 1inch Hot Mix Asphalt Wedge (1100 x 23.5)	<u>170</u> ton	\$_____/ton	\$_____
2. 2 inch Compacted, (5LT-58-28s) Asphaltic Surface Course	<u>340</u> ton	\$_____/ton	\$_____
3. Traffic Control			\$_____
<u>TOTAL</u>			\$_____

Notes:

- 1.) Milling of butt joints, cleaning of pavement, application of tack coat, match driveways, is incidental to 2" asphalt surface item.
- 2.) Asphalt Pavement overlay (5LT-58-28s) to be placed at a depth of 2" at locations indicated plus 1 inch Wedge
- 3.) Final Tonnage not to exceed 5% of bid estimate.
- 4.) Milestone Markers need must be preserved or replacement will be charged to contractor
- 5.) Project needs to be completed by September 15, 2026