

ACKNOWLEDGMENT OF RECEIPT OF ADDENDUM

**REMODELING FOR LIVING QUARTERS
AT
TOWN OF LINN FIRE/EMS STATION
LAKE GENEVA, WISCONSIN**

Job No. 2326

Contractor shall, upon receipt of the enclosed Addendum, fill out and mail or email this form to the Architect-Engineer's office.

KEHOE-HENRY & ASSOCIATES, INC.

Architecture & Engineering

25 North Wisconsin Street

Elkhorn, Wisconsin 53121

wrh@kehoe-henry.com

We hereby acknowledge receipt of the enclosed Addendum No. 2.

CONTRACTOR:

Name: _____

Address: _____

Phone: _____

Email: _____

Signature: _____

NOTE: Also acknowledge receipt of Addendum on Proposal Form in space provided.

ADDENDUM NO. 2

**REMODELING FOR LIVING QUARTERS
AT
TOWN OF LINN FIRE/EMS STATION
LAKE GENEVA, WISCONSIN**

OWNER

TOWN OF LINN
W3728 Franklin Walsh Street
P.O. Box 130
Zenda, Wisconsin 53195

JOB NO.

2326

ARCHITECT-ENGINEER

KEHOE-HENRY & ASSOCIATES, INC.
25 North Wisconsin Street
Elkhorn, Wisconsin 53121
262-723-4399
wrh@kehoe-henry.com

BIDS DUE

May 3, 2024
10:00 a.m.

ADDENDUM NO. 2 DATED: April 26, 2024

This Addendum is being issued to explain, correct, add to, or deduct from the original Drawings and Specifications. Each Contractor who has work or material indicated in this Addendum shall furnish and/or install such work even though not specifically mentioned under the division or section to which it pertains. Each Contractor shall read entire Addendum for any reference to work required.

This Addendum is hereby made a part of the Construction Documents.

Bidders shall list on their Proposal forms that they have included all work required by this Addendum in preparing their Bids.

1 **DRAWINGS ADDENDUM**

2
3 **SHEET A101 - FIRST FLOOR PLAN**

4
5 **1/A101 - First Floor Plan:**

6
7 On west wall of Work Room 101, remove and reinstall existing flat screen TV and
8 wall bracket as required for additional layer of fire rated drywall. See electrical addendum included
9 herewith for additional work required. See Sheet E101 for location.

10
11 On east wall of Dorm 102, patch hole in wall with fire-rated drywall prior to
12 installation of additional layer of fire rated drywall. See electrical addendum included herewith for
13 additional work required. See Sheet E101 for location.

14
15 **SHEET E101 – EXISTING ELECTRICAL PLAN**

16
17 **1/E101 – Existing Electrical Plan:**

18
19 Add to Keynote 12: Receptacle and data box for flat screen TV on Workroom
20 side of 2 hour wall will also require putty pads. General contractor to cut drywall
21 around screen boxes as required for electrical contractor to install putty pads.
22 Install putty pads on all boxes as required by code.

23
24 On east wall of Dorm 102, symbol of a square with an H is for a hole in the wall
25 for IT cables removed by owner. Hole in drywall to be fixed and second layer of
26 fire rated gypsum added by general contractor.

27
28 **1/E102 – Electrical Lighting Plan:**

29
30 Keynote 5 should read “Connect exterior EM2 light to unswitched outdoor
31 lighting circuit LA1-25. Mount 7’6” AFG.” Drawing incorrectly states EM1.
32