

05-06-2024

Public Informational Meeting North Avenue, North Wall Street and Danish Way

- Welcome to the Public Informational Meeting for the Village of Denmark 2024 construction projects that include North Ave., N. Wall Street and Danish Way. See project maps for reference.
- Introductions
- Please sign in and include all contact information.
- The purpose of this meeting is to present information related to the planned construction project.
- Individual questions will not be answered as part of this presentation. Please submit your questions or comments regarding the projects to the Village Clerk no later than May 10th, 2024. All questions and answers will be posted on the Village website by May 15th, 2024.
- **PROJECT DETAILS: North Wall Street**
North Wall Street is planned to have an urban section width of 44-feet from back of curb to back of curb starting at a point 180' south of the North Ave. intersection continuing north to North Ave. The curb and gutter will be constructed on the north side of the North Ave. intersection to match the same width. A bike lane will be added to the east and west side of North Wall Street which will match the existing bike lanes south of the project limits and will continue to the North Ave. intersection. A variable width terrace area with a 5-foot sidewalk is planned on the east side of the road, where the west side sidewalk will stay in place except for the connection to the new sidewalk on North Ave. New inlets and storm sewer will be installed on the south side of the North Ave. intersection which will connect into the existing storm sewer on North Wall Street.
- **PROJECT DETAILS: CTH T**
CTH T is planned to have a variable rural section width from 25-feet to 32-feet starting from the end of the curb and gutter continuing north 131-feet. Minor ditch adjustments will be needed to blend into the new roadway elevations as well as a new storm sewer structure in the ditch on the northwest corner of the North Ave. intersection.
- **PROJECT DETAILS: Danish Way**
Danish Way will have the existing asphalt removed and a new 3 ½" asphalt pavement will be placed to match the existing curb and gutter from the intersection of North Ave. to the southerly roadway limits.

- **PROJECT DETAILS: North Ave.**

The Village of Denmark will be reconstructing North Avenue from a point 170' West of Danish Way to a point 1500' East of North Wall Street.

North Ave. is planned to have an urban section width of 37-feet from back of curb to back of curb which will result in an approximate 5 FT increase in the overall driving surface width. A bike lane will be added to North Ave. on both sides of the road starting on the East side of Danish Way and continue to the Eastern limits of the project. A variable width terrace area with a 5-foot sidewalk is planned on the south side of the road. Sanitary sewer manhole adjustments and water main relay along with existing water laterals to be installed to a new curb box will occur from Danish Way to N Wall Street. A new 12-inch water main and storm sewer will be installed from N Wall Street and continue east. The water main will end at the Eastern project limits, while the storm sewer will end at the newly constructed pond by the High School.

In order to construct the project, some trees and brush will need to be removed. These trees are located within the grading limits and cannot be saved. Property owners will be notified of tree removals prior to construction.

The water and storm sewer on the project will have three components: (1) installation of the mains; (2) installation of the laterals (if needed) from the main to the new curb stop location.

The Village will install water laterals from the main to the property line within the Village right-of-way as part of the project. Village ordinances require that every user of the Village's sanitary sewer, water, or storm sewer system shall permit the Village or its authorized agent to enter the premises being served to inspect the pipes and fixtures.

The Village has no documented lead water laterals within the project, but if a lead lateral, or portions of a lateral are found to be lead the Village's ordinance states that the owner, after notification from the Village, will have 18 months to remove and replace the lead in conformity with the State Plumbing Code. Village ordinance states that the property owner is responsible for the water lateral from the shut off valve (curb stop) to the building.

The project will include some work on private property to grade and shape the lawn areas to meet the new sidewalk. Also, driveways will be cut back to match the elevation of the sidewalk and new road. Construction permits will be distributed to all affected

residents. The permit will allow the Village's contractor to complete work on private property and will include an exhibit, aerial photo and linework to show the extent of the work beyond the public right-of-way. After reviewing the construction permit, the property owners will sign the permit and return it to the Village by May 17th, 2024.

- **PROJECT SCHEDULE**

The Village of Denmark 2024 Street and Utility project is expected to begin in early June with an anticipated completion date in late August 2024.

- **TRAFFIC AND ACCESS DURING CONSTRUCTION**

North Ave., N. Wall St., and Danish Way will remain open to local traffic during construction. Road closures on North Ave., N. Wall and Danish Way will be necessary at various times during the project.

Residential access will be maintained except when work is being completed immediately adjacent to the driveways and during the construction of curb and gutter, sidewalks and driveways. Driveways will be closed for up to 25 calendar days to allow the construction of curb and gutter, sidewalks and driveways.

Every attempt will be made to restore residential driveway access at the end of each day, except when work is occurring at or immediately adjacent to the driveways and during curb and gutter, sidewalk and driveway operations. During periods of driveway closures, residents will be allowed to park on the opposite side of the road and on the adjacent sideroads. During this time, residents are asked to put their name and phone number on a piece of paper and place it on their dashboard. This will allow the contractor to contact you in the event that the vehicle needs to be moved.

The contractor will coordinate driveway closures 24 hours in advance of residential driveway access interruptions.

Access for emergency vehicles will be maintained at all times.

Access will be maintained for mail and general deliveries and garbage and recycling vehicles.

The contractor will prepare a traffic control plan and this information will be posted on the Village website as well as communicated through the field staff.

If any access questions arise during construction, please do not hesitate to ask.

McMahon will have a representative onsite during construction and his contact information will be posted on the Village website.

- **PROJECT COST**

Preliminary construction cost is \$1.36 million for North Ave., N. Wall Street, CTH T and Danish Way.