

TOWN OF BURLINGTON

RACINE COUNTY, WISCONSIN

ADVERTISEMENT FOR BIDS

Lake Street Reconstruction – Town Project No. 222614

Bid #3 – 2026

1. NOTICE TO BIDDERS

The Town of Burlington, Racine County, Wisconsin, will receive sealed bids for road construction work described herein until 12:00 PM (local time), Tuesday, August 11, 2026 at the Town Hall, 32288 Bushnell Road, Burlington, WI 53105. Bids will be publicly opened and read aloud immediately thereafter.

The Town reserves the right to reject any or all bids, waive informalities, and accept the bid deemed most advantageous to the Town.

2. PROJECT DESCRIPTION

Project includes sawcutting existing asphalt, milling 4 inches, regrading of base course and driveways, and repaving with 4 inches of compacted asphalt placed in two lifts on Lake Street, in accordance with the project plans (Project No. 222614).

Road Name(s): Lake Street

Approximate Limits: Sta. 38+75 to Sta. 40+85 (vicinity of #4203 through #4223 Lake Street), per plan Sheets 5 and 9

Approximate Length: 210 LF

Approximate Width: 10 FT typical (varies 8.5–11 FT), plus driveway aprons at #4213 (14.4 FT) and #4223 (13.0 FT)

All dimensions are approximate. Contractor is responsible for field verification.

3. BID SECURITY

Each proposal must be accompanied by a certified check payable to the Town of Burlington, or a Bid Bond, in an amount not less than 5% of the total bid amount.

4. PERFORMANCE & PAYMENT BOND

The successful bidder shall furnish a Performance Bond equal to 100% of the contract amount and a Payment Bond as required by Wisconsin Statutes § 779.14.

5. INSURANCE REQUIREMENTS

Contractor shall maintain Commercial General Liability coverage of \$1,000,000 per occurrence and \$3,000,000 aggregate, Automobile Liability of \$1,000,000, and Workers Compensation per State Statute. The Town of Burlington shall be named as Additional Insured.

6. COMPLETION & LIQUIDATED DAMAGES

All work shall be completed by October 1, 2027.

Failure to complete by this date shall result in liquidated damages of \$500.00 per calendar day.

7. STANDARD SPECIFICATIONS

All work shall conform to the Wisconsin Department of Transportation (WisDOT) Standard Specifications for Highway and Structure Construction – Latest Edition, and current MUTCD standards.

8. TECHNICAL SPECIFICATIONS

Milling: 4 inches depth. Sawcut asphalt at removal limits (typ.) per plan.

Base Regrading: Regrade base and driveways prior to paving, per plan.

Asphalt Pavement: 4 inches total compacted thickness, placed in two lifts, per plan.

Binder Course: 2.25 inches compacted, Mix Type 5LT 58-28 S.

Surface Course: 1.75 inches compacted, Mix Type 3LT 58-28 S.

Cross Slopes: 2.0% to 6.0% as shown on plan, with 80-foot cross slope transitions.

Compaction minimum: 91.5% of Maximum Theoretical Density (Gmm).

Load tickets from certified scale required.

9. WARRANTY

Contractor shall warrant workmanship and materials for a period of one (1) year from date of final acceptance.

10. BID SCHEDULE (UNIT PRICE FORMAT)

Item	Description	Estimated Qty	Unit	Unit Price	Total
1	Sawcut Asphalt	215	LF	\$	\$
2	Milling, 4"	265	SY	\$	\$

	Depth				
3	Base & Driveway Regrading	265	SY	\$	\$
4	Binder Course, 2.25" (5LT 58-28 S)	35	TON	\$	\$
5	Surface Course, 1.75" (3LT 58-28 S)	27	TON	\$	\$
6	Traffic Control	LS	LS	\$	\$

Quantities are engineer's estimates derived from the project plan sheets and are for bid comparison only. Payment shall be based on actual measured quantities.

TOTAL BID AMOUNT: \$_____

11. CERTIFICATION

I certify that I have examined all contract documents, inspected the project site, and have authority to bind the company.

Company Name: _____

Authorized Signature: _____

Printed Name & Title: _____

Date: _____