

Northern Pacific Railway Company. Engineering Department Records.

Copyright Notice:

This material may be protected by copyright law (U.S. Code, Title 17). Researchers are liable for any infringement. For more information, visit www.mnhs.org/copyright.

964

The Grand Coulee Dam, and the Columbia Fesia Reclemation Project

A descriptive paper, to be presented November 6, 1939, with projected illustrations, to the Northwest Section, American Society of Civil Engineers, St. Paul, Minnesota.

S. E. Button, Hom. A.I.E.E., Hem. A.S.M.E., Assistant Director of Information, U. S. Buresu of Recismation.

(Freliminary draft, subject to correction and editing. - Oct. 9, 1939)

Teble of Contents

Purposes	
Columbia River Pasin	2 5
Raterahed Above Dam	5
Flow, Run-off, etc.	6
Geology - Grand Coulse, etc.	
Lake Quincy	10
Dry-farming Development	11
General Scheme - Columbia Basin Project	12
The Dem	14
Storage Reservoir	18
Power Plant	18
Pumping Flent	20
Belencing Reservoir and Genels	21
Project Lands	22
Anti-Speculation Act	24
Surveying - Appraising, etc.	26
Construction Contracts	27
Auxiliary Construction and Towns	30
Excevation	38
Frozen-Marth Dam	34
Diversion of the River	37
Bedrock	41
	4.8 4.5 5.0
Bedrock Grouting	45
Placing Comorete	45
Cooling	50
Concrete (wellty	51
Concrete Wixing	50
Aggregate	
Coment	51 54
A STATE OF S	5
Financing U.S.Bureau of Reclamation Projects	
Retimated Costs	61 61 61
Retimeted Fower Output	
Herket for Power	
Meed for More Land	6
Proceeding Association and the Control of the Contr	District Control of the

Purposes of the Grogest

The development of the Columbia Basia Reclamation Project in seatral Reshington is the culmination of several decades of investigations, planning, and promotion. The objects of the enterprise are to irrigate, within the next 25 to 50 years, a million and a quarter across of dry-ferms, abandoned land, and desert, to develop electrical energy for use on the project and elsewhere, and to regulate the flow of the upper Columbia for the benefit of future downstream power plants. Flood central for the protection of property is a minor consideration; but regulation of the winter flow is potentially important to navigation in the lower Columbia, where the low water of winter can be increased two feet in depth by the releasing of stored water.

The Columbia River is of very great economic importance to the Pacific Sorthwest. It drains an erea of 259,000 square miles -- an erea greater than that of Minnesota, Iown, Illinois, and Misconsin combined -- four times the erea of the New England States. The drainage basin includes nearly all of Maho, the greater parts of Gregon and Machington, small areas in Myoning, Utab and Mayada, and large cross in Montana and British Columbia.

Fithout irrigation from the Columbia and its tributaries, but few people could live in the Facific Northwest; and, as a consequence, the Middle West and the East would pay much higher prices for western products, and would have a more restricted market for middle-west food-stuffs and austern manufactured scods.

The Columbia is second in flow to the Missiesippi alone, among the rivers of North America, and greater than any other in potential power.

Deventy-four thousand one hundred square miles of the Columbia Basia lie above the site of the Grand Coules Dem, 39,000 square miles of it in Ganada. Sixty per cent of the water passing the dam comes out of Ganada.

The most important contribution is the main stem of the Columbia. It rises in lake Columbia, between the Consdien Nockies and the Selkirks, flows northwesterly 195 miles, and thence southerly 270 cites to the interestional border. It brings down about 36 per cent of the water that passes the dam.

The most important tributary to the upper Columbia is the Footenei River which rises in the Capadian Rockies 75 miles morth of Lake Columbia, source of the Columbia River. It flows south 180 miles into Bontana, passing within a few miles of Lake Columbia. After making a 167-mile loop through northwestern wontone and northern Idaho, the Roctenei returns into Sanada, and joins the Columbia 30 miles morth of the border. Rearly 28 per cent of the flow at the dat, an average of 25,200,000 acre-feet a year, comes from the Footenei.

Third largest of the streams above the des ix is Clark's Fork. Its source is on the western clops of the Rocky Mountains near Butte, and not far from the sources of the Riesouri River and the Oneke, large downstream tributary of the Columbia. Most of the drainage of western Montans is collected by the Clark's Fork in its 260-sile course northwesterly

to Lake Fend Creille in north Edaho. Thence, the river runs northwesterly through Edaho and northeastern Esskington to a junction with the Columbia helf a mile north of the Canadian border.

The Clark's Fork furnishes about 24 per cent of the flow at the day, the Spokene, draining a part of the western slope of the Bitterroot Mts., seven per cent, and the Kottle, Colville, and San Poil rivers half as much.

Floring Remodes Ele

The everage annual run-off of the Columbia at the dem site during the past 25 years was 80 million acre-feet, and the everage flow 110,000 second-feet, ranging from a minimum of 17,000 second-feet to a maximum of 492,000.

the Columbia and Mootensi Mivers, comes from glaciers and ice fields high in the Selkirks and Canadian Mockies, the peak is reached in June or early in July, and the flow always continues high throughout the number. Fortunets consequences are that surplus water will provide both water for irrigation and power for pumping it, and that all firm or primary power will be available for industrial, domestic, and municipal uses.

Levery of the Liverist service Region

at least a superficial understanding of the general geological features of central Mashington is necessary if one is to understand the power potentialities of the Columbia, and the scheme for expending a little the limited agricultural resources of the arid west, where, in a third of the country, the government holds more than helf the land, and irrigation can never cover more than a thirteenth of the mation's farm land.

the earth's surface, first in an arm of the sea, and later in low land, lying between the Rocky Bountain agatem and the Cascades; and floods of highly fluid Lava poured out on many successive occasions, separated by thousands, and perhaps by millions of years. Thus was formed the Columbia Lava Flatean, covering parts of Samhington, Oregon, Idaho, Utah, Nevada, and California.

out of its short course to the scuthwest, and compelled it to cut, to the west and south, a new channel which was completed before the close of the last ice age, and is now occupied by the river. The Mig Bend of the Columbia follows, generally, the contact of the laws plateau with the Chancean Mighlands on the north and the Cancades on the mest; and, at the dam site, is a canyon 1800 feet deep, 3000 feet wide at the bottom and a mile wide at the top. No doubt great seasonal

floods from the ice eap, vestly greater then the floods of this day, are largely responsible for the depth and width of the easyon.

4

Nountain building forces that forced up the Okunogen Highlands and the Cascades lifted the northerly and mesterly margins of the lave plateau, causing its surface to slope sway to the south and east from the Columbia canyon well. They also lifted the northwesterly portion, known as the Materville Plateau, about 800 feet above the interior of the hig Bend country, the southeastern boundary of the Materville Plateau being marked by the Coulee Managine.

Into the Pecific Northwest produced profound changes in the Columbia Basin. The Spokane Ice Lobe appears to have closed for a long time the Spokane River and the Columbia above its junction with the Spokane, while the Skanogan lobe at the same time occupied the Chanogan valley, closed the Columbia from the vicinity of the dam site westward to some point above Chelen, and covered the northwestern part of the Saterville Pintenu. The San Poil valley and the Solumbia from the dam site seatward to the Spokane River remained open.

During that period of thousands of years, tramendous floods of glacial water, overflowing the divide a few miles south of the river canyon, along a hundred-mile front, swept

away the soil and out rugged channels in the lave plateau, to carry the floods away southwesterly to the lower Columbia and its tributaries. The most westerly of these relief channels, and by far the greatest in size, is the Grand Coulee.

Seter backing up in Rattlesnake Canyon, neer the Market site of the dam, spilled over into the basin of a smell stream which flowed southwesterly across the Saterville Plateau. Fouring over the Coulee Monocline, which drops 800 feet in a mile to the Hartline Basin, the glacial torrent formed great rapide and them a stupendous waterfall, which by beadward erosion out through the Saterville Platesu the upper Grand Coules, 800 feet deep, 25 miles long, and one and a half to five miles wide. It intersects the Columbia River canyon 600 feet above the bottom of the gorge.

After spilling over the Coulee Monocline, the outflow filled the Eartline Sasia and overflowed its southern mergin at several places, forming rapids and materfalls which produced the lower Grand Coulec, the Bry Coules, and the Opring Coulee, all opening into the Guincy Basin.

In the broken rock of the Coules Monocline, the Coules Coules lower Grand Coules was cut to elevations far below the bawildering network of channels that lie anat of it, by a weterfall that originated in rapids near the site of Soap Lake. The west wall of the lower coules, an edge of the Saterville Flateau, is 300 to 1000 feet above the lakes on the coules floor, and the sest wall, of the Hartline Rasin,

is about helf as high. Islands in the lakes are remnants of the Coulee Menocline, and show its sloping strate.

The 17-mile box-campon of the lower Grand Coulce terminates at its northerly and in the Pry Falls, 400 feet high and with a brink five miles long.

Okenogen lobe of the Tee Cep, the Glacial Columbia resumed, for a time, its course through the cenyon which the Columbia now occupies. Later, the canyon was closed again by the Okenogen lobe, the Misconein Tee Front extending as far south as the Dry Falls, along the west side of the upper coules, the entrance to which was closed. During this period the channel on the east side of Steamboat Rock was probably formed or enlarged, and the Dry Falls advanced three miles further borth, to their present site.

spread out over the Martline Basin, and laid down, over an area of 50 square miles, deep deposits of gravel, sand, and ailt. This basin was finally almost completely drained by the Dry Fells, which advenced to within about 6 miles of the outlet of the upper soules.

Talio Ening

Below the cutlet of the lower couler, the turbid run-off from the lee Cap spread over the Quincy Besin, forming Lake Quincy, and covering an area of SEC square miles with detritus from the les Cap. Through three outlets to the west, one now traversed by the highway east of the Vantage bridge, the lake everflowed into the Columbia Siver canyon, and to the south it found one outlet around the Frenchmen Hills and another past the Saddle Sts. through the Drumbeller and Othello Channels.

These outlets ultimately drained the lake, and exposed hundreds of thousands of acres of land that ere to be irrigated from the Grand Coules Dan.

Kleyton in

Sillions of acres of land west of the Missouri Siver, and millions more west of the Mocky ata. were formerly characterized in the geographies as desert. Large areas were used for grazing, but people native to humid climates believed they would never relac cultivated crops. In the 70's, settlers in the Palouse country relaced crops in the flats and ran stock on the bunch-grass bills, which they believed to be otherwise useless. Then someone learned that wheet would grow on the hills too, and dry-farming developed.

4

In the 80's, fermore pushed further out into the range country of central Mashington; and as let as 1900, bumesteaders were still settling on the sage-covered lands in the Mig Send. Some still remain, dry-ferming the rim of the area to be irrigated, but thousands of families, after a brief success, followed by years of drought, long ago noved every.

The Columbia Basia Reclamation Project will reclaim thousands of abundance farms, and thousands of scree of descriptions, and will some day save thousands of scree of dry-farm wheat lend from the fate of the Great Plains dust bowl.

Irregation of the Bealesson

It was but natural that engineers and early settlers should think of bringing the abundant water of the Columbia or one of its tributeries to land that sparse streams and deep wells had proved to be rich, and, if irrigated, highly productive.

contemplated exercises water entirely by gravity from Alberty Falls, on the Clark's Fork in northern Idehe, agross the country to the southwest, through canels, inverted siphone, and tunnels, to irrigate the lower part of the eres now to be served. Another scheme proposed a day, a power house, and a pumping plant on the Columbia River near the mouth of the Grand Coulse, and the use of the Grand Coulse as the route to the irrigable lands. Technological developments of the lest quarter century have made that plan feasible, and in 1982 it was approved by the Army Engineers as a consequence of a comprehensive study of the Columbia Resis.

The enterprise involves building, in an isolated, 1600-foot conyon, a dam of unprecedented size to raise the 335 river above it about 525 feet; and, as the project develops, the construction of the biggest power plant in the morld, a pumping plant to raise irrigating water an additional 280 feet at the rate of 500 tons a second, a reservoir 27 miles long in the upper Grand Coules, hundreds of siles of main and lateral canals, numerous auxiliary power and pumping plants

on the project lands, and a wariety of structures and control works.

1

The Columbia River falls 1310 feet in its 750-mile 10. Cartains to course from the Canadian border to the see. According to plans of the Army Engineers, ten dans will someday utilize 32 per cent of this head. Two of the Same are already completed, one at Bonneville, at the head of tidewater, and one at Bock Island. Uppermost and most important of the ten will be the Grand Coules Dam. It will utilize 27 per cent of the total head; and will regulate the flow of the river for the benefit of power plants at other dams, doubling the firm power capacities of such plants above the junction of the Columbia with the Snake River, and increasing by 50 per cent the firm power capacities of others.

The Granest Comme

The Grand Gouleo Dam is of the gravity type, and extends straight across the river canyon. Its maximum height from lowest bedrock will be 550 feet, and its maximum length 4300 feet. The base is 500 feet wide at the bottom of the canyon, and about 2000 feet long.

The dosnatream face has a uniform slope of 0.8 to 1; and, in the 1850-foot spillway section, it terminates in a so-called bucket, designed to dissipate the energy of water folling over the dea, and thus prevent serious erosion of the river bod downstream. The bucket is 90 feet wide, and 30 feet deep. Its crest is at Blovetion 900, about 33 feet below average low-water level and nearly 80 feet below the high-water average.

complished by means of 11 drum gates at the creat of the spillway, each 136 feet long and 28 feet high, and 60 cutlet tunnels through the dam. The tunnels are 8-1/2 feet in diameter, and are arranged in 2 sets of 10 pairs, one set at approximately low-mater level, one set 100 feet higher, and one set 200 feet above low water. The estimated capacity of the spillway is a million second feet, and that of the outlet tunnels 252,000 second feet. The turbines, fully loaded, will pass 81,000 second feet.

Track reaks protect the entrances to the outlet works, and two gate valves are installed near the upstream and of each tunnel. Air ports and control valves will admit

air to the tunnels when valves are closed, to prevent the creation of vacuum in the tunnels, and consequent demage to linings and valves. Entrances to the tunnels are lined with heavy, ribbed, semi-steel castings, flared to reduce or climinate cavitation.

at vertical intervals of 50 feet, galleries extend from end to end of the dee. These, with a number of adits extending from them toward the face of the dam, are provided for use in inspecting, cooling, and grouting the dam. One cross-channel gallery follows closely the bedrock. From it, holes will be drilled for final bedrock grouting, when the dam is nearly completed; and, later, 50-foot open uplift relief holes will be put down.

Above the Coules Dam, a storage reservoir 151 miles long will extend to the Ganadian border. It will average about 4,000 feet in width; and will extend about 80 miles up the Spokene River and about 8 miles up the Kettle and San Poil Rivers.

-

The storage capacity will be about 10 million sere-feet, of which a little more than 5 million will be useful for regulating purposes with an 80-foot drawdown. No stored water will be needed for irrigation or for pumping irrigating mater, since the season of high water coincides with the growing season; hence the antire useful storage capacity of the reservoir will be available for the benefit of future downstream power pleats.

The flood line will be at elevation 1290 to 1292, but all land below elevation 1210, an area of 128 square miles, will be acquired by the government. It has been surveyed and evaluated for the government by local appraisers. With very rare exceptions, owners have accepted the prices offered. Chiefly grazing and out-over timber land are involved. Two small towns, and several small cattlements, including a little ordered land, are included. Several miles of railroad and of primary and other highways will be relocated.

Lettle Fells, a 30-foot irregular cataract, will be flooded; and the long highway bridge at that location will be replaced with emother which will accommodate both the

reilroed and highway.

Clearing of the reservoir area of bucygat and combustible materials is in progress as a W.P.A. project, the Bureau of Reclamation furnishing all material and equipment. Merebentable logs are sold to commercial sawnills.

Planking the spillway section on each side is a power house and abutment section. The foundation for the east power house has been completed, but no further work will be done on it until the west power house is developed. It is a reinforced concrete building 765 feet long and 85 feet wide, now under construction.

1

Shen completed, the power plant is to contain 18 generating sets, each consisting of a 108,000 kvm generator, driven by a 180,000 k.p. turbine, sine in each power house. In the west power house, there will be also three station service units, each a 12,500 kvm generator driven by a 14,000 h.p. turbine.

The three large and two small generators are under construction at the Sectionhouse plant in Fittaburgh. The Memport News Emiphuilding and Prydock Co. is building the three large turbines, and the Felton Seter Sheel Co. the two small mechines. The three large generators are to cost \$2,611,000, installed, and the two small mechines \$193,480. The low bid on the three large turbines (to be installed by the Eureau) was \$1,477,200, and that on the two small sheels \$106,498. Installations are to be complete early in 1942. Governors will cost 187,090.

The large generators will run 120 r.p.m., and will generate 13,800 volts, 5 phase, at 60 cycles. Rotors will be

16 feet high and 25 feet in dismeter; and the stater and frame 22 feet high and 45 feet in dismeter. One generator will weigh about a thousand tone. Turbine scroll cases will be 52 feet in dismeter with 152-foot draft-tube throats. Such will weigh about 756 tons.

The pumping plant will be located on a wing dam, approximately 150 feet high and about 600 feet long, located behind the west and of the dam. It is designed to include, ultimately, 12 contributal pumps, each with a capacity of 1600 second-feet against a head of 295 feet. Two pumps will be spare units.

Ì

Each pump will be driven by a 65,000 h.p. mynchronous motor. Two motors will take their power supply directly from one generator, and the two pumps will be sterted by controlling generator and motor field excitation as a turbine is started. It will be possible to adjust pump speeds to pumping heads by controlling turbine speeds.

The base of the pumping plent is now under sometruetion, but pumping equipment and the building will not be added until the irrigation phase of the project is undertaken.

The output of such pump will be delivered by means of a 12-foot steel pipe, through one of 12 tunnels already driven diagonally upward through the canyon wall, to be traced carried by an open canal to the upper of the two earth-fill dams which will form a 27-mile belancing reservoir in the upper Grand Coulee.

The construction of two earth-fill diese in the upper Grand Coules is justified chiefly by the fact that 27 miles of main canal would be more expensive, but the balancing reservoir so formed will be useful in adjusting the demand for water, and the supply is the irrigation system. Off-peak power can be used for pumping; and in the distant future, when other power sites on the river are fully developed, water stored in the balancing reservoir will start the season's irrigating if a late spring about eause a low run-off in april.

Not all of the floor of the upper Coulse will be flooded, but most of the construction reliroud and 8 or 10 miles of the highway will be ocvered. No water will flow through the lower coulse.

A main canni, 12 miles long, will pass east of the Dry Fells; and from it a canal, ultimately to be 100 miles long, will supply the west side, and a 150-mile canal will supply the east side of the project with water. The west canal will crose the lower coules, between hosp and lenore lakes, by inverted siphon or violact.

Project Lands

The land to be irrigated extends from the vicinity of Bosp Lake, 50 miles south of the dam, to Pasco, about 80 miles further south, at the junction of the Snake and Columbia Rivers. The greatest winth of the area, east and west, is sixty miles. Elevations range from about 1800 is the north to 400 in the south. The soil resembles others of placial origin.

4

The climate is temperate, but of low humidity, predipitation varying from 5 to 16 or 17 inches, vary little felling during the growing season. The meet control temperature is about 50 degrees, and the average during the growing season about 52. Sugger days are bot, but the nights are reasonably tool.

The everage frost-free period over a number of years was 150 days. Temperate come crops can be grown, but they must be of varieties to be consumed locally or to stand high shipping costs. Forage crops will occupy large areas. Staples like wheat and sorn can not be grown profitably on small tracts of irrigated land. The climate is not suited to cotton, and marketing conditions will not favor tobacco. Diversified farming will be practiced.

planest all of the land to be irrigated was patented years ago and is now held by individuals and corporations.

It includes desert, abandoned dry farms, and dry-farm wheat land.

No land on the project is open to homestead entry. Settlers will be obliged to buy from private owners, but they will be protected from land speculators by the "Anti-Speculation Act", of May 27, 1937.

The principal objects of the Anti-Appeculation Act are to insure prospective settlers that they will be able to tay lend at its actual unirrigated value without the addition of any speculative increment, and to provide homes for many femilies by preventing the holding of large acreages. This is accomplished without depriving the landowner of any of his legal rights, by the simple expedient of introducing suitable conditions into the contracts under which the government undertakes to build, maintain, and operate irrigation works for the benefit of the isndowners. The plan has already been followed successfully on the Kittites and Caybee Projects.

Friefly, the principal provisions of the Anti-Speculation Act are:

- (a) that contracts for the repayment of that part of the cost of the project, allocated by the decretary of the Interior to irrigation, and contracts for other purposes, be entered into by the government and the landousers as members of irrigation districts;
- (b) that landowners agree to limit their holdings to 40 scree for an individual or 30 scree for a man and wife;
- (c) that landowners agree to sell lands held in excess of these minime at the government-appraised price 2.
- (d) that lands to be served with water be impartially appraised by the government to determine their present-day market values without reference to the proposed irrigation works;

(c) that in the event "excess" lable are sold at higher prices, or are retained, no water shall be delivered to either the land so sold or to non-excess or excess lands retained;

1

- (f) that water may be obtained for lands which were purchased at prices above the government apprecial, unless they were "excess" lands so purchased, upon payment to the government of a portion of the excess price, varying from 50 to 100 per cent with the delay in payment, this money to be applied as credit against the last construction payments to be charged against the land; and
- (g) that the State of Washington by appropriate legisletion shall authorize, edopt, ratify, and consent to all the provisions of the act which case within the jurisdiction of the State.

any tract of land run with the land as part of any title to it. Records of government appraisals will be accessible free to prospective land buyers at appropriate time and places. The State of Eschington has complied with the previsions of the act, and landowners are active in carrying out the preliminary steps of their obligations.

In order that the Secretary of the Interior may be enabled to discharge his duties under the act, an enormous surveying end appraising project is in progress by the Bureau of Reclamation on the project lands.

1

It involves, first, the retrecement of original contract surveys, made 30 to 75 years ago, in an erea of two and a helf million acros (3780 sections). Lost corners are released according to the practices of the Coneral Lend Office, and all section and quarter-section corners are marked with concrete and metal monuments. About two million across have been covered.

Level parties determine the elevations of all monuments, and they are used as beachmarks by topographere who take contours at two-foot intervals on all land likely to be irrigable. Topographic work has been completed on nearly a million and a half seres of land.

the soil on seen 60-sere tract; and apprelsers, taking into secount any improvements on the land, are fixing the values at which each parcel of land is to be sold.

Actual development of the irrigation phase of the project must depend upon the progress made by landowners in organizing their districts and contracting with the government, and on appropriations by Congress.

summer of 1933 with discord drilling, the disging of test pits, and preliminary surveying on the dam site. In Becamber, a contract for the removal of 2 million yards of overburden was let to Bevid H. Ayan, and a slide the following spring added a million yards to that job. Fower showels, heavy dump trucks, and tractor-drawn scrapers were used.

July 18, 1934 to the Enson-Salab-Atkinson-Sier Co., and work on that contract was started on October 1. On account of technical problems involved, and because the Bouneville power project had been recently initiated, the contract was altered June 5, 1935 to cover, instead of a complete low dam, the base for the high dam originally planned as the basic feature of a combined irrigation and power project. The work was completed Norch 21, 1938 (due April 2, 1939).

Completion of the dam, the west power bouse, and the base of the pumping plant is covered by a contract let February 7, 1938 to the Consolidated Builders, Inc., a first composed of the R.B.A.E. Go., the Six Companies, builders of the Boulder Dam, and the General Construction Co., builder of the Crybes Bem.

Coverament took over from the M.W.A.K. Company, at the termin27.5ation of its work, the town Meson City for \$25,000, the \$1-mile
110,000-volt transmission line for \$25,000, and, for \$100,000
the entire installation of construction equipment, including
crushing, screening, washing, conveying, concrete mixing, and
other installed facilities, but excluding shovels, drag-lines,
treators, trucks, and other mobile equipment. All of the
property taken over from the M.W.A.K. Company, except 5% houses
in Meson City, was transferred to Consolidated Buildors, Inc.
at a price specified in its contract.

Superous additional contracts covered a 30-mile reilroad to the site, details of the government construction camp, construction materials, and dan and power plant equipment. The government formishes all auterial and equipment in the permanent justillation.

If funds are evaluable at the necessary rate, the dawn, the west power house, the base of the pumping plant, two station-service generating units, and three mein generating units will be complete in 1942.

No part of the irrigation phase of the project will be undertaken until lendowners contract with the government for its construction, and until Concress their series necessary appropriations for financing it.

the pioneer crews, but with the letting of the E.W.A.Z. contract, more substantial facilities became necessary. Highways leading to the dan were realigned, regraded, widered, and hard-ourfeded by County Commissioners and the State Highway Department; 32 miles of standard gauge reilroad were built from Odeir to the mouth of the Coulea by the Covernment; 29,5% a 20-mile 110,000-volt transmission line was constructed by the contractor in 42 days; a 950-foot centilever highway bridge was built across the Columbia by the Covernment, and a heavy timber Howe trues bridge by the contractor; telegraph and telephone lines were run in by the public utility companies; and two towns were built below the dan site.

town. Since it is to be dissentled when the des is finished, its houses and public facilities are of a less substantial character than those in Coulee Des, the Covernment town on the opposite side of the river; but houses are confortable. streets are ciled, and efficient water, street lighting, and sever systems were provided. There are 290 houses in Mason City, all but a dozen of them of three standard types, containing one, two, or three rooms, bath, and hitchen or kitchenette There are, also, of ashin-type dormitories with accommodations for 1360 men, 2 dormitories for women, a hospital, a hotel, two school houses, a gymnasium, two churches, a laundry, stores,

recreation hell, office and shop buildings, warehouses, storage yards, a large mess hall, a notion picture theatre, a garage, and a service station.

Coulee Dam is a pervenent town to house operating and handquarters employees of the Columbia Busin Project, composed of 77 permanent residences of six standard types, 3 large dormitories, administration building, school house, post office, garages, firs station, shops, warehouse, and service station. Fifty-seven 3-room, court-type residences, and 7 temporary dormitories are to be removed after the dam is completed.

The two towns cooperate in Speritific their school systems. High school and primary grade pupils attend school in Mason City, others in Coules Dam.

Private towns and villeges, that spring up in the vicinity of the dam, have a combined population of nearly 10,000.

Expansition

Among the major tasks included in the building of the Goulee New was the exceptation of overburden from the dam site.

While the canyon was blockeded downstream furing the last ice age, glasiel water deposited fine rock flour, side streams brought in sand and gravel, and icebergs dropped boulders to fill the canyon, principally with sand and rock flour, to depths of several hundred feet.

Such of the saterial was carried out into the Quincy Busin when the cutting of the upper scules was completed, and later much of it was carried down the river, but much still remains.

at the dear site, the river flows in a rock canyon 3,000 feet wide at the bettom, in an 800-foot bed between send and clay slopes and terraces against the canyon walls. Twenty to 70 feet of hard clay, interspersed with boulders, sand, and gravel, covered the bedrock beneath the river channel at the dem site.

In order to ley bore the 35-acre site of the dam and to provide foreboye and tailbays for the power bouses.

about 15 million yerds of everturded were removed. Material, 12 dag by large electric shovels, was hauled in 8- to 16-yerd trucks and 12- to 25-yerd tractor-drawn buggles to grizzlies over feeder pits, where boulders over 13 inches in size were pushed off, to be healed sway later by trucks, and other material was broken up and forced through the grizzlies by bulldozers.

Feeders under several grizzlies delivered material by belt conveyors to the surge feeder on the 60-inch main conveyor system, which was made up of several sections, each drives by a 200-horsepower motor, and long or short depending upon the grade.

More than 13 million yerds of overburden were carried a mile away to Sattleanake Canyon, and dusped at elevations 500 to 600 feet above the excevated area. Several million yards of overburden from the east side were carried by belts 2000 feet across the river, and thence on the main conveyor to Battlesnake Canyon. After excevation on the west side was finished, the conveyor system was moved to the east side of the river.

Overburden was saved at the rate of about a million yards a month -- as much as 50,829 yards in one 31-hour day.

Cosmon excavation under the N.W.A.A. sontract exceeded 17 million yards, and to date it has run over 20 million, not including, in either case, the abying of sand and gravel.

A Francis Excell

A frozen-clay dam was a unique and spectacular feeture of excavation operations at the Coulse Dam. Threatened with serious delay and great expense by a moving mass of plastic clay which, in spite of ordinary efforts to hold it, poured into one of the deep gorges in the bedrock, angineers of the bureau conceived and carried out the idea of freezing the toe of the clay alope.

The gorge in question was a hundred feet wide just upstream from the dam site, extended about 120 feet below adjacent bedrock, and opened into a deep pit in the dam site. A thick deposit of clay overlying it and extending further upstream, was not stable on a 3 to 1 clope, and it continued to flow into the pit over a concrete dam and a heavy timber crib built by the contractor at the bottom of the gorge.

of 1988, and the entire cost excavation was flooded. Sloughing recurred as soon as unwetering was started into in the susser, and the freezing venture was then undertaken. The water level in the pit was maintained at elevation 850 to stabilize the material while the ide dan was formed.

although measur information was available in connection with freezing of wat ground in shaft sinking, design data to suit local conditions could not be found. On the basis of a compressive strength of 200 pounds per square inch, a weight of

90 pounds per cubic foot, 75 per cent liquid pressure, and a cylindrical formula, a thickness of 10 feet on a radius of 105 feet was indicated. The long radius was chosen in order to give the frozen section vertical support on the timber orib. to avoid uplift, and to minimize the risk of slipping at the househes. The arch thickness decided upon was 20 feet, the height was 40 feet, and the span 100.

Considering the time evaluable and the probable rate of freezing, refrigeration pipes were spaced 80 inches each may. The water content in the mixture was 32 per cent of the dry weight of the clay, and heat conductivity and the rate of freezing exceeded expectations.

Precising points consisted of 3-inch black from pipe in two sections of 21 to 24 feet, driven one after another with a 300-lb, drep hasmer. In addition to 8 rews of pipes evenly speced, about 25 extra pipes were driven at each and of the erch to increase its strength and to make alipping on the rock abutments unlikely. There was a total of 377 points, of 43 feet average length. Lower ends were closed with standard pipe caps, which were found to produce less misalignment than pointed caps.

A tee and other standard fittings at the top of each 3-inch pipe supported within it a 1-1/2-inch pipe extending within 6 inches of the bottom, and facilitated hose connections

between the inner pipe in one freezing point with the exterior pipe of the next one. Groups of sixteen points were connected in series between 3-inch supply and return headers.

Forward movements of the upper portion of the freezing clay, and intermal adjustments of the freezing material as it expended caused the breaking of a few 3-inch pipes at the couplings between upper and lower sections. Ten were out out of the line without serious delay in the freezing.

A drainage well, such 55 feet to the bottom of the supporting crit, 80 feet upstress from the dam, collected about 25 gallons of water per minute, reduced the water content of the clay beak, and disinished the pressure on the ice dam.

Two numeric compressors of a combined ice expecity of 50 tons were used to chill the selt brice circulated through the system at the rate of 170 gallons per minute. Twenty tons of selt and 2200 pounds of ammonia were used.

The driving of freezing points was started August 14, 1886; the freezing of the first section completed was started August 25 and of the remainder September 3; and dewatering began September 18. The ice dem was dismoutled in April 1937, after concrete had been built up to a higher level; and the clay bank promptly moved forward against it.

(Engineering News-Record, Feb. 11, 1987, Reclaration Era, Jan. 1937)

The diversion of the Columbia River was the most preparious phase of construction work at the dem. The river has been known to reach a summer peak of 492,000 second-feet (clev. 981.5), and the flow actually averaged 445,000 secondfest (elev. 978) in tem years of the 33-year period for which records were swallable. The flood of 1894 is believed to have been 725,000 second-feet. Flans for the diversion of the river word based on a maximum exammed flow of SEO,000 secondfeet, and on assumed water levels of 1000 above the dam and 990 below it. The maximum flow in the years 1935 to 1937, inclusive, while the cofferdans were in use, aid not exceed 400.000 second-feet.

At the dea site, the river channel was about 800 feet wide. Semesth it was a bed of hard clay. 20 to 70 feet thick, and on each side exbankments of clay, send, and gravel. Along the west side of the river there was built in 90 days, in the winter of 1934-35, the world's largest cofferdam. Its total length was about 3,000 feet, and it inclosed as area of 65 cores, in which excevatious were made for the west third of the dam and for a forebay and tailbay for the west nower house.

The erector part of the cofferdum consisted of cells of 15-inch interlooking steel piles, but wings at the ends consisted of an outer single line of steel piles and an inner timber well joined to it with the rods, the intervening 37-foot space being filled with gravel. (Sections S end I, slide No. 481). Cells sensisted of straight disphrages specied 36 feet or 40 feet apart and joined by curved outer faces. Share supporting berms could not be maintained in the tailbay (Section S), the cells were 36 x 90 feet in plan, elsewhere they were 40 x 50 feet in area. (Sections C and N). Two clusters of larger cells (Sections D and S) were constructed about 800 feet apart, to be joined later to a corpleted section of the data (Slock 40) and to cross-river cofferdance, for the purpose of diverting the river and making the riverbed accessible for excavation.

Theet piling was driven by 50 steem harmors handled by long-arm crames and derricks, and by special gantries sade to spen the row of cells and carry 4 harmors each. An average of 35 blows of 15,000 foot-pounds were required per inch of penetration, and it was found to be impractical to drive the steel piles through the "young shale" everburded to bedrock.

"Refusel" was fixed at 50 blows per inch.

The first steel pile was driven on January 1, 1935, and by April 10th 13,000 tons, 127 miles, of piling had been driven to complete the west cofferdem. All of the steel had been trucked in 38 miles, 12 to 15 trucks being in operation 24 hours a day.

we was coffered was under construction, excevation was carried on actively within the area inclosed by it; and as soon as the coffered was completed, a heavily timbered excevation was sunk to bedrock just inside it.

Within the deep excevation, then was built to slev. 1000 a complete 50-foot section of the dam, block 40. It was joined, by concrete upstream and by means of a heavy timber crib downstream, with the two large cell-clusters of the cofferem.

the dam, terminating in Block 40, was built within the west cofferdam. Blocks 32, 34, 36, and 38, each 50 feet wide, were built up only to clev. 910, even with the bottom of the river channel, and the three intervening blocks were raised to clev. 950. The resulting 350-foot low gap was designed as the diversion channel for the river; but in order to prevent reverse currents and crosion in the thilbsy, several blocks in the power house section, eggregating 225 feet in width, were also left at clev. 950. The four deep gaps carried the flow up to about 85,000 second-feet, but the summer peak flowed about 18 feet deep over the high blocks and through the low gaps in the power house section.

Considerable excevation on the east side of the river was done inside of a low timber cofferdam, but the final excevation there and all of the excevating under the river channel were done in an area enclosed by block 40, parts of

the west cofferdam above end below it, and two cross-river cofferdams.

From soundings taken at 2-foot intervals over the sites of the cross-river cofferdams, cribs to fit the river bottom were built inside the west cofferdam; and subsequently they were floated into position after the diversion channel through the west cofferdam had been opened. The down-atream 32 cribs were 80 feet long and 64 feet wide, U-shaped, with 32-foot channels through them. After being sunk in their proper positions by having their compartments filled with gravel, stop-logs closed the channels and stilled the water to expedite the completion of the expectativer cofferdams.

Nov. 1926, the cribs of the down-stream cofferdam were all in place on Dec. 9, stoplogs were placed within 30 hours, and by Dec. 12 the river was flowing through the diversion channel. The up-stream cofferdam was substantially complete and dewatering was begun on Jan. 3, 1937. By Jan. 9, 30 million gallons of water had been removed, and excevation was underway.

In the system of cofferdams, 18,500 tons of cheet piling and E.828 tons of miscellaneous steel, and 18,500,000 board feet of timbers were used. Excavation for the cofferdams totalled 1,888,735 yards, and fills 1,502,000 yards. The contractor's reported cost for the diversion of the river sag nearly six million dollars.

Bedroch

The dam site is a granite spur of the Chanogen
Highleras, once buries in the Columbia Lava Flatenu and later
exposed and croded deeply when the Columbia cut out its
canyon. The rock is coarsely crystalline except where
fine-grain, such-jointed gray granite was intruded.

Farly investigations of the dam site included the drilling of fourteen diamond-drill helps in 1921, and two in 1920. Subsequent examinations brought the total of diamond drilling to about 53,000 feet, helps extending to depths as great as 380 feet. In all cases, only dense granite was penetrated. After bedrock was exposed, a number of 35-inch Calyx holes were drilled to depths of 29 to 58 feet in the areas showing greatest jointing. The bedrock was found to be satisfactory, and was prepared for foundation by removing 3 to 10 feet of weathered and loose rock.

Bedrock Growthing

Grouting of crevices in bedrock under a dam is done primarily for the purpose of preventing or reducing scepage of veter under the dam, and of preventing the development of up-lift pressure. Incidentally, it may reduce or prevent slight settlement as the load increases.

Bedrock grouting at Grand Coules is done in three stages. Shallow grouting, carried out before any concrete is placed, produces a general solicification of the upper layers of rock so that deeper penetration and more effective sealing may be secured with the higher pressures used in deeper grouting. Intermediate grouting is done after 25 feet or more of concrete has been placed; and final grouting, to produce the pain ent-off or grout curtain, will be done from a gellery near the upstream face, after the dam is built up 200 feet or more.

spacing of grout holes and for grouting pressures, actual requirements are determined by the Contracting Officer on the basis of information gained from excevations, drilling, water tests, and other investigations.

The quantity of grout "accepted" by grout holes veried over a wide range. In a "sheeted zone", much jointed and containing horizontal crevices of considerable size, two holes about 25 feet deep each took over 3,000 barrels of cement,

£

Low pressure growing was done through boles 20 to 50 feet deep (usually 30 feet), and at pressures of 50 to 200 pounds per square inch. So-called "B" holes were arranged generally in 5 rows 20 feet apart, extending from end to and of the dem site along the upstream boundary, the holes being spaced 20 feet apart is each row and staggard with respect to the holes in adjacent rows.

A single row of intermediate bolos was drilled under the dam et an engle of about 32 degrees, through the curved fillet connecting the upstream face of the dam with bedrock, to a vertical depth of 75 feet; and was grouted at pressures up to 300 pounds after at least 50 feet of concrete had been placed within a distance of 100 feet.

The final grout curtain will be created by grouting at pressures up to 1,000 pounds a series of holes 150 to 200 feet deep, to be drilled from a gallery which follows the bedrock closely from and to and of the dam. The first holes to be drilled and grouted will be spaced some distance apart. Then, repeatedly, holes spaced intermediately will be drilled and grouted until operations indicate that an effective cut-off has been effected.

within a distance of 600 feet, uplift pressure relief holes will be drilled at intervals of 10 feet clong the lowerment gallery to a depth of 50 feet, and will remain open to admit any accepage water from bedrock to the drainage system within the dam. Forous concrete tile, set vertically about 12 feet from the upstreem face of the dam, and spaced at 10-foot intervals, will intercept any seepage through the face of the dam.

1

4.

Placing concrete in the Grand Couler Dam involved, criginally, distributing it over an area 500 feet side and more than 3,000 feet long. The plan evolved for doing that for the construction of the base of the dam, provided two high steel treatles, one with its deck at elev. 1024 and its center line 93 feet from the upstream face of the dam, and one with its dock at elevation 950, and its center line 512.5 feet from the upstream face. Decks were 32 feet wide, and each carried three standard-gauge railroad tracks. The dea is to be completed from a 3600-foot 4-track treatle, 140 feet from the upstream face, with its deck at elevation 1180.

Practically all of the two original treatles, except their docks, is buried in the dam. The deck and parts of the vertical members of the third treatle will be univeged. About 20,000 tons of steel were used in the three treatles.

Concrete is handled in 4-yerd bottom-damping buckets, bauled on flateers by 10-ton Diesel-electric locomotives which are operated by the hook-tenders from any one of six stations along a runway from which they couple crane books and suckets. When a car leaves the mixing plant, it carries four locked buckets and space for an empty bucket which it will pick up from the first crane served.

Two types of cremes are used. One type consists of Wiley Whirleys sounted on traveling towers appaning the reilroad tracks. They are suited especially to the headling of forms, equipment, and supplies. Except under special circumstances, they will handle only about half as much concrete as the double-exatilever cranes. Of the latter, there are seven, four from the first contractor's equipment, overhauled and increased in working span from 250 to 500 feet by C.B.I., and three new and larger cranes with a working span of 330 feet.

1

The Chirley erases have 110-foot booss, and have a reach of 115 feet from the center-line of the treatle.

Capacities range from 11 tons with a flat boom to 40 tons et 75 degrees. Prequently two such cranes have been used together to handle heavy sections of penatock and heavy cost limings for outlet tunnels. The larger double centilever cranes lift 22 tons on a 100-foot arm, lower buckets at 375 feet per minute and heist empties at 750 feet per minute. They handle 100 to 150 buckets an hour to points 100 feet below the treatle deck. They have 460 volt a.c. meters driving 250 volt d.c. generators and meters with Mari-Leonard controls. Mein hoist motors are rated at 150 h.p. Two 50 h.p. meters can move the crane along the treatic 160 feet per minute.

Concrete is placed in movemble forms 5 feet deep and generally 50 feet square. They are set each time with reference to meints located with transits and levels, the dem being, in effect, made up of a group of columns composed of 5-feet lifts. Columns are interlocked along up- and down-stream joints by vertical keys and keysays 3 feet wide and 6 inches deep, and

slong cross-stream joints by borizontal keys about three and a half feet wide, vertically, and 16 inches deep. Oross-stream joints are staggared in adjacent 50-foot blocks.

1

The everage content of a 5-foot lift, 55 feet square, is 465 cubic yards, and it is placed in about 4 hours in layers about 18 inches deep. Vibrators compact and distribute the concrete.

placed, and exposed surfaces must then be kept met at least 16 days. After a period of 72 hours or more, the surface of a lift is cleaned by a black of air, send, and mater, exposing unconted surfaces of gravel and mand perticles to reaction with coment in a cont of sand-cement grout brushed on before the next lift is placed. This insures strong water-tight bonds between lifts.

jets of eir end water, the blasting sand and the water being carried away through a hole opening into a drainage system from a depression at the center of the block. Surplus water is removed with sponges or air jets before grout is spread.

supported on the insides of the forms are pipes and outlets through which grout is injected into spaces between columns after cooling is completed. On the surface of each lift, 1-inch thin-wall steel tubing is spaced 5'-9", and joined by means of compression couplings with tubes in adjoining columns. About 8,000 miles of such tubing will be used in the entire cooling system.

This dem, like Foulder and like other concrete dees under construction by the Sureau, is being cooled, shrunk, and grouted during construction, in order to prevent the development, years hance, of cracks due to natural alex cooling and shrinking. In time, any massive day will reach, and thereafter will vary but little, if any. From a temperature close to the mean annual temperature in its locality.

1

Scorete is placed in dams at various temperatures shows that finally to be reached. The reaction of vater with coment liberates neet. Concrete is a relatively poor confector; and, unless measures are taken to prevent it, maximum temperatures in mass concrete may be reached months or years after placing, and xxx slow cooling and consequent shrinking will produce cracks years after construction is completed.

reach 100 to 130 degrees F. The temperature will finally be about 50 degrees. Shrineage in the 4300-foot length of the dam will eggregate about 8 inches. Shrinkage aracks are produced artificially in the Coules Dam during construction.

They are made to occur at predetermined locations, and they are closed with grout.

This is accomplished by placing, on the surface of each 5-foot lift, 1-inch thin-well steel tubing, spaced

blocks by compression couplings. Dold river water is circulated through the cooling pipes, final cooling to 65 degrees F. being done in the winter. Into the thin cracks (3/25° ± in 50 feet) that open up between the blocks, grout of commut and water is pumped through a special system of piping embedded in the concrete. Copper gazakanana grout-strips prevent the excape of grout into galleries or elsewhere. Future expension will put the concrete under compression.

1

Totarnel temperatures are determined by means of resistance thermometers buried in the concrete, and connected with terminals in the inspection relleries. By means of Theatstone bridges, resdings are taken directly in degrees.

bearing to Deraletty

construction, containing aggregate up to 5 inches in size.

a minimum of one berrel of cament per yard, and water to c.600 feet, for containing water-cement ratio of one by volume, to congrate muitable for heavily relatoreed structures, containing aggregate of three-fourths inch maximum size, about one and a balf barrels of cament per yard, and mater to give a nice-tenths water-cement ratio, by relima. Minimum compression strengths acceptable are 8800 pounds for mass contracts and 5000 pounds for the structural grade. Strengths actually run 3600 to 5000 pounds. Slumps range from 8-1/2 to 4-1/2 inches.

Operated on each side of the river at elevation 1024, and construction of the base of the dan was carried on from both sides of the river. At that time, sand and gravel were carried to the west mixing plant by a 36-inch conveyor over a suspension bridge 3400 feet long. Cement for the east mixing plant crossed the river over the same bridge through an 11-inch pipe.

After the base of the dam was completed by the W.W.A.K. Company, the mixing plants were dismential, over-bauled, and reconstructed together on the east side of the river at elevation 1180 by the Consolidated Builders, Inc.

Such mixing plant includes, at the top, a bin for sand, four bins for gravel, and two bins for cement; below that, a weigh-bin and scale for each concrete component, including water; and on the next lower floor a swiveled shute and four four-yerd mixers, arranged about a conical delivery chute, centered above a railroad track over which concrete is delivered.

The mixing and moving of concrete is controlled by a dispatcher who receives his orders from the contractor's field office. By means of corresponding switches, he turns on lights on the batchers' signal boards on the weighing floors to indicate the kind and the number of batches of concrete required. With occasional exceptions, when grout or structural econcrete are required, the lamp boards are set for mass concrete.

Sestinations of special mixes are indicated to train operators by notes placed within their reach. Mass concrete is "peddled" from craze to orane until loads are disposed of, every effort being made to avoid any delay in placing concrete.

1

onerate component, including water, a weigh-bin suspended on a scale mechanism provided with 5 beams, which makes it possible to weigh out any one of five different mixes without shifting weights on the scale beams. By means of an air valve on his control board, the batcher selects the set of scale beams to make the mix he requires. By the movement of a second mir valve, the sir-operated gates over the weigh-bins are caused to open. Dercoid switches on the scale beams close the gates when the scales are balanced.

beigh-bias cannot be desped until the mixer operator has a mixer ready to receive a batch, shows the proper signal light on the batcher's board, and releases the lock on the air valve by means of which the batcher dumps the weigh-bias.

by means of time-controlled switches, cobbles and course gravel are dumped in the first 5 seconds of the 17-second mixer-charging period. Between the 4th and 12th second, cond, coment, and rine and intermediate gravel run simultaneously; and throughout the 17-second period, water flows into the mixer. During the charging period, controls on the mixer and the swivel chute are locked electrically.

the notions of weigh-bins and mixers. As bins are located, a pen swinging to the right records the weight of each component. Dumping is recorded as pens swing left. Wixer operations are recorded in curves which show concrete consistency as well as locating and dusping. A plactic batch is concentrated further back in a mixer than a stiff mix. This difference in the position of the center of gravity of the located mixer is recorded by means of heavy springs, a system of levers, and some solenoids connected with the air cylinders which dump the mixer. By comparing slump tosts with the curves drawn by the mechanism, the curves can be interpreted as indications of consistency.

1

The mixer operator controls the swivel chute by means of which the mixers are loaded, and the starting, stopping, and dumping of the mixers. Timing devices prevent the dumping of the mixers within two minutes after charging, and the moving of the servel chute or the dumping of the mixer during the 17-second charging period. No mixer center dumped until a trainmen signals that he is roady, and in so doing unlocks dumping controls.

Specifications provide, among other things, that the concrete shall be a "homogeneous made of uniform consistency such that the difference in the sand-dement or water-assent ratios between any two portions of any batch

shall not exceed 10 per cent." As originally built and operated, a 5-sinute mixing period was necessary; but as a result of experimental work of the contractor and the Eureau, the original sine blades in each 6-yard mixer were replaced by three simple blades, a definite order and period for loading concrete components into the mixers was fixed, and the mixing time was reduced to two minutes.

Limiting temperatures specified for comprete are a maximum of 85 degrees and minima of 40 degrees in moderate and 50 degrees in freezing weather.

A594-124

Approprie is obtained by the contractor from a send and gravel pit furnished by the government. Electric shovels, equipped with 7-yerd dippers, move the material from the face to as 13-inch grizzly over a feeder bin. Oversize is rejected, to be bauled by trucks to the primary crusher, and undersize material is carried away by a 60-inch conveyor belt system which consists of a stationary conveyor, extended from time to time as the pit developes, and a "pendulum" conveyor which feeds it. The pendulum conveyor is carried on a steel truss, one end of which is pivoted on a carriage astride the stationary conveyor, and the other cerried on tractor treads which support the feed hopper and grizzly. The pendulum conveyor arings through a half circle, enabling the shovels to cut a 350-foot swatch through the pit parellel to the stationary conveyor.

A large jew crusher in the gravel pit breaks down to a maximum of 10 inches all course enterial delivered by the belt system as well as boulders delivered to it by truck. A secondary crushing plant, containing two cylindrical troumels and two gyratory crushers, reduces all material to a maximum size of 5 inches.

Four large vibrating acreans take out cobbles (5" to 3") and coarse gravel (3" to 1-1/2"); and eight acreans separate the intermediate (1-1/2" to 3/4") and fine gravel (3/4" to 3/16") from the sand and wash water, which go to Dorr thickeners. They feed material under 100 mesh and wash actor to two large clarifiers, and sand to hydraulic classifiers.

40

Send is washed in three sizes -- 3/16" to 20-mesh, 20- to 43-mesh, and 48- to 100-mesh, and the three sizes are blanded to a fineness medalus of 2.5 to 3.0. About half the output of the pit goes to waste as surplus sand. The pit turns out 60,000 to 70,000 tons per day, and the seresaing and washing plant produces about 16,000 yerds of finished material.

Aggregate is moved from the processing plant to stockpiles near the dam over 43-inch conveyor belts, running 450 feet
per minute, at the rate of 2,000 to 2,700 tons per hour. The
movement is down grade, and it is consequently possible to use
here the longest single conveyor belt in the world -- 4,968 feet
between pulley axes -- eight 10-ton sections vulcanized on the
job into one endless band.

Near the dam, sand and gravel are stored in two rows of piles parallel to the tripper belt. Belt systems carry aggregate from tumpels under these stock piles up inclines to smell bins at the top of the mixing plant.

Cement is furnished by the government and may be of the standard, modified, or low-heat varieties, which differ chiefly in volume change and heat of hydration, which are progressively less in the three kinds of cement, in the order camed. In modified cement, and to a greater extent is low-heat cement, the percentage of tricalcium silicate is limited. The compounds of lime with alumina and with iron and alumina are also limited. Fineness is specified in terms of surface exposed, and must average 1906 of accordance square centimeters per spein and be not less than 1600 in any one sample.

The greater part of the cement has been produced in five of the six plants in Mashington, but shipments have been sade from one plant in Montena and three in Galifornia, also. The cement moves in bulk in boxcars assigned to the service. Deliveries have occasionally exceeded a hundred cars a day, and have averaged above 50 cars a day over long periods.

Cars are unloaded by means of Fuller-Kinyon portable pumps with remote control, each brand being delivered through a system of pipes to an assigned sile. Different brands are blended, in approximately the ratio in which they are furnished, before the cement is pumped to the mixing plants 6,800 feet away. A Fluxo system operates through a 14-inch pipe and a Fuller-Kinyon pump through an 3-inch pipe.

on this job. M.S.A.K. once made 9,290 yards in the sest mixing plant in 24 hours, and produced 15,344 yards in one day in the two plants. Available forms in which to place concrete limited that record. C.B.I. mixed and placed 20,684 yards on May 25, 1939, at an average rate of one yard in 4.18 seconds, a record unsurpassed saywhere. The average daily output in the fall of 1939 was about 15,000 yards requiring about 71 carloads of cament and the equivalent of 650 carloads of aggregate. M.M.A.K. placed a little over 4-1/2 million yards of concrete in the base of the dam and power house, and C.B.I. has placed more than 5 million yards. The total is to be about 11 million.

while the contractor is now occupied almost ontirely in processing aggregate, and mixing and placing concrete, the handling of the river is still a matter of importance, as is also the installation of trashracks, valves, and gates.

The original four diversion slots having been left open to the lavel of the river bed, it was necessary to close them at both ends before they could be built up after numerous other higher gaps had been left elsewhere in the spillway section of the base. N.F.A.K. built four arched timber gates about 54 feet square, loaded one end of each with concrete, and closed the gaps two at a time.

During seasons of high water, the river flows through numerous 50-foot gaps left low in the spillway section. As the water falls, the gaps are closed one after another, at the upper end, with 70-ton steel gates. Being above the downstream water-level, the gaps drain, and after cleaning are built up. The twenty 8-1/2-foot outlet tuenels at elevation 934 carry the fall and winter flow, and the entire spillway section can be built up without interruption by diversion activities.

Liners and valves for the uppermost set of 20 outlet tunnels, and eleven drum gates, 135 feet long and 23 feet high,

are the principal pieces of equipment yet to be idetalled by 0.8.1.

1

in the dam, 13 penstocks aggregating a mile in length. From steel plates, planed and curved in Chicago, 20-foot sections were rade up in a plant 2 miles from the dam. They are moved into place by means of flatours, trucks, a barge, a floating crane, and special facilities arranged in the tunnels. This job is communing 5.7 acres (8,000 tone) of steel plate, 23 tone of welding rod, and 11-1/2 miles of X-rey film for the testing of welding rod, and 11-1/2 miles of X-rey film for the testing

Installation of turbines and generators will begin in 1940, and, in case Congress makes the necessary appropriations, the dam, the base for the pumping plant, and west power house, with three large and two smell generating sets will be complete in 1948.

Ordinarily, reclassion projects are financed out of a revolving fund created by the sale of vesters land and western natural resources; and the fund is reimbursed by the beseficieries over a period of years, without interest.

This may be regarded as a subsidy, or as reinvesting, in the west, funds reclines from the sale of land or from western westing assets. As a subsidy, it has a precedent in the generous government support of highways, railroads, canals, ship operations, rivers and herbors improvements, and a variety of other activities which return neither interest nor capital.

1

Changed conditions in the west have made necessary the development of large, multi-purpose projects, such as Boulder Dam, which deprives the turbulent Colorado River of its destructive power and supplies water and power to southern Galifornia, and the Central Valley Project, which will conserve the spring flood waters of the Sacramento and Man Josquin Rivers, prevent flood damage and salt-water encroschment in the low lands, furnish power, and save irrigated districts now vanishing for west of water.

The revolving fund administered by the Euresu of Meclamation is far too small to finence such huge projects, and privets enterprise was long ago found inadequate to carry out
even the remaining larger reclamation works, notwithstanding
that it had irrigated 20 million seres in the west, so further
development of the arid west is dependent upon Congressional
appropriations to be fix refunded.

obviously, the precise total cost of the project cannot be determined because the greater part of the necessary excenditures remain to be sade over a period of 25 to 50 years. The estimated cost of the dem is \$119,000,000, and of the power plant \$67,000,000. It is probable that the total required financing will not exceed \$260,000,000, for income from the sale of power and from repayments by land-owners will finance the later development of the power plant and the greater part of the \$208,000,000 irrigation system.

The costs of the dem and power plant, and the cost of that part of the irrigation system not assessed against the landowners are to be repeid with interest. In the esa, the project will cost the government nothing, for the income from power sales will be far greater than the interest lost on the money advanced for the construction of a part of the project.

Until the project is much further edvanced, it will not be possible to determine propisely the per-sere cost of the irrigation works chargeable to landowners, nor the annual operation and maintenance cost.

at present, it is estimated that after meter is available the landowner will pay \$2.60 per acre per year for operation and maintenance of irrigation works, lacluding one dellar per acre per year for surplus power used in pumping. During the first four years after water is available, it is anticipated that no collections will be made on the construction account.

The construction charge is expected to be 385 to \$100 per scre. On that basis, the sattler would probably pay \$2.60 per scre per year for operation and maintenance and nothing on account of construction during the first 4 about years, then/\$4.60 per scre per year for construction, and operation and maintenance for 4 years, and finally about \$5.10 per scre per year for 32 years. Thereafter, only the charge for operation and maintenance would be paid.

The estimated annual output of firs power, available 2,100,000,000 at a uniform rate throughout the year, will be 3,200,000 k.w. hrs. Of the seasonal output of 4,200,000 k.w. hrs., generated largely during the susper, about 2-1/4 billion will ultimately be required for numbing irrigating aster from the storage reservoir to the belancing reservoir in the Grand Coules.

1

Financial estimates have been based on sales of firm power at 2-1/4 mills at the power plant, and on a charge of one dollar per more per year for power for pumping.

The Englet for Fower

The tree within which power can be distributed economically from Coulee Dem includes all of Bashington, the northern part of Bregon, northern Idaho, and western Montane.

Retween 1920 and 1920, power requirements in that territory increased at an average rate of 9.8 per cent per year, compounded sanually. Following a reduction of growth from 1930 to 1965, the rate of increase in demand since 1934 has exceeded the 1930-1930 rate.

from 8 per cent to 4 per cent in the next 30 years, and eliciting half of it to the Grand Coulec plant, the output of the plant would be absorbed in 15 years; and at 2-1/4 miles per kilomett hour, the cost of the dam and power plant would be liquidated in 50 years, with a surplus of \$144,500,000 to apply on the irrigation system. Thereafter, the annual surplus would be \$15,000,000.

Shen automobiles were first built, about 1900, businessmen of long experience were convinced that they would never cose into general use. About 1912 most expenseturers of automobiles were of the opinion that the actor car market was saturated, and that no future expension of the industry was possible. The annual production of automobiles now runs into millions; and the United States, with 15 per cent of the population, has 70 per cent of automobiles in the world.

People in general were not able to forceast the growth of markets for sutomobiles, telephones, airplanes, radios, wrist watches, and hundreds of other things unknown a few years or a

few decades ago, nor do they now realise the tremendous numbers of such things that would be required to supply all people, or even those in assrice, to the extent of the average use of them. Neither do they realize that America enjoys more of services and goods then does the rest of the world chiefly because energy from coal, cil, and waterpower is abundant and cheap in America. So long as there is an unsatisfied or a growing demand for services or manufactured goods, there will be a demand for additional supplies of power.

1

The average central station output per capita in the Saited States rose from 33 kilometts in 1900 to about 103 in 1910, and to about 850 in 1920. It is still growing. The consumption of electrical energy per capita, in both domestic uses and manufacturing activities, ranges from a small fraction of the average in some cases to many times the average in others. There is no means of knowing the limit to which the per capita use of electricity will go, but it is known that with the nation's reterpower fully developed the minimum use could not reach the present average use.

A large part of the output of the power plant at Coulee Dam will be used by the population of the area to be irrigated; and grant quantities will be used in metallurgical operations which will provide industry with magnesium, tungston, mangament, and other metals.

The Need for More land

Cur agricultural lands are shrinking. Natural forces and wasteful methods of farming are destroying each year more land than the Eureau of Reclamation has irrigated in the 36 years of its existence. Large areas throughout the country yield only a meager living for the occupants, and repeated droughts have driven 100,000 farm families off of semi-arid lands of the Great Plains. Sub-marginal lands are serious contributors to crop surpluses and crop deficits, and the National Resources Committee proposes to take out of cultivation 75,345,000 seres of land on which economical farming has been proved to be impossible, 40,464,300 acres in 17 western states. Only 10,000,000 seres of land economically irrigable remains in the fer-west states, and 50 to 100 years will be required to reclaim it.

Soil erosion, according to the Department of Agriculture, has impoverished or ruined 200,000,000 seres of once productive fare lands; and 10,000,000 seres of useful farm land is actively affected by erosion.

We import from countries of low buying power great quantities of agricultural products -- in 1935 the equivalent of the output of 72,461,118 American scree -- of butter and chasse, or of corn, or of sugar, or of tobacco slone, enough to use more land than is to be reclaimed by the Columbia Basin Project in the next 40 or 50 years.

The natural growth of population, and the need of farm homes for the growing younger generation of farmers, as well as for farm femilies from impoverished lands, will absorb irrigated land more rapidly then it can be developed.

Surplus Crops

The troublesome surplus crops are corn, hoge, wheat, cotton and tobacco, all products of hund-region fures. We have such surpluses, not because we could not consume them, but because many of our people cannot buy them.

4.

Cally one of them, wheat, is produced in any quentity in the for-west states. The irrigated lands produce sixth-tenths of one per cent of the country's wheat crop, only a third of the wheat consumed by their occupants. Most of the wheat produced in the far-west is grown on dry-farms, such of it on sub-marginal dust-bowl land. Such lands chrink and the western market for middle-west foodstuffs grows with the growth of irrigation.

Cotton is grown in some parts of the southwestern states, but only one-half of one per cent of the country's cotton versege is on Federal Irrigation Projects. The cotton production of the west fells far short of the cotton consumption of the west, which produces some long-staple cotton, of which there is no Surplus.

The west is only a consumer, not a producer of tobacco. It beys annually \$81,000,000 worth of tobacco and tobacco products; and pays to the government each year \$88,000,000 in tobacco teres-enough to pay for the Coulse Dam, the storage reservoir, and the west power plant in 8 years.

In the ten-year period from 1926 to 1935, middle-west hog growers and pork packers had an average annual income of \$123,000,000 from the western states. Mashington buys from the

buys a middle-west pork. The growth of the west rease the market for middle-west pork.

of corn, Minnesota produces 4 times as much, Illinois 3 times as much, and Iowa 12 times as much as the sleven western states combined. In recent years, Argentiae corn has been imported not only to the Pavific Coast but into Kensas City, on the edge of the corn belt.

The cleven western states buy great quentities of the middlewest surplus crops, and must always do so -- more as the western population increases for the west can never be agriculturally self sufficient. It has already one-tenth of the population and only one-twentieth of the grable land.

Standard Form No. 20 Approved by the President Nov. 19, 1926 (Rev. USBR Nov. 15, 1949) STANDARD GOVERNMENT FORM OF INVITATION FOR BIDS (CONSTRUCTION CONTRACT) DEPARTMENT OF THE INTERIOR Specifications No. R1-CB-70 BUREAU OF RECLAMATION Coulee Dam, Washington, July 31, 1950 SEALED BIDS, in single, subject to the conditions contained herein. will be received at Coulee Dam, Washington, until 11 a.m., Pacific Standard Time, August 31, 1950, and then publicly opened, for furnishing labor and materials and performing all work for removing construction railroad and miscellaneous structures, Coulee Dam Division, Columbia Basin Project, Washington. The work is situated between Grand Coulee Dam and Odair, Washington. The principal items of work and the estimated quantities involved are as follows: 30.7 track miles - Removing track and disposing of track materials; Lump sum - Moving stockpiled materials from Electric City yard; Lump sum - Removing bridges and trestles along railroad; Lump sum - Razing engine house, soal bunker and motor-car house; Lump sum - Moving pumphouse, sand house, oil house and office; Lump sum - Moving service pump and two steel storage tanks; Lump sum - Removing bridges along Secondary State Highway 2-F; Lump sum - Removing signs and posts along Secondary State Highway This invitation for bids does not cover the purchase of materials which are to be furnished by the Government. Materials to be furnished by the contractor and those furnished by the Government are described in the specifications which will be a part of the contract. The work shall be commenced within ten (10) calendar days after date of receipt of notice to proceed and shall be completed within two hundred (200) calendar days from the date of receipt of such notice. Liquidated damages for delay will be one hundred dollars (\$100) per day for each calendar day's delay. Partial payments will be made monthly. (See Article 16 of the contract.) Article on patents will be made a part of the contract. Bid bond .- Guarantee will be required with each bid in an amount not less than 10 per cent of the amount of the bid. Attention is called to Paragraph 8 of Instructions to Bidders (U. S. Standard Form No. 22) which

reads in part: "Where security is required to insure the execution of contract and bond for performance of the service, no bid will be considered unless it is so guaranteed."

Performance bond.—A performance bond will be required in the sum of one-half of the total amount payable by the terms of the contract.

Payment bond.—If the total amount payable by terms of the contract exceeds \$2,000 the payment bond shall be in the sum of one-half of the total amount payable by the terms of the contract.

All prospective bidders are hereby notified that, before any bid submitted in response to this invitation is considered for award, the Government may require the bidder to submit a statement of facts in detail as to the previous experience of the bidder in performing similar or comparable work and of the business and technical organization and financial resources and plant of the bidder available and to be used in performing the contemplated work. The Government expressly reserves the right to reject any bid on which the facts as to business and technical organization, plant, financial, and other resources, or business experience, compared with the work bid upon, justify such rejection.

The right is reserved, as the interest of the Government may require to reject any and all bids, to waive any informality in bids received, and to accept or reject any schedule of any bid, unless such bid is qualified by specific limitation.

Bids must be submitted upon the standard Government form of bid (Standard Form No. 21), and the successful bidder will be required to execute the standard Government form of contract for construction (Standard Form No. 23).

Envelopes containing bids must be sealed, marked, and addressed as follows:

SPECIFICATIONS NO. R1-CB-70
BID FOR REMOVING CONSTRUCTION
RAILROAD AND MISCELLANEOUS STRUCTURES
TO BE OPENED AT 11 A.M.
PACIFIC STANDARD TIME,
AUGUST 31, 1950

BUREAU OF RECLAMATION

COULEE DAM, WASHINGTON

(Sgd.) H. T. NELSON, Regional Director

Notes: See Standard Government instructions to bidders and copies of the standard Government forms of contract, bid bond, performance bond, and payment bond, which may be obtained upon application.

Copies of the standard forms and of the specifications may be obtained from the following offices of the Bureau of Reclamation: H. T. Nelson, Regional Director, Box 937, Boise, Idaho; F. A. Banks, District Manager, Coulee Dam, Washington. No charge for copies of the specifications and drawings furnished for bidding purposes; for all others \$0.25 per copy, not returnable.

Prospective bidders desiring to visit the site of the work should communicate with the District Manager.

UNITED STATES

DEPARTMENT OF THE INTERIOR

BUREAU OF RECLAMATION

REGION I

Schedule, Specifications, and Drawings

REMOVING CONSTRUCTION

RAILROAD AND

MISCELLANEOUS STRUCTURES

COULEE DAM DIVISION
COLUMBIA BASIN PROJECT, WASHINGTON

Bids will be received at the office of the Bureau of Reclamation, Coulee Dam, Washington, until ll a.m., Pacific Standard Time, August 31, 1950.

CONTENTS

Schedule Guaranty

SPECIFICATIONS

Genera	l Conditions:	Track	and track materials:
1.	Bonds	32.	Removal of railroad
2.	Climatic conditions	33。	Track materials to be salvaged
3.	Rights-of-way		Track materials not to be
	Quantities and unit prices		salvaged
	Staking out work	35.	
	Bench marks and survey stakes	36.	
	Data to be furnished by		from Electric City yard
	contractor		are and or are or are are are are are are are are are ar
8.	Sanitation	Remov	ing miscellaneous structures and
	Extras		rials:
	Cleaning up		Removal and disposition
	Patents and/or copyrights	38.	
	Protests	, , ,	and tanks
	Accident prevention	39。	Bridges, signs, and posts along
	Suspension of work	270	Secondary State Highway 2-F
741.257.0			booming bond Haginay 12-1
Specia	1 Conditions:		
15.	The requirement		
16.	Description		
17.	Drawings		
18.	Rates of wages		
	Labor statistics		
	Discrimination against employees	3	
	or applicants for employment		
	prohibited		
21.	Payments and funds		
	Commencement, prosecution, and		
	completion of work		
23.	Liquidated damages		
	Operation of railroad		
	Materials and equipment		
100	Construction equipment available	4	
W.S. Co.	for the contractor's use		
27.	Camp sites		
	Fire protection		
	Roads, interference with other w	ork	
	and safety of the public		
30.	Transmission, telegraph, and		
	telephone lines.		
31.	Investigation of the site		

REMOVING CONSTRUCTION RAILROAD

AND

MISCELLANEOUS STRUCTURES

COULEE DAM DIVISION COLUMBIA BASIN PROJECT, WASHINGTON

Bids will be considered on the following schedule, but no bid will be considered for only part of the schedule.

SCHEDULE

tem No.	Work or material	Quantity and price	Amount
1.	Removing track and disposing of track materials	30.7 track miles at	
		(words) (\$)per track mile	\$
2. Moving stockpiled materials from Electric City yard	For the lump sum of		
	biccoric croy yard	(words) dollars	
3.	Removing bridges and trestles along rail- road	For the lump sum of	
	1044	(words) dollars	-
40	Razing engine house, coal bunker and motor-car house	For the lump sum of	
	mo oor dar modad	(words) dollars	

SCHEDULE (Continued)

Item No.	Work or material	Quantity and pri	ce	Amount
5.	Moving pump house, sand house, oil house, and office	For the lump sum of		
		(words)	dollars	\$
6.	Moving service pump, and two steel stor- age tanks	For the lump sum of		
		(words)	dollars	CONTRACTOR DATES
7.	Removing bridges along Secondary State Highway 2-F	For the lump sum of		
	inging sol	(words)	dollars	
8.	Removing signs, and posts along Second- ary State Highway 2-F	For the lump sum of	and the second	
		(words)	dollars	
		TOTAL FOR SCHEDULE		\$

GUARANTY

	It is hereby guaranteed that in the event award is made to the
unde	ersigned, all articles, materials, and supplies used will conform to
the	article "Domestic preference" of the contract, except as noted below:
-	
-	

	The cost of the articles, materials, and supplies listed above will
be	per cent of the total cost of all of the articles,
mate	erials, and supplies used.

SPECIFICATIONS GENERAL CONDITIONS

1. Bonds. The contractor shall furnish bonds as follows:

(a) Performance bond.—The performance bond shall be furnished in accordance with the following table:

Amount of contract

Up to \$ 1,000,000

\$ 1,000,000 to \$ 5,000,000

\$ 5,000,000 to \$ 10,000,000

\$ 5,000,000 to \$ 25,000,000

Not less than 40 percent of contract

Not less than 30 percent of contract

\$ 10,000,000 to \$ 25,000,000

Not less than 20 percent of contract

\$ 25,000,000 and over

\$ 5,000,000

Bonds in amounts of \$1,000 or less will be made in multiples of \$100; in amounts exceeding \$1,000 but not exceeding \$5,000, in multiples of \$500; in amounts exceeding \$5,000, in multiples of \$1,000: Provided, That the amount of the bond shall be fixed by the contracting officer at the lowest sum that fulfills all conditions of the contract.

(b) Payment bond.—If the amount of the contract exceeds \$2,000, the contractor shall furnish to the United States, in addition to the bond required under (a) hereof, a payment bond with a surety or sureties satisfactory to the officer awarding the contract, for the protection of all persons supplying labor and material in the prosecution of the work provided for in the contract, for the use of each such person. Whenever the total amount payable by the terms of the contract shall be not more than \$1,000,000, the payment bond shall be in the sum of one-half of the total amount payable by the terms of the contract. Whenever the total amount payable by the terms of the contract shall be more than \$1,000,000 and not more than \$5,000,000, the payment bond shall be in the sum of 40 percent of the total amount payable by the terms of the contract. Whenever the total amount payable by the terms of the contract. Whenever the total amount payable by the terms of the contract shall be more than \$5,000,000, the payment bond shall be in the sum of \$2,500,000.

2. Climatic conditions. The contracting officer may order the contractor to suspend any work that may be subject to damage by climatic conditions.

3. Rights-of-way. The Government will provide the right-of-way or the site forpermanent works or installations, the site for borrow pits, channels, spoil banks, and ditches, and right-of-way for access thereto over routes established by the contracting officer. The contractor will be permitted to use such land for construction purposes, but any additional right-of-way or land desired by the contractor for construction purposes shall be provided by the contractor without expense to the Government.

4. Quantities and unit prices. The quantities noted in the schedule are approximations for comparing bids, and no claim shall be made against the Government for excess or deficiency therein, actual or relative. Payment at the prices agreed upon will be in full for the completed work and will cover materials, supplies, labor, tools, machinery, and all other expenditures incident to satisfactory compliance with the contract, unless otherwise specifically provided.

5. Staking out work. The work to be done will be staked out for the contractor who shall, without cost to the Government, provide such material and give such assistance as may be required by the contracting officer.

6. Bench marks and survey stakes. Bench marks and survey stakes shall be preserved by the contractor, and in case of their destruction or removal by him or his employees, they will be replaced by the contracting officer at the contractor's expense, and his sureties shall be liable therefor.

7. Data to he furnished by contractor. The contracting officer, through his authorized agents, shall have access to all pay rolls, records of personnel, invoices of materials, and any and all other data relevant to the performance of the contract or necessary to determine its cost, and the contractor shall furnish at the end of each month an itemized statement in a form satisfactory to the contracting officer of the cost of all work under the contract.

8. Sanitation. The contracting officer may establish sanitary and police rules and regulations for all forces employed under this contract, and if the contractor fails to enforce these rules the contracting officer may enforce them at the expense of the contractor.

9. Extras, The contractor shall, when ordered in writing by the contracting officer, perform extra work and furnish extra material, not required by the specifications or included in the schedule, but forming an inseparable part of the work contracted for. Extra work and material will ordinarily be paid for at the lump-sum or unit price stated in the order, Whenever, in the judgment of the contracting officer, it is impracticable, because of the nature of the work or for any other reason to otherwise fix the price in the order, the extra work and material shall be paid for at the actual necessary cost as determined by the contracting officer, plus an allowance, not to exceed 10 percent of such

actual necessary cost of the extra work and materials, for superintendence, general expense, and profit. The actual necessary cost will include all reasonable expenditures for material, labor (including compensation insurance and social security taxes), and supplies furnished by the contractor, and a reasonable allowance for the use of his plant and equipment, where required, but will in no case include any allowance for office expenses, general superintendence, or other general expenses.

- 10. Cleaning up. Upon completion of the work the contractor shall remove from the vicinity of the work all plant, buildings, rubbish, unused materials, concrete forms, and other like material, belonging to him or used under his direction during construction, and in the event of his failure to do so the same may be removed by the Government at the expense of the contractor, and his surety or sureties shall be liable therefor.
- 11. Patents and/or copyrights. The contractor shall hold and save the Government, its officers, agents, servants, and employees, harmless from liability of any nature or kind, including costs and expenses, for or on account of any copyrighted or uncopyrighted composition, secret process, patented or unpatented invention, article, or appliance manufactured or used in the performance of this contract, including their use by the Government, unless otherwise specifically stipulated in this contract. Any patented invention the use of which by these specifications is required, or permitted in the alternative to be used, and which the United States has the right to use, royalty free, shall be available to the contractor without the payment of royalty.
- 12. Protests. If the contractor considers any work demanded of him to be outside of the requirements of the contract, or considers any record or ruling of the contracting officer or of the inspectors to be unfair, he shall immediately upon such work being demanded or such record or ruling being made, ask, in writing, for written instructions or decision, whereupon he shall proceed without delay to perform the work or to conform to the record or ruling, and, within twenty (20) calendar days after date of receipt of the written instructions or decision (unless the contracting officer shall grant a further period of time prior to commencement of the work affected) he shall file a written protest with the contracting officer, stating clearly and in detail the basis of his protest. Except for such protests as are made of record in the manner herein specified and within the time limit stated, the records, rulings, instructions, or decisions of the contracting officer shall be final and conclusive. Instructions and/or decisions of the contracting officer contained in letters transmitting drawings to the contractor shall be considered as written instructions or decisions subject to protest as herein provided.
- Accident prevention. The contractor shall, at all times, exercise rea sonable precautions for the safety of employees in the performance of this contract, and shall comply with all applicable provisions of Federal, State, and municipal safety laws and building and construction codes. The contractor shall also comply with the provisions of the Safety Handbook of the Bureau of Reclamation (Volume XII of the Bureau Manual) as approved by the Commissioner and in effect on the date of award of contract, so far as applicable, as determined by the contracting officer and unless such instructions are incompatible with Federal, State, or municipal laws or regulations. Monthly reports of all lost-time accidents shall be promptly submitted giving such data as may be prescribed by the contracting officer. Nothing in this paragraph shall be construed to permit the enforcement of any laws, codes, or regulations herein specified by any except the contracting officer.
- 14. Suspension of work. The Government may at any time suspend the whole or any portion of the work under this contract but this right to suspend the work shall not be construed as denying the contractor actual, reasonable, and necessary expenses due to delays, caused by such suspension, it being understood that expenses will not be allowed for such suspensions when ordered by the Government on account of weather conditions or on account of the failure of Congress to make the necessary appropriations for expenditures under this contract.

SPECIAL CONDITIONS

- 15. The requirement. It is required that there be completed, in accordance with these specifications and the drawings listed in paragraph 17 hereof, the removal of 30.7 miles of standard-gage railroad track, stock-piled track materials, bridges, buildings, and miscellaneous structures. The work is situated between Grand Coulee Dam and Odair, Washington, as shown on the Location Map.
- 16. <u>Description of the work</u>. The principal components of the work to be done under these specifications include the following:
- (a) The removal and disposal of approximately 30.7 track miles of standard-gage railroad track with appurtenances.
- (b) The moving of stockpiled track materials from Electric City yard.
 - (c) The moving of a service pump and two steel storage tanks.
 - (d) The razing of three buildings.
 - (e) The moving of four buildings.
- (f) The removal and disposal of 13 timber railroad bridges and three timber highway bridges.
- (g) Removal and disposal of signs and posts along existing Secondary State Highway $2-F_{\circ}$ which highway is to be abandoned.
- 17. <u>Drawings</u>. The following drawings are made a part of these specifications:

1.	222-D-1901	Location Map
2.	222-117-11511	USBR Construction Railroad-Location Map
3.	222-117-11512	Grand Coulee Dam-Vicinity Map
4.	222-117-11513	USBR Construction Railroad-Siding and

The contractor will be furnished such additional copies of the specifications and drawings as may be required for carrying out the work. Contact prints of the original drawings from which the attached reproductions were made will be furnished to the contractor for construction purposes upon request.

18. Rates of wages. Pursuant to the provisions of the Davis-Bacon Act, as amended (49 Stat. 1011; U.S.C. ti. 40, sec 276(a)), the Secretary of Labor has determined that the following rates of wages are the prevailing rates of wages for the classifications specified in the locality of the work covered by these specifications, and said rates of wages shall be the

minimum rates per hour to be paid for the work covered by these specifications?

Classification	Rate per hour
Air tool operator (jackhammermen, vibrator)	\$1.70
Electricians	
1st 6 months 40% of journeymen's rate	
2nd 6 months 45% of journeymen's rate	
3rd 6 months 50% of journeymen's rate	
4th 6 months 55% of journeymen's rate	
5th 6 months 60% of journeymen's rate	
6th 6 months 65% of journeymen s rate	
7th 6 months 75% of journeymen's rate	
8th 6 months 90% of journeymen's rate	
	1.60
General laborers	o o 1,000
Bulldozer, tractor, carry-all (including tandem)	2.15
Compressors, one only (portable)	1.75
Derrick and pile drivers	2.35
Firemen	1.80
Heavy duty mechanic or welder	2.15
Hoist, one drum (heavy construction)	1.90
Hoist, two or more drums (heavy)	2.10
Oilers, mechanic helpers	1.70
Power shovels and shovel-rigged machines (cranes,	
clamshells, etc.)	2.35
Power shovels, 4 yds. and over (factory rating)	2.70
Wheel-type tractor	1.75
Truck drivers:	
Flat bed trucks	1.65
Service and supply trucks	1.65
Dump trucks:	1 70
Including 6 yds	1.70
Over 6 yds. and including 8 yds	1.80
Over 12 yds. and including 20 yds	1.90
Over 20 yds	2.15
	0 0 601)

The wage rates contained in this decision are straight hourly wage rates. In some areas, management and labor organizations in the construction industry have collectively bargained for health and welfare fund contributions. Such contributions are not included in wage rates determined by the Secretary of Labor for construction projects.

Apprentices employed pursuant to this determination of wage rates must be registered in a bona fide apprenticeship program registered with a State apprenticeship agency recognized by the Federal Committee on Apprenticeship, U. S. Department of Labor; or if no such recognized agency exists in a State, it shall mean a program registered with the Federal Committee on Apprenticeship, Bureau of Apprenticeship, U. S. Department of Labor.

Any class of laborers and mechanics not listed above, which will be employed on this contract, shall be classified or reclassified conformably to the foregoing schedule. In the event the interested parties cannot agree on the proper classification or reclassification of a particular class of laborers and mechanics to be used, the question, accompanied by the recommendation of the contracting officer, shall be referred to the Secretary of Labor for final determination. While the wage rates shown are the minimum rates required by these specifications to be paid during the life of the contract, it is the responsibility of bidders to inform themselves as to local labor conditions such as the length of workday and workweek, overtime compensation, health and welfare contributions, labor supply, and prospective changes or adjustments of wage rates. No increase in the contract price will be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

19. <u>Labor statistics</u>. It is requested that the bidder agree to comply with the provision of the following clause:

"The contractor will report monthly, and will cause all subcontractors to report in like manner, within 5 days after the close of each calendar month, on forms to be furnished by the Department of Labor, the number of persons on their respective pay rolls, the aggregate amount of such pay rolls, the man hours worked, and the total expenditures for materials. He shall furnish to the Department of Labor the names and addresses of all subcontractors on the work at the earliest date practicable. The foregoing is applicable only to work at the site of the construction project."

20. Discrimination against employees or applicants for employment prohibited. The contractor shall not discriminate against any employee or applicant for employment because of race, creed, color, or national origin and shall require an identical provision to be included in all subcontracts.

- 21. Payments and funds. Special provisions relating to payments and funds are as follows:
- (a) Section 12 of the Reclamation Project Act of 1939 provides as follows: "When appropriations have been made for the commencement or continuation of construction or operation and maintenance of any project, the Secretary may, in connection with such construction or operation and maintenance, enter into contracts for miscellaneous services, for materials and supplies, as well as for construction, which may cover such periods of time as the Secretary may consider necessary but in which the liability of the United States shall be contingent upon appropriations being made therefor" (43 U.S.C. 388).
- (b) Under the contract to be entered into under these specifications, the liability of the United States is contingent on the necessary appropriations and reservation of funds therefor.
- (c) When funds become available for payment for contractor's earnings, including percentages to be retained and payable when due (hold-backs), the Government will notify the contractor of the sum that has been reserved and is available for that purpose.
- (d) If at any time it becomes apparent to the contracting officer that the balance of this reservation is in excess of the estimated amount required to meet all payments due and to become due the contractor because of work performed or to be performed until June 30, 1951, the right is reserved to reduce said reservation by the amount of such excess. The contractor will be advised of any reduction so made.
- (e) If the rate of progress of the work is such that it becomes apparent to the contracting officer that the balance of the reservation is less than the estimated amount required to meet all payments due and to become due because of work performed until June 30, 1951, the Government may reserve additional funds for payments under this contract if there be funds available for such purpose. The contractor will be advised of any additional reservation so made.
- (f) It is expected that Congress will make appropriations applicable to work under this contract, but as to this it must be distinctly understood and agreed that the Government is in no case to be made liable for damages in connection with this contract on account of delays in payments on same due to a lack of available funds. Should it become apparent to the contracting officer that available funds will be exhausted before additional funds are appropriated, the contracting officer will give 30 days written notice to the contractor that work may be suspended by the contractor, but if the contractor so elects, he may continue work under the conditions and restrictions of the specifications, after the time set by such notice, so long as there are funds for inspection and superintendence, concerning which he will be advised, with the understanding, however, that no payment will be made for such work until sufficient additional funds have been provided by the Congress. When funds again become available, the contractor will be notified in writing as to the

amount thereof reserved for payments under this contract. The amount so reserved shall be subject to decrease or increase in a manner similar to that provided in subparagraphs (d) and (e) hereof. Should work be thus suspended, additional time for completion will be allowed equal to the period during which the work is necessarily so suspended as determined by the dates specified in the above-mentioned notices.

- (g) So long as funds are available, payments will be made in accordance with the provisions of the contract. Unless otherwise authorized in writing by the contracting officer, the items of work for which payment will be made shall be limited to those listed and enumerated in the contract. The unit or lump-sum price or prices stated in the contract will be used in determining the amount to be paid and shall constitute full and final compensation for all work.
- (h) The procedure above described in this paragraph shall be repeated as often as necessary on account of exhaustion of available funds and the necessity of awaiting the appropriation of additional funds by Congress.
- (i) Should Congress fail to provide additional funds during its regular session as expected, the contract may be terminated and considered to be completed at the option of the contractor, without prejudice to him, at any time not later than 30 days after payments are discontinued, or, if payments have been previously discontinued, not later than 30 days after passage of the Act which would ordinarily carry an appropriation for continuing the work or after the adjournment of Congress without passing such Act.
- 22. Commencement, prosecution, and completion of work. The contractor shall begin work within ten (10) calendar days after date of receipt of notice to proceed and shall complete all of the work within two hundred (200) calendar days from the date of receipt of such notice: Provided, That the period allowed for completion of the work shall be reduced by one (1) calendar day for each calendar day of delay in excess of ten (10) calendar days, or any extension thereof, in returning properly executed contract, performance and payment bonds as required in U.S. Standard Form No. 21 (Rev. 4/6/50).

A commitment has been made to the Washington State Highway Department that the railroad crossing of Secondary State Highway 10-B, West of Grand Coulee, will be removed by October 15, 1950, in order to accommodate the surfacing program for that highway. The work shall be prosecuted in such a manner that all materials are removed from the right-of-way for this crossing by the date specified above unless other arrangements are made by the contractor with the State Highway Department. In the event notice to proceed is not issued prior to October 3, 1950, the contractor will not be required to perform this work and the track crossing will be removed by others.

Removal of bridges and signs from the existing Secondary State Highway 2-F will not be permitted until the relocated Highway 2-F is open for public travel. If the relocated Highway 2-F is not open for public travel within 170 calendar days from receipt by the contractor of notice to proceed, the contractor will not be required to remove the bridges and signs.

Capacity of the contractor's equipment, sequence of operations, method of operations, forces employed shall, at all times during continuance of the contract, be subject to approval of the contracting officer and shall be such as to insure completion of the work within the specified period of time.

- 23. <u>Liquidated damages</u>. The contractor shall pay to the Government, as fixed, agreed, and liquidated damages, the sum of one hundred dollars (\$100) per day for each calendar day's delay.
- 24. Operation of Railroad. Operation of the railroad will be permitted only for removal of materials under these specifications. Hauling of freight will not be permitted.
- 25. Materials and equipment. The contractor will be required to furnish all labor, materials and supplies, and all equipment except as provided in paragraph 26, necessary for completing the work.
- 26. Construction equipment available for the contractor's use. Various items of government-owned construction equipment, as listed below are available for the contractor's use only on work to be performed under these specifications. The Government will assume no responsibility for the condition of the equipment, or for the capacity of the items of construction equipment or for their adaptability to the work to be performed. Prospective bidders shall inspect the equipment. The contractor shall submit a written request to the contracting officer for the equipment within 20 days after the date of notice to proceed, and the items of equipment will be turned over to the contractor for his use by written order from the contracting officer. Upon receipt of such written order from the contracting officer, the contractor shall immediately accept the equipment and assume its operation and maintenance. The contractor may at any time during the continuation of the contract return any equipment to the Government subject to the provisions of this paragraph: Provided, That any equipment so returned will not again be made available for use by the contractor. The contractor shall furnish the necessary operators and maintenance personnel who are satisfactory to the contracting officer. Fuel, lubricants, and other operational supplies shall be furnished by the contractor, and the cost of all maintenance shall be borne by the contractor. The Government shall have the right to make such inspections of the equipment as to its use, maintenance, storage, and protection facilities afforded by the contractor as the contracting officer may deem necessary, and may demand the immediate return of such equipment to the Government for failure to comply with the requirements of this paragraph as determined by the contracting officer. The contractor shall not remove any of the equipment from the site of the work without the written approval of the contracting officer. The equipment made available to the contractor by the Government shall remain the property

of the Government, and upon completion of the work under this contract all Government-owned equipment remaining in possession of the contractor shall be returned to the Government at the Odair terminal in the same condition as received, reasonable wear and tear excepted. No charge will be made to the contractor for the use of the items of construction equipment listed in this paragraph. On all work to be done under extra work orders, the contractor shall use Government-owned construction equipment. where available and suitable as determined by the contracting officer, and no payment will be made for rental or for maintenance of Governmentowned equipment. Payment for work done under extra work orders will exclude any charge with regard to rental or for maintenance of Governmentowned equipment. The contractor hereby releases and agrees to indemnify and hold harmless the United States, its officers, agents, and employees on account of all damage or claims for damage by whomsoever made, and of any nature whatsoever arising out of or in any manner connected with the Government's furnishing of the equipment as provided in this paragraph. The contractor shall perform any and all repairs and shall make all replacements as may be required at his own expense to keep the equipment in first-class operating condition, as determined by the contracting officer.

Inventory of equipment available for contractor's use:

- (1) 1 Locomotive, G. E. Diesel-electric, 65 ton, 400 hp, USBR No. 4620.5.
- (2) 1 Crane, locomotive, Industrial Brown Hoist Model 7, 30-ton cap. with a 50-ft. boom, USBR No. 1976.1.
- (3) 1 = Motor car, USBR No. 1220.1
- (4) 1 Flat car, USBR No. 1210.1
- (5) 1 Flat car, USBR No. 1210.2
- (6) 1 Flat car, USBR No. 1210.4
- (7) 1 = Push car, USBR No. 1215.2

27. Camp sites. The contractor will be permitted to use for construction plant and storage purposes such land that is the property of the Government, as is designated by the contracting officer: Provided, That such use shall not interfere with any part of the work or of the work of other contractors or of the Government in the vicinity. If private land is used by the contractor for residential camp, construction plant, or other construction purposes, the contractor shall make all necessary arrangements with the owner and shall pay all rentals or other costs connected therewith. The location, construction, maintenance, operation, and removal of the contractor's construction plant and storage facilities shall be subject to approval of the contracting officer.

- 28. Fire protection. All burning shall be subject to the regulations and precautions prescribed by the State Fire Marshal and no fire or other burning operation shall be left unguarded or unattended at any time. The contractor shall at all times take special precaution to prevent fire from spreading to the area outside of the limits of the work sites and shall be liable for any damage inside or outside the work sites caused by his burning operations. The contractor shall have available at all time suitable materials and supplies for use in preventing and suppressing fires.
- 29. Roads, interference with other work, and safety of the public. Access to the work from existing roads shall be provided by the contractor. No payment will be made to the contractor by the Government for any work done in constructing, improving, repairing, or maintaining any road or structure thereon for use in the performance of the work under these specifications. The Government assumes no responsibility for the condition or maintenance of any road or structure thereon that may be used by the contractor in performing the work under these specifications or in traveling to and from the site of the work. Roads subject to interference by the work shall be kept open or suitable detours shall be provided by the contractor. During the period of time covered by this contract, the Government and others may be engaged in other construction work in the vicinity of the work covered by these specifications. The contractor shall arrange and prosecute the work under these specifications so as not to interfere with other work or with existing improvements. The contractor shall not obstruct traffic unnecessarily and shall cause as little inconvenience as possible to occupants of abutting property and to the general public. The contractor shall provide, erect, and maintain all necessary barricades; suitable and sufficient red lights, danger signals, and signs; and shall take all necessary precautions for the protection of the work and the safety of the public. Roads closed to traffic shall be protected by effective barricades on which shall be placed acceptable warning and detour signs. All barricades and obstructions shall be illuminated at night, and all lights shall be kept burning from sunset until sunrise. The cost of all work required by this paragraph shall be included in the prices bid in the schedule for the various items of the work.
- 30. Transmission, telegraph, and telephone lines. The contractor shall make all necessary or required provisions and shall perform all work required by his operations under the contract and incident to any interference with the transmission, telegraph, and/or telephone lines, with their operation, or with the maintenance of traffic or service thereon, all in a manner satisfactory to the owners or operators thereof and to the contracting officer. The cost of providing and maintaining all necessary or required watchmen, signals, guards, and temporary structures; of making any necessary repairs, replacements, or similar operations; of furnishing indemnity or other bonds, if required; and of all or any other costs required by this paragraph shall be paid by the contractor and shall be included in the prices bid in the schedule for other items of work.

31. Investigation of the site. Bidders shall visit the site of the work and by their own investigations, shall satisfy themselves as to the existing conditions affecting the work to be done under these specifications. Bidders and the contractor shall assume all responsibility for deductions and conclusions as to the difficulties in performing the work.

TRACK AND TRACK MATERIALS

- 32. Removal of Railroad. (a) Removal.—The contractor shall remove all track and track materials from the construction railroad to be removed under this contract. Removal of track materials shall include removal of spare rails located along the construction railroad for emergency use, spare rail stands, road crossings, sign posts, appurtenant railroad equipment, and 4 cattle guards. The cattle guards are located 2 each near stations 63/61 and 161/00. Materials to be salvaged shall be removed without damage. All component parts of the track except frogs, switches and switch stands, shall be completely disassembled. Metal parts to be salvaged shall be reasonably free of dirt and foreign matter. After the track materials have been removed from within the town of Grand Coulee, the roadbed shall be graded so as to leave it neat and sightly. After cattle guards have been removed, fences similar to those attached to the cattle guards shall be built across the right-of-way.
- (b) Measurement and payment.—Measurement for payment for removing track and disposing of track materials will be made along the center line of track in place, through switches and cross—overs, to the center lines of intersecting tracks, and to the nearest one—hundredth of a mile. Payment for removing track and disposing of track materials will be made at the unit price per track mile bid therefor in the schedule, which price shall include all cost of removing materials, including spare rails, cattle guards and appurtenant materials; of burning, cleaning, separating, handling, stockpiling, and loading materials as required by these specifications; of grading road bed; of repair and maintenance of road crossings; of constructing fences; and of all other work connected with removal and disposal of track materials from the existing railroad.
- 33. Track materials to be salvaged. (a) Track materials to be loaded on cars at Odair.—The materials listed below are to be delivered ready for shipment on railroad cars at Odair, Washington. The Northern Pacific Railroad Company has agreed to furnish the railroad cars that will be required, but all arangements for procurement, loading, and use of these cars shall be made by the contractor. Any demurrage or other expense connected with use of the cars shall be paid by the contractor. Cars shall be loaded so that each kind and class of material will be separate, and in a manner that will be acceptable to the railroad. Ties, other than those to be stockpiled as provided in subparagraph 33 (c), may be used to side—board cars on which track fastenings are to be loaded: Provided That such side—boarding and loading is acceptable to the railroad. Transportation of loaded cars from Odair will be at the expense of others.

Material

Quantities

All available up to the following:

90-pound rail	365,716	lin. feet
72-pound rail	1,316	lin. feet
No. 11 Frogs, 90-1b., with 162-ft. spring rail	6	
No. 9 Frogs, 90-lb., with 15-ft. spring rail	4	
Split Switches, compromise, 162-ft., 90-lb.	17	
High Banner Switch Stands	8	
Low Banner Switch Stands	9	
Switch Stand connecting Rods	17	
Guard rails, 90-lb., compromise	18	sets
Guard Rail Clamps	1	
Guard Rail Base Plates	20	sets
Angle Bars, 90-lb., common	12,130	pairs
Angle Bars, 72-1b., common	72	pairs
Tie Plates, 90-lb.	27,564	
Bolts, track, for 90-lb. Rail	720	

⁽b) Materials to be stockpiled at Coulee Dam, Washington.—The requirements for track materials listed under subparagraph (a) above shall have first consideration. Insofar as possible, the materials listed below are to be placed in stockpiles at the Salvage Yard located north of the Coulee Dam Industrial Area as shown on Drawings No. 3 (222-117-11512).

Material

Quantities

All available up to the following:

90-lb. rail

6,930 lin. feet

No. 9 Switches, 90-lb. complete with Switch-stands

3

Tie Plates for 90-lb. rail

3,250

Spikes

7,000

- (c) Bonneville ties.—All ties from the Bonneville Spur as shown on the drawing shall be salvaged and stockpiled on the right-of-way at one end of the spur.
- (d) Materials to be stockpiled at Odair Yard.—All remaining metal track materials, other than track bolts and spikes, not listed under (a) or (b) above, shall be stockpiled at Odair Yard. Component parts and accessories shall be stockpiled separately. Stockpiles of track fittings shall be placed on wooden platforms provided by the contractor. Ties obtained from track removal may be used for these platforms.
- 34. Track materials not to be salvaged. All materials not to be salvaged shall become the property of the contractor and shall be removed from Government property, or may be disposed of as follows:
 - (1) Track bolts and spikes may be left on the right-of-way in the reservoir area below elevation 1570.
 - (2) Combustible materials not to be salvaged, such as ties (all ties except as provided in paragraph 33), piling, sign posts, bridge timbers, cattle guards, and other wooden pieces may be burned. All material burned shall be completely consumed. Any charred pieces remaining shall be reburned until completely consumed, or shall be removed from Government property. Burning shall be subject to approval of the contracting officer and in accordance with paragraph 28.
- 35. Repair of highway crossings. After the railroad crossing at U. S. Highway No. 2 near Coulee City has been removed, the highway shall be repaired and resurfaced. Replacement of subgrade and shoulders shall be performed so as to make the patched area the same as adjacent subgrade and shoulders, and the surface course shall be the same as the surface course on the highway. The new surface material shall be placed so as to make a smooth continuous road surface across the railroad right-of-way. Highway 2-F crossings from which track has been removed, shall be filled, graded, and maintained in a good, safe condition approved by

the contracting officer until the new Highway 2-F is open to public travel. Other road crossings shall be filled and graded to form a serviceable roadway. Ballast material from the railroad right-of-way may be used for repair of highway crossings.

36. Moving stockpiled materials from Electric City Yard. All railroad materials, including metal parts and ties, stockpiled along the north side of the main line track between approximate stations 1415/00 and 1425/00 in the Electric City Yard shall be moved by the contractor. The stockpiled materials contained in the yard at time of advertisement for bids will be augmented by the addition of the rails, angle bars, tie plates, and switch materials from approximately 0.25 mile of an existing spur track located east of the North Coulee Dam. This additional material from the spur track will be stockpiled in the above described area by others in time to avoid delay in removal of stockpiled material. Disposition of the stockpiled material shall be made as provided in paragraphs 33 and 34. The contractor shall give the contracting officer ten (10) days' notice in writing before removal of stockpiled material is commenced. Payment for moving and disposing of materials as described above will be made at the lump sum price bid in the schedule for moving stockpiled materials from Electric City Yard, which price shall include all cost of moving, loading, separating, stockpiling, and removing or destroying all materials described in this paragraph.

REMOVING MISCELLANEOUS STRUCTURES AND MATERIALS

- 37. Removal and disposition. (a) Removal.—The contractor shall remove structures and materials as listed in the following paragraphs, including concrete floors and concrete footings for buildings, but not the engine pit. All service lines to tanks and buildings such as air, water, sewer, oil and electrical conduits shall be cut and plugged or capped so as to be water tight. The plug or cap on water lines shall be not less than 3 feet underground, and on others not less than 1 foot underground. All holes including the engine pit shall be filled with earth or gravel obtained from the adjacent area.
- (b) Disposal.—The pump house, sand house, oil house, and office and the oil pump and storage tanks shall be moved without dismemberment. Other materials removed shall become the property of the contractor and shall be removed from Government property, or may be disposed of as follows:

- (1) Concrete from floor and footings of buildings razed or moved may be hauled to the disposal site near the sawmill south of the Industrial Area.
- (2) Other non-combustible material may be deposited in the Brett Canyon Yard.
- (3) Combustible material may be burned as provided in paragraph 34.
- 38. Railroad bridges, buildings, and tanks. (a) Removing bridges and trestles along railroad.—The contractor shall remove all combustible materials in bridges and trestles along the railroad. All wood piling shall be cut off within 6 inches of the ground surface, or water surface, at time of cutting. Some of the bridge bents rest on timber mud sills, timber mats, or sleepers, which may be buried or partly buried, and the contractor will be required to remove all such sills, mats, sleepers, or other buried or partly buried combustible material.

Railroad Bridges and Trestles

Railroad station	Number spans	Approximate length in feet
125/25 420/00 463/86	2 8	31
463486	4	71 61
520≠00 740≠20 801≠47	5	76
801/47	4 2	61 31
978/50 1044/50 1089/00	2	31 106
1089/00	7 8	76
1175/00	2 2	31
1225/00 1286/00 1325/00	2 2	31 31 31
2,2,700	~	7

Payment for removing bridges and trestles along railroad will be made at the lump sum price bid therefor in the schedule, which price shall include all cost of removal and disposition.

(b) Razing engine house, coal bunker, and motor-car house. -- The contractor shall remove the buildings listed below:

Engine house - - - - Approximately 43 x 72 feet, 35 feet high Coal bunker - - - - Approximately 16 x 46 feet, 13 feet high Motor-car house - - - Approximately 14 x 20 feet, 12 feet high

Payment for razing engine house, coal bunker, and motor-car house, will be made at the lump sum price bid therefor in the schedule, which price shall include all cost of removal, disposition, and filling of holes.

(c) Moving pump house, sand house, oil house, and office.—The contractor shall lift structures listed below from their foundations, transport them to the Brett Pit Yard, and place each structure in an upright position on timber blocking at sites designated by the contracting officer. The structures shall be handled carefully and the entire moving operation shall be conducted so as to insure no physical damage to the structures.


Pump house - - - - - - Approximately 12 x 16 feet, 10 feet high Sand house - - - - - - Approximately 10 x 12 feet, 10 feet high Oil house - - - - - - - Approximately 10 x 12 feet, 10 feet high Office - - - - - - - - Approximately 14 x 20 feet, 12 feet high


Payment for moving pump house, sand house, oil house, and office will be made at the lump sum price bid therefor in the schedule, which price shall include all cost of moving the buildings, removing and disposing of footings and floors, and filling of holes.

- (d) Moving service pump and two steel storage tanks.—The contractor shall move the service pump, excavate and remove the 1,000—gallon storage tank buried in the rear of the motor—car house, and the 10,000—gallon storage tank buried beneath the concrete floor of the pump house, and deliver them to the Government salvage yard. No piping will be required to be salvaged. The tanks shall be cleaned of adhering dirt. Any damage caused by the contractor to the pump or tanks shall be repaired by and at the expense of the contractor. Payment for moving service pump and two steel storage tanks will be made at the lump sum price bid therefor in the schedule, which price shall include all cost of disconnecting, moving, and cleaning tanks, and of filling holes.
- 39. Bridges, signs, and posts along Secondary State Highway 2-F.


 (a) Bridges.—The contractor shall remove all combustible material from 3 timber bridges on Secondary State Highway 2-F as shown on the drawing. Piles shall be cut, and sills or sleepers shall be removed as required for railroad bridges in paragraph 38.
- (b) Signs and posts.—The contractor shall remove all highway signs, advertising signs, and all guard and guide posts along Secondary State Highway 2-F within 300 feet of the highway. All posts shall be pulled.
- (c) Payment.—Payment for removing bridges along Secondary State Highway 2-F will be made at the lump sum price bid therefor in the schedule, which price shall include all cost of removal and disposal of

the materials. Payment for removing signs and posts along Secondary State Highway 2-F will be made at the lump sum price bid therefor in the schedule, which price shall include all cost of removal and disposal of the materials. The contractor shall be entitled to no additional compensation because either item of this work is not required, due to a delay in opening the relocated State Highway 2-F, and the application of provisions in paragraph 22.









PO-8-FSO

