



## ADVANCE CONSTRUCTION NOTICE

→ Storm Drain Lining Work Will Be Undertaken In Your Area ←

Insituform Technologies® Limited (ITL) is under contract by the City of Victoria to complete the rehabilitation of storm sewers in your area using trenchless methodologies.

**We will be in your area between the following dates:**

<b>Stage 1: Cleaning</b>	<u>Complete</u>
<b>Stage 2: Manhole Modification</b>	<u>Mar 6</u> TO <u>Apr 25</u>
<b>Stage 3: Lining</b>	<u>Apr 26</u> TO <u>May 26</u>
<b>Stage 4: Manhole Restoration</b>	<u>May 23</u> TO <u>June 16</u>

During the construction, there may be some minor traffic disruptions, parking restrictions, and lane closures.

In order to repair the storm sewer system, the work is to be conducted as follows:

**Stage 1: Pipe Cleaning and Video Inspection** (Work by Insituform Technologies) – **completed in 2022.**

- Involves video inspection of the pipes and pipe cleaning by use of low-pressure water jetting equipment to remove debris.

**Stage 2: Existing Manholes Modification** (Work by Scansa Construction Ltd) – **deferred to 2023.**

- Involves local open excavations to existing manholes for access to the sewer and drainpipes.

**Stage 3: Pipe Lining** (Work by Insituform Technologies) – **deferred to 2023.**

- Involves the lining of pipe mains with a fiberglass resin "sock"
- Residents may experience a slight chemical smell while our crews are lining pipes. This is only temporary, and it is not harmful. If any problem occurs with your service(s) during this rehabilitation process or after we are complete, please call our representatives as provided below and one of our onsite personnel will visit you.
- The lining work is a 24-hour continuous operation due to the curing process of the fiberglass resins. The liner is first installed via air-inversion using compressors and then cooked with steam.
- The noise level during our general construction activity is of 80dBa (non-continual at night). Air-inversion installations of the cured-in-place-pipe are scheduled during the day with pumps and trucks to be running through the night.



**Stage 4: Manhole Restoration** (Work by Scansa Construction Ltd) – **deferred to 2023.**

- Involves rebuilding previously modified manholes and restoring surface works back to original condition (landscaping and paving).



For **Stage 3**, you will receive a notice on your door or in your mailbox 48 hours prior to lining. The 48-hours notification will provide you with information regarding the time and duration of the disruption as well as contact information should you have any concerns. If we must change our schedule due to unexpected wet weather conditions, you will receive a cancellation notice. We will then reschedule the work and provide you with a new 48-hour notice advising you of the updated date and time of work.

Please be advised that the use of pressurized jetting equipment and fiberglass resin odour could pose some inconvenience to the home and/or business owner, however these issues do not pose any health concerns. To prevent odours from entering your home and / or business please ensure you fill your "p-trap", as detailed below:



Over time the odour will diminish as the liner cures. Should you experience any inconveniences, please do not hesitate to contact an ITL representative at the number listed below.

If any problems occur during or after the work has been completed, please contact one of our representatives and we will address your concerns.

**For general information please call Jordan Oliver – Jr. Project Manager 1.587.341.6911**  
**For more information on our process please visit: [www.insituform.com](http://www.insituform.com).**

**For a City of Victoria representative please call Derk Wevers at 1.250.883.3496**

**Thank you for your cooperation!**



**WORK AREA EXTENT**

