

SPECIFICATIONS

CONCRETE - 6000 PSI minimum in 28 days.

REINFORCEMENT - 6X6 10 gauge ASTM A185 65 KSI plain finish cont. around perimeter of tank, #3 bars (Grade 60) rebar, per engineering spec. as required for tanks design.

LID REINFOREMENT - #3 rebar 6" center, both ways plus a mat on 6X6 10 gauge wire.

PIPE PENETRATIONS - Inlet and outlet seals water tight that meet ASTM C923.

PARTITION WALLS - If present, is poured monolithically


required. Depth of base and material shall meet the specifications and requirements for the INSTALLATION - By contractor per code with minimum of 12" on allsides of unit is type of soil at the setting location. The leveling of the material will prevent tank from

BACK FILL - Before filling with water! This must be done on all sides by lowering sand. cracking after filling with water.

BUOYANCY - 18" of water must remain in the tank with ____ DO NOT PUSH FROM SIDES. " of soil on the top of the tank.

Full warranty provided with tank purchase at location and at www.texasprecast.net TANK WARRANTY - Limited to replacement for 1 year.

Approx. Capacity - 550 gallons Approx. Weight - 4980 lbs.



TEXAS PRECAST, L.L.C. SEPTIC TANK BODY

SANTA FE, TEXAS 77510 18303 HIGHWAY 6 WWW.TEXASPRECAST.NET

SECTION "A" FRONT VIEW

TOLL FREE: 800-633-3235 PHONE: 409-925-2502

MODEL

500 SQUARE PUMP