

SPECIFICATIONS

CONCRETE - 6000 PSI minimum in 28 days.

REINFORCEMENT - 6X6 10 gauge ASTM A185 65 KSI plain finish cont. around perimeter of tank, #3 bars (Grade 60) rebar, per engineering spec. as required for tanks design.

LID REINFOREMENT - #3 rebar 6" center, both ways plus a mat on 6X6 10 gauge wire.

PIPE PENETRATIONS - Inlet and outlet seals water tight that meet ASTM C923.

PARTITION WALLS - If present, is poured monolithically.

INSTALLATION - By contractor per code with minimum of 12" on all sides of unit is required. Depth of base and material shall meet the specifications and requirements for the type of soil at the setting location. The leveling of the material will prevent tank from cracking after filling with water.


BACK FILL - Before filling with water! This must be done on all sides by lowering sand.

DO NOT PUSH FROM SIDES.

<u>BUOYANCY</u> - 18" of water must remain in the tank with ____ " of soil on the top of the tank. TANK WARRANTY - Limited to replacement for 1 year.

Full warranty provided with tank purchase at location and at www.texasprecast.net
Approx. Capacity - 869 Gallons

Approx. Weight - ____ lbs.



RIGHT SIDE VIEW

WWW.TEXASPRECAST.NET

TOLL FREE: 800-633-3235 PHONE: 409-925-2502 TEXAS PRECAST, L.L.C.

18303 HIGHWAY 6 SANTA FE, TEXAS 77510 MODEL 800 SQUARE TRASH