

# Item IV.D.

11/03/2022

PROJECT/SITE OWNER:	PROJECT SUMMARY:
Bayside Development Partners II, LLC	New mixed occupancy 5 story building
PROJECT ADDRESS: 600 Block of West Glencoe Place	

I have reviewed the proposed single-story addition for compliance with the Village's ordinances and have determined the following for consideration

**Sec. 125-109. - Planned unit development district number one**

1. Meets current setbacks
2. Meets the required height restrictions
3. A current survey was provided
4. The applicant had supplied coloring renderings with materials
5. The submittal appears to comply with the above ordinance section
6. The board always considers the aesthetics of the project
7. **This review is only for ARC and not for a building permit.**

**VILLAGE CODE REVIEW**

**Supporting documentation or testimony must be provide at the meeting to verify code compliance with the above observations in red.**

**Dave Hendrix  
SAFEbuilt  
Wisconsin Operations Manager**

# Project Proposal

Date 10/24/22

Property Address 600 Block of West Glencoe Place

Zoning District APPROVED PUD

Proposed Project Details (type of work, size, materials, location, etc.):

This building is located at the heart of the Bayside Mixed-Use Development, and is perfectly situated to serve as a signature building and community destination. With a central courtyard and amenity deck, the building will have activated outdoor connections to greenspace, which will activate the site for both residents and visitors alike. The design will set the tone for the remaining building on site and therefore will have a highlighted presence representing its significance to the overall development and community. The building design will feature quality materials, a contemporary aesthetic with traditional elements, specifically masonry cladding. The building is to be constructed as 4 stories of wood framed construction above a 2-story concrete podium. 1 story of the concrete podium is fully below grade. The residential units are to be supplemented with amenity spaces such as clubroom, outdoor patios, and three separate tenants on the first floor.

<ul style="list-style-type: none"><li><input type="checkbox"/> ARC Agenda Date: <b>11/14/22</b></li><li><input type="checkbox"/> Parcel Number:</li><li><input type="checkbox"/> Color photographs showing project location, elevations, and surround views.</li><li><input type="checkbox"/> Two (2) complete digital sets of building plans (including elevations and grading).</li><li><input checked="" type="checkbox"/> Samples or brochures showing materials, colors, and designs.</li><li><input type="checkbox"/> Survey or Milwaukee County Land Information Officer Aerial</li></ul> <p>PERMITS:</p> <table><thead><tr><th>Y</th><th>N</th><th>Payment</th></tr></thead><tbody><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Building</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Electrical</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Plumbing</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> HVAC</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Fill</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Impervious Surface</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Dumpster</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> ROW/Excavation</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Conditional Use</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Occupancy</td></tr><tr><td><input type="checkbox"/></td><td><input type="checkbox"/></td><td><input type="checkbox"/> Special Exception/Variance</td></tr><tr><td colspan="3"><input type="checkbox"/> ARC</td></tr></tbody></table>	Y	N	Payment	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Building	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Electrical	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Plumbing	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> HVAC	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Fill	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Impervious Surface	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Dumpster	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> ROW/Excavation	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Conditional Use	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Occupancy	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Special Exception/Variance	<input type="checkbox"/> ARC			<ul style="list-style-type: none"><li><input type="checkbox"/> Accessory Structures/Generators</li><li><input type="checkbox"/> Additions/Remodel</li><li><input type="checkbox"/> Commercial Signage</li><li><input type="checkbox"/> Decks/Patios</li><li><input type="checkbox"/> Fence</li><li><input type="checkbox"/> Fire Pits</li><li><input type="checkbox"/> Landscaping requiring Impervious Surface/Fill/Excavation Permit</li><li><input type="checkbox"/> New Construction</li><li><input type="checkbox"/> Play Structures</li><li><input type="checkbox"/> Recreational Facilities/Courts</li><li><input type="checkbox"/> Roofs</li><li><input type="checkbox"/> Solar Panels/Skylights</li><li><input type="checkbox"/> Swimming Pools</li><li><input type="checkbox"/> Windows/Doors – change exceeds 25% of opening</li><li><input checked="" type="checkbox"/> Other DESIGN APPROVAL</li></ul> <p>ITEMS INCLUDED:</p> <ul style="list-style-type: none"><li><u>SITE PLAN</u></li><li><u>FLOOR PLANS</u></li><li><u>ELEVATIONS</u></li><li><u>EXTERIOR MATERIAL BOARD</u></li><li><u>DEVELOPMENT SUMMARY (PARKING&amp; UNIT COUNTS)</u></li><li><u>LANDSCAPE PLAN AND LANDSCAPE RATIO CALCULATOR AS DEFINED IN PUDD1</u></li><li><u>PARKING PLAN AND CALCS (STREET AND OFF STREET)</u></li><li><u>BUILDING SF (OVERALL BY USE)</u></li><li><u>EXTERIOR LIGHTING PLAN</u></li><li><u>SIGNAGE PLAN</u></li><li><u>SETBACKS</u></li><li><u>SIDEWALK AND STREETSCAPING PLAN</u></li><li><u>GREEN INFRASTRUCTURE, IF ANY</u></li><li><u>STORMWATER MANAGEMENT PLAN</u></li><li><u>PUBLIC IMPROVEMENT AGREEMENT/SITE IMPROVEMENT AGREEMENT</u></li><li><u>UPDATED RENDERINGS</u></li></ul>
Y	N	Payment																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Building																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Electrical																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Plumbing																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> HVAC																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Fill																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Impervious Surface																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Dumpster																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> ROW/Excavation																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Conditional Use																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Occupancy																																						
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Special Exception/Variance																																						
<input type="checkbox"/> ARC																																								



**Date:** November 4, 2022

**To:** Village of Bayside

**From:** Jackie Mich, AICP; Jeff Maloney; and Dean Proctor, AIA

**Re:** **Building C – Architectural Review Committee Submittal**

---

## **Introduction**

Planned unit development districts are intended to allow for greater flexibility, variety of use, and design freedom in order to achieve a higher quality of development than would otherwise be possible using a standard zoning district. Specifically, PUDD 1 is intended to facilitate the development of a high-quality professional services, health/fitness, general commercial, retail, restaurant, medical office, multi-family housing, civic/recreational/public library, hospitality, and office mixed use area.

Building C is the first project to come before the Architectural Review Committee for review. All development within PUDD 1 must comply with the requirements of the Municipal Code except as otherwise specifically set forth in Section 125-109 (PUDD 1 ordinance) and the improvement agreements.

A recommendation and summary of changes suggested by Vandewalle staff is provided on the last page of this report.

## **Description**

The Building C site is located at the center of the PUDD 1 development, with access from Glencoe Place and Brown Deer Road. Currently, surrounding uses include commercial development along Brown Deer Road to the south (partially vacant), an existing apartment building on Port Washington Road to the southeast, and an office building to the north on Glencoe Place. Surrounding uses identified in the Conceptual Site/Master Plan for the entire development include future multi-family to the north, existing office to the northeast, existing apartment building on Port Washington Road to the southeast, and mixed use/multi-family to the south.

The applicant proposes a five-story mixed use building with space reserved for a library/civic space, two other tenant spaces on the first floor, and 98 multi-family units on the four upper stories. A sizeable greenspace is provided immediately to the east of the building.

The approximately 24,000-square-foot library space includes an entry on the west side of the building and a recessed courtyard entrance on the east side of the building, facing a large greenspace area. Two additional entrances are provided on the south side of the building. The library also includes a drive-through window on the southeast side, ostensibly for book drop-off and pickup. The entrance ramp to the underground parking is located on the northwest side of the building. The north side of the building includes the multi-family entrance lobby, trash chute discharge room, and an approximately 4,000-square-foot future tenant space. An approximately 2,500-square-foot future tenant space is located on the southeast corner of the building. The four upper stories include a mix of junior one-bedroom, one-bedroom/studio, one-bedroom, two-bedroom, and three-bedroom units. Level 2 includes an amenity room and outdoor deck with fireplace. Levels 3-5 included a U-shaped floor plan, with interior units overlooking the outdoor deck and library courtyard below. The lower level includes 98 parking spaces for residents, bike storage, and a dog wash.

### **Land Uses**

The proposed uses specified in the submittal include civic/library, multi-family residential, parks/public recreation, and parking. These are all permitted uses per the PUDD and comply the maximum area and maximum heights permitted for the PUDD 1 as a whole. No outdoor storage or outdoor dining is proposed.

A conditional use permit may be required for first-floor retail/commercial uses, depending on the use. Per PUDD 1, the building owner must notify the Village of any addition or change of tenants, in part to ensure that all Village approvals are sought and requirements met.

### **Site Plan, Access, Circulation, and Parking**

The Conceptual Site Plan for the larger development shows linked pedestrian greenspaces connecting the different phases of development, including a pedestrian connection to a planned greenspace to the northwest. These links are not clearly reflected in the submitted site plan. A key consideration for this site and other developments in PUDD 1 will be to ensure that these pedestrian connection, linkages, and thoughtfully planned greenspaces are integrated across the distinct developments as they are developed.

The Minimum Landscape Surface Ratio of 15% is met, particularly with the inclusion of greenspace to the east of the building. Maximum Building Site Area of 70% is also met. Staff notes that the underground stormwater facility beneath the greenspace may limit the types of permanent improvements that can be placed (lighting, structures, etc.) in the greenspace.

Ample sidewalks are proposed throughout the Building C site, ensure safe pedestrian access within the site. Crosswalks are proposed at multiple through parking areas.

Vehicular and pedestrian access is provided from Glencoe Place (anticipated to become a private street) and Brown Deer Road. The site plan includes surface parking on three sides of the building and on the east side of the village green. This includes a mix of perpendicular and angle parking spaces, all accessed by private streets/drives.

PUDD 1 requires four parking spaces for every 1,000 square feet of most types of commercial uses and 1.4 spaces for each residential unit. These requirements may be met by a combination of off-street, on-street and structured parking. Per the PUDD 1 ordinance, upon approval of site plans, the Plan Commission may waive the minimum parking requirements based on, among other factors, demand for and time of usage of parking spaces.

Proposed parking is depicted clearly on the “Parking Plan and Calculations” page of the submittal. Based on the size and number of the uses proposed, a total of 260 parking spaces are required. A total of 285 parking spaces are provided in the project, and therefore the project exceeds minimum parking requirements.

A minimum of 138 parking spaces are required to serve the 98 residential units. Parking requirements are met and exceeded through 98 underground parking spaces plus 71 surface parking spaces, for a total of 169 parking stalls for residents.

Based on square footage alone and assuming a total of 30,500 square feet of general commercial, a minimum of 122 parking spaces are required to serve the first floor uses. Only 116 parking spaces are provided for the first floor uses; however, given that the majority of the first floor will likely be devoted to library space, and given that total parking requirements are met and exceeded, the Plan Commission could consider a modification to the mix of parking permitted.

Vandewalle staff recommends the addition of bike parking to accommodate at least 20 bicycles for library patrons and customers of the first floor uses.

### **Signage**

According to the PUDD 1 ordinance, signage shall be in accordance with any signage plan submitted with the improvement agreements.

The submitted “Site Signage Plan” identifies two ground monument signs. The first, located along the proposed Glencoe Avenue will be double sided, a maximum of four feet in height, and a maximum of 24 square feet in area on each side. The second, located at the library entrance ion the west side of the building, will be double sided, a maximum of six feet in height, and a maximum of 48 square feet in area on each side. Pedestrian-oriented wayfinding signage is proposed at the northwest, northeast, and southeast corners of the site. These will be double-sided and limited four feet in height and eight square feet in area. The proposed site signage is appropriate given the size of the building and surrounding context.

As for on-building signage, the submitted “Signage Elevations” identify primary and secondary signage zones on the first floor. Major entry tenant signs are to be limited to one column bay width per side. Sign permits will be reviewed and approved by the Village as tenants are finalized.

## **Landscaping**

The PUDD 1 ordinance requires a minimum Landscape Surface Ratio (LSR) of 15% per lot. The proposed site plan meets this requirement.

Plants located on the north side of building will generally be shaded by the five-story building, which affects selection of plant species. Vandewalle staff offers the following notes on plantings located on the north side of the building:

- Quaking Aspen needs four hours of direct sunlight daily. If not provided, consider a more shade-tolerant species.
- Morning Star Sedge prefers direct sunlight. May not grow successfully in shade.
- Black Eye Susan prefers direct sunlight. May not grow successfully or flower in shade.
- Cream and Blue False Indigo may not flower in shade.
- Tufted Hair Grass may not flower/seed in shade.
- Sky Blue and New England Aster may flop in shade.
- Blue Sage prefers some direct sun daily.

A final note is that “Native Mix 1” is noted in the legend but not shown on the plan.

## **Architectural Design**

The transparent first floor impressively reflects its function as an inviting and accessible semi-public space. Façades are well-articulated with generous glazing and recessed massing at the balconies. Corner balconies provide good visibility of activity/life in the building and articulate the building’s corners. Balconies are well integrated into the façades, creating desirable semi-private space, and offer a good balance of recess and projection. Overall, the scale of the building is nicely reduced by the different architectural treatments of the upper levels. Building entries are well located and integrated with site functions.

Vandewalle staff offers the following comments and suggestions:

- The library entry area should be adequately covered for protection from the elements and create a sense of welcoming.
- The library drive-through window should also be covered for protection from the elements.
- To maintain the clean look of the façades, all utility elements (i.e., venting) should be carefully located and well-integrated into the building design.
- Because the underside of the balconies will be very visible, its structural elements should be attractive and well-detailed. Consider upgrading materials for durability.

Changes to architectural design (such as the final design of the library entry) will be subject to future review and approval by the Village.

## **Recommendation**

Overall, this is an excellent project that reflects thoughtful site planning, and which includes good architecture, landscaping, and stormwater management practices. Vandewalle staff recommends

approval and offers the following recommendations/modifications, in addition to any other recommendations or modifications suggested by the Architectural Review Committee:

1. Add a pedestrian linkage to future greenspace associated with the future multi-family to the northwest of Building C.
2. Update the Conceptual Site Plan as buildings are approved to ensure that the Village has a comprehensive master plan reflects both planned and approved development. This will help ensure that PUDD 1 requirements are met sitewide, support careful planning of uses as plans evolve, and ensure that interconnectivity between buildings/sites is achieved.
3. Approve 116 parking spaces for the first floor tenants rather than the 122 required, as the total minimum parking requirements for Building C as a whole are met and exceeded. (Requires approval by Plan Commission)
4. Add bicycle parking for at least 20 bicycles for library patrons and customers of the first floor uses.
5. Submit applications for sign permits for review and approval as tenants are finalized.
6. Use shade-tolerant plant species on the north side of the building, as described on page 4 of this report.
7. Add a canopy over the library entry area and drive-through window.
8. Conceal vents and other utility elements to the extent possible; locate vents in balconies perpendicular to the building façade.



# ONE NORTH - MULTIFAMILY BUILDING C

RINKA+

VILLAGE OF BAYSIDE ARC REVIEW

10.24.2022

# SITE PLAN

## DEVELOPMENT SUMMARY

### MIXED USES

- + 24K TENANT SPACE
- + 4K TENANT SPACE
- + 2.5K TENANT SPACE
- + 98 MULTIFAMILY UNITS

### PARKING

#### -MULTIFAMILY

98 UNDERGROUND STALLS

71 SURFACE PARKING STALLS

169 TOTAL PARKING STALLS

**1.7 STALL PER 1 UNIT**

#### -LIBRARY

81 STALLS

#### -TENANT A

22 STALLS

#### -TENANT B


13 STALLS

### TOTAL PARKING SPACES

187 SURFACE

98 UNDERGROUND


SCALE:NTS



# PARKING PLAN AND CALCULATIONS

MULTI-FAMILY   LIBRARY TENANT   TENANT A   TENANT B

B1




## UNDERGROUND PARKING

98 SPACES

TOTAL: 98 SPACES

SITE PLAN



## SURFACE PARKING

71 SPACES


81 SPACES

22 SPACES

13 SPACES

TOTAL: 187 SPACES

# BUILDING FLOOR PLANS | LEVEL B1




SCALE:NTS

## KEY PLAN

- (BS) - BIKE STORAGE
- (DW) - DOG WASH
- (PR) - PARKING RAMP
- UNDERGROUND PARKING

# BUILDING FLOOR PLANS | LEVEL 1

SCALE:NTS 



## KEY PLAN

- (BA) - BUILDING ACCESS (ENTRY/EXIT)
- (TD) - TRASH CHUTE DISCHARGE ROOM
- (TG) - TRANSFORMER/ GENERATOR PAD
- (CY) - COURTYARD
- LIBRARY TENANT
- MULTIFAMILY
- TENANT A
- TENANT B

# BUILDING FLOOR PLANS | LEVEL 2

SCALE:NTS 



## KEY PLAN

- BA - BUILDING ACCESS (ENTRY/EXIT)
- TA - TRASH CHUTE ACCESS ROOM
- OD - OUTDOOR DECK
- FP - FIREPLACE
- ST - STORAGE
- - JR ONE BED UNIT
- - ONE BED STUDIO UNIT
- - ONE BED UNIT
- - TWO BED UNIT
- - THREE BED UNIT

# BUILDING FLOOR PLANS | LEVEL 3-4



SCALE:NTS

## KEY PLAN

- TA - TRASH CHUTE ACCESS ROOM
- ST - STORAGE
- - JR ONE BED UNIT
- - ONE BED UNIT
- - TWO BED UNIT
- - THREE BED UNIT

# BUILDING FLOOR PLANS | LEVEL 5



SCALE:NTS

## KEY PLAN

- TA - TRASH CHUTE ACCESS ROOM
- ST - STORAGE
- JR ONE BED UNIT
- ONE BED UNIT
- TWO BED UNIT
- THREE BED UNIT

# EXTERIOR MATERIAL BOARD

A. MV-1 MASONRY VENEER 1



A.

B. MV-2 MASONRY VENEER 2



B.



C.

C. FCS-1 FIBER CEMENT 1



D.

D. FCS-2 WOOD LOOK FIBER CEMENT 2



E.

E. MP-4 METAL PANEL



F.

F. DCMU-1 BURNISHED BLOCK









ONE NORTH - MULTIFAMILY BUILDING C - VILLAGE OF BAYSIDE ARC REVIEW


10.24.2022 | P. 12/20



# BUILDING ELEVATIONS

## EXTERIOR MATERIAL KEY

MV-1 MASONRY VENEER 1	FCS-1 FIBER CEMENT 1
MV-2 MASONRY VENEER 2	FCS-2 WOOD LOOK FIBER CEMENT 2
MP-4 METAL PANEL	DCMU-1 BURNISHED BLOCK



SCALE:NTS

# BUILDING ELEVATIONS

## EXTERIOR MATERIAL KEY

MV-1 MASONRY VENEER 1	FCS-1 FIBER CEMENT 1
MV-2 MASONRY VENEER 2	FCS-2 WOOD LOOK FIBER CEMENT 2
MP-4 METAL PANEL	DCMU-1 BURNISHED BLOCK




SCALE:NTS

# BUILDING ELEVATIONS

## EXTERIOR MATERIAL KEY

MV-1 MASONRY VENEER 1	FCS-1 FIBER CEMENT 1
MV-2 MASONRY VENEER 2	FCS-2 WOOD LOOK FIBER CEMENT 2
MP-4 METAL PANEL	DCMU-1 BURNISHED BLOCK



SCALE:NTS

1 ELEVATION COURTYARD SOUTH

# SITE SIGNAGE PLAN


Site signage locations shown indicate potential sign locations, subject to change.

## ② Ground Monument Sign

- 2A
- Double Sided
- 4' Tall Max
- 24 SF max (each side)
- 2B
- Double Sided (Optional)
- 6' Tall Max
- 48 SF Max (each side)

## ④ Pedestrian Wayfinding Signs

- Directional sign for tenant & visitor parking
- 48" Tall Max
- 8 SF Max
- Double Sided



SCALE:NTS

BROWN DEER RD

# SIGNAGE ELEVATIONS



## PRIMARY SIGNAGE ZONE





## SECONDARY SIGNAGE ZONE

SIGNAGE TYPES AS INDICATED BY LOCATION ARE INTENDED TO ABIDE BY DESIGN GUIDELINES OUTLINED IN OVERALL MASTERPLAN SIGNAGE GUIDELINES.

- PRIMARY SIGNAGE
    - ARCHITECTURAL
    - EXTRUDED
    - CUT-OUT
    - AWNING SIGNS
  - SECONDARY SIGNAGE
    - FLAG SIGNS
    - FLAG SIGN (SUSPENDED)
    - VINYL (ON GLAZING)

**NOTE: MAJOR ENTRY TENANT SIGNS TO BE  
LIMITED TO ONE COLUMN BAY WIDTH PER  
SIDE**



SCALENTS

# SIGNAGE ELEVATIONS



PRIMARY SIGNAGE ZONE






SECONDARY SIGNAGE ZONE

SIGNAGE TYPES AS INDICATED BY LOCATION ARE INTENDED TO ABIDE BY DESIGN GUIDELINES OUTLINED IN OVERALL MASTERPLAN SIGNAGE GUIDELINES.

- PRIMARY SIGNAGE
- ARCHITECTURAL
- EXTRUDED
- CUT-OUT
- AWNING SIGNS
- SECONDARY SIGNAGE
- FLAG SIGNS
- FLAG SIGN (SUSPENDED)
- VINYL (ON GLAZING)

NOTE: MAJOR ENTRY TENANT SIGNS TO BE LIMITED TO ONE COLUMN BAY WIDTH PER SIDE



SCALE:NTS



# SIGNAGE ELEVATIONS



PRIMARY SIGNAGE ZONE




SECONDARY SIGNAGE ZONE

SIGNAGE TYPES AS INDICATED BY LOCATION ARE INTENDED TO ABIDE BY DESIGN GUIDELINES OUTLINED IN OVERALL MASTERPLAN SIGNAGE GUIDELINES.

- PRIMARY SIGNAGE
- ARCHITECTURAL
- EXTRUDED
- CUT-OUT
- AWNING SIGNS
- SECONDARY SIGNAGE
- FLAG SIGNS
- FLAG SIGN (SUSPENDED)
- VINYL (ON GLAZING)

NOTE: MAJOR ENTRY TENANT SIGNS TO BE LIMITED TO ONE COLUMN BAY WIDTH PER SIDE



KEY PLAN



SCALE:NTS



PROJECT:  
**BAYSIDE  
DEVELOPMENT -  
MULTI-FAMILY  
BUILDING C**

LOCATION:

CLIENT:

RELEASE:  
**SCHEMATIC  
DESIGN**

REVISIONS:		
#	DATE	DESCRIPTION




SEAL:

all in  
SHEET:  
**OVERALL SITE  
LAYOUT PLAN**

PROJECT MANAGER: DMJ  
PROJECT NUMBER: 210709.01  
DATE: 10.10.2022

SHEET NUMBER:  
**C102**




PROJECT:  
**BAYSIDE  
DEVELOPMENT -  
MULTI-FAMILY  
BUILDING C**

LOCATION:

CLIENT:

RELEASE:  
**SCHEMATIC  
DESIGN**

REVISIONS:		
#	DATE	DESCRIPTION




SEAL:

all in  
SHEET:  
**SITE LAYOUT PLAN**

PROJECT MANAGER: DMJ  
PROJECT NUMBER: 210709.01  
DATE: 10.10.2022

SHEET NUMBER:  
**C102A**



PROJECT:  
**BAYSIDE  
DEVELOPMENT -  
MULTI-FAMILY  
BUILDING C**

LOCATION:

CLIENT:

RELEASE:  
**SCHEMATIC  
DESIGN**

#	DATE	DESCRIPTION




SEAL:

all in  
**SITE LAYOUT PLAN**

PROJECT MANAGER: DMJ  
PROJECT NUMBER: 210709.01  
DATE: 10.10.2022

SHEET NUMBER:  
**C102B**





**7711 N. Port Washington Road  
Milwaukee, Wisconsin 53217**

[kapurinc.com](http://kapurinc.com)

PROJECT:  
**BAYSIDE  
DEVELOPMENT -  
MULTI-FAMILY  
BUILDING C**

---

**LOCATION:**

**CLIENT:**

**RELEASE:**  
**SCHEMATIC**  
**DESIGN**

A black upward-pointing arrow inside a white circle with a black border.


SEAL:

# all in

PROJECT MANAGER:	DMJ
PROJECT NUMBER:	210709.01
DATE:	10.10.2022

SHEET NUMBER:  
**C102C**

# PROPOSED BUILDING FFE = 695.00



FILENAME: S:\SiteDsgn\Cobalt Partners LLC\210709 Bayside Development\Design\C102 - SITE LAYOUT PLAN.dwg

PROJECT:  
**BAYSIDE DEVELOPMENT -  
 MULTI-FAMILY BUILDING C**


LOCATION:

CLIENT:

 RELEASE:  
**SCHEMATIC DESIGN**

REVISIONS:		
#	DATE	DESCRIPTION

NORTH ARROW:




SEAL:

all in  
 SHEET:  
**OVERALL STORM WATER PLAN**

PROJECT MANAGER: DMJ  
 PROJECT NUMBER: 210709.01  
 DATE: 10.10.2022

SHEET NUMBER:

**SWMP**


PROJECT:  
**BAYSIDE  
DEVELOPMENT -  
MULTI-FAMILY  
BUILDING C**


LOCATION:

CLIENT:

RELEASE:  
**SCHEMATIC  
DESIGN**

#	DATE	DESCRIPTION

NORTH ARROW:



SEAL:

Scale: 0 15 30 60  
Scale: 1" = 30'  
**DIGGERS HOTLINE**  
Dial 811 or (800)242-8511  
[www.DiggersHotline.com](http://www.DiggersHotline.com)

all in


Sheet:  
**OVERALL SITE  
LANDSCAPE PLAN**

PROJECT MANAGER: DMJ  
PROJECT NUMBER: 210709.01  
DATE: 10.10.2022

SHEET NUMBER:

**L101**

EXISTING  
BUILDING  
FFE = 695.17  
LLE = 684.67



PROJECT:  
**BAYSIDE  
DEVELOPMENT -  
MULTI-FAMILY  
BUILDING C**


LOCATION:

CLIENT:

RELEASE:  
**SCHEMATIC  
DESIGN**

#	DATE	DESCRIPTION

NORTH ARROW:




SEAL:

all in

SHEET:  
**SITE LANDSCAPE  
PLAN**

PROJECT MANAGER: DMJ  
PROJECT NUMBER: 210709.01  
DATE: 10.10.2022

SHEET NUMBER:

**L101A**

PROJECT:  
**BAYSIDE  
DEVELOPMENT -  
MULTI-FAMILY  
BUILDING C**

LOCATION:

**Plant Schedule**

Code	Scientific Name	Common Name	Quantity	Spacing	Install Size	Mature Size
(Height/Spread)						
<b>Canopy Trees: (Install in accordance with detail 3/L201)</b>						
ACFAF	Acer x freemanii 'Autumn Fantasy'	Autumn Fantasy Maple	5	Per Plan	3" caliper B&B	50'x30'
ACMSS	Acer miyabei 'Morton'	State Street Miyabei Maple	6	Per Plan	3" caliper B&B	50'x40'
AEGEG	Aesculus glabra 'JN Select'	Early Glow Buckeye	1	Per Plan	3" caliper B&B	35'x35'
CEOC	Celtis occidentalis	Common Hackberry (Native)	4	Per Plan	3" caliper B&B	40'-60'x40'-60'
GIBPS	Ginkgo biloba 'Princeton Sentry'	Princeton Sentry Ginkgo	6	Per Plan	3" caliper B&B	40'x15'
GLTDR	Gleditsia triacanthos 'Draves'	Street Keeper Honeylocust	12	Per Plan	3" caliper B&B	45'x20'
GLTIS	Gleditsia triacanthos 'Shademaster' PP1,515	Shademaster Honeylocust	5	Per Plan	3" caliper B&B	60'x35'
GYDIE	Gymnocladus dioicus 'Espresso'	Espresso Kentucky Coffee Tree	5	Per Plan	3" caliper B&B	50'x35'
POTR	Populus tremuloides	Quaking Aspen (Native)	7	Per Plan	3" caliper B&B	40'-50'x20'-30'
QUBI	Quercus bicolor	Swamp White Oak (Native)	5	Per Plan	3" caliper B&B	50'x40'
QUMA	Quercus macrocarpa	Bur Oak	2	Per Plan	3" caliper B&B	70'-90'x60'-80'
QURU	Quercus rubra	Red Oak (Native)	2	Per Plan	3" caliper B&B	60'-75'x60'-75'
ULAMP	Ulmus americana 'Princeton'	Princeton Elm	4	Per Plan	3" caliper B&B	70'x50'
<b>Ornamental Trees: (Install in accordance with detail 3/L201)</b>						
AMGAB	Amelanchier x grandiflora 'Autumn Brilliance'	Autumn Brilliance Serviceberry	4	Per Plan	8' multi-stem B&B	20'-25'x20'-25'
SYRIS	Syringa reticulata 'Ivory Silk'	Ivory Silk Japanese Tree Lilac	2	Per Plan	2.5" caliper B&B	25'x15'
<b>Evergreen Trees: (Install in accordance with detail 4/L201)</b>						
PIGLD	Picea glauca var. densata	Black Hills Spruce	2	Per Plan	6' tall B&B	25'-45'x15'-25'
<b>Deciduous Shrubs: (Install in accordance with detail 5/L201)</b>						
HYPAL	Hydrangea paniculata 'ILVOBO' PP22,782	Bobo Hydrangea	5	Per Plan	18" tall pot	3'-3'-4'
RHARG	Rhus aromatica 'Gro-Low'	Gro-Low Sumac	62	Per Plan	18" spread pot	2'-3'-6'-8'
RORDP	Rosa rugosa 'Dwarf Pavement'	Dwarf Pavement Rugosa Rose	19	Per Plan	15" tall pot	2'-3'-5'
SPBAW	Spiraea x bumalda 'Anthony Waterer'	Anthony Waterer Spirea	55	Per Plan	18" tall pot	2'-3'-4'
SPBET	Spiraea betulifolia 'Tor'	Tor Birchleaf Spirea	22	Per Plan	18" tall pot	2'-3'-3'
SYMEP	Syringa meyeri 'Palibin'	Meyer Lilac (Dwarf Korean Lilac)	5	Per Plan	24" tall pot	4'-5'/5'-7'
SPYJU	Syringa patula 'JN Upright Select' PPAF	Violet Uprising Lilac	1	Per Plan	24" tall pot	4'-6'/4'-5'
<b>Evergreen Shrubs: (Install in accordance with detail 5/L201)</b>						
JUHWI	Juniperus horizontalis 'Wisconsin'	Wisconsin Juniper	3	Per Plan	18" spread pot	8'/5'+
<b>Perennials: (Install in accordance with detail 6/L201)</b>						
ALSPB	Allium 'Summer Peek-a-Boo'	Summer Peek-a-Boo Globe Lily	196	Per Plan	#1 cont.	8"-12"/18"-24"
CAAC	Calamagrostis x acutiflora Karl Foerster	Karl Foerster Reed Grass	166	Per Plan	#1 cont.	5'-6"-18"-24"
ECPWB	Echinacea purpurea 'Wow Wild Berry'	PowWow Wild Berry Coneflower	76	Per Plan	#1 cont.	18"-24"/12"-16"
HEHH	Heuchera 'Happy Returns'	Happy Returns Daylily	8	Per Plan	#1 cont.	12"-18"/16"-24"
IRSCB	Iris sibirica 'Caesar's Brother'	Caesar's Brother Siberian Iris	33	Per Plan	#1 cont.	30"-36"/18"-24"
LESDM	Leucanthemum x superbum 'Daisy May' (Daisy Duke)	Daisy May Shasta Daisy	63	Per Plan	#1 cont.	12"-24"/12"-18"
MODPW	Monarda didyma 'Petite Wonder'	Petite Wonder Bee Balm	49	Per Plan	#1 cont.	9"-12"/12"-18"
NFWLW	Neptunia x 'Walker's Low'	Walker's Low Catmint	75	Per Plan	#1 cont.	24"-36"/18"-36"
PANO	Panicum virgatum 'Northwinds'	Northwinds Switch Grass	20	Per Plan	#1 cont.	4"-5"/24"-30"
PEALS	Pervomia atriplicifolia 'Little Spike'	Little Spike Russian Sage	125	Per Plan	#1 cont.	24"-30"/18"-24"
SANEC	Salvia nemorosa 'Caradonna'	Caradonna Meadow Sage	29	Per Plan	#1 cont.	24"-30"/12"-18"
SPHET	Sporobolus heterolepis 'Tara'	Tara Prairie Dropseed	15	Per Plan	#1 cont.	18"-24"/18"-24"
<b>Native Forbs and Grasses (Salt Tolerant - full sun): (Install in accordance with detail 6/L201)</b>						
ALCE	Allium cernuum	Nodding Pink Onion	170	Per Plan	Half gallon	18"-24"/6"-8"
ASER	Aster ericoides	Heath Aster	46	Per Plan	Half gallon	18"-24"/12"-18"
DAPU	Dalea purpurea	Purple Prairie Clover	61	Per Plan	Half gallon	24"-36"/15"-18"
LIPY	Liatris pycnostachya	Prairie Blazingstar	71	Per Plan	Half gallon	3'-5'/12"-15"
LOSI	Lobelia siphilitica	Great Blue Lobelia	68	Per Plan	Half gallon	24"-36"/12"-18"
PAVI	Panicum virgatum	Switch Grass	65	Per Plan	Half gallon	4"-5"/24"-30"
PEDI	Pentstemon digitalis	Foxglove Beard Tongue	59	Per Plan	Half gallon	30"-36"/12"-15"
SCSC	Schizachyrium scoparium	Little Bluestem	97	Per Plan	Half gallon	24"-48"/12"-18"
SPHE	Sporobolus heterolepis	Prairie Dropseed	184	Per Plan	Half gallon	30"-36"/12"-15"
<b>Native Forbs and Grasses (Salt Tolerant - part shade/shade): (Install in accordance with detail 6/L201)</b>						
ASNOA	Aster novae-angliae	New England Aster	13	18" o.c.	Half gallon	48"-60"/18"-24"
ASAZ	Aster azorensis	Sky Blue Aster	30	12" o.c.	Half gallon	36"-48"/12"-18"
AGCCA	Aquilegia canadensis	Wild Columbine	24	12" o.c.	Half gallon	24"-30"/12"-15"
BAAU	Baptisia austriensis	Blue False Indigo	7	18" o.c.	Half gallon	36"-48"/18"-24"
BABIB	Baptisia bracteata	Cream False Indigo	5	24" o.c.	Half gallon	24"-30"/24"-30"
CAGR	Carex grayii	Morning Star Sedge - or- Bur Sedge	107	18" o.c.	Half gallon	30"-36"/18"-24"
DECE	Deschampsia cespitosa	Tufted Hair Grass	78	18" o.c.	Half gallon	36"-48"/24"-36"
CHLA	Chasmanthium latifolium	Northern Sea Oats	51	24" o.c.	Half gallon	36"-48"/24"-36"
ECPU	Echinacea purpurea	Purple Coneflower	13	15" o.c.	Half gallon	36"-60"/15"-18"
ELVI	Elymus virginicus	Virginia Wild Rye	53	18" o.c.	Half gallon	24"-48"/18"-24"
HEAM	Heuchera americana	Alum Root	16	12" o.c.	Half gallon	12"-15"/12"-18"
MOFI	Monarda fistulosa	Bergamot	6	24" o.c.	Half gallon	36"-48"/24"-36"
RUHI	Rudbeckia hirta	Black-Eyed Susan	33	12" o.c.	Half gallon	36"-48"/12"-18"
SAAZ	Salvia azurea	Blue Sage	3	24" o.c.	Half gallon	36"-60"/24"-48"
ZIAU	Zizina aurea	Golden Alexanders	3	36" o.c.	Half gallon	24"-30"/36"-48"

NOTE: Plant quantities indicated in the plant schedule are for convenience only. Installation contractor is responsible for verifying plant count on the landscape plan. When discrepancies between the plant schedule, labels and the landscape plan occur, the quantity drawn on the landscape plan shall be the official quantity.





**1 LANDSCAPE SCHEDULE**

REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION

- ALL PLANT MATERIAL SHALL BE OBTAINED FROM A NURSERY LOCATED IN ZONE 5, CONFORM TO APPLICABLE REQUIREMENTS OF THE CURRENT EDITION OF THE AMERICAN STANDARD FOR NURSERY STOCK, AND BOTANICAL NAMES SHALL BE ACCORDING TO THE CURRENT EDITION OF "STANDARDIZED PLANT NAMES PREPARED BY THE AMERICAN JOINT COMMITTEE ON HORTICULTURE NOMENCLATURE".
- CONTRACTOR TO PROVIDE TO THE LANDSCAPE ARCHITECT SAMPLES OF ALL BARK AND MINERAL/STONE MULCHES, DECORATIVE GRAVELS, MAINTENANCE STRIP STONE, OR OTHER GROUND COVER MATERIALS FOR APPROVAL PRIOR TO INSTALLATION.
- BARK MULCH TO BE FRESHLY ACQUIRED HARDWOOD SHREDDED BARK MULCH. NOT DOUBLE MILLED, EXCESSIVE DIRT AND DUST LIKE MATERIAL OR OLD MATERIAL IS NOT ACCEPTABLE.
- LANDSCAPE EDGING TO BE ALUMINUM EDGING. REFER TO SPECIFICATION 32 93 00 PLANTS FOR ADDITIONAL INFORMATION.
- ALL PLANTING AREAS TO RECEIVE A 3-INCH THICK LAYER OF HARDWOOD SHREDDED BARK MULCH OVER TYPR WEED FABRIC WITH EDGING. EDGING TO BE INSTALLED BETWEEN DIFFERENT TYPES OF MULCHES, BETWEEN MULCHES AND TURF, AND/OR WHERE SPECIFICALLY NOTED ON THE PLAN. REFER TO SPECIFICATION 32 93 00 PLANTS FOR ADDITIONAL INFORMATION.
- INSTALL SHOVEL CUT EDGE AROUND ALL INDIVIDUAL TREES AND SHRUBS IN LAWN AREAS AND ALONG PAVEMENT WHERE PLANTING AREAS ABUT TO PREVENT HARDWOOD SHREDDED BARK MULCH FROM SPILLING OUT OF PLANTING AREA.
- CONTRACTOR RESPONSIBLE FOR MAINTENANCE OF PLANT MATERIAL FOR 90 DAYS FROM INSTALLATION, INCLUDING WATERING, WEEDING, ETC.. CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OF SEDED AREAS FOR 60 DAYS FROM INSTALLATION, INCLUDING WATERING, WEEDING, ETC.. CONTRACTOR TO PROVIDE AND REVIEW MAINTENANCE INSTRUCTIONS WITH THE OWNER PRIOR TO THE COMPLETION OF THESE MAINTENANCE PERIODS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- CLEANLY PRUNE AND REMOVE DAMAGED BRANCHES, DEAD WOOD, AND ROOTS IMMEDIATELY PRIOR TO PLANTING. DO NOT CUT LEADERS OR LEAVE "V" CROTCHES OR DOUBLE LEADERS UNLESS A MULTI-STEM TREE IS SPECIFIED.
- REMOVE BURLAP, WIRE BASKET, ROPE, TWINE, AND ALL SYNTHETIC MATERIAL FROM THE ROOTS, TRUNK, OR CROWN OF PLANT.
- REMOVE EXCESS SOIL ABOVE ROOT COLLAR.
- PLANT TREES AND SHRUBS SO THAT THE ROOT COLLAR IS 2" ABOVE FINISHED GRADE OR SEVERAL INCHES ABOVE GRADE IF PLANT IS INSTALLED IN POOR SOILS.
- PLANT TREES AND SHRUBS WITH SAME ORIENTATION AS WHEN HARVESTED FROM THE NURSERY OR TO SHOWCASE THE MOST AESTHETIC VIEW.
- PLANT ALL TREES WITH THREE SLOW RELEASE FERTILIZER PACKETS, SPACED EQUIDISTANT AROUND THE EDGE OF THE ROOT BALL.
- PLANT ALL SHRUBS WITH ONE SLOW RELEASE FERTILIZER PACKET, PLACED BELOW THE ROOTING SYSTEM.
- WATER AND TAMP BACKFILL AND ROOTS OF ALL NEWLY SET PLANT MATERIAL SO THE SOIL AND ROOTS ARE THOROUGHLY SOAKED AND AIR POCKETS ARE REMOVED.
- FOR INDIVIDUAL TREES & SHRUBS PLANTED IN TURF AREAS, PROVIDED CONTINUOUS 3" SOIL SAUCER TO CONTAIN WATER & MULCH (TREES ON SLOPES SHALL BE SAUCERED ON THE DOWNSHILL SIDE).
- INSTALL 3" THICK SHREDDED HARDWOOD BARK MULCH 3'-0" DIA. FOR DECIDUOUS TREES AND ALL INDIVIDUAL SHRUBS IN LAWN AREAS, 5'-0" DIA. FOR EVERGREEN TREES. KEEP MULCH 2" AWAY FROM TRUNKS.
- STAKING - ONLY STAKE EVERGREEN TREES 5'-0" OR GREATER IN HEIGHT OR TREES THAT ARE UNABLE TO REMAIN UPRIGHT AFTER PLANTING. TREES WILL BECOME STRONGER FASTER WHEN THE TOP 2/3 OF THE TREE IS FREE TO SWAY. DO NOT ATTACH WIRES DIRECTLY TO TREES OR THROUGH HOSES - UTILIZE GROMMETED, SYNTHETIC STRAPS AT LEAST 2" WIDE AROUND THE TREE, ATTACH STRAPPING TO STAKE WITH WIRE. STAKE ONLY WHEN NECESSARY. STAKES SHOULD BE DRIVEN DEEPLY INTO THE GROUND TO PREVENT DISLODGING. CHECK AT LEAST EVERY THREE MONTHS FOR BINDING OR OTHER PROBLEMS. STAKES AND TIRES SHOULD BE REMOVED SIX MONTHS TO ONE YEAR AFTER PLANTING.
- LIGHT POLES AND BOLLARDS SHOWN ARE FOR REFERENCE ONLY. SEE OFFICIAL SITE LIGHTING PLAN FOR OFFICIAL LIGHT POLE LOCATIONS. SITE UTILITIES SHOWN ARE FOR REFERENCE ONLY. SEE OFFICIAL SITE CIVIL DRAWINGS FOR OFFICIAL SITE UTILITY LOCATIONS.
- REFER TO SPECIFICATIONS 32 93 00 PLANTS AND 32 92 00 TURF AND GRASSES FOR ADDITIONAL INFORMATION.

**2 LANDSCAPE NOTES**

REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION


 SHEET NUMBER:  
**L201**

 PROJECT MANAGER: DMJ  
 PROJECT NUMBER: 210709.01  
 DATE: 10.10.2022

 all in  
 SHEET:  
**SITE LANDSCAPE DETAILS**

 NORTH ARROW: