

# **DEMOLITION/CLEARING NOTES**

- 1. BOUNDARY INFORMATION TAKEN FROM A GIS DATA AND TOPOGRAPHIC INFORMATION PROVIDED BY TIDEMARK LAND SERVICES. SURVEY DATED
- 2. CONTRACTOR SHALL REMOVE EXISTING TREES, CONCRETE, ASPHALT AND OTHER EXISTING STRUCTURES INDICATED ON PLAN. CONTRACTOR TO
- 3. PROTECT ADJACENT CURBS, TREES, BUILDINGS, UTILITIES AND OTHER ITEMS TO REMAIN FROM DAMAGE. CONTRACTOR SHALL BE RESPONSIBLE
- 4. CONTRACTOR SHALL VERIFY LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO BEGINNING WORK, BOTH PUBLIC AND PRIVATE. CONTRACTOR IS
- FULLY RESPONSIBLE FOR ALL UNDERGROUND UTILITIES AND SHALL REPAIR ANY DAMAGE AS A RESULT OF THIS CONTRACT.
- IMMEDIATELY TO ALFRED BENESCH & COMPANY FOR DECISION.
- 6. CONTRACTOR SHALL MAKE EVERY EFFORT TO SAVE ADDITIONAL TREES WHEREVER FEASIBLE.
- 7. NO SOIL DISTURBANCE OR COMPACTION, CONSTRUCTION MATERIALS, TRAFFIC, BURIAL PITS, TRENCHING OR OTHER LAND DISTURBING ACTIVITY
- ALLOWED IN THE TREE SAVE AREA. 8. CLEARING LIMITS ON THE PLAN INDICATE THE EXTENT OF ALL MAJOR
- CLEARING REQUIRED, CONTRACTOR IS ALSO RESPONSIBLE FOR ANY INCIDENTAL CLEARING REQUIRED FOR MINOR DISCREPANCIES IN GRADE, UTILITY OR STORM PIPE INSTALLATIONS, EROSION CONTROL MEASURES,

# Sheet List Table

Sheet umber	Sheet Title
C100	EXISTING CONDITIONS & DEMOLITION PLAN
C200	SITE PLAN
C201	RETAINING WALL PROFILES
C300	EROSION CONTROL NOTES
C301	EROSION CONTROL PLAN - PRE DEVELOPMENT
C302	EROSION CONTROL PLAN - POST DEVELOPMENT
C303	GRADING & DRAINAGE PLAN
C304	GRADING AND DRAINAGE ENLARGEMENTS
C305	STORM PROFILES
C400	UTILITY PLAN
C401	UTILITY PLAN & PROFILE
C500	CONSTRUCTION DETAILS
C501	CONSTRUCTION DETAILS
C502	CONSTRUCTION DETAILS
C503	CONSTRUCTION DETAILS
C504	CONSTRUCTION DETAILS
C505	CONSTRUCTION DETAILS
C600	LANDSCAPE PLAN

# **LEGEND**

LLGLIAD	
<del>- o -</del>	EXISTING SIGN
EIP	EXISTING IRON PIN
<b>\(\phi\)</b>	EXISTING LIGHT POLE
0	EXISTING UTILITY POLE
R/W	RIGHT-OF-WAY
НС	ACCESSIBLE SPACE
	EXISTING TREE TO REMAIN
	EXISTING TREE TO BE REMOVE
	EXISTING FIRE HYDRANT
$\otimes^{WV}$	EXISTING WATER VALVE
⊠ <sup>WM</sup>	EXISTING WATER METER
(S)	EXISTING SEWER MANHOLE
D	EXISTING STORM MANHOLE
	EXISTING DRAINAGE STRUCTURE
осо	EXISTING CLEANOUT
+XXX.X	EXISTING SPOT ELEVATION
$\otimes^{GV}$	EXISTING GAS VALVE
⊠ <sup>GM</sup>	EXISTING GAS METER


×	OR \\\\\	EXISTING ITEMS TO BE REMOVED
		EXISTING PAVEMENT TO BE REMOVED

	SAWCUT LINE
=====	EXISTING CURB AND GUTTER
	PROPERTY LINE
xx	EXISTING FENCE
UGE	EXISTING UNDERGROUND ELECTRIC LIN
OH/U	EXISTING OVERHEAD ELECTRIC LINE
T	EXISTING UNDERGROUND TELEPHONE L
——FO/C——	EXISTING FIBER OPTIC LINE
——————————————————————————————————————	EXISTING SANITARY SEWER LINE
W	EXISTING WATER LINE


SS	EXISTING SANITARY SEWER LINE
W	EXISTING WATER LINE
G	EXISTING GAS LINE
xxx	EXISTING CONTOUR LINE

	TEMPORARY TREE PROTECTION BARRICADE
~~~	EXISTING TREELINE
- E	EXISTING EASEMENT










Project no: 17000385 Date: 02.17.21

Sheet Title:

Revisions:

**EXISTING CONDITIONS & DEMOLITION PLAN** 



# SITE DEVELOPMENT DATA

PROJECT NAME: BELMONT COMMUNITY RECREATION CENTER PROJECT ADDRESS: 1401 CATAWBA STREET, BELMONT, NC 28012 OWNER: CITY OF BELMONT PLANS PREPARED BY: BENESCH ZONING: IC-D JURISDICTION: CITY OF BELMONT PROPOSED USE: RECREATION CENTER TAX PARCEL #: 222095 WATERSHED DISTRICT: WS-IV-CA BUILDING HEIGHT: 45' 8" \_\_ Feet, Stories: \_\_\_\_\_2\_ BUILDING COVERAGE: 33,959 Sq. Ft. GROSS FLOOR AREA: 42,025 Sq. Ft. LOT SIZE: 4.5 Sq. Ft. Acres YARD REQUIREMENTS: Setback (front): 25 Ft. from R/W, Side Yard (L): 25 Ft.
Rear Yard: 25 Ft Side Yard (R): 25 Ft.

Rear Yard: REQUIRED BUFFERS: Front: NO / YES \_\_ Ft. Rear: NO / YES \_\_ Ft. Side (L): NO / YES \_\_ Ft. REQUIRED SCREENING Front: NO / YES Side (L): NO / YES Rear: Side (L): NO / YES Side (R): NO / YES Parking, Dumpster & Utilities Only: NO / YES

184 SP. includes: 7 (2 van sp.)

VEHICLE PARKING DATA: EXISTING PARKING: 81 SP. includes: 3 accessible sp. NET LOSS W/ PARKING LOT TIE IN 106 SP. includes: 4 accessible sp.

ALL SIGNAGE WILL BE APPROVED AND PERMITTED SEPARATELY.

PROJECT TIMETABLE:

FEBRUARY 2021 - MAY 2021 CONSTRUCTION BALANCE OF WORK BEGINS: JULY 2021 OCTOBER 2022

SITE LIGHTING (PARKING LOT AND PEDESTRIAN) IS TO BE PROVIDED BY DUKE ENERGY. BENESCH IS CURRENTLY COORDINATING THIS PLAN WITH DUKE. PLAN TO BE SUBMITTED WHEN AVAILABLE.

EXISTING SIGN


# **LEGEND**


<del></del>	PROPOSED SIGN
EIP	EXISTING IRON PIN
ф	EXISTING LIGHT POLE
0	EXISTING UTILITY POLE
R/W	RIGHT-OF-WAY
HC	ACCESSIBLE SPACE
	EXISTING TREE TO REMAIN
	EXISTING FIRE HYDRANT
#	# OF PARKING SPACES
ę	CENTERLINE
R	ACCESSIBLE RAMP
• B	PROPOSED BOLLARD
=====	EXISTING CURB AND GUTTER
	PROPOSED CURB AND GUTTER
	PROPOSED FLUSH CURB AND GUTTER
	PROPERTY LINE
——— E———	EXISTING EASEMENT
xx	EXISTING FENCE
——●——	PROPOSED FENCE
OH/U	EXISTING OVERHEAD UTILITY LINE
	EXISTING ASPHALT PAVEMENT
	PROPOSED STANDARD DUTY ASPHALT PAVEMENT

15 30

PROPOSED HEAVY DUTY ASPHALT PAVEMENT

PROPOSED VEHICULAR CONCRETE PAVEMENT






1315 Cataw Belmont, Nor OM


Project no: 17000385 Date: 02.17.21

Sheet Title:


Revisions:

SITE PLAN











Wall 2 Profile





GENERAL CONTRACTOR SHALL EMPLOY PROFESSIONAL ENGINEER, LICENSED IN THE STATE OF NORTH CAROLINA, TO PREPARE & SEAL FULL CONSTRUCTION SHOP DRAWINGS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

- 1. TYPICAL SECTION SHOWING FULL RANGE OF WALL HEIGHTS & CONDITIONS, GRID PLACEMENTS.
- 2. WALL ELEVATION INDICATING TOP, BOTTOM & EXTENT OF WALL, GRID SPACING. WALL HEIGHT/GEOGRID SCHEDULE FOR ALL CONDITIONS GIVING LENGTH, SPACING, GRID SPECIFICATIONS, ETC.
- 4. WALL CAPPING DETAIL. 5. CONSTRUCTION SPECIFICATIONS FOR ALL MATERIALS, METHODS, EXECUTIONS.
- THE ABOVE DATA SHALL BE SUBMITTED TO THE CONSULTANT FOR APPROVAL PRIOR TO BEGINNING EARTHWORK.
- APPROVED MANUFACTURERS: VERSA-A-LOK, KEYSTONE, RIDGEROCK, ALLAN BLOCK, OR APPROVED EQUAL.
- CONTRACTOR SHALL SUBMIT WALL FOR REQUIRED BUILDING PERMITS.
- CONTRACTOR SHALL PROVIDE ALL WALL CERTIFICATIONS OR SPECIAL INSPECTIONS IF REQUIRED. FOOTING SYSTEM MUST BE INSTALLED DURING WALL CONSTRUCTION (GENERAL CONTRACTOR'S WALL INSTALLER MUST COORDINATE POST LOCATIONS WITH FENCE OR RAILING INSTALLER).











Eo

 $\mathbf{\Omega}$ Project no: 17000385 Date: 02.17.21

Revisions:

Sheet Title:

**RETAINING** WALL **PROFILES** 

# SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes			
Site Area Description		Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b)	High Quality Water (HQW) Zones	7	None
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e)	Areas with slopes flatter than 4:1	14	<ul> <li>-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zone</li> <li>-10 days for Falls Lake Watershed unless there is zero slope</li> </ul>

**Note:** After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

# GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
<ul> <li>Temporary grass seed covered with straw or other mulches and tackifiers</li> </ul>	Permanent grass seed covered with straw or other mulches and tackifiers
<ul> <li>Hydroseeding</li> </ul>	Geotextile fabrics such as permanent soil
Rolled erosion control products with or	reinforcement matting
tol and	

- Geotextile fabrics such as permanent soil reinforcement matting without temporary grass seed Hydroseeding Shrubs or other permanent plantings covered Appropriately applied straw or other mulch Plastic sheeting with mulch
  - Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed

# POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures. Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.

PART II

Self-inspections are required during normal business hours in accordance with the table

below. When adverse weather or site conditions would cause the safety of the inspection

personnel to be in jeopardy, the inspection may be delayed until the next business day on

SELF-INSPECTION, RECORDKEEPING AND REPORTING

4. Provide ponding area for containment of treated Stormwater before discharging

**SECTION A: SELF-INSPECTION** 

5. Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

# **EQUIPMENT AND VEHICLE MAINTENANCE**

- Maintain vehicles and equipment to prevent discharge of fluids. Provide drip pans under any stored equipment.
- Identify leaks and repair as soon as feasible, or remove leaking equipment from the
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

# LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff
- from upland areas and does not drain directly to a storm drain, stream or wetland. Cover waste containers at the end of each workday and before storm events or
- provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds. Empty waste containers as needed to prevent overflow. Clean up immediately if

9. On business days, clean up and dispose of waste in designated waste containers.

containers overflow. 8. Dispose waste off-site at an approved disposal facility.

# PAINT AND OTHER LIQUID WASTE

- Do not dump paint and other liquid waste into storm drains, streams or wetlands. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- I. Containment must be labeled, sized and placed appropriately for the needs of site. 5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

# EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- 3. Provide stable stone access point when feasible. Stabilize stockpile within the timeframes provided on this sheet and in accordance
- with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.

# HERBICIDES, PESTICIDES AND RODENTICIDES Store and apply herbicides, pesticides and rodenticides in accordance with label Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of

CONCRETE WASHOUTS

lot perimeter silt fence.

spills or overflow.

approving authority

Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately. Do not stockpile these materials onsite.

SCINCRETE VASHOLIT STRUCTURE HEERS TO BE CLEARY NAMED VITH SERVICE NOTING SEVICE.

. Do not discharge concrete or cement slurry from the site.

and state solid waste regulations and at an approved facility.

types of temporary concrete washouts provided on this detail.

be pumped out and removed from project.

products, follow manufacturer's instructions.

Dispose of, or recycle settled, hardened concrete residue in accordance with local

Manage washout from mortar mixers in accordance with the above item and in

addition place the mixer and associated materials on impervious barrier and within

Install temporary concrete washouts per local requirements, where applicable. If an

review and approval. If local standard details are not available, use one of the two

Do not use concrete washouts for dewatering or storing defective curb or sidewalk

sections. Stormwater accumulated within the washout may not be pumped into or

discharged to the storm drain system or receiving surface waters. Liquid waste must

Locate washouts at least 50 feet from storm drain inlets and surface waters unless it

install protection of storm drain inlet(s) closest to the washout which could receive

can be shown that no other alternatives are reasonably available. At a minimum,

Locate washouts in an easily accessible area, on level ground and install a stone

entrance pad in front of the washout. Additional controls may be required by the

Install at least one sign directing concrete trucks to the washout within the project

Remove leavings from the washout when at approximately 75% capacity to limit

components when no longer functional. When utilizing alternative or proprietary

overflow events. Replace the tarp, sand bags or other temporary structural

At the completion of the concrete work, remove remaining leavings and dispose of

in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance

limits. Post signage on the washout itself to identify this location.

alternate method or product is to be used, contact your approval authority for

**HAZARDOUS AND TOXIC WASTE** 

caused by removal of washout.

- Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment.
- 3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.

# NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

**EFFECTIVE:** 04/01/19

SCHERETE VASHBUT STRUCTURE HEERS TO ME CLEARY HARRED VIT SUBMICE HOTTING DEVICE.

ABOVE GRADE VASHOUT STRUCTURE

## which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record. Inspection records must include: (1) Rain gause Daily rainfall amount If no daily rain gauge observations are made during weekend or oliday periods, and no Individual day rainfall information good working available, record the cumulative rainattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as zero." The permittee may use another rain-monitoring device identification of the measures inspected Date and time of the inspection, calendar days Name of the person performing the inspection ind within 24 urs of a rai Indication of whether the measures were operating vent <u>></u> 1.0 inch in Description of maintenance needs for the measure, escription, evidence, and date of corrective actions taken Date and time of the inspection, discharge outralls (SDCs) and within 24 Name of the person performing the inspectio iurs of a rain Evidence of indicators of stormwater pollution such as oil indication of visible sediment leaving the site, Description, evidence, and date of corrective actions take of the following shall be made: ind within 24 Actions taken to clean up or stabilize the sediment that has left. hours of a rain the site limits. Description, evidence, and date of corrective actions taken, and vent ≥ 1.0 inch in vetlands onsite 7 calendar days stream has visible increased turbidity from the construction and within 24 activity, then a record of the following shall be made accessible) vent ≥ 1.0 inch in Records of the required reports to the appropriate Division Regional Office per Part III, Section C. Item (2)(a) of this permit After each phase The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm of grading stabilization drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent

measures have been provided within the required

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

timeframe or an assurance that they will be provided as

# SELF-INSPECTION, RECORDKEEPING AND REPORTING

NORTH CAROLINA

**B** Environmental Quality

# 1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

I and date each E&SC measure on a copy, a approved E&SC plan or complete, date ign an inspection report that lists each measure shown on the approved E&SC. This documentation is required upon the I installation of the E&SC measures or if. &SC measures are modified after initial llation.  I and date a copy of the approved E&SC or complete, date and sign an inspection of the indicate completion of the truction phase.  I and date a copy of the approved E&SC or complete, date and sign an inspection of the truction phase.
or complete, date and sign an inspection of the truction phase.  I and date a copy of the approved E&SC
rt to indicate compliance with approved and cover specifications.
olete, date and sign an inspection report
I and date a copy of the approved E&SC or complete, date and sign an inspection of the completion of the ctive action.
The same of the sa

(a) This General Permit as well as the Certificate of Coverage, after it is received.

(b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

## PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- (a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items,
- (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit, (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include
- properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems, (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,
- (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- (f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

# SELF-INSPECTION, RECORDKEEPING AND REPORTING SECTION C: REPORTING 1. Occurrences that Must be Reported

Permittees shall report the following occurrences: (a) Visible sediment deposition in a stream or wetland.

(b) Oil spills if:

They are 25 gallons or more,

- They are less than 25 gallons but cannot be cleaned up within 24 hours,
- They cause sheen on surface waters (regardless of volume), or They are within 100 feet of surface waters (regardless of volume).
- Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- (d) Anticipated bypasses and unanticipated bypasses.
- (e) Noncompliance with the conditions of this permit that may endanger health or the

# 2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800)

Reporting Timeframes (After Discovery) and Other Requirements

Occurrence	Reporting Timetrames (Arter Discovery) and Other Requirements
(a) Visible sed ment deposition in a stream or wetland	<ul> <li>Within 24 hours, an oral or electronic notification.</li> <li>Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case by case basis.</li> <li>If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired waters conditions.</li> </ul>
(b) Oil spills and release of hazardous substances per item 1(b)-(c) above	• Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(c) Anticipated bypasses (40 CFR 122 41(m)(3))	<ul> <li>A report at least ten days before the date of the bypass, if possible.</li> <li>The report shall include an evaluation of the anticipated quality and effect of the bypass.</li> </ul>
(d) Unanticipated bypasses [40 CFR i 122.41(m)(3)]	Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass.
(e) Noncompliance with the conditions of this permit that may endanger health or the environment [40 CFR 122.41(I)(7)]	Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance; including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue, and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(1)(6)]. Division staff may waive the requirement for a written report on a

# NORTH CAROLINA # Environmental Quality

# TOTAL DISTURBED AREA: 4.1 ACRES **EROSION CONTROL/GROUND STABILIZATION NOTES:**

SOIL STABILIZATION SHALL BE ACHIEVED ON ANY AREA OF A SITE WHERE LAND-DISTURBING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED ACCORDING TO THE FOLLOWING SCHEDULE: 1A. ALL PERIMETER DIKES, SWALES, PERIMETER SLOPES AND ALL SLOPES

STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1) SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY

1B. ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY

2. CONDITIONS - IN MEETING THE STABILIZATION REQUIREMENTS ABOVE, THE FOLLOWING CONDITIONS OR EXEMPTIONS SHALL APPLY:

2B. ALL SLOPES 50' IN LENGTH OR GREATER SHALL APPLY THE GROUND

COVER WITHIN 7 DAYS EXCEPT WHEN THE SLOPE IS FLATTER THAN 4:1. SLOPES

2A. EXTENSIONS OF TIME MAY BE APPROVED BY THE PERMITTING AUTHORITY BASED ON WEATHER OR OTHER SITE-SPECIFIC CONDITIONS THAT MAKE COMPLIANCE IMPRACTICABLE.

LESS THAN 50' SHALL APPLY GROUND COVER WITHIN 14 DAYS EXCEPT WHEN SLOPES ARE STEEPER THAN 3:1, THE 7 DAY REQUIREMENT APPLIES. 2C. ANY SLOPED AREA FLATTER THAN 4:1 SHALL BE EXEMPT FROM THE 7

2D. SLOPES 10' OR LESS IN LENGTH SHALL BE EXEMPT FROM THE 7 DAY GROUND COVER REQUIREMENT EXCEPT WHEN THE SLOPE IS STEEPER THAN

2E. FOR PORTIONS OF PROJECTS WITHIN THE SEDIMENT CONTROL COMMISSION-DEFINED HIGH QUALITY WATER ZONE (15A NCAC 04A. 0105), STABILIZATION WITH GROUND COVER SHALL BE ACHIEVED AS SOON AS PRACTICABLE BUT IN ANY EVENT ON ALL AREAS OF THE SITE WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACT.

- 3 ADDITIONAL MEASURES TO CONTROL FROSION AND SEDIMENT MAY BE REQUIRED BY A REPRESENTATIVE OF NCDEQ STAFF, ANY LAND-DISTURBING ACTIVITY >1 ACRE REQUIRES COMPLIANCE WITH ALL CONDITIONS OF THE GENERAL PERMIT TO DISCHARGE STORM WATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (PERMIT NO.NCG010000), ANY PERMIT NONCOMPLIANCE IS A VIOLATION OF THE CLEAN WATER ACT AND MAY REQUIRE ENFORCEMENT
- 4. DISTURBED AREAS DRAINING GREATER THAN ONE ACRE MUST HAVE AN EROSION CONTROL MEASURE THAT DRAINS FROM THE WATER SURFACE
- 5. REQUIRED ARMY CORPS 404 PERMIT AND WATER QUALITY 401 CERTIFICATION MUST BE OBTAINED FOR STREAM DISTURBANCES OVER 150
- 6. ANY BORROW OR WASTE MATERIAL SHALL BE TAKEN/PLACED ON A SITE THAT HAS AN ACTIVE APPROVED GRADING PERMIT. IF THIS IS NOT OBTAINABLE, THEN CONTRACTOR MAY SUBMIT PLAN FOR APPROVAL TO NCDEO PRIOR TO ANY OFF-SITE BORROW/WASTE AREAS BEING DENUDED.
- 7. ANY GRADING BEYOND THE DENUDED LIMITS SHOWN ON THE PLAN IS A VIOLATION OF THE NCDEQ EROSION CONTROL ORDINANCE AND IS

AND ANY GRADING OPERATIONS STARTING ON THIS SITE.

- 8. GRADING MORE THAN ONE ACRE WITHOUT AN APPROVED EROSION CONTROL PLAN IS A VIOLATION OF THE NCDEQ EROSION CONTROL ORDINANCE AND IS SUBJECT TO A FINE.
- 9 ANY AND ALL SITE FINES IMPOSED BY NCDEQ OR ANY OTHER GOVERNING AGENCY SHALL BE PAID BY THE GRADING CONTRACTOR.
- 10. SLOPES SHALL BE GRADED NO STEEPER THAN 2:1. FILL SLOPES GREATER THAN 10' REQUIRE ADEQUATE TERRACING.
- 11. SOIL TYPES:
- CfB, CECIL URBAN LAND; CLASS B
- LdB2, LLOYD SANDY CLAY LOAM; CLASS B - LdD2, LLOYD SANDY CLAY LOAM; CLASS B

12. NAME OF RECEIVING WATER COURSE: CATAWBA RIVER

13. CLASSIFICATION OF RECEIVING WATER COURSE: WS-IV, B; CA

# **CONSTRUCTION SEQUENCE:**

DAY GROUND COVER REQUIREMENT.

- 1. CONTACT NCDEQ EROSION CONTROL INSPECTOR TO INFORM HIM THAT CONSTRUCTION IS READY TO BEGIN
- 2. SET UP AN ON-SITE PRE-CONSTRUCTION CONFERENCE WITH THE NCDEQ EROSION CONTROL INSPECTOR, CITY OF BELMONT, CONTRACTOR, AND BENESCH TO DISCUSS EROSION
- INSTALL CONSTRUCTION ENTRANCE WITH CULVERT AT 13TH STREET, SKIMMER BASIN, PERIMETER SILT FENCE, CHECK DAMS AND DIVERSION DITCHES. DEMO AND CLEAR ONLY AS NECESSARY TO INSTALL THESE MEASURES. USE MATERIAL EXCAVATED FROM SEDIMENT BASIN TO CONSTRUCT BERM FOR DIVERSION DITCHES. STABILIZE BASIN SLOPES AND DIVERSION DITCHES WITH MATTING IMMEDIATELY AFTER CONSTRUCTION.
- 5. INSTALL INITIAL (BYPASS) STORM SEWER ALONG PRIVATE DRIVE.
- 6. INSTALL SEDIMENT TRAP AND STABILIZE.
- 7. CONTACT NCDEQ EROSION CONTROL INSPECTOR TO INSPECT INITIAL MEASURES. BEGIN DEMOLITION OF EXISTING INFRASTRUCTURE.
- 8. INSTALL REMAINING CONSTRUCTION ENTRANCES. CLEAR AND GRUB THE REMAINING SITE WITHIN THE DISTURBED LIMITS. INSTALL REMAINING TEMPORARY INITIAL PHASE DIVERSIONS
- 9. COMPLETE NCDEQ SELF INSPECTION REPORT FOR THE INITIAL PHASE EROSION CONTROL.
- 10. MINIMIZE THE EXPOSURE OF BARE SOIL AT ALL TIMES.
- 11. INSTALL INLET PROTECTION AS SHOWN ON SHEETS C301 AND C302 AS STORM DRAINAGE IS INSTALLED.
- 12. ONLY WATER FROM ROOF DRAINS SHOULD ENTER THE STORM PIPE THAT PASSES BY THE BASINS.
- 13. STABILIZE ALL NEW DENUDED AREAS WITH TEMPORARY SEEDING AND MULCH. SEE SEEDING SCHEDULE FOR SEED TYPE, DATES, AND RATES FOR DISTURBED AREAS WITH GRADED SLOPES FLATTER THAN 3:1 SEE FROSION CONTROL BLANKET NOTE (THIS SHEET) FOR SEEDING ON DISTURBED AREAS WITH GRADED SLOPES AT 3:1 OR STEEPER
- 14. WHEN STORM DRAINAGE IS INSTALLED, CONTRIBUTING DRAINAGE AREAS ARE STABILIZED AND PERMISSION IS GRANTED BY THE INSPECTOR, REMOVE SKIMMER BASIN AND SEDIMENT
- 15. AFTER BASIN IS REMOVED, GRADES ARE TO FINISH ELEVATION. COMPLETE PAVING AND SIDEWALK. MAT ANY NEWLY DISTURBED AREAS.
- 16. COMPLETE ALL CONSTRUCTION WITHIN PROJECT LIMITS. CONTINUE TO STABILIZE ALL OPEN AREAS WITHIN STABILIZATION REQUIREMENTS WHERE LAND-DISTURBING ACTIVITIES HAVI TEMPORARILY OR PERMANENTLY CEASED.
- 17. EROSION CONTROL MEASURES DIRECTLY AFFECTED BY THIS CONTRACT SHALL BE MAINTAINED/REMOVED UNDER THIS CONTRACT. DEVICES SHALL BE MAINTAINED TO MAX. 50% CAPACITY UNTIL AREAS THEY SERVE ARE FULLY STABILIZED.
- 18. PROVIDE PERMANENT GRASSING FOR ALL DISTURBED AREAS.
- 19. CONTACT NCDEQ FOR PERMISSION TO REMOVE EROSION CONTROL DEVICES.
- 20. REMOVE ALL EROSION CONTROL DEVICES. SPREAD AND SEED ACCUMULATED SEDIMENT
- 21. ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE N.C. EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL, U.S. DEPT. OF AGRICULTURE, AND THE SCS EROSION CONTROL ORDINANCE.
- 22. THE CONTRACTOR SHALL DILIGENTLY AND CONTINUOUSLY MAINTAIN ALL EROSION CONTROL DEVICES AND STRUCTURES TO MINIMIZE EROSION.
- 23. STOCKPILE AREAS AS SHOWN ARE ONLY APPROXIMATE AND IT IS PERMISSIBLE FOR THE CONTRACTOR TO CHANGE AS NECESSARY, AS LONG AS IT DOES NOT OBSTRUCT ANY EROSION CONTROL MEASURES, IS NOT LOCATED WITHIN 50' OF A STORM DRAIN, BASIN OR STREAM, AND DOES NOT EXCEED 2:1 SLOPE.

# **SELF INSPECTION REQUIREMENTS**

CONSTRUCTION ACTIVITIES NCG010000.

BE MADE AVAILABLE ON THE SITE.

- 1. SELF-INSPECTIONS WILL BE PERFORMED IN ACCORDANCE WITH THE NPDES GENERAL PERMIT FOR
- 2. ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES, INCLUDING SEDIMENTATION CONTROL BASINS, SEDIMENTATION TRAPS, SEDIMENTATION PONDS, ROCK DAMS, TEMPORARY DIVERSIONS, TEMPORARY SLOPE DRAINS, ROCK CHECK DAMS, SEDIMENT FENCE OR BARRIERS, ALL FORMS OF INLET PROTECTION, STORM DRAINAGE FACILITIES, ENERGY DISSIPATERS, STABILIZATION METHODS OF OPEN CHANNELS, AND GROUND COVER SHALL BE INSPECTED BY THE GENERAL CONTRACTOR.
- THE DIMENSIONS OF THE BASINS SHALL BE CHECKED AND COMPARED TO THE DIMENSIONS ON THE APPROVED SEDIMENTATION AND EROSION CONTROL PLAN. NOTIFY BENESCH IF THE DIMENSIONS OF ANY OF THE EROSION CONTROL MEASURES DEVIATE FROM THE PLANS.
- A "SELF-INSPECTION REPORT FORM FOR LAND DISTURBING ACTIVITY" (AS REQUIRED BY NCGS 113A-54.1) IS AVAILABLE ON THE NCDEQ WEBSITE OR PROVIDED WITHIN THE PROJECT MANUAL. ALTERNATIVELY THE OWNER OR DESIGNATED REPRESENTATIVE COMPLETING THE INSPECTIONS MAY MAKE NOTATIONS ON THE COPY OF THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN THAT IS KEPT ON THE PROJECT SITE. DOCUMENTATION SHALL BE ACCOMPLISHED BY INITIALING AND DATING EACH MEASURE OR PRACTICE SHOWN ON A COPY OF THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN OR BY COMPLETING, DATING AND SIGNING AN INSPECTION REPORT THAT LISTS EACH MEASURE, PRACTICE OR DEVICE SHOWN ON THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN. ALL DOCUMENTATION AND/OR REPORTS OF INSPECTIONS MUST
- 5. THE SELF-INSPECTION REPORT IS TO BE COMPLETED AFTER EACH PHASE OF THE APPROVED EROSION AND
- SEDIMENTATION CONTROL PLAN IS COMPLETE. THESE PHASES APPLY FOR THIS PROJECT: 5.1. INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROL MEASURES;
- 5.2. CLEARING AND GRUBBING OF EXISTING GROUND COVER; 5.3. COMPLETION OF ANY PHASE OF GRADING OF SLOPES OR FILLS;
- 5.4. INSTALLATION OF STORM DRAINAGE FACILITIES; 5.5. COMPLETION OF CONSTRUCTION OR DEVELOPMENT;
- 5.6. ESTABLISHMENT OF PERMANENT GROUND COVER SUFFICIENT TO RESTRAIN EROSION.

NOTE: CONTRACTOR TO PROVIDE TREE PROTECTION AT THE COMMENCEMENT OF INITIAL EROSION CONTROL STAGE. SEE ADDITIONAL PLANS FOR TREE PROTECTION LOCATIONS.

ANY OFF-SITE BORROW AND WASTE REQUIRED FOR THIS PROJECT MUST COME FROM A SITE WITH AN APPROVED EROSION CONTROL PLAN, A SITE REGULATED UNDER THE MINING ACT OF 1971, OR A LANDFILL REGULATED BY THE DIVISION OF SOLID WASTE MANAGEMENT. TRASH/DEBRIS FROM DEMOLITION ACTIVITIES OR GENERATED BY ANY CTIVITIES ON SITE MUST BE DISPOSED OF AT A FACILITY REGULATED BY THE DIVISION OF SOLID WASTE MANAGEMENT EFFECTIVE: 04/01/19 OR PER DIVISION OF SOLID WASTE MANAGEMENT OR DIVISION OF WATER RESOURCES RULES AND REGULATIONS. [15A]

# **MAINTENANCE PLAN:**

ALL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL, BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGN.

2. SEDIMENT WILL BE REMOVED FROM THE TEMPORARY SEDIMENT TRAPS WHEN STORAGE

CAPACITY HAS BEEN APPROXIMATELY 50% FILLED. GRAVEL WILL BE CLEANED OR REPLACED

- WHEN THE SEDIMENT POOL NO LONGER DRAINS PROPERLY 3. SEDIMENT WILL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES ABOUT 0.5 FEET DEEP AT THE FENCE.
- ENGINEER MAY DIRECT THAT ADDITIONAL SILT FENCING OR EROSION CONTROL MATTING BE INSTALLED AT ANY TIME PRIOR TO FINAL ACCEPTANCE. 5. ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH THE DETAILS INCLUDED IN THESE PLANS UNLESS OTHERWISE DIRECTED BY THE ENGINEER IN

4. THE SEDIMENT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER. THE

6. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED ONCE THE ENTIRE SITE


# EROSION CONTROL BLANKET ALL DISTURBED AREAS WITH GRADED SLOPES AT 3:1 OR STEEPER SHALL RECEIVE THE

FOLLOWING EROSION CONTROL BLANKET:

70% STRAW FIBER (.35 LBS/SQ YRD.) 30% COCONUT FIBER (0.15 LBS/SQ. YRD.) NETTING ON BOTH SIDES, LENO WOVEN, 100% BIODEGRADABLE ORGANIC JUTE FIBER, 9.3 LBS./1000 SQ. FT. STAPLE WITH .11 GA. 8" U STAPLES AT 2' O.C. DOWN THE SLOPE AND 1.6' O.C. ACROSS THE

CONTRACTOR SHALL STRIP AND STOCK PILE EXISTING TOPSOIL STOCKPILE ENOUGH TO PLACE 6" OVER ENTIRE VEGETATED SITE. REVIEW SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS. TOPSOIL SHALL BE CLEAN, FREE OF ROOT, DEBRIS, ROCK AND STUMPS. CONTRACTOR SHALL PROVIDE A SOIL SAMPLE TEST OF EXISTING MATERIAL. CONTRACTOR SHALL AMEND EXISTING SOILS AS REQUIRED TO MEET THE SPECIFICATION.





Corp. NC license: F-1320


Project no: 17000385 Date: 02.17.21

Revisions:


**EROSION** 

Sheet Title:

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING







# Corp. NC license: F-1320


Project no: 17000385 Date: 02.17.21

Revisions:

**EROSION** CONTROL PLAN - PRE **DEVELOPMENT** 

# Alfred Benesch & Company 9 Perimeter Pointe Parkway, Suite 350





# Corp. NC license: F-1320

# Belmont Community Co

Project no:	17000385
Date:	02.17.21

Revisions:

EROSION
CONTROL
PLAN POST
DEVELOPMENT

Sheet No:

C302

NORTH



SCALE: 1"=30'

**LEGEND** 

EXISTING FIRE HYDRANT

EXISTING STORM MANHOLE

PROPOSED STORM MANHOLE

EXISTING CURB AND GUTTER

EXISTING CONTOUR LINE

PROPOSED CONTOUR LINE

EXISTING STORM DRAINAGE PIPE

PROPOSED STORM DRAINAGE PIPE

TEMPORARY SILT FENCE

EXISTING DRAINAGE STRUCTURE

PROPOSED DRAINAGE STRUCTURE

STONE OPENING IN TEMPORARY SILT FENCE

TEMPORARY INLET PROTECTION


TEMPORARY ROCK CHECK DAM

TEMPORARY GRAVEL ENTRANCE


PROP. EROSION CONTROL MATTING

OUTLET PROTECTION

LIMITS OF GRADING/CONSTRUCTION







Project no: 17000385 Date: 02.17.21

Sheet Title:

**Revisions:** 


**GRADING DRAINAGE PLAN** 

Sheet No:


15 30


SCALE: 1"=30'


Call before you dig.



SCALE: 1"=20'







Seals:

Corp. NC license: F-1320

Project no: Revisions:

Sheet Title:

**GRADING** AND **DRAINAGE ENLARGEMENTS** 

Sheet No:

SCALE: 1"=10'







1315 Catawba Street Belmont, North Carolina Communit


Belmont Project no: 17000385 Date: 02.17.21 Revisions:

Sheet Title:

STORM **PROFILES** 

Sheet No: C305

SCALE: 1"=40'



Project no: 17000385

Date: 02.17.21

Revisions:

Seals:

041664

Corp. NC license: F-1320


1315 Cataw Belmont, Nor


Sheet Title:

UTILITY PLAN


Sheet No:

C400














SEAL 041664

Output

O

Belmont Community Cent
1315 Catawba Street
Belmont, North Carolina

Project no: 17000385

Date: 02.17.21

Sheet Title:

Revisions:

UTILITY PLAN & PROFILE

Sheet No: C 4 0 1

# **GENERAL NOTES:**

- 1. FILTER FABRIC FENCE SHALL BE A MINIMUM OF 32" IN WIDTH AND SHALL HAVE A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING.
- WOVEN FILTER FABRIC BE USED WHERE SILT FENCE IS TO REMAIN FOR A PERIOD OF MORE THAN 30 DAYS.
- 3. STEEL POSTS SHALL BE 5'-0" IN HEIGHT AND BE OF THE SELF-FASTENER ANGLE STEEL TYPE.
- 4. WIRE FENCING SHALL BE AT LEAST #10 GAGE WITH A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING.

6. WIRE MESH SHALL BE MIN. 14 GAGE WITH MAXIMUM 6"

- 5. TURN SILT FENCE UP SLOPE AT ENDS.
- OPENINGS. ORANGE SAFETY FENCE IS REQUIRED AT BACK OF SILT FENCE (WITHIN 5 FT.) WHEN GRADING IS ADJACENT TO SWIM BUFFERS OR WETLANDS (REFER TO SWIM BUFFER GUIDELINES).

# **MAINTENANCE NOTES:**

- 1. INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFTER
- EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY. 2. SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR
- DECOMPOSE OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY. 3. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE FENCE. TAKE CARE TO AVOID UNDERMINING THE FENCE
- DURING CLEANOUT. 4. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS AND BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

END OF FLARED

SECTION

' MIN.

FILTER FABRIC LAF

(IF NEEDED)

NATURAL

GRADE

NOTE: MINIMUM

 $H=\frac{2}{3}$  PIPE DIAMETER

FILTER FABRIC

SECTION B-B

**ELEVATION** 

# Temporary Silt Fence NCDEQ STD. 6.62

\* d50 (SEE FIG. 8.06 A&B "NC SEDIMENT AND

Riprap Outlet Protection

EROSION CONTROL MANUAL'

DMAX = 1.5 X d50

T = 1.5 X DMAX

— STEEL POST

WIRE FENCING

FABRIC

WOVEN FILTER

BACKFILL TRENCH

AND COMPACT

THOROUGHLY

— EXISTING GROUND

1. A STABILIZED ENTRANCE PAD OF 2"-3" COURSE AGGREGATE SHALL BE LOCATED WHERE TRAFFIC WILL ENTER OR LEAVE THE CONSTRUCTION SITE ONTO A PUBLIC STREET.

—\_**⊁** PUBLIC STREET

SOIL STABILIZATION

FABRIC UNDER 2"-3"

COURSE AGGREGATE

- 2. FILTER FABRIC OR COMPACTED CRUSHER RUN STONE MAY BE USED AS A BASE FOR THE CONSTRUCTION ENTRANCE. 3. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC STREETS OR EXISTING PAVEMENT. THIS MAY
- REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS WARRANT AND REPAIR OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. 4. ANY SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PUBLIC STREETS MUST BE
- REMOVED IMMEDIATELY. 5. WHEN APPROPRIATE, WHEELS MUST BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTERING A PUBLIC STREET. WHEN WASHING IS REQUIRED, IT SHALL BE DONE IN AN

AREA STABILIZED WITH CRUSHED STONE WHICH DRAINS INTO AN APPROVED SEDIMENT

6. SOIL STABILIZATION FABRIC (AS SPECIFIED BY THE DESIGNER) SHALL BE USED.

# **MAINTENANCE NOTES:**

FES

TSD 1

TSD 2

FES 52

FES 100 9.0

8.0

8.0

9.0

9.5

1. MAINTAIN THE GRAVEL PAD IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOPDRESSING WITH 2-INCH STONE. AFTER EACH RAINFALL, INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT AND CLEAN IT OUT AS NECESSARY. IMMEDIATELY REMOVE ALL OBJECTIONABLE MATERIALS SPILLED, WASHED OR TRACKED ONTO TO PUBLIC ROADWAYS.

1. CLASS OR MEDIAN SIZE OF RIPRAP AND LENGTH, WIDTH AND DEPTH OF APRON TO BE DESIGNED

EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL FOR RIPRAP APRON DESIGN

3. RIPRAP SHOULD EXTEND UP BOTH SIDES OF THE APRON AND AROUND THE END OF THE PIPE OR CULVERT AT THE DISCHARGE OUTLET AT A MAXIMUM SLOPE OF 2:1 AND A HEIGHT NOT LESS

4. THERE SHALL BE NO OVERFLOW FROM THE END OF THE APRON TO THE SURFACE OF THE RECEIVING CHANNEL. THE AREA TO BE PAVED OR RIPRAPPED SHALL BE UNDERCUT SO THAT THE INVERT OF THE APRON SHALL BE ATTHE SAME GRADE (FLUSH) WITH THE SURFACE OF THE RECEIVING CHANNEL. THE APRON SHALL HAVE A CUTOFF OR TOE WALL AT THE DOWNSTREAM

5. THE WIDTH OF THE END OF THE APRON SHALL BE EQUAL TO THE BOTTOM WIDTH OF THE

7. THE PLACING OF FILL, EITHER LOOSE OR COMPACTED IN THE RECEIVING CHANNEL SHALL NOT

9. FILTER FABRIC SHALL BE INSTALLED ON COMPACTED SUBGRADE PRIOR TO PLACEMENT OF RIP

8. NO BENDS OR CURVES IN THE HORIZONTAL ALIGNMENT OF THE APRON WILL BE PERMITTED.

10. ANY DISTURBED AREA FROM END OF APRON TO RECIEVING CHANNEL MUST BE STABILIZED.

DESIGN DATA TAKEN FROM THE USDA NOMOGRAPH LOCATED

OUTLET PROTECTION SUMMARY

W2

9.25

9.25

10.25

10.75

10.50

9

RR

10

10

10

10

12

IN THE NC SEDIMENT AND EROSION CONTROL MANUAL

3.75

3.75

3.75

3.75

4.50

2. REFER TO THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES'

# Temporary Gravel Construction Entrance NCDEQ STD. 6.06

THAN TWO THIRDS THE PIPE DIAMETER OR CULVERT HEIGHT.

RECEIVING CHANNEL. MAXIMUM TAPER TO RECEIVING CHANNEL 5:1

6. ALL SUBGRADE FOR STRUCTURE TO BE COMPACTED TO 95% OR GREATER.

# SEEDING MIXTURE SPECIES

RYE (GRAIN)

RATE (LB/ACRE)

<u>SEEDING DATES</u> MOUNTAINS—AUG. 15 — DEC. 30 COASTAL PLAIN AND PIEDMONT-AUG. 15 - DEC. 30

SOIL AMENDMENTS FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 1,000 LB/ACRE 10-10-10

APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING

WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

REPAIR AND RE-FERTILIZE DAMAGED AREAS IMMEDIATELY. TOPDRESS WITH 50 LB/ACRE OF NITROGEN IN MARCH. IF NECESSARY TO EXTENT TEMPORARY COVER BEYOND JUNE 15, OVERSEED WITH 50 LB/ACRE KOBE (PIEDMONT AND COSTAL PLAIN) OR KOREAN (MOUNTAINS) LESPEDEZA IN LATE FEBRÚARY OR EARLY MARCH.

# TEMPORARY SEEDING RECOMMENDATIONS FOR FALL SEEDING MIXTURE

SPECIES RATE (LB/ACRE) GERMAIN MILLET

IN THE PIEDMONT AND MOUNTAINS, A SMALL-STEMMED SUDANGRASS MAY BE SUBSTITUTED AT A RATE OF 50 LB/ACRE.

MOUNTAINS-MAY 15 - AUG. 15 PIEDMONT-MAY 1 - AUG. 15 COASTAL PLAIN-APR. 15 - AUG. 15

SOIL AMENDMENTS FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10 FERTILIZER.

APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A

MULCH ANCHORING TOOL. EFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED,

# REFERTILIZE, AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE. TEMPORARY SEEDING RECOMMENDATIONS FOR SUMMER

NCDEQ STD. 6.10

- FILL SLOPE

Seeding Specifications for Temporary Erosion Control

# SEEDING MIXTURE RATE (LB/ACRE) SPECIES RYE (GRAIN) ANNUAL LESPEDEZA (KOBE IN PIEDMONT AND COSTAL PLAIN,

KOREAN IN MOUNTAINS) OMIT ANNUAL LESPEDEZA WHEN DURATION OF TEMPORARY COVER IS NOT TO EXTEND BEYOND JUNE.

MOUNTAINS-ABOVE 2500 FEET: FEB. 15 - MAY 15 BELOW 2500 FEET: FEB. 1 - MAY 1 PIEDMONT-JAN. 1 - MAY 1 COASTAL PLAIN-DEC. 1 - APRIL 15

SOIL AMENDMENTS FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10 FERTILIZER.

APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.


REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE, AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

# TEMPORARY SEEDING RECOMMENDATIONS FOR LATE WINTER AND EARLY SPRING

- COMPACTED

**SECTION** 

BERM



19-GUAGE —

4' MAX.

AND GRAVEL INLET PROTECTION


# **CONSTRUCTION SPECIFICATIONS**


- UNIFORMLY GRADE A SHALLOW DEPRESSION APPROACHING INLET. 2. DRIVE 5-FOOT STEEL POSTS 2 FEET INTO THE GROUND SURROUNDING THE INLET. SPACE POST EVENLY AROUND THE PERIMETER OF THE INLET, A MAXIUM OF 4 FEET APART. SURROUND THE POSTS WITH WIRE MESH HARDWARE CLOTH. SECURE THE WIRE MESH TO THE STEEL
- POSTS AT THE TOP, MIDDLE, AND BOTTOM. PLACING A 2-FOOT FLAP OF WIRE MESH UNDER THE GRAVEL FOR ANCHORING IS RECOMMENDED.
- 4. PLACE CLEAN GRAVEL (NCDOT#5 OR #57 STONE) ON A 2:1 SLOPE WITH A HEIGHT OF 16 INCHES AROUND THE WIRE, AND SMOOTH TO AN EVEN GRADE.
- ONCE THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE ACCUMULATED SEDIMENT, AND ESTABLISH FINAL GRADING ELEVATIONS. 6. COMPACT THE AREA PROPERLY AND STABILIZED IT WITH GROUNDCOVER.

INSPECT INLETS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2 INCH OR GREATER) RAINFALL EVENT. CLEAR THE MESH WIRE OF ANY DEBRIS OR OTHER OBJECTS TO PROVIDE ADEQUATE FLOW FOR SUBSEQUENT RAINS. TAKE CARE NOT TO DAMAGE OR UNDERCUT THE WIRE MESH DURING SEDIMENT REMOVAL. REPLACE STONE AS NEEDED.

6.52, BLOCK AND GRAVEL INLET PROTECTION 6.54, ROCK DOUGHNUT INLET PROTECTION

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATION FOR ROADS AND STRUCTURES








# Temporary Diversion

NATURAL GRADE


# DIRECTION OF THE INSPECTOR Temporary Stone Opening in Silt Fence



\ Straw Wattle

DIA: 12" IN.

# L = THE DISTANCE SUCH THAT POINTS A AND B ARE EQUAL ELEVATIONS




- 1. PLACE STONE TO THE LINES AND DIMENSIONS SHOWN IN THE PLAN ON A FILTER FABRIC
- 2. KEE THE CENTER STONE SECTION AT LEAST 9 INCHES BELOW NATURAL GROUND LEVEL WHERE THE DAM ABUTS THE CANNEL BANKS.
- 3. EXTEND STONE AT LEAST 1.5 FEET BEYOND THE DITCH BANK TO KEEP WATER FROM CUTTING AROUND THE ENDS OF THE CHECK DAM. 4. SET SPACING BETWEEN DAMS TO ASSURE THAT THE ELEVATION AT THE TOP OF THE


LOWER DAM IS THE SAME AS THE TOE ELEVATION OF THE UPPER DAM.

PROTECT THE CHANNEL AFTER THE LOWEST CHECK DAM FROM HEAVY FLOW THAT COULD 6. MAKE SURE THAT THE CHANNEL REACH ABOVE THE MOST UPSTREAM DAM IS STABLE 7. ENSURE THAT OTHER AREAS OF THE CHANNEL, SUCH AS CULVERT ENTRANCES BELOW THE

CHECK DAMS, ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FORM DISPLACED STONES.

Check Dam NCDEQ STD. 6.83





TYPICAL INLET PROTECTION DETAIL 1" REBAR FOR BAG REMOVAL FORM INLET SEDIMENT SACK INSTALLATION DETAIL EXPANSION RESTRAINT -(1/4" NYLON ROPE, 2" FLAT WASHERS) - DUMP STRAPS **BAG DETAIL** MAINTENANCE NOTES:

1. SILT SACKS SHALL BE INSPECTED BY THE FINANCIALLY RESPONSIBLE PARTY OR HIS AGENT IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS NEEDED SHALL BE MADE IMMEDIATELY.

SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE SILT SACK STILL IS NECESSARY, THE DEVICE SHALL BE REPLACED PROMPTLY. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN DEPOSITS REACH APPROX. HALF THE HEIGHT OF

Temporary Silt Sack





1315 Cat selmont, l 0


**M** 17000385 Project no: 02.17.21

Sheet Title:

Date:

Revisions:

CONSTRUCTION **DETAILS** 



CROSS-SECTION VIEW

# **GENERAL NOTES:**

- 1. CONSTRUCTION OPERATION SHALL BE CARRIED OUT IN SUCH A MANNER THAT FROSION AND WATER POLLUTION IS MINIMIZED, CLEAR, GRUB, AND STRIP THE AREA UNDER THE EMBANKMENT OF ALL VEGETATION AND ROOT MAT. REMOVE ALL SURFACE SOIL CONTAINING HIGH AMOUNTS OF ORGANIC MATTER AND STOCKPILE OR DISPOSE OF IT PROPERLY. PLACE TEMPORARY SEDIMENT CONTROL MEASURES BELOW BASIN AS NEEDED
- 2. THE FILL MATERIAL FOR THE EMBANKMENT SHALL BE FREE OF ROOTS OR OTHER WOODY VEGETATION AS WELL AS OVERSIZED STONES, ROCKS, ORGANIC MATERIAL, OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE BEING CONSTRUCTED. PLACE THE FILL IN LIFTS NOT TO EXCEED 9 INCHES, AND MACHINE COMPACT IT. OVERFILL THE EMBANKMENT 6 INCHES TO ALLOW FOR SETTLEMENT. SPILLWAYS SHOULD NOT BE CONSTRUCTED THROUGH FILL SECTIONS. ALL
- 3. ALL CUT AND FILL SLOPES SHALL BE 2:1 OR FLATTER, UNLESS CERTIFIED BY REGISTERED GEOTECHNICAL

SPILLWAYS SHOULD BE LINED AND/OR INSTALL RIPRAP.

- 4. SEDIMENT BASIN EMBANKMENTS SHOULD BE PROVIDED WITH EROSION CONTROL AND STABILIZATION.
- 5. STORAGE AREA IS SHOWN AS RECTANGULAR FOR ILLUSTRATIVE PURPOSES ONLY. AND MAY BE CONSTRUCTED IN ANY SHAPE PROVIDED THE MINIMUM STORAGE VOLUME REQUIREMENT IS MET. THE BASIN SHOULD ALSO B ORIENTED SUCH THAT THE FILTER AND THE MAIN FLOW OF WATER AND SEDIMENT ARE ON OPPOSITE ENDS ON THE LONGER BASIN DIMENSIONS.
- 6. REQUIRED STORAGE IS 1800 CUBIC FEET OF STORAGE VOLUME PER ACRES OF DISTURBED AREA. MINIMUM REQUIRED SURFACE AREA REQUIRED SHALL BE 325 ST PER CFS OF Q10 PEAK INFLOW.
- 7. THE LENGTH OF THE STONE OUTLET (SPILLWAY) IS TO BE BASED ON A 10 YEAR STORM. EARTHEN SPILLWAYS-INSTALL THE SPILLWAY IN UNDISTURBED SOIL TO THE GREATEST EXTENT POSSIBLE. THE ACHIEVEMENT OF PLANNED ELEVATIONS, GRADES, DESIGN, WIDTH, AND ENTRANCE AND EXIT CHANNEL SLOPES ARE CRITICAL TO THE SUCCESSFUL OPERATION OF THE SPILLWAY. THE SPILLWAY SHOULD BE LINED WITH LAMINATED PLASTIC OR IMPERMEABLE GEOTEXTILE FABRIC. THE FABRIC MUST BE WIDE AND LONG ENOUGH TO COVER THE BOTTOM AND SIDES AND EXTEND ONTO THE TOP OF THE DAM FOR ANCHORING IN A TRENCH THE EDGES MAY BE SECURED WITH 8-INCH STAPLES OR PINS. THE FABRIC MUST BE LONG ENOUGH TO EXTEND DOWN THE SLOPE AND EXIT ONTO STABLE GROUND. THE WIDTH OF THE FABRIC MUST BE ONE PIECE, NOT JOINED OR SPLICED; OTHERWISE WATER CAN GET UNDER THE FABRIC. IF THE LENGTH OF THE FABRIC IS INSUFFICIENT FOR THE ENTIRE LENGTH OF THE SPILLWAY, MULTIPLE SECTIONS, SPANNING THE COMPLETE WIDTH, MAY BE USED. THE UPPER SECTIONS(S) SHOULD OVERLAP THE LOWER SECTIONS(S) SO THAT WATER CANNOT FLOW UNDER THE FABRIC. SECURÈ THE UPPER EDGES AND SIDES OF THE FABRIC IN A TRENCH WITH STAPLES OR PINS.
- 8. INLETS-DISCHARGE WATER INTO THE BASIN IN A MANNER TO PREVENT EROSION. USE TEMPORARY SLOPE DRAINS OR DIVERSIONS WITH OUTLET PROTECTION TO DIVERT SEDIMENT-LADEN WATER IN UPPER END OF THE
- 9. EROSION CONTROL CONSTRUCT THE STRUCTURE SO THAT THE DISTURBED AREA IS MINIMIZED. DIVERT SURFACE WATER AWAY FROM BARE AREAS. COMPLETE THE EMBANKMENT BEFORE THE AREA IS CLEARED STABILIZE THE EMERGENCY SPILLWAY EMBANKMENT AND ALL OTHER DISTURBED AREAS ABOVE THE CREST OF THE PRINCIPAL SPILLWAY IMMEDIATELY AFTER CONSTRUCTION.
- 10. WHENEVER TOPOGRAPHY ALLOWS, THE BASIN LENGTH SHOULD BE TWICE (2X) THE BASIN WIDTH, TO ALLOW FOR SETTLING. BAFFLES SHOULD BE PROVIDED IN THE BASIN, BASED ON SECTION 6.65.
- 11. CLEANOUT STAKES SHALL BE PLACED IN ALL SEDIMENT BASINS AT THE LOW POINT IN THE BASIN. THE STAKES SHALL BE MARKED SHOWING THE HALF FULL, CLEANOUT POINT, OF THE BASIN.
- 12. SAFETY FENCING 3' HIGH SHOULD BE PLACED AROUND ALL SEDIMENT TRAPS THAT ARE IN VICINITY TO NON-CONSTRUCTION PEDESTRIAN TRAFFIC AND NOT ALREADY PROTECTED BY FENCING.
- 13. FOR SLOPES GREATER THAN 10' IN LENGTH AND PROTECTED BY SILT FENCE AT THE TOE OF THE SLOPE,
- 14. THE BERM ON SEDIMENT BASINS SHALL BE SEEDED ONCE FINAL GRADE HAS BEEN REACHED. THE SILT FENCE AND BASIN MAY BE REMOVED IF PERMISSION HAS BEEN GRANTED BY NCDENR LAND DEVELOPMENT INSPECTOR AFTER THE GRASS HAS GERMINATED AND STABLE GROUND HAS BEEN ESTABLISHED.
- 15. ALL EROSION CONTROL MEASURES ARE TO BE DESIGNED TO THE STANDARDS DOCUMENTED IN THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT, HEALTH, AND NATURAL RESOURCES, EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL.

# SKIMMER CONSTRUCTION SPECIFICATIONS


- 1. SHAPE THE BASIN TO THE SPECIFIED DIMENSIONS. PREVENT THE SKIMMING DEVICE FROM SETTLING INTO THE MUD BY EXCAVATING A SHALLOW PIT UNDER THE SKIMMER OR PROVIDING A LOW SUPPORT UNDER THE SKIMMER OF STONE OR TIMBER.
- 2. PLACE THE BARREL (TYPICALLY 4-INCH LAYERS AND COMPACT IT UNDER AND AROUND THE PIPE OR AT LEAST THE SAME DENSITY AS THE ADJACENT EMBANKMENT. CARE MUST BE TAKEN NOT TO RAISE THE PIPE FROM THE FIRM CONTACT WITH ITS FOUNDATION WHEN COMPACTING UNDER THE PIPE HAUNCHES. PLACE A MINIMUM DEPTH OF 2 FEET OF COMPACTED BACKFILL OVER THE PIPE SPILLWAY BEFORE CROSSING IT WITH CONSTRUCTION EQUIPMENT. IN NO CASE SHOULD THE PIPE CONDUIT BE INSTALLED BY CUTTING A TRENCH THROUGH THE DAM AFTER THE EMBANKMENT IS COMPLETE.
- 3. ASSEMBLE THE SKIMMER FOLLOWING THE MANUFACTURER'S INSTRUCTIONS. OR AS DESIGNED.
- 4. LAY THE ASSEMBLED SKIMMER ON THE BOTTOM OF THE BASIN WITH THE FLEXIBLE JOINT AT THE INLET OF THE BARREL PIPE. ATTACH THE FLEXIBLE JOINT TO THE BARREL PIPE AND POSITION THE SKIMMER OVER THE EXCAVATED PIT OR SUPPORT. BE SURE TO ATTACH A ROPE TO THE SKIMMER AND ANCHOR IT TO THE SIDE OF THE BASIN. THIS WILL BE USED TO PULL THE SKIMMER TO THE SIDE FOR MAINTENANCE.

# <u>MAINTENANCE</u>

- 1. INSPECT SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (ONE-HALF INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE—HALF THE HEIGHT OF THE FIRST BAFFLE. PULL THE SKIMMER TO ONE SIDE SO THAT THE SEDIMENT UNDERNEATH IT CAN BE EXCAVATED. EXCAVATE THE SEDIMENT FROM THE ENTIRE BASIN, NOT JUST AROUND THE SKIMMER OR THE FIRST CELL. MAKE SURE VEGETATION GROWING IN THE BOTTOW OF THE BASIN DOES NOT HOLD DOWN THE SKIMMER.
- 2. REPAIR THE BAFFLES IF THEY ARE DAMAGED. RE-ANCHOR THE BAFFLES IF WATER IS FLOWING UNDERNEATH OR AROUND THEM.
- 3. IF THE SKIMMER IS CLOGGED WITH TRASH AND THERE IS WATER IN THE BASIN, USUALLY JERKING ON THE ROPE WILL MAKE THE SKIMMER BOB UP AND DOWN AND DISLODGE THE DEBRIS AND RESTORE FLOW. IF THIS DOES NOT WORK, PULL THE SKIMMER OVER TO THE SIDE OF THE BASIN AND REMOVE THE DEBRIS. ALSO CHECK THE ORIFICE INSIDE THE SKIMMER TO SEE IT IF IS CLOGGED; IF SO REMOVE THE DEBRIS.
- 4. IF THE SKIMMER ARM OR BARREL PIPE IS CLOGGED, THE ORIFICE CAN BE REMOVED AND THE OBSTRUCTION CLEARED WITH A PLUMBER'S SNAKE OR BY FLUSHING WITH WATER. BE SURE AND REPLACE THE ORIFICE BEFORE REPOSITIONING THE SKIMMER.
- 5. CHECK THE FABRIC LINED SPILLWAY FOR DAMAGE AND MAKE ANY REQUIRED REPAIRS WITH FABRIC THAT SPANS THE FULL WIDTH OF THE SPILLWAY. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE SKIMMER AND POOL AREAS.
- 6. FREEZING WEATHER CAN RESULT IN ICE FORMING IN THE BASIN. SOME SPECIAL PRECAUTIONS SHOULD BE TAKEN IN THE WINTER TO PREVENT THE SKIMMER FROM PLUGGING WITH ICE.

						DATA E	BLOCK							
BASIN NO.	DRAINAGE AREA (AC.)	DENUDED AREA (AC.)	(CFS)	BASIN VOLUME		BASIN SURFACE AREA		CLEANOUT DEPTH	н	Z		Т	w	SKIMME
				REQUIRED (CU. FT.)		REQUIRED (SQ. FT.)	PROVIDE (SQ. FT.)	(FT.) H/2	(FEET)	(FEET)	(FEET)	(FEET)	(FEET)	ø (IN.)
PRE	1.85	1.85	7.33	3330	6810	2381	4520	1.00	2.00	5.00	15.0	2.00	5.00	3.0
POST	2.30	0.64	13.89	1152	6810	4514	4520	1.00	2.00	5.00	15.0	2.50	5.00	3.0

# Temporary Skimmer Basin



	DATA BLOCK												
TRAP	DRAINAGE AREA (AC.)	DENUDED AREA (AC.)	(CFS)	TRAP VOLUME		TRAP SURFACE AREA		CLEANOUT DEPTH	X		н	Z	w
NO.						REQUIRED (SQ. FT.)		(FT.) H/2	(FEET)	(FEET)	(FEET)	(FEET)	(FEET)
1	2.75	2.66	10.55	9576	9946	4590	7041	1.27	2.53	10	1.53	5	7

# <u>MAINTENANCE</u>

- 1. INSPECT SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (ONE-HALF INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE HEIGHT OF THE FIRST BAFFLE.
- 2. REPAIR THE BAFFLES IF THEY ARE DAMAGED. RE-ANCHOR THE BAFFLES IF WATER IS FLOWING UNDERNEATH OR AROUND THEM.
- 3. CHECK THE FABRIC LINED SPILLWAY FOR DAMAGE AND MAKE ANY REQUIRED REPAIRS WITH FABRIC THAT SPANS THE FULL WIDTH OF THE SPILLWAY. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE POOL AREAS.


# Temporary Sediment Trap NCDENR STD. 6.60

# **GENERAL NOTES:**

- 1. CONSTRUCTION OPERATION SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION IS MINIMIZED. CLEAR, GRUB, AND STRIP THE AREA UNDER THE EMBANKMENT OF ALL VEGETATION AND ROOT MAT. REMOVE ALL SURFACE SOIL CONTAINING HIGH AMOUNTS OF ORGANIC MATTER AND STOCKPILE OR DISPOSE OF IT PROPERLY. HAUL ALL OBJECTIONABLE MATERIAL TO THE DESIGNATED DISPOSAL AREA. PLACE TEMPORARY SEDIMENT CONTROL MEASURES BELOW TRAP
- 2. THE FILL MATERIAL FOR THE EMBANKMENT SHALL BE FREE OF ROOTS OR OTHER WOODY VEGETATION AS WELL AS OVERSIZED STONES, ROCKS, ORGANIC MATERIAL, OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE BEING CONSTRUCTED. PLACE THE FILL IN LIFTS NOT TO EXCEED 9 INCHES, AND MACHINE COMPACT IT. OVERFILL THE EMBANKMENT 6 INCHES TO ALLOW FOR SETTLEMENT. SPILLWAYS SHOULD NOT BE CONSTRUCTED THROUGH FILL SECTIONS. ALL SPILLWAYS SHOULD BE LINED AND/OR RIPRAPPED.
- ALL CUT AND FILL SLOPES SHALL BE 2:1 OR FLATTER, UNLESS CERTIFIED BY REGISTERED GEOTECHNICAL ENGINEER.
- 4. SEDIMENT TRAP EMBANKMENTS SHOULD BE PROVIDED WITH EROSION CONTROL AND STABILIZATION.
- 5. STORAGE AREA IS SHOWN AS RECTANGULAR FOR ILLUSTRATIVE PURPOSES ONLY. AND MAY BE CONSTRUCTED IN ANY SHAPE PROVIDED THE MINIMUM STORAGE VOLUME REQUIREMENT IS MET. THE TRAP SHOULD ALSO BE ORIENTED SUCH THAT THE FILTER AND THE MAIN FLOW OF WATER AND SEDIMENT ARE ON OPPOSITE ENDS ON THE LONGER TRAP DIMENSIONS.
- 6. REQUIRED STORAGE IS 3600 CUBIC FEET OF STORAGE VOLUME PER ACRES OF DISTURBED AREA. MINIMUM REQUIRED SURFACE AREA REQUIRED SHALL BE 435 ST PER CFS OF Q10 PEAK INFLOW.
- 7. THE LENGTH OF THE STONE OUTLET (SPILLWAY) IS TO BE BASED ON A 10 YEAR STORM. EARTHEN SPILLWAYS-INSTALL THE SPILLWAY IN UNDISTURBED SOIL TO THE GREATEST EXTENT POSSIBLE. THE ACHIEVEMENT OF PLANNED ELEVATIONS, GRADES, DESIGN, WIDTH, AND ENTRANCE AND EXIT CHANNEL SLOPES ARE CRITICAL TO THE SUCCESSFUL OPERATION OF THE SPILLWAY. THE SPILLWAY SHOULD BE LINED WITH LAMINATED PLASTIC OR IMPERMEABLE GEOTEXTILE FABRIC. THE FABRIC MUST BE WIDE AND LONG ENOUGH TO COVER THE BOTTOM AND SIDES AND EXTEND ONTO THE TOP OF THE DAM FOR ANCHORING IN A TRENCH. THE EDGES MAY BE SECURED WITH 8-INCH STAPLES OR PINS. THE FABRIC MUST BE LONG ENOUGH TO EXTEND DOWN THE SLOPE AND EXIT ONTO STABLE GROUND. THE WIDTH OF THE FABRIC MUST BE ONE PIECE, NOT JOINED OR SPLICED; OTHERWISE WATER CAN GET UNDER THE FABRIC. IF THE LENGTH OF THE FABRIC IS INSUFFICIENT FOR THE ENTIRE LENGTH OF THE SPILLWAY, MULTIPLE SECTIONS, SPANNING THE COMPLETE WIDTH, MAY BE USED. THE UPPER SECTIONS(S) SHOULD OVERLAP THE LOWER SECTIONS(S) SO THAT WATER CANNOT FLOW UNDER THE FABRIC. SECURE THE UPPER EDGES AND SIDES OF THE FABRIC IN A TRENCH WITH STAPLES OR PINS.
- 8. INLETS-DISCHARGE WATER INTO THE TRAP IN A MANNER TO PREVENT EROSION. USE TEMPORARY SLOPE DRAINS OR DIVERSIONS WITH OUTLET PROTECTION TO DIVERT SEDIMENT-LADEN WATER IN UPPER END OF THE TRAP.
- 9. EROSION CONTROL CONSTRUCT THE STRUCTURE SO THAT THE DISTURBED AREA IS MINIMIZED. DIVERT SURFACE WATER AWAY FROM BARE AREAS. COMPLETE THE EMBANKMENT BEFORE THE AREA IS CLEARED. STABILIZE THE EMERGENCY SPILLWAY EMBANKMENT AND ALL OTHER DISTURBED AREAS ABOVE THE CREST OF THE PRINCIPAL SPILLWAY IMMEDIATELY AFTER CONSTRUCTION
- 10. WHENEVER TOPOGRAPHY ALLOWS, THE TRAP LENGTH SHOULD BE TWICE (2X) THE TRAP WIDTH, TO ALLOW FOR SETTLING. BAFFLES SHOULD BE PROVIDED IN THE TRAP, BASED ON SECTION 6.65.
- 11. CLEANOUT STAKES SHALL BE PLACED IN ALL SEDIMENT TRAPS AT THE LOW POINT IN THE TRAP. THE STAKES SHALL BE MARKED SHOWING THE HALF FULL, CLEANOUT POINT, OF THE TRAP.
- 12. SAFETY FENCING 3' HIGH SHOULD BE PLACED AROUND ALL SEDIMENT TRAPS THAT ARE IN VICINITY TO NON-CONSTRUCTION PEDESTRIAN TRAFFIC AND NOT ALREADY PROTECTED BY FENCING.
- 13. FOR SLOPES GREATER THAN 10' IN LENGTH AND PROTECTED BY SILT FENCE AT THE TOE OF THE SLOPE, SLOPE TERRACING WILL BE REQUIRED. 14. THE BERM ON SEDIMENT TRAPS SHALL BE SEEDED ONCE FINAL GRADE HAS BEEN REACHED. THE
- ESTABLISHED. 15. ALL EROSION CONTROL MEASURES ARE TO BE DESIGNED TO THE STANDARDS DOCUMENTED IN THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT, HEALTH, AND NATURAL RESOURCES, EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL.

SILT FENCE AND TRAPS MAY BE REMOVED IF PERMISSION HAS BEEN GRANTED BY NCDENR LAND

DEVELOPMENT INSPECTOR AFTER THE GRASS HAS GERMINATED AND STABLE GROUND HAS BEEN




GRADE THE BASIN SO THAT THE BOTTOM IS LEVEL FRONT TO BACK AND SIDE TO SIDE. INSTALL POSTS ACROSS THE WIDTH OF THE SEDIMENT TRAP, SEDIMENT BASIN AND/OR SKIMMER BASIN AS SHOWN.


- 3. STEEL POSTS SHOULD BE DRIVEN TO A DEPTH OF 24 INCHES, SPACED A MAXIMUM OF 4 FEET APART, AND INSTALLED UP THE SIDES OF THE BASIN AS WELL. THE TOP OF THE FABRIC SHOULD BE 6 INCHES HIGHER THAN THE INVERT OF THE SPILLWAY. TOPS OF BAFFLES SHOULD BE 2 INCHES LOWER THAN THE TOP OF THE BERMS.
- 4. BAFFLE MATERIAL SHALL BE 700 G/M2 COIR EROSION FABRIC INSTALL AT LEAST THREE ROWS OF BAFFLES BETWEEN THE INLET AND OUTLET DISCHARGE POINT. BASINS LESS THAN 20 FEET IN LENGTH MAY USE 2 BAFFLES THAT DIVIDES THE BASIN IN THIRDS.
- ADD A SUPPORT WIRE OR ROPE ACROSS THE TOP OF THE MEASURE TO PREVENT SAGGING. WRAP BAFFLE MATERIAL OVER THE TOP WIRE. ATTACH FABRIC TO A ROPE AND A SUPPORT STRUCTURE WITH ZIP TIES, WIRE, OR STAPLES. USE 3 TIES PER POST ALL WITHIN TOP 8" OF FABRIC.
- 8. THE BOTTOM AND SIDES OF THE FABRIC SHOULD BE ANCHORED IN A TRENCH 8" DEEP. IN LIEU OF EXCAVATING A TRENCH, THE FABRIC MAY BE INSTALLED WITH A PIECE OF EQUIPMENT SPECIFICALLY DESIGNED TO SLICE THE GROUND WITH A DISC.

- INSPECT BAFFLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
- BE SURE TO MAINTAIN ACCESS TO THE BAFFLES. SHOULD THE FABRIC OF A BAFFLE COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.

9. DO NOT SPLICE THE FABRIC, BUT USE A CONTINUOUS PIECE ACROSS THE BASIN.

 REMOVE SEDIMENT DEPOSITS WHEN IT REACHES HALF FULL TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE BAFFLES. TAKE CARE TO AVOID DAMAGING THE BAFFLES DURING CLEANOUT. SEDIMENT DEPTH SHOULD NEVER EXCEED HALF THE DESIGNED STORAGE DEPTH.





# **CONSTRUCTION SPECIFICATIONS:**

- THE TOP OF THE EARTH DIKE OVER THE INLET PIPE AND THOSE DIKES CARRYING WATER TOT HE PIPE SHALL BE AT LEAST 1.5 FEET HIGHER AT ALL POINTS THAN THE TOP OF THE INLET PIPE.
- 2. THE PIPE SHALL BE FLEXIBLE WITH WATER TIGHT CONNECTING BANDS. FLEXIBLE PIPE SHOULD BE STAKED ON EITHER SIDE.
- 3. A RIPRAP APRON SHALL BE PROVIDED AT THE OUTLET, IF EMPTYING INTO A DISTURBED AREA.
- 4. THE SOIL AROUND AND UNDER THE INLET PIPE AND ENTRANCE SECTION SHALL BE HAND TAMPED IN 4" LIFTS TO THE TOP OF THE EARTH DIKE.
- 5. FOLLOW-UP INSPECTION AND ANY NEEDED MAINTENANCE SHALL BE PERFORMED AFTER EACH STORM BY THE FINANCIALLY RESPONSIBLE PARTY OR HIS AGENT.
- 6. OUTLET PIPE SHOULD BE TAKEN OVER OR THROUGH ANY SILT FENCE, TAKING CARE NOT TO VOID THE EFFECTIVENESS OF THE SILT FENCE.










1315 elmor 0


Project no: 17000385 Date: 02.17.21 Revisions:

Sheet Title:

**DETAILS** 

CONSTRUCTION





MAINTENANCE NOTES

STANDARD CURB & GUTTER

STANDARD CURB & GUTTER

EQUALLY SPACED (3) #8 BARS

10" MAX. 2%

Ĩ "ẃ"@́3" o.c.

DEPRESSED

**GUTTER LINE** 

AND OVER

ON LIGHT GRADES

ELEVATION

#4 BARS "V"

PLAN OF TOP SLAB

4. ALL CATCH BASINS OVER 3'-6" IN DEPTH SHALL BE PROVIDED

WITH STEPS 12" ON CENTERS IN ACCORDANCE WITH NCDOT

5. CONCRETE BRICK MAY BE USED IN LIEU OF HARD COMMON

7. FOR 8'-0" IN HEIGHT OR LESS USE 8" WALL OVER 8'-0" IN

8. ALL PIPE IN STORM DRAIN STRUCTURE TO BE STRUCK EVEN WITH THE INSIDE WALL, GROUTED AND BRUSHED SMOOTH.

9. WEEP HOLE(S) SHALL BE PLACED IN BACK WALL. A STONE

10. BRICK SHALL BE BONDED WITH FULL HEADERS EVERY 3

HEIGHT USE 12" WALL TO 6'-0" FROM TOP OF WALL AND 8"

WALL FOR THE REMAINING 6'-0". QUANTITIES TO BE ADJUSTED

DRAIN CONSISTING OF 1 (ONE) CUBIC FOOT OF NUMBER 78M

STONE CONTAINED IN A BAG OF POROUS FABRIC SHALL BE

11. FRAME AND GRATE SHALL BE IN ACCORDANCE WITH NCDOT STD.

NO. 840.03 WITH DIRECTIONAL GRATES AS APPROPRIATE.

MORTAR JOINTS SHOULD BE BETWEEN  $\frac{1}{2}$ "  $\pm \frac{1}{8}$ " THICK. ALL CONCRETE TO BE 3000 P.S.I. COMPRESSIVE STRENGTH. 3. PRECAST CAN BE SUBSTITUTED. SUBMIT SHOP DRAWINGS ON

ALL STRUCTURES.

STD. #840.66.

6. JUMBO BRICK WILL BE PERMITTED.

CLAY BRICK.

ACCORDINGLY.


PLACED AT WEEP HOLE.

ON STEEP GRADES

NORMAL


**GUTTER LINE** 


- INSPECT ROLLED EROSION CONTROL PRODUCTS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT ( INCH OR GREATER) RAINFALL EVENT. REPAIR IMMEDIATELY.
- 2. GOOD CONTACT WITH THE GROUND MUST BE MAINTAINED AND EROSION MUST NOT OCCUR BENEATH 3. ANY AREAS OF THE RECP THAT ARE DAMAGED OR NOT IN CLOSE CONTACT WITH THE GROUND SHALL
- BE REPLACED AND STAPLED. 4. IF EROSION OCCURS DUE TO POORLY CONTROLLED DRAINAGE, THE PROBLEM SHALL BE FIXED AND
- THE ERODED AREA PROTECTED.
- 5. MONITOR AND REPAIR THE RECP AS NECESSARY UNTIL GROUND COVER IS ESTABLISHED.



6.17.11 Rev. 6/06

Rolled Erosion Control Products NCDEQ STD. 6.17





OR 4" SOLID CONCRETE BLOCKS MAY BE USED IN LIEU OF HARD COMMON CLAY BRICK. 6. FOR 8'-0" IN HEIGHT OR LESS USE 8" WALL OVER 8'-0" IN HEIGHT USE 12" WALL TO 6'-0" FROM TOP OF WALL AND 8" WALL FOR THE REMAINING 6'-0". QUANTITIES TO BE ADJUSTED ACCORDINGLY. ALL PIPE IN STORM DRAIN STRUCTURE TO BE STRUCK EVEN WITH THE INSIDE WALL, GROUTED AND BRUSHED ALL SLABS SHALL BE FORMED. FRAME AND GRATE FOR THIS STRUCTURE IN ALL SITUATIONS SHALL BE "US FOUNDRY" #4139 & #6429 OR APPROVED EQUAL WITH H20 LOADING CAPACITY. 10. REFER TO NCDOT STRUCTURE DETAILS FOR PIPE SIZES 11. USE CONCRETE MASONRY UNITS OR (2) 6" PRECAST GRADE RINGS TO SET GRATES. ALLOW FOR TOP 1' TO 12. PRE-CAST BOXES CAN BE SUBSTITUTED. SUBMIT SHOP DRAWINGS ON ALL STRUCTURES. CONC. PIPE CONC. **SECTION Y-Y** 0.313 | 0.037 | 0.871 | 0.020 | 0.032 0.976 0.031 0.047

**Drop Inlet Detail** 

Street Carolina vba rth 1315 Cat selmont, I 0  $\mathbf{\Omega}$ 

Seals:


041664

Corp. NC license: F-1320

17000385 Project no: Date: 02.17.21 Revisions:

Sheet Title:

**CONSTRUCTION DETAILS** 



DUAL RAMPS ANY RADII (4' MIN. FLOOR WIDTH)


848.05

DETECTABLE WARNING DOMES

Curb Ramp Detail

Concrete Wheelstop Detail





Street Carolina 0

Project no: 17000385 Date: 02.17.21 Revisions:


Sheet Title:


**CONSTRUCTION DETAILS** 


848.05

CURB RAMPS THROUGH MEDIAN ISLANDS, SINGLE RAMPS AT DUAL CROSSWALKS OR LIMITED R/W SITUATIONS, WILL BE HANDLED BY SPECIAL DETAILS.


CONTACT THE CONTRACT STANDARDS AND DEVELOPMENT UNIT FOR THE DETAILS OR FOR A SPECIAL DESIGN.















Concrete Steps with Handrail
N.T.S.










# vba rth ( Eo Belm

Project no: 17000385 Date: 02.17.21

Sheet Title:

Revisions:

SITE **CONSTRUCTION DETAILS** 




 $_{
m A}$  2 I/2" - I0" Reduced Pressure Principle Assembly

(Above Ground), N.T.S.

、3" Water Meter Vault





Corp. NC license: F-1320

Street Carolina 1315 Cataw Belmont, Nor Eo

P  $\mathbf{\Omega}$ 17000385

02.17.21

**CONSTRUCTION DETAILS** 

10. EACH CITY OF BELMONT REQUIRED BPA IS REQUIRED TO

BE TESTED BY A CITY OF BELMONT APPROVED

SYSTEM IN SERVICE.

CERTIFIED TESTER PRIOR TO PLACING THE WATER

TYPICAL LOCATION REQUIREMENT

FOR <u>ABOVE GROUND I</u>NSTALLATION N.T.S.

Full Specimen 15" O.C.


Stachys byzantina 'Big Ears' / Big Ears Lamb's Ear

# LANDSCAPE NOTES

- 1. MINIMUM TREE SIZE AT PLANTING IS 2" CALIPER AND 8' TALL FOR SINGLE-STEM TREES. ALL MULTI-STEM PLANTS MUST BE TREE FORM, MAXIMUM 3 TO 5 TRUNKS, AND MINIMUM
- 2. ALL NEW TREES MUST HAVE STRAIGHT TRUNKS WITH STRONG CENTRAL LEADERS
  INTACT TO THE TOP OF THE CROWN UNLESS MULTI-STEM TREES ARE SPECIFIED. ALL TREES SHALL BE TYPICAL OF THEIR SPECIES AND VARIETY, HAVE NORMAL GROWTH HABITS, HAVE WELL-DEVELOPED BRANCHES, BE VIGOROUS AND HAVE FIBROUS ROOT SYSTEMS. TREES WITH CO-DOMINANT BRANCHING WILL NOT BE ACCEPTED. TREES THAT HAVE BEEN SHEARED, TOPPED OR CUT BACK TO MULTIPLY THE BRANCHING STRUCTURE WILL NOT BE ACCEPTED. TREES SHALL BE FREE OF ABRASIONS, DAMAGE, DISEASE, PESTS AND CRACKS. ALL PRUNING CUTS GREATER THAN 1" DIAMETER SHALL HAVE CALLUS TISSUE FORMED PRIOR TO PLANTING. NO PRUNING CUT ON THE TRUNK SHALL
- BE MORE THAN ONE-HALF THE DIAMETER OF THE CENTRAL LEADER AT THE HEIGHT WHERE THE CUT WAS MADE. ROOT FLARES SHALL BE LOCATED AT GRADE. TREES WITH MORE THAN 2" OF SOIL COVERING THE ROOT BALL/FLARE FROM WILL NOT BE ACCEPTED. 3. SIZE OF PLANTS, SPREAD OF ROOTS AND SIZE OF BALLS SHALL BE IN ACCORDANCE WITH ANSI Z60.1 (LATEST EDITION) AS PUBLISHED BY THE AMERICAN NURSERY & LANDSCAPE
- 4. ALL TREES OF A PARTICULAR SPECIES AND VARIETY SHALL BE UNIFORM IN SIZE AND
- 1. PLASTIC HOSE PARTS WILL <u>NOT</u> BE ACCEPTED FOR TREE STAKING. SEE DETAILS AND
- SPECIFICATIONS FOR APPROVED STAKING METHOD/MATERIALS. 2. ALL STRAPPING, AND TOP  $\frac{1}{2}$  OF WIRE BASKET AND BURLAP MUST BE CUT AWAY AND
- REMOVED FROM ROOT BALL WHEN PLANTING. 3. FOR NEW PLANTING AREAS, REMOVE ALL PAVEMENT, GRAVEL SUB-BASE AND
- TILL AND AMEND THE TOP 24" OF EXISTING SOIL TO MEET TOPSOIL/ PLANTING MIX
- 4. ALL SAUCERS SHALL BE SOAKED WITH WATER AND MULCHED IMMEDIATELY FOLLOWING
- 5. THE TOP OF ALL ROOT BALLS FOR SHRUBS & GROUNDCOVERS SHALL BEAR THE SAME RELATIONSHIP TO FINISHED GRADE, AS BORN TO PREVIOUS GROWING CONDITIONS.
- 7. MULCH A MINIMUM 4 FOOT AREA AROUND EACH TREE AND MULCH A CONTINUOUS AREA AROUND ALL SHRUB BEDS, AS INDICATED ON THE PLAN. MULCH SHALL BE 3-4" THICK.
- 1. LARGE MATURING TREES MAY NOT BE PLANTED WITHIN 25' OF OVERHEAD POWER DISTRIBUTION OR TRANSMISSION LINES. IF TREES CONFLICT WITH POWER LINES OR
- SIGNS, CALL LANDSCAPE ARCHITECT TO RESOLVE BEFORE PLANTING. 2. CONTRACTOR IS RESPONSIBLE FOR HAVING ALL UNDERGROUND UTILITIES LOCATED AND CLEARLY PAINTED WITHIN 10 DAYS OF ANY GROUND DISTURBING ACTIVITY. OWNER WILL NOT PAY FOR UTILITY REPAIRS DUE TO FAILURE TO MARK AND OBSERVE UTILITY
- 3. ADJUST TREE PLANTING LOCATIONS TO AVOID UNDERGROUND UTILITIES- PLANT 15'
  FROM ALL UNDERGROUND UTILITIES (SEWER AND STORM DRAINAGE, GAS WATER, PHONE
- 1. THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR THE QUANTITY OF PLANTS SHOWN ON THE PLAN. ANY DISCREPANCIES BETWEEN QUANTITIES ON PLAN AND PLANT LIST SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT AND ANY FIELD ADJUSTMENTS OR QUANTITY ADJUSTMENTS MUST BE AUTHORIZED PRIOR TO
- 2. ALL PLANTS SHALL BE GUARANTEED TO BE IN HEALTHY CONDITION FOR ONE (1) YEAR AFTER ACCEPTANCE BY OWNER OF ALL PLANT MATERIAL
- 3. ALL DISTURBED AREAS SHALL BE SEEDED AS SPECIFIED. 4. SEE EROSION CONTROL/GRADING PLAN FOR ADDITIONAL TREE PRESERVATION NOTES.

THERE ARE NO EXISTING TREES WITH IN THE PROJECT LIMITS. REQUIRED TREE SAVE AREA TO BE PROVIDED IN WOODED AREA NORTH AND EAST OF CITY WORKS &





Sheet Title:

Date:


**Revisions:** 

**LANDSCAPE PLAN** 

Sheet No:







Project no: 17000385 02.17.21