CITY OF KETTERING
2020 ASPHALT OVERLAY PROGRAM
PROJECT NO. 04-120
STREET PAVING LIST

STREET	BEGIN LIMITS	END LIMITS	PAV'T AREA (SY)	OVERLAY DEPTH	441 ASPHALT SURFACE (TON)	441 ASPHALT INTERMEDIATE (TON)
FORRER BLVD	WILMINGTON PIKE	SMITHVILLE RD	6,776	2.5 INCH	593	395
SCHANTZ AVE	SOUTH DIXE	CORPORATION LIMIT	11,333	2.5 INCH	992	661
SWIGART RD	EAST RAHN RD	CORPORATION LIMIT	4,093	2.5 INCH	358	239
CLAYBOURNE RD	E STROOP RD	MARSHALL RD	4,783	1.5 inch	419	0
URBAN AVE	MARSHALL RD	CLAYBOURNE RD	1,140	1.5 inch	100	0
BERWIN AVE	MARSHALL RD	CLAYBOURNE RD	2,284	1.5 inch	200	0
CLOVERFIELD AVE	MARSHALL RD	CLAYBOURNE RD	2,076	1.5 inch	182	0
WHEATLAND AVE	MARSHALL RD	CLAYBOURNE RD	3,050	1.5 inch	267	0
VINEYARD DR	E STROOP RD	CLAYBOURNE RD	2,031	1.5 inch	178	0
OAKDALE AVE	TABOR AVE	CORPORATION LIMIT	3,438	1.5 inch	301	0
ASHMORE DR	MOLER AVE	TABOR AVE	3,185	1.5 inch	279	0
LAKEWOOD DR	MOLER AVE	TABOR AVE	4,360	1.5 inch	382	0
MOLER AVE	SMITHVILLE RD	RITCHFIELD DR	3,365	1.5 inch	294	0
RICHFIELD DR	MOLER AVE	TABOR AVE	5,423	1.5 inch	475	0
MAYL DR	FORRER BLVD	MOLER AVE	853	1.5 inch	75	0
SUNRAY RD	HOLLENDALE DR	E DAVID RD	4,793	1.5 inch	419	0
HOLLENDALE DR	SHROYER RD	ACKERMAN BLVD	6,458	1.5 inch	565	0
STONEBRIDGE RD	W STROOP RD	BIG HILL RD	6,563	1.5 inch	574	0
BLOSSOMHEATH RD	STONEBRIDGE RD	WINDING WAY	5,503	1.5 inch	482	0
HILLSIDE AVE	AVON WAY	W DOROTHY LN	2,396	1.5 inch	210	0
			83,903		**7,342**	**1,295**

*Note: The Pavement Milling limits will be determined in the field.