

April 10, 2020

Loomis Downtown Master Plan Phase 3

Town of Loomis

ADDENDUM NO. 1

TO ALL PROSPECTIVE CONSULTANTS:

Please incorporate the following revisions as part of the contract documents for subject project.

ITEM	PAGE OR DRAWING	LOCATION AND DESCRIPTION OF CHANGE
1.1	Technical Specifications Section 15-1.03D Relocate Boulders	Delete- there are not large rock anticipated on this project
1.2	Section 47 – EARTH RETAINING SYSTEM – Section 47-4.01D Quality Assurance.	Evidence of experience and insurance Shall be due at bid time.
1.3	Estimate	\$1,240,000 Base Bid \$1,480,000 Base Bid plus Bid Alternate
1.4	Plan Sheet C1	Delete note 5 callout near station 103+90
1.5	Working at Night	The project shall be bid as no night work. During construction, the Town may allow night work for certain operations on a case by case basis.
1.6	Compaction testing	Initial testing to be done by Town any retesting will be the responsibility of the Contractor.
1.7	Section 47-4.04 Payment – “Keystone Retaining Wall”	Revised Bid Quantity to 750 SF. SF includes the bottom base layer of stone to the top of wall. See Revised Bid Form
1.8	Revised Sheet 21 of 30	Added Note 2 to the attached plan sheet. ¾” tubing to be 1 lga minimum. 1” and 1-1/2” tubing to be HSS2 3/16” minimum.

1.9	N Line Cross Sections XS	Reference Sheet added for additional detail
1.10	S Line Cross Sections XS	Reference Sheet added for additional detail
1.11	Bid Alternate	No additional working days will be added for this work.
1.12	Soils Report	No soils report is available
1.13	Demo of PCC	Demolition of PCC will be paid in Roadway Excavation.
1.14	Section 39-3.04 Cold Planning Asphalt	Refer to Section 39-3.04 Cold Planning Asphalt Concrete Pavement of the State Standard Specifications. This includes the number of days between cold planning and pave back.

END OF ADDENDUM



Brit Snipes
Public Works Director

4-10-2020