



TOWN OF LOOMIS

3665 Taylor Road, Loomis CA 95650 • (916) 652-1840

ATTN: All Prospective Bidders
PROJECT: Boyington Road Paving and Dig Out Repairs Project
SUBJECT: **ADDENDUM NO. 1**

Based upon comments received, this Addendum is being issued to make the following changes or clarifications to the Contract Documents. In accordance with Public Contract Code § 4104.5 (b), the Town does not believe any of these changes to be a “material change” defined as having a substantial cost impact on the total bid. As such, the bid opening date shall remain as August 4, 2021 at 10:00am.

General Provisions:

- Section 3.10, Paragraph (c) calls for a 2-year warranty bond. This is inconsistent with other sections of the contract documents which call for a 1-year guarantee. Only a 1-year guarantee is required.

Special Provisions:

- Bid Item Descriptions, Traffic Striping. The description under Traffic Striping refers to payment by lump sum. This is wrong. Payment will be made based upon field measured quantities per the units stated on the Bid Schedule, for the various items of striping work.

Technical Provisions:

- Section 19- Hot Mix Asphalt (HMA), Paragraph 21-03C, Construction Sequencing, is clarified with no change to what is written. The reference to pavement replacement being completed on the same day as removal is only for “Remove and Replace HMA” (Dig-Outs) work scope. With proper tapers and signage, the road may remain cold-planed to allow crack sealing and dig out work to occur over subsequent days.

Plans:

- Page 2 – Dig Outs. The 6’ x 28’ dig out on Taylor Road at Walnut Street will go across a decorative thermoplastic stamped brick crosswalk. The Town will complete the restoration of the decorative brick thermoplastic, by others. Only the 12-inch white portion of the crosswalk at this location needs to be restored by the Contractor. Note that at this location there are also in-pavement. LED crosswalk lights. This system has been abandoned and does not need to be restored.
- Page 3 – Grinding Disposal Location. The work scope that consisted of transporting and disposing grindings along Rutherford Canyon has been withdrawn. Instead, the Contractor shall make arrangements to dispose of the grinding at an appropriate recycling facility and include this cost in the bid unit prices for those items that generate grindings. Contractor shall furnish tags to the Town, which the Town will use to document waste diversion.

Miscellaneous:

- Plan Holder’s List. The Town is not maintaining a plan holders list for this project.

Acknowledgement:

Receipt of this Addendum must be acknowledged by bidders. Acknowledgement may be made by placing the number “1” in the Signature Pages, Addenda Section of the Proposal Forms **or** by signing and submitting this page with the bid proposal.

Name of Firm

Printed Name of Person Signing

Signature

Date