



CITY OF PETALUMA

POST OFFICE BOX 61
PETALUMA, CA 94953-0061

ADDENDUM NO. 2

Hardin Lane Tank Recoating Project C67502328

May 16, 2024

This Addendum No. 2 modifies the Bidding Documents for the Hardin Lane Tank Recoating Project C67502328. This Addendum shall become part of the Contract and all provisions of the Contract shall apply thereto. Bidders shall acknowledge all Addendums in the Bid Schedule.

TECHNICAL SPECIFICATIONS CHANGE

Technical Specifications – Section 01 11 00 – Summary of Work – 1.03 Description of Bid Items – 8. Electrical Work – Page 3 – DELETE the description in section 8. Electrical Work and REPLACE with:

“This bid item shall include all labor, material, and equipment necessary to complete all electrical work, including but not limited to conduit, wiring, weather protective enclosures, replacing or adding intrusion switches, new electrical cabinet, removal of all cathodic protection devices, equipment and cabinet, removal of electrical cabinets for tank coating, replacing or relocating electrical components from old cabinet to new cabinet, site lighting, vault lighting and start-up, testing, and commissioning as required, complete in accordance with the Drawings and as specified herein.”

TECHNICAL CLARIFICATION TO CONTRACTORS – QUESTION AND RESPONSE

Question #1: Please clarify scope for CP specifically define "Replacement".

Spec - 1.03 D - 8. "Electrical Work" "removal and later replacement of cathodic protection devices and cabinet"

Response #1: The work regarding cathodic protection will include the removal of the protection system such as the wiring, the cabinet on the tank, etc.). The work will not include installing a new system – only the removal. The Technical Specifications section 01 11 00 – Summary of Work – 1.03 Description of Bid Items – 8. Electrical Work has been updated to reflect that and is attached.

Question #2: Is there any lead-based paint/hazardous material on the Hardin Lane Tank Recoating project? If there is, is there an Analysis Report?

Response #2: The coating on the tank is not Testing was done in March of 2023 that confirmed the tank does not have any lead-based paint. There is no analysis report.

Kevin McDonnell
Mayor

Brian Barnacle
Janice Cader-Thompson
Mike Healy
Karen Nau
Dennis Pocekay
John Shribbs
Councilmembers

Public Works & Utilities

City Engineer
11 English Street
Petaluma, CA 94952
Phone (707) 778-4303

Environmental Services

Ellis Creek Water
Recycling Facility
3890 Cypress Drive
Petaluma, CA 94954
Phone (707) 776-3777
Fax: (707) 656-4067

Parks & Facility Maintenance

840 Hopper St. Ext.
Petaluma, CA 94952
Phone (707) 778-4303
Fax (707) 206-6065

Transit Division

555 N. McDowell Blvd.
Petaluma, CA 94954
Phone (707) 778-4421

Utilities & Field Operations

202 N. McDowell Blvd.
Petaluma, CA 94954
Phone (707) 778-4546
Fax (707) 206-6034

E-Mail: publicworks@cityofpetaluma.org

This Addendum No. 2 shall become part of the Contract and all provisions of the Contract shall apply thereto.

City of Petaluma,



Mary White
Assistant Engineer II
Public Works & Utilities Department

Attachments:

Revised Technical Specifications 01 11 00 – Summary of Work – 1.03 Description of Bid Items - 8. Electrical Work

A signed copy of this Addendum and the attached acknowledgement form shall be attached to the bid proposal. Failure to do so may cause rejection of your bid as being non-responsive.

ADDENDUM NO. 2

**Hardin Lane Tank Recoating Project
C67502328**

May 16, 2024

ACKNOWLEDGEMENT

Receipt of Addendum No. 2 is hereby acknowledged by _____
(Contractor's Name)

on the _____ day of _____, 2024.

By: _____
Signature

Title

Company

replacement of the internal ladder, removal of the internal grated platform, modifications to the external and internal sensing piping including modification to the water sampling station, replacing expanded metal and screen for the center vent, new gaskets for hatches and manways, replacement of hand hole covers on the roof, handling and disposal of all items to be removed, welding, cutting, capping, pipe and fittings as necessary, and other work incidental thereto, complete in accordance with the Drawings and as specified herein.

6. Replace Rafter Ties: This bid item shall include all labor, material, and equipment necessary to remove, furnish, prepare, and construct the replacement of rafter tie rods designated by the engineer for replacement after initial abrasive blasting including welding, and other work incidental thereto, complete in accordance with the Drawings and as specified herein.
7. Door Sheet: This bid item shall include all labor, material, and equipment necessary to cut out, store and replace the door sheet in the shell of the tank for equipment access to the interior, including but not limited to cutting, removal, temporary storage, replacement, full-penetration butt welding and complete radiographic testing of the full length of all associated welds complete in accordance with the AWWA D100, Section 11, the Drawings and as specified herein.
8. Electrical Work: This bid item shall include all labor, material, and equipment necessary to complete all electrical work, including but not limited to conduit, wiring, weather protective enclosures, replacing or adding intrusion switches, new electrical cabinet, removal of all cathodic protection devices, equipment and cabinet, removal of electrical cabinets for tank coating, replacing or relocating electrical components from old cabinet to new cabinet, site lighting, vault lighting and start-up, testing, and commissioning as required, complete in accordance with the Drawings and as specified herein.

E. Alternate Bid Items

1. Item A - Seal Welding Roof Plates: This bid item shall include all labor, material, and equipment necessary to seal weld the bottom joints on all steel roof plate joints including surface preparation and cleaning, lifting plates off the rafters as needed, welding, grinding and other work incidental thereto, complete in accordance with the Contract Documents and as specified herein.
2. Item B - Seal Welding Rafters: This bid item shall include all labor, material, and equipment necessary to seal weld the rafters to the tank roof including surface preparation and cleaning, welding, grinding and other work incidental thereto, complete in accordance with the Contract Documents and as specified herein.

The work to be performed under these specifications is at the City of Petaluma's Hardin Tank located on Hardin Lane in Petaluma, California.

1.04 COORDINATION

- A. Coordinate with operations and maintenance personnel to maintain uninterrupted operation of critical site equipment.