



LYNCH CREEK TRAIL - PAYRAN SECTION
 STA 1+00 TO STA 4+50

CONSTRUCTION NOTES:

- 1 INSTALL A REINFORCED 6" THICK CONCRETE PATHWAY. SEE TYPICAL SECTION ON SHEET D-1. MAINTAIN 0.5% TO 1% MAX CROSS SLOPE AND 2% TO 4% MAX LONGITUDINAL SLOPE.
- 2 REMOVE ROOTS LARGER THAN 2" DIAMETER IN THE WAY OF THE PATHWAY SECTION UPON APPROVAL OF THE CITY OF PETALUMA ARBORIST. INSTALL ROOT BARRIER. USE CENTURY PRODUCTS OR EQUIVALENT.
- 3 INSTALL DOWEL PER DETAIL SHOWN ON SHEET D-1.
- 4 CONFORM TO EXISTING ELEVATIONS.
- 5 TEMPORARY CONSTRUCTION ACCESS: CURB CUT ACROSS FROM 860 HOLLY LN. EXISTING FENCE TO BE REMOVED AND RE-INSTALLED. PROVIDE TEMPORARY FENCING AROUND THE PERIMETER OF THE ACCESS. CONTRACTOR TO RESTORE AT PROJECT COMPLETION TO CITY'S SATISFACTION.
- 6 CITY OPERATIONS DEPARTMENT REQUIRES ALL-WEATHER ACCESS THROUGH THIS POINT.
- 7 REMOVE EXISTING FENCE WHEN IN THE WAY OF CONSTRUCTION AND RE-INSTALL WHEN WORK IS COMPLETE.
- 8 REMOVE EXISTING SIGN, REINSTALL WHEN WORK IS COMPLETE.
- 9 VEHICULAR TRAFFIC NOT ALLOWED WITHOUT PRIOR CITY APPROVAL.
- 10 ALTERNATE BID- INSTALL TWO 2-INCH CAPPED SCHEDULE 80 CONDUITS AT 7" BELOW GRADE.
- 11 A CONCRETE WASHOUT AREA, SUCH AS A TEMPORARY PIT, SHALL BE DESIGNATED TO CLEAN CONCRETE TRUCKS AND TOOLS. AT NO TIME SHALL CONCRETE PRODUCTS AND WASTE BE ALLOWED TO ENTER COUNTY WATERWAYS SUCH AS CREEKS OR STORM DRAINS. REFER TO SPECS.
- 12 ALTERNATE BID: CONTRACTOR TO INSTALL 5 CY OF ¾ CRUSHED CLEAN ROCK ON MIRAFI 160N GEOTEXTILE FABRIC.
- 13 REPLACE SIGN WITH NEW SIGN ON EXISTING POST.
- 14 REMOVE EXISTING AC AND INSTALL 6" CONCRETE PATHWAY 12 FT WIDE TO MATCH BRIDGE WIDTH.
- 15 EXISTING MANHOLE TO BE RAISED TO FINISH GRADE.



1+00



1+75



3+00

DATE: MARCH 2021 DESIGNED BY: EMO DRAWN BY: ETL CHECKED BY: KEE	PROJECT NO. C16101823
CITY OF PETALUMA PUBLIC WORKS & UTILITIES 202 N. McDowell Blvd., PETALUMA, CALIFORNIA, 94954 PH. 707-778-4546 FAX. 707-778-4508	
MULTI-USE PATH - LYNCH CREEK TRAIL PAYRAN SECTION STA 1+00 TO STA 4+50	
SHEET C1 4 OF 7	