

# DOMINICAN VALLEY HOUSING PLANNING SUBMITTAL

March 25, 2024

## PROJECT DATA

---

Total Site Area: 905,768 sq ft  
 Total Development Area (Subdivisions): 340,819 sq ft  
 APN: 015-163-03  
 Zoning District: Planned Development Distrct (PD)  
 Single Family Housing: 27  
 Duplex Units: 6  
 Townhomes: 17 (includes 14 ADU's)  
 Parking: 86 spaces enclosed  
     64 guest parking in driveways  
     6 parallel guest parking on Margarita Dr

## PROJECT NARRATIVE

---

The Dominican Valley property is a 20.79 Acre site located in the Dominican / Black Canyon neighborhood of San Rafael. The subject site is bordered northwesterly between the streets of Gold-Hill grade and Deer Park Ave and southerly by Highland Ave and Margarita Drive. The development proposes Sub Division of the site into 50 lots with 50 units of residential housing (+14 Attached Junior ADUs).

The projects 50 lot layout has been designed as a “Clustered development”, specifically Clustering’s of development areas utilizing portions of the site which provide ease of access to the Public Right of Way (R.O.W) street frontages including Magnolia Drive, Deer-Park Ave, Gold-Hill Grade and Margarita Drive. Many of the lots are positioned along these public R.O.W street frontages where connections are available to Public Utilities and vehicular access, the remainder have public utility and vehicular access through private streets.

The designed Clustering of the development focused on avoidance of areas onsite with steep topography which thereby helped retain over +70% of the site as undisturbed natural terrain and avoided development of highly visible Hillside or ridgelines while preserving hillside as visual backdrop. The significant amount of undisturbed natural terrain also helps minimize removal of natural, vegetation and significant trees.

The development maintains a 25ft top of bank buffer to Sisters Creek meandering along Goldhill grade. The Drainageway onsite which are outside of the development footprint areas shall be piped / culverted and diverted towards Sisters Creek.

The proposed private streets have been designed with appropriate width, slope gradient and emergency Vehicle turn outs to ensure meeting Fire Code standards while also providing safe vehicular and pedestrian access to the development.

The 50 residential units (+ 14. Junior ADUs) comprises of the following types of units.

- 27 Single-Family Homes ranging in size from 2612 sq ft - 3215 sq ft
- 17 Townhomes ranging in size from 1150 sq ft - 1390 sq ft (Townhomes with attached junior ADUs)
- 6 Duplex units each 1705 sq ft

The homes have been designed to blend into the surrounding area, with the use of both step back massing and flat or low pitched roofs. The architectural design of the home’s exterior reflects a modern California feel with natural materials and muted colors. The building forms and open floor plans create strong connections to the outdoors utilizing large areas of glazing in combination with numerous outdoor patios.

The landscape will utilize a low-water, low-maintenance planting palette of native and climate-appropriate plants, with selected areas for bioretention and stormwater treatment. The plan preserves and protects the open space outside the area of disturbance as much as possible.

## SHEET INDEX

---

A1	SITE PLAN
A2	UNIT TYPE A - PLANS
A3	UNIT TYPE B - PLANS
A4	UNIT TYPE C - PLANS
A5	UNIT TYPE D1 - PLANS
A6	UNIT TYPE D2 - PLANS
A7	UNIT TYPE E - PLANS
A8	UNIT TYPE F - PLANS
A9	UNIT TYPE A - TYPICAL ELEVATIONS
A10	UNIT TYPE A - SECTIONS
A11	UNIT TYPE B - TYPICAL ELEVATIONS
A12	UNIT TYPE B - SECTIONS
A13	UNIT TYPE C - TYPICAL ELEVATIONS
A14	UNIT TYPE C - SECTIONS
A15	UNIT TYPE D1 - TYPICAL ELEVATIONS
A16	UNIT TYPE D1 - SECTIONS
A17	UNIT TYPE D2 - TYPICAL ELEVATIONS
A18	UNIT TYPE D2 - SECTIONS
A19	UNIT TYPE E - TYPICAL ELEVATIONS
A20	UNIT TYPE E - SECTIONS
A21	UNIT TYPE F - TYPICAL ELEVATIONS
A22	UNIT TYPE F - SECTIONS
A23	MATERIALS PALETTE

L1	TREE DISPOSITION PLAN
L2	LANDSCAPE PLAN
L3	SOIL PLACEMENT PLAN
L4	PLANTING BIOME PLAN & SCHEDULE

C1.0	TENTATIVE MAP
C1.1	PROPERTY LINES
C2.0	BOUNDARY & TOPOGRAPHIC SURVEY
C3.0	NATURAL STATE PLAN
C4.0	PRELIMINARY GRADING PLAN (OVERALL)
C4.1	PRELIMINARY EARTHWORK CUT-FILL
C4.2	PRELIMINARY GRADING PLAN-1
C4.3	PRELIMINARY GRADING PLAN-2
C4.4	PRELIMINARY GRADING PLAN-3
C4.5	PRELIMINARY GRADING PLAN-4
C5.0	DRIVEWAY/SITE SECTIONS-1
C5.1	DRIVEWAY/SITE SECTIONS-2 AND CULVERT DETAIL
C5.2	CULVERTY SECTION DETAILS
C6.0	PRELIMINARY DRAINAGE AND UTILITY PLAN
C6.1	PRELIMINARY FIRE PREVENTION PLAN
C7.0	PRELIMINARY STORMWATER CONTROL PLAN
C7.1	PRELIMINARY STORMWATER CONTROL DETAILS

G1	SITE PHOTOS
G2	SITE PHOTOS
G3	SITE PHOTOS



FAR CALCULATIONS					
LOT #	LOT AREA (SF)	UNIT TYPE	BUILDING AREA (NSF)	MAX BUILDING AREA (2,500 SF + 10% Lot)	FLOOR AREA RATIO
1	7,500	E	2,595	3,300	0.35
2	7,993	E	2,595	3,349	0.32
3	7,930	E	2,595	3,343	0.33
4	7,500	E	2,595	3,300	0.35
5	7,500	E	2,595	3,300	0.35
6	7,606	F	3,165	3,311	0.42
7	7,658	F	3,165	3,316	0.41
8	8,410	F	3,165	3,391	0.38
9	22,735	F	3,165	4,824	0.14
10	14,855	B	2,825	4,036	0.19
11	14,855	B	2,825	4,036	0.19
12	11,085	B	2,825	3,659	0.25
13	10,967	B	2,825	3,647	0.26
14	8,937	B	2,825	3,444	0.32
15	2,276	D2 (+ADU)	1,380	2,778	0.61
16	1,207	D2 (+ADU)	1,380	2,671	1.14
17	1,207	D2 (+ADU)	1,380	2,671	1.14
18	1,207	D2 (+ADU)	1,380	2,671	1.14
19	1,207	D2 (+ADU)	1,380	2,671	1.14
20	1,207	D2 (+ADU)	1,380	2,671	1.14
21	1,207	D2 (+ADU)	1,380	2,671	1.14
22	1,207	D2 (+ADU)	1,380	2,671	1.14
23	1,207	D2 (+ADU)	1,380	2,671	1.14
24	1,207	D2 (+ADU)	1,380	2,671	1.14
25	1,207	D2 (+ADU)	1,380	2,671	1.14
26	1,207	D2 (+ADU)	1,380	2,671	1.14
27	1,207	D2 (+ADU)	1,380	2,671	1.14
28	1,207	D2 (+ADU)	1,380	2,671	1.14
29	1,204	D1	1,150	2,670	0.96
30	1,122	D1	1,150	2,662	1.02
31	1,006	D1	1,150	2,651	1.14
32	11,210	F	3,165	3,671	0.28
33	7,571	F	3,165	3,307	0.42
34	7,500	F	3,165	3,300	0.42
35	7,500	F	3,165	3,300	0.42
36	7,500	F	3,165	3,300	0.42
37	7,500	F	3,165	3,300	0.42
38	7,650	F	3,165	3,315	0.41
39	9,300	F	3,165	3,480	0.34
40	7,502	F	3,165	3,300	0.42
41	7,133	C	3,030	3,263	0.42
42	8,055	C	3,030	3,356	0.38
43	8,189	C	3,030	3,369	0.37
44	7,737	C	3,030	3,324	0.39
45	3,509	A	1,805	2,901	0.51
46	4,818	A	1,805	3,032	0.37
47	3,344	A	1,805	2,884	0.54
48	3,429	A	1,805	2,893	0.53
49	4,263	A	1,805	2,976	0.42
50	6,413	A	1,805	3,191	0.28

LOT / BLDG CALCS			
AVG LOT WIDTH	MAX BLDG HT <sup>1</sup>	MAX STEP BACK HT <sup>2</sup>	HILLSIDE GUIDELINE COMPLIANT <sup>3</sup> *See Footnotes
50'-0"	30'-0"	14'-3"	3
53'-3"	30'-0"	14'-3"	3
52'-10"	30'-0"	14'-3"	3
50'-0"	30'-0"	14'-3"	3
50'-0"	30'-0"	14'-3"	3
50'-3"	30'-0"	15'-3"	yes
50'-8"	24'-9"	15'-3"	yes
60'-8"	24'-3"	15'-3"	yes
99'-4"	24'-6"	15'-3"	yes
86'-0"	28'-8"	12'-0"	yes
81'-11"	28'-8"	15'-10"	yes
75'-1"	28'-8"	12'-0"	yes
73'-6"	28'-8"	12'-0"	yes
68'-5"	28'-8"	12'-0"	yes
28'-2"	26'-4"	22'-0"	4
15'-0"	28'-0"	22'-0"	4
15'-0"	26'-10"	22'-0"	4
15'-0"	26'-11"	22'-0"	4
15'-0"	26'-6"	22'-0"	4
15'-0"	28'-0"	22'-0"	4
15'-0"	27'-6"	22'-0"	4
15'-0"	27'-6"	22'-0"	4
15'-0"	27'-8"	22'-0"	4
15'-0"	27'-11"	22'-0"	4
15'-0"	24'-10"	22'-0"	4
15'-0"	26'-6"	22'-0"	4
15'-0"	24'-6"	22'-0"	4
15'-0"	24'-6"	22'-0"	4
15'-0"	23'-4"	21'-6"	4
15'-1"	23'-4"	22'-0"	4
15'-0"	23'-4"	21'-6"	4
69'-4"	20'-6"	15'-3"	yes
50'-5"	20'-9"	15'-3"	yes
50'-0"	21'-0"	15'-3"	yes
50'-0"	21'-3"	15'-3"	yes
50'-0"	21'-6"	15'-3"	yes
50'-0"	21'-3"	15'-3"	yes
50'-0"	21'-0"	15'-3"	yes
82'-2"	30'-0"	15'-3"	yes
50'-1"	30'-0"	15'-3"	yes
89'-8"	36'-6"	20'-0"	5
99'-2"	34'-0"	17'-6"	5
96'-8"	35'-6"	19'-0"	5
97'-7"	48'-0"	16'-3"	5
38'-10"	46'-10"	19'-0"	5
50'-1"	47'-6"	19'-8"	5
38'-10"	44'-10"	17'-0"	5
38'-4"	40'-10"	13'-0"	5
47'-0"	30'-10"	15'-0"	5
75'-11"	29'-10"	14'-0"	yes

**FOOTNOTES**  
 1: measured from (E) grade  
 2: measured at front and back planes only  
 3: balcony projection breaks 20'+ wall  
 4: stepback at 10' level, 20'+ of wall plane above  
 5: road access and steepness of grade preclude full compliance

**SQUARE FOOTAGE DEFINITIONS:**  
**NSF:** Sum of all enclosed areas, measured to the interior of enclosing walls, excluding non conditioned areas. Stairs counted at one floor only.

**GSF:** "Hillside areas gross building square footage" means the sum of all enclosed or covered areas of each floor or all structures on the site, measured to the exterior of the enclosing walls, columns or posts including basement areas, unfinished attic or loft spaces and other areas capable of being finished into habitable space as determined by the California Building Code; garages and carport areas six feet (6') or more above the natural grade, measured to the exterior face of surrounding walls, column, or posts; other roofs or covered areas supported by walls, columns or posts and capable of being enclosed, measured to the exterior face of surrounding walls, columns or posts; roof penthouses; and accessory structures greater than one hundred twenty (120) square feet in floor area. Excluded are areas permanently open to the sky; exterior areas under roof eaves, trellises or cantilevered overhangs and attic spaces and underfloor spaces that are not capable of being finished into habitable space.




Scale: 1/64" = 1'-0"






LOWER LEVEL



ENTRY LEVEL




GARAGE LEVEL


**UNIT TYPE - A**

LOWER LEVEL	= 970 NSF
ENTRY LEVEL	= 835 NSF
<b>TOTAL</b>	<b>= 1,805 NSF</b>

LOWER LEVEL	= 1,090 GSF
ENTRY LEVEL	= 960 GSF
GARAGE LEVEL	= 520 GSF
<b>TOTAL</b>	<b>= 2,570 GSF</b>



LOWER LEVEL




ENTRY LEVEL


**UNIT TYPE - B**

LOWER LEVEL	= 975 NSF
ENTRY LEVEL	= 1,850 NSF
<b>TOTAL</b>	<b>= 2,825 NSF</b>


LOWER LEVEL	= 1,150 GSF
ENTRY LEVEL	= 2,520 GSF
<b>TOTAL</b>	<b>= 3,670 GSF</b>



LOWER LEVEL



ENTRY LEVEL




GARAGE LEVEL


**UNIT TYPE - C**

LOWER LEVEL	= 1,395 NSF
ENTRY LEVEL	= 1,635 NSF
<b>TOTAL</b>	<b>= 3,030 NSF</b>


LOWER LEVEL	= 1,540 GSF
ENTRY LEVEL	= 1,740 GSF
GARAGE LEVEL	= 660 GSF
<b>TOTAL</b>	<b>= 3,940 GSF</b>



FIRST LEVEL



SECOND LEVEL




THIRD LEVEL


**UNIT TYPE - D1**

FIRST LEVEL	= 85 NSF
SECOND LEVEL	= 525 NSF
THIRD LEVEL	= 540 NSF
<b>TOTAL</b>	<b>= 1,150 NSF</b>


FIRST LEVEL	= 570 GSF
SECOND LEVEL	= 630 GSF
THIRD LEVEL	= 630 GSF
<b>TOTAL</b>	<b>= 1,830 GSF</b>




Scale: 1/8" = 1'-0"



FIRST LEVEL



SECOND LEVEL




THIRD LEVEL

**UNIT TYPE - D2 (+ ADU)**


FIRST LEVEL	= 315 NSF
SECOND LEVEL	= 525 NSF
THIRD LEVEL	= 540 NSF
<b>TOTAL</b>	<b>= 1,380 NSF</b>

FIRST LEVEL	= 570 GSF
SECOND LEVEL	= 630 GSF
THIRD LEVEL	= 630 GSF
<b>TOTAL</b>	<b>= 1,830 GSF</b>




Scale: 1/8" = 1'-0"






FIRST LEVEL



SECOND LEVEL



THIRD LEVEL


**UNIT TYPE - E**

FIRST LEVEL	= 170 NSF
SECOND LEVEL	= 1,045 NSF
THIRD LEVEL	= 1,380 NSF
<b>TOTAL</b>	<b>= 2,595 NSF</b>


FIRST LEVEL	= 880 GSF
SECOND LEVEL	= 1,360 GSF
THIRD LEVEL	= 1,600 GSF
<b>TOTAL</b>	<b>= 3,840 GSF</b>




Scale: 1/8" = 1'-0"



FIRST LEVEL



SECOND LEVEL



THIRD LEVEL

**UNIT TYPE - F**

FIRST LEVEL	= 320 NSF
SECOND LEVEL	= 1,035 NSF
THIRD LEVEL	= 1,810 NSF
<b>TOTAL</b>	<b>= 3,165 NSF</b>


FIRST LEVEL	= 1,020 GSF
SECOND LEVEL	= 1,270 GSF
THIRD LEVEL	= 2,140 GSF
<b>TOTAL</b>	<b>= 4,430 GSF</b>

**LEGEND**

- ① CEMENT PLASTER
- ② ENGINEERED WOOD SIDING - STAINED
- ③ WOOD/CEMENT BOARD SIDING - PAINTED
- ④ STONE VENEER
- ⑤ METAL CLAD WOOD WINDOW
- ⑥ METAL CLAD WOOD DOORS
- ⑦ GLASS GUARDRAIL
- ⑧ ENGINEERED WOOD GARAGE DOOR
- ⑨ STANDING SEAM METAL ROOF
- ⑩ ENGINEERED WOOD RAFTERS
- ⑪ METAL SHADE SCREEN
- ⑫ METAL RAILING
- ⑬ ENGINEERED WOOD DECK WITH METAL EDGE
- ⑭ WALL SCONCE
- ⑮ RECESSED LIGHT FIXTURE
- ⑯ ADDRESS NUMBERS



SIDE ELEVATION






FRONT ELEVATION




REAR ELEVATION



SIDE ELEVATION



LOT 50 - LEAST GRADE CHANGE



LOT 46 - MOST GRADE CHANGE

**LEGEND**

- ① CEMENT PLASTER
- ② ENGINEERED WOOD SIDING - STAINED
- ③ WOOD/CEMENT BOARD SIDING - PAINTED
- ④ STONE VENEER
- ⑤ METAL CLAD WOOD WINDOW
- ⑥ METAL CLAD WOOD DOORS
- ⑦ GLASS GUARDRAIL
- ⑧ ENGINEERED WOOD GARAGE DOOR
- ⑨ STANDING SEAM METAL ROOF
- ⑩ ENGINEERED WOOD RAFTERS
- ⑪ METAL SHADE SCREEN
- ⑫ METAL RAILING
- ⑬ ENGINEERED WOOD DECK WITH METAL EDGE
- ⑭ WALL SCONCE
- ⑮ RECESSED LIGHT FIXTURE
- ⑯ ADDRESS NUMBERS




SIDE ELEVATION






FRONT ELEVATION




REAR ELEVATION



SIDE ELEVATION



LOT 14 - LEAST GRADE CHANGE




LOT 11 - MOST GRADE CHANGE

**LEGENED**

- ① CEMENT PLASTER
- ② ENGINEERED WOOD SIDING - STAINED
- ③ WOOD/CEMENT BOARD SIDING - PAINTED
- ④ STONE VENEER
- ⑤ METAL CLAD WOOD WINDOW
- ⑥ METAL CLAD WOOD DOORS
- ⑦ GLASS GUARDRAIL
- ⑧ ENGINEERED WOOD GARAGE DOOR
- ⑨ STANDING SEAM METAL ROOF
- ⑩ ENGINEERED WOOD RAFTERS
- ⑪ METAL SHADE SCREEN
- ⑫ METAL RAILING
- ⑬ ENGINEERED WOOD DECK WITH METAL RAILING
- ⑭ WALL SCONCE
- ⑮ RECESSED LIGHT FIXTURE
- ⑯ ADDRESS NUMBERS




SIDE ELEVATION






FRONT ELEVATION



REAR ELEVATION



SIDE ELEVATION



LOT 43 - LEAST GRADE CHANGE



LOT 44 - MOST GRADE CHANGE



**LEGEND**

- ① CEMENT PLASTER
- ② ENGINEERED WOOD SIDING - STAINED
- ③ WOOD/CEMENT BOARD SIDING - PAINTED
- ④ STONE VENEER
- ⑤ METAL CLAD WOOD WINDOW
- ⑥ METAL CLAD WOOD DOORS
- ⑦ GLASS GUARDRAIL
- ⑧ ENGINEERED WOOD GARAGE DOOR
- ⑨ STANDING SEAM METAL ROOF
- ⑩ ENGINEERED WOOD RAFTERS
- ⑪ METAL SHADE SCREEN
- ⑫ METAL RAILING
- ⑬ ENGINEERED WOOD DECK WITH METAL EDGE
- ⑭ WALL SCONCE
- ⑮ RECESSED LIGHT FIXTURE
- ⑯ ADDRESS NUMBERS



SIDE ELEVATION




REAR ELEVATION





SIDE ELEVATION



FRONT ELEVATION





LOT 29 - TYPICAL GRADE CHANGE

**LEGEND**

- ① CEMENT PLASTER
- ② ENGINEERED WOOD SIDING - STAINED
- ③ WOOD/CEMENT BOARD SIDING - PAINTED
- ④ STONE VENEER
- ⑤ METAL CLAD WOOD WINDOW
- ⑥ METAL CLAD WOOD DOORS
- ⑦ GLASS GUARDRAIL
- ⑧ ENGINEERED WOOD GARAGE DOOR
- ⑨ STANDING SEAM METAL ROOF
- ⑩ ENGINEERED WOOD RAFTERS
- ⑪ METAL SHADE SCREEN
- ⑫ METAL RAILING
- ⑬ ENGINEERED WOOD DECK WITH METAL EDGE
- ⑭ WALL SCONCE
- ⑮ RECESSED LIGHT FIXTURE
- ⑯ ADDRESS NUMBERS



SIDE ELEVATION



REAR ELEVATION




SIDE ELEVATION






FRONT ELEVATION


**UNIT TYPE D2 - TYPICAL ELEVATIONS**

Scale: 1/8" = 1'-0"






LOT 15 - LEAST GRADE CHANGE




LOT 28 - MOST GRADE CHANGE

**LEGEND**


- ① CEMENT PLASTER
- ② ENGINEERED WOOD SIDING - STAINED
- ③ WOOD/CEMENT BOARD SIDING - PAINTED
- ④ STONE VENEER
- ⑤ METAL CLAD WOOD WINDOW
- ⑥ METAL CLAD WOOD DOORS
- ⑦ GLASS GUARDRAIL
- ⑧ ENGINEERED WOOD GARAGE DOOR
- ⑨ STANDING SEAM METAL ROOF
- ⑩ ENGINEERED WOOD RAFTERS
- ⑪ METAL SHADE SCREEN
- ⑫ METAL RAILING
- ⑬ ENGINEERED WOOD DECK WITH METAL EDGE
- ⑭ WALL SCONCE
- ⑮ RECESSED LIGHT FIXTURE
- ⑯ ADDRESS NUMBERS



SIDE ELEVATION






REAR ELEVATION




FRONT ELEVATION



SIDE ELEVATION



LOT 1 - LEAST GRADE CHANGE




LOT 5 - MOST GRADE CHANGE

**LEGEND**


- ① CEMENT PLASTER
- ② ENGINEERED WOOD SIDING - STAINED
- ③ WOOD/CEMENT BOARD SIDING - PAINTED
- ④ STONE VENEER
- ⑤ METAL CLAD WOOD WINDOW
- ⑥ METAL CLAD WOOD DOORS
- ⑦ GLASS GUARDRAIL
- ⑧ ENGINEERED WOOD GARAGE DOOR
- ⑨ STANDING SEAM METAL ROOF
- ⑩ ENGINEERED WOOD RAFTERS
- ⑪ METAL SHADE SCREEN
- ⑫ METAL RAILING
- ⑬ ENGINEERED WOOD DECK WITH METAL EDGE
- ⑭ WALL SCONCE
- ⑮ RECESSED LIGHT FIXTURE
- ⑯ ADDRESS NUMBERS



SIDE ELEVATION






REAR ELEVATION




FRONT ELEVATION



SIDE ELEVATION



LOT 32 - LEAST GRADE CHANGE



LOT 36 - MOST GRADE CHANGE





14 WALL SCONCE



15 RECESSED LIGHT FIXTURE



16 ADDRESS NUMBERS

## LIGHTING & ORNAMENTATION



1 CEMENT PLASTER



2 ENGINEERED WOOD SIDING - STAINED



3 WOOD/CEMENT BOARD SIDING - PAINTED



4 STONE VENEER




5 6 METAL CLAD WOOD WINDOW & DOOR



7 GLASS GUARDRAIL



9 STANDING SEAM METAL ROOF



11 METAL SHADE SCREEN




2 ENGINEERED WOOD SIDING - STAINED



8 ENGINEERED WOOD GARAGE DOOR



10 ENGINEERED WOOD RAFTERS






12 13 METAL RAILING & DECK

## MATERIALS

### DOMINICAN VALLEY HOUSING | PLANNING SUBMITTAL

San Rafael, CA 94901 March 25, 2024  
Project No. : 2023043

**TREE REMOVAL & PROTECTION LEGEND**

-  TREES TO BE REMOVED, TYP
-  SIGNIFICANT NATIVE TREES TO BE REMOVED, TYP
-  SIGNIFICANT NATIVE TREES TO REMAIN, TYP

SPECIES TREE TAG  
 TREE ID REFER TO ARBORIST REPORT  
 XX' DBH DATED 1/5/17

**TREE PROTECTION & REMOVAL NOTES**

1. CLEAR AND GRUB LANDSCAPE AREAS PER SPECS.
2. REFER TO ARBORIST REPORT, DATED 3/18/24 & PREPARED BY ORACL OAK, LLC, FOR TREE ID, SPECIE, LOCATION, DBH, HEALTH AND RECOMMENDATIONS FOR CARE.
3. ALL TREE REMOVAL AND PROTECTION MEASURES SHALL BE IMPLEMENTED CONSISTENT WITH MEASURES IN SPECS AND THE CITY OF BELMONT TREE PRESERVATION GUIDELINES.
4. ALL TREES SCHEDULED FOR PRESERVATION SHALL BE TEMPORARILY FENCED DURING CONSTRUCTION. FENCING SHALL BE INSTALLED PRIOR TO STARTING WORK. FENCING SHALL CONSIST OF 60" HIGH CHAIN LINK FENCE. FENCING SHALL BE RIGIDLY SUPPORTED AND MAINTAINED DURING CONSTRUCTION. FENCED AREAS SHALL BE MAINTAINED IN A NATURAL CONDITION AND NOT COMPACTED. REMOVAL OF FENCING SHALL BE ALLOWED FOLLOWING APPROVAL BY THE TOWN ARBORIST. THE FENCING LOCATIONS SHALL BE DETERMINED IN FIELD BY THE TOWN ARBORIST.
5. THE CONTRACTOR SHALL NOT BE ALLOWED TO STORE EQUIPMENT OR MATERIAL WITHIN THE DRIPLINE AREA UNDER TREES TO REMAIN.
6. SELECTIVELY PRUNE ANY TREE CROWNS THAT LEAN INTO THE CONSTRUCTION AREA. PRUNING TO BE DONE UNDER SUPERVISION OF ARBORIST AND LANDSCAPE ARCHITECT.
7. PROTECT EXISTING TREES AND BRANCHES FROM DAMAGE DURING CONSTRUCTION. DAMAGED TREES TO BE REPLACED IN KIND WITH TREE OF EQUAL VALUE OR AS APPROVED BY OWNER. ALL WORK WITHIN TREE PROTECTION ZONE TO BE DONE BY HAND.
8. TREE PROTECTION ZONE TO BE 1' FOR EVERY INCH IN DIAMETER OF BREST HEIGHT.

**TREE REMOVAL & REPLACEMENT SUMMARY**

	TOTAL
NUMBER OF NON-SIGNIFICANT TREES TO BE REMOVED	509
NUMBER OF SIGNIFICANT NATIVE TREES TO BE REMOVED	11
REQUIRED TREE REPLACEMENT QUANTITY (3:1)	33
PROPOSED TREE QUANTITY	98






**SIGNIFICANT NATIVE TREE REMOVAL TABLE**

TREE # - TAG	SPECIES	DBH	CONDITION
#1 - 20	COAST LIVE OAK	17.8"	MODERATE
#2 - 21	COAST LIVE OAK	11.3", 8.5"	FAIR
#3 - 22	COAST LIVE OAK	12"	FAIR
#4 - 23	COAST LIVE OAK	12.2"	MODERATE
#5 - 24	COAST LIVE OAK	12", 8.5"	FAIR
#6 - 25	COAST LIVE OAK	16.1"	FAIR
#7 - 26	COAST LIVE OAK	12.5"	MODERATE
#8 - 27	COAST LIVE OAK	12"	FAIR
#9 - 28	COAST LIVE OAK	13.8"	GOOD
#10 - 29	COAST LIVE OAK	13.5"	GOOD
#11 - 30	COAST LIVE OAK	17.7"	GOOD

SIGNIFICANT NATIVE TREES ARE ANY CALIFORNIA NATIVE TREES WITH 12" DBH OR GREATER



**LEGEND**



-  EXISTING TREES
-  PROPOSED TREE
-  PLANTING AREA
-  STORMWATER PLANTING AREA
-  PEDESTRIAN PAVING

**LANDSCAPE CALCULATIONS:**

	SQUARE FEET	ACRE	%
LOT SIZE	905768	20.80	100
LOT COVERAGE	163568	3.75	18
STPA	4644	0.10	1
LANDSCAPED AREA	70080	1.60	7
NATURAL OPEN AREA	667665	15.30	73




**SOIL PLACEMENT LEGEND**

SYMBOL	SOIL TYPE	SF	DESCRIPTION
	PLANTING SOIL	73078	12" MIN. AMENDED PLANTING SOIL, SEE NOTES
	PLANTING SOIL AT TREES	1600	AMENDED PLANTING SOIL TO DEPTH OF TREE ROOT BALL & 2X WIDTH OF ROOTBALL, SEE NOTES

**SOIL PLACEMENT NOTES:**

1. CONTRACTOR TO PROVIDE IMPORTED PLANTING SOIL UNLESS ADEQUATE TOPSOIL HAS BEEN STRIPPED AND STOCKPILED PER SPECIFICATIONS. AMENDED SUBSOIL IS NOT AN ACCEPTABLE PLANTING SOIL. REFER TO SPECIFICATIONS FOR DETAILED SOIL REQUIREMENTS, SOIL STRIPPING AND STOCKPILING INFORMATION.
2. TREES TO RECEIVE AMENDED PLANTING SOIL AT 2X ROOTBALL DIMENSION TO FULL DEPTH OF ROOTBALL.
3. SEE SPECIFICATIONS FOR MORE INFORMATION ABOUT SOIL PREPARATION.



QTY	SYMBOL	ABBR.	SCIENTIFIC NAME	COMMON NAME	SIZE	SPACE	MATURE HEIGHT	MATURE WIDTH	WUCOLS
TREES									
98	ACE OCT		ACER RUBRUM 'OCTOBER GLORY'	OCTOBER GLORY MAPLE	24" BOX	SEE PLAN	40'	30'-0"	L
	ARB MAR		ARBUTUS 'MARINA' MULTI-STEM	STRAWBERRY TREE MULTI-STEM	24" BOX	SEE PLAN	25'	20'	L
	CER OCC		CERCIS OCCIDENTALIS	WESTERN REDBUD	24" BOX	SEE PLAN	15'	15'-0"	L
	QUE AGR		QUERCUS AGRIFOLIA	COAST LIVE OAK	24" BOX	SEE PLAN	40'	40'	VL
	QUE GAR		QUERCUS GARRYANA	OREGON WHITE OAK	24" BOX	SEE PLAN	20-90'	30'	L
	QUE TOM		QUERCUS TOMENTELLA	ISLAND OAK	24" BOX	SEE PLAN	35-65'	35'	L
	ULM PAR		ULMUS PARVIFOLIA	CHINESE ELM	24" BOX	SEE PLAN	40'	50'	L

**PLANTING NOTES:**

1. ALL PLANTING AREAS TO RECEIVE 3" OF MULCH, SEE SPECS.

**IRRIGATION NOTES:**

1. IRRIGATION SYSTEM IS INTENDED TO MEET ALL STATE MWELD & LOCAL WATER DISTRICT REQUIREMENTS.
2. IRRIGATION SYSTEM TO HAVE AUTOMATIC IRRIGATION CONTROLLER W/ ET BASED WEATHER SENSOR. SYSTEM WILL USE LOW WATER USE DRIP IRRIGATION AND TREE BUBBLERS.

QTY	SYMBOL	ABBR.	SCIENTIFIC NAME	COMMON NAME	SIZE	SPACE	MATURE HEIGHT	MATURE WIDTH	WUCOLS	STPA
SHRUBS										
-	ARC HOW		ARCTOSTAPHYLOS 'HOWARD MCMINN'	HOWARD MCMINN MANZANITA	5 GAL	4" O.C.	5'	5'	L	N
-	CEA JUL		CEANOTHUS 'JULIA PHELPS'	SMALL LEAF MOUNTAIN LILAC	5 GAL	6" O.C.	5'	7'	L	N
-	HET ARB		HETEROMELES ARBUTIFOLIA	TOYON	5 GAL	6" O.C.	10'	10'	L	N
-	RHA CAL		RHAMNUS CALIFORNICA	COFFEE BERRY	5 GAL	5" O.C.	5'	5'	L	Y
-	WES SMO		WESTRINGIA FRUTICOSA	VARIEGATED COAST ROSEMARY	5 GAL	5" O.C.	5'	5'	L	N
PERENNIALS										
-	AGA RUP		AGASTACHE RUPESTRE 'APACHE SUNSET'	APACHE SUNSET HYSSOP	1 GAL	18" O.C.	18"	18"	L	N
-	AH MIL		ACHILLEA MILLEFOIUM	YARROW	1 GAL	12" O.C.	2'	2'	L	Y
-	EPI CAN		EPILOBIUM CANUM	CALIFORNIA FUSCIA	1 GAL	24" O.C.	3'	2'	L	N
-	VER LIL		VERBENA LILACINA DE LA MINA	CEDROS ISLAND VERBENA	1 GAL	30" O.C.	30"	3'	L	Y
-	CHO TEC		CHONDROPETALUM TECTORUM	CAPE RUSH	1 GAL	36" O.C.	4'	4'	L	Y
GRASSES & RUSHES										
-	FES MAR		FESTUCA MAREI	ATLAS FESCUE	1 GAL	30" O.C.	30"	30"	L	N
-	JUN PAT		JUNCUS PATENS	CALIFORNIA GREY RUSH	1 GAL	30" O.C.	30"	30"	L	Y
-	LEY CAN		LEYMUS CONDENSATUS 'CANYON PRINCE'	CANYON PRINCE WILD RYE	1 GAL	3" O.C.	3'	3'	L	Y
-	LOM PLA		LOMANDRA 'PLATINUM BEAUTY'	VARIEGATED DWARF MAT RUSH	1 GAL	36" O.C.	3'	3'	L	N
GROUNDCOVERS										
-	BAC PIG		BACCHARIS PILULARIS 'PIGEON POINT'	PROSTRATE COYOTE BRUSH	1 GAL	5" O.C.	24"	8"	L	N
-	CEA ANC		CEANOTHUS 'ANCHOR BAY'	ANCHOR BAY CEANOTHUS	1 GAL	4" O.C.	18"	6"	L	N
-	ARC PAC		ARCTOSTAPHYLOS 'PACIFIC MIST'	PACIFIC MIST MANZANITA	1 GAL	3" O.C.	18"	4"	L	N

