

## COMMUNITY DEVELOPMENT DEPARTMENT - BUILDING DIVISION

1400 Fifth Avenue, San Rafael, CA 94901

TEL. (415) 485-3367; FAX (415) 485-3184

## SPECIAL INSPECTION AGENCY RECOGNITION LIST

Key: RC = Reinforced Concrete

PC = Prestressed/Post-tensioned Concrete

SM = Structural Masonry

SS = Structural Steel Welding/Bolting

FP = Spray-Applied Fireproofing

Agency Name	nHQ Address	Phone/FAX	RC	PC	SM	SS*	FP
Achievement	2455 Autumnvale Drive Suite E	408-217-9174	X	X	X	X	X
Engineering Corp	San Jose, CA 95131	408-217-9632					
Applied Materials	980 41st Street	510-420-8190	X	X	X	X	X
Engineering	Oakland, CA 94608	510-420-8186					
B.S.K. Associates	1181 Quarry Lane, #300	510-462-4000	X	X	X	X	X
	Pleasanton, CA 94566	510-462-6283					
CTE CAL	46716 Fremont Blvd.	510-573-6362	X	X	X	X	X
	Fremont, CA 94538	510-573-6684					
Construction Test	2118 Rheem Drive	925-462-515	X	X	X	X	X
Services	Pleasanton, CA 94588	925-462-5183					
Geissler Engineering	The Russ Building, Suite 101	415-992-9393	X	X			
6 11 6	235 Montgomery St., SF, CA 94104						
Inspection Consultants,	1515 North C Street	916-321-5580	X	X	X	X	X
Inc.	Sacramento, CA 95814	916- 321-5590					
Krazan and Associates,	215 West Dakota Avenue	559-348-2200	X	X	X	X	X
Inc.	Clovis, CA 93612	559-348-2201					
Neil O. Anderson	902 Industrial Way	209-367-3701	X	X	X	X	X
and Associates	Lodi, CA 95240	209-333-8303					
NorCon LLC	1661 Tennessee Street #201	415-692-0519	X	X	X	X	X
	San Francisco, CA 94107						
PJC & Associates, Inc	600 Martin Avenue, Ste 200	707-584-4804	X	X	X	X	
	Rohnert Park, CA 94928	707-584-4811					
RMA Group	257 Wright Brothers Ave.	925-243-6662	X	X	X	X	X
	Livermore, CA 94551	925-243-6663					
Salem Engineering	4729 West Jacquelyn Ave	559-271-9700	X	X	X	X	X
Group, Inc.	Fresno, CA 93722	559-275-0827					
Signet Testing	3121 Diablo Ave.	510-887-8484	X	X	X	X	X
Laboratories	Hayward, CA 94545	510-783-4295					
Smith-Emery Company	P. O. Box 880550	415-642-7326	X	X	X	X	X
	1940 Oakdale Ave	415-330-3030					
	San Francisco, CA 94124						
Testing Engineers Inc.	2811 Teagarden St	510-835-3142	X	X	X	X	X
	San Leandro, CA 94577	510-834-3777					

<sup>\*</sup>Agencies have not been evaluated for nondestructive testing.

Agencies have not been evaluated for geotechnical special inspection. Agencies may have offices in more than one location. Other agencies may also be qualified; the building official has the ultimate responsibility for approval. (Updated 6/19/2018)



#### SPECIAL INSPECTION AND TESTING AGREEMENT

Applicable to projects requiring special inspection and/or testing per Se	ction 1701 of the California Building Code
Project Name/Address:	Building Permit No:
-	

**BEFORE A PERMIT CAN BE ISSUED**: The owner, or the engineer or architect of record acting as the owner's agent, shall complete two (2) copies of this agreement and the attached structural tests and inspections schedule including the required acknowledgements. A preconstruction conference with the parties involved may be required to review the special inspection requirements and procedures.

**APPROVAL OF SPECIAL INSPECTORS**: Each special inspector shall be approved by the building department prior to performing any duties. Each special inspector shall submit his/her qualifications to the building department and is subject to a personal interview for prequalification. Special inspectors shall display approved identification, as stipulated by the building department, when performing the function of a special inspector.

Special inspection and testing shall meet the minimum requirements of CBC section 1701. The following conditions are also applicable:

### A. Duties and Responsibilities of the Special Inspector

## 1. Observe work

The special inspector shall observe the work for conformance with the building department approved (stamped) design drawings and specifications and applicable workmanship provisions of the CBC. Architect/engineer-reviewed shop drawings and/or placing drawings may be used only as an aid to inspection.

Special inspections are to be performed on a continuous basis, meaning that the special inspector is on site in the general area at all times observing the work requiring special inspection. Periodic inspections, if any, must have prior approval by the building department based on a separate written plan reviewed and approved by the building department and the project engineer or architect.

### 2. Report nonconforming items

The special inspector shall bring nonconforming items to the immediate attention of the contractor and note all such items in the daily report. If any item is not resolved in a timely manner or is about to be incorporated in the work, the special inspector shall immediately notify the building department by telephone or in person, notify the engineer or architect, and post a discrepancy notice.

### 3. Furnish daily reports

On request, each special inspector shall complete and sign both the special inspection record and the daily report form for each day's inspections to remain at the jobsite with the contractor for review by the building department's inspector.

## 4. Furnish weekly reports

The special inspector or inspection agency shall furnish weekly reports of tests and inspections directly to the building department, project engineer or architect, and others as designated. These reports must include the following:

- a. Description of daily inspections and tests made with applicable locations;
- b. Listing of all nonconforming items;
- c. Report on how nonconforming items were resolved or unresolved as applicable; and
- d. Itemized changes authorized by the architect, engineer and building department if not included in nonconformance items.

# 5. Furnish final report

The special inspector or inspection agency shall submit a final signed report to the building department stating that all items requiring special inspection and testing were fulfilled and reported and, to the best of his/her knowledge, in conformance with the approved design drawings, specifications, approved change orders and the applicable workmanship provisions of the C.B.C. Items not in conformance, unresolved items or any discrepancies in inspection coverage (i.e., missing inspections, periodic inspections when continuous was required, etc.) shall be specifically itemized in this report.

## **B.** Contractor Responsibilities

## 1. Notify the special inspector

The contractor is responsible for notifying the special inspector or agency regarding individual inspections of items listed on the attached schedule *and* as noted on the building department approval plan. Adequate notice shall be provided so that the special inspector has time to become familiar with the project.

### 2. Provide access to approved plans

The contractor is responsible for providing the special inspector access to approved plans at the jobsite.

## 3. Retain special inspection records

The contractor is also responsible for retaining at the jobsite all special inspection records submitted by the special inspector, and providing these records for review by the building department's inspector upon request.

### C. Building Department Responsibilities

### 1. Approve special inspection

The building department shall approve all special inspectors and special inspection requirements.

#### 2. Monitor special inspections

Work requiring special inspection and the performance of special inspectors shall be monitored by the building department's inspector. His/her approval must be obtained prior to placement of concrete or other similar activities in addition to that of the special inspector.

# 3. Issue Certificate of Occupancy

The building department may issue a Certificate of Occupancy after all special inspection reports and the final report have been submitted and accepted. FINAL SIGN-OFF WILL NOT BE GIVEN UNTIL ALL FINAL INSPECTION LETTERS ARE RECEIVED.

## **ACKNOWLEDGEMENTS**

I have read and agree to comply with t	he terms and conditions of this agreer	ment;	
Owner:	By:	Date:	
Contractor:Special Inspector	By:	Date:	
or Inspection Agency: Project Engineer/	By:	Date:	
Architect:	By:	Date:	
ACCEPTED FOR THE BUILDING D	EPARTMENT		
By:		Date:	



# SPECIAL INSPECTION AND TESTING SCHEDULE

PROJECT NAME					BUILDING PERMIT NO.			
	Pl	ROJECT AD	DRESS		TESTING/INSPECTION AGENCY or SPECIAL INSPECTOR			
REIN	FORCED CO	NCRETE, (	GUNITE, GF	ROUT AND MORTAR:	STRUCTURAL STEEL/WELDING:			
Concr	ete Gunite	Grout	Mortar		Complementary (For example of the last)			
001101		Grout	11101111	Aggregate Tests	Sample and Test (list specific members below) Shop Material Identification			
				Reinforcing Tests				
				Mix Designs	Welding Inspection Shop Field Ultrasonic Inspection Shop Field			
				Reinforcing Placement	High-strength Bolting			
				Batch Plant Inspection	Inspection Shop Field			
				Inspect Placing	Inspection Shop Field A325 N X F A490 N X F			
				Cast Samples				
				Pick-up Samples	Metal Deck Welding Inspection			
				Compression Tests	Reinforcing Steel Welding Inspection			
			•		Metal Stud Welding Inspection			
PREC	AST/PRESTI	RESSED C	ONCRETE:		Concrete Insert Welding Inspection			
Piles	Post-Tens	Pre-tens	Cladding		FIREPROOFING:			
				Aggregate Tests				
				Reinforcing Tests	Placement Inspection			
				Tendon Tests	Density Tests			
				Mix Designs	Thickness Tests			
				Reinforcing Placement	Inspect Batching			
				Insert Placement	NIGHT ATTING GOLIGINETTE			
				Concrete Batching	INSULATING CONCRETE:			
				Concrete Placement	0 1 177 /			
				Installation Inspection	Sample and Test			
				Cast Samples	Placement Inspection Unit Weights			
				Pick-up Samples	Onit weights			
				Compression Tests	FILL MATERIAL:			
					THE MITTERNIE.			
MASC	ONRY:				Acceptance Tests			
					Placement Inspection			
Special Inspection Stresses Used Preliminary Acceptance Tests (Masonry Units, Wall Prisms) Subscript Tests (Marter Creat Field Well Brisms)					Field Density			
<ul><li>Subsequent Tests (Mortar, Grout, Field Wall Prisms)</li><li>Placement Inspection of Units</li></ul>				wan Prisms)	STRUCTURAL WOOD:			
P	racement insp	bection of U	ints					
ADDITIONAL INSTRUCTIONS OR OTHER TESTS AND			NS OR OTH	ER TESTS AND	Shear Wall Nailing Inspection			
INSPECTIONS:			OK OIII	LK ILDID AND	Inspection of Glu-lam Fab			
11 101 1	20110110.				Inspection of Truss Joist Fab			
Epoxy Set Bolts					Sample and Test Components			