

2023 Annual Paving Program

Municipality of West Milton

By Location

Work Sheet For File / Bid Information Only

Street Location	Limits	Length	Width	Depth	Sq. Ft	Tons
-----------------	--------	--------	-------	-------	--------	------

Project Detail:

- Mill 1.5 Inch X 7 Foot Pass Beside Curbs
- Add 1.5 Inch Surface Course Curb Line to Curb Line

Street Name and Limits

<u>Hamilton St</u>	Main St to Hasket Rd	2832'	33'	1.5	93456	865
<u>Spring St</u>	Hamilton St. South to End	1381'	31'	1.5	42811	396

Total Tons:1261

2023 Paving to take place after CenterPoint gas line replacement project and Municipality of West Milton ADA sidewalk ramp replacements. Tentative paving begin schedule: August 2023

Sealed Bid Leader – Questions:
Ben Herron – Service Director
(937) 698-1500 ext. 116
herron@westmiltonohio.gov

Municipality of West Milton
2023 Street Resurfacing Project Project's Official "SEALED BID"

Sealed Bids DUE BY and OPENED - 11 AM Monday February 6, 2023
West Milton Municipal Building 701 S. Miami St West Milton, OH 45383

GENERAL NOTES

- The contractor shall be solely responsible complying with Federal, State and Local safety requirements for the protection of workers, residents, and property.
- All Asphalt Contractors MUST be ODOT Prequalified.
- One full payment will be made "post project" after both parties agree that work meets quality standards.
- Bidder must submit bid bond in according to ORC 153
- All ODOT construction and material specifications shall apply to this project.
- All delivered asphalt must be accompanied with a submitted load ticket.
- It is the winning bidder's responsibility to verify field measurements prior to submitting bids.
- Bidder will have a preconstruction walk through to mark start and stop areas and project specific special needs.
- Winning bidder provides signage and traffic control working with Municipal representatives to keep the work zones safe for workers and public during all phases of construction. Local traffic shall be maintained including ingress and egress to driveways whenever possible.
- Winning bidder applies all no parking signs a minimum 48 hours prior to project start date.
- No more than 48 Hours shall pass between milling and asphalt application.
- All butt joints shall be sealed with Asphalt Binder.
- Asphalt shall be applied in a continuous operation wherever possible.
- Any Iron within the project limits shall be set at proper grade as NOT to interfere with winter plow operations.
- Contractor to ensure that the applied street profile drains from center crown to gutter plates/edges.
- Bidders Must include Bid Guaranty and Contract Bond
- Bidder Must furnish Insurance Certificate of Compliance
- Bidder Must furnish minimum of 3 references.
- Bid Must be in sealed envelope marked "2023 PAVING BIDS"

Municipality of West Milton
Final Bid Total Page - 2023

Street Resurfacing

<u>Description</u>	<u>Unit Type</u>	<u>Approx. Qty.</u>	<u>Unit Cost</u>	<u>Total</u>
<u>Asphalt Milling</u>	<u>SY</u>			
<u>Tack Coat</u>	<u>Gal</u>			
<u>Surface Course</u>	<u>CY</u>			
<u>Base Course</u>	<u>CY</u>			
<u>Traffic Control</u>	<u>LUMP</u>			

Bidders Total Cost of Project \$ _____

Bidder Owner/Officer Printed Name: _____

Bidder Owner/Officer Printed Title: _____

Bidder Owner/Officer Signature: _____

Sworn to and subscribed in my presence this _____ **day of** _____, **2023**

NOTARY SEAL