City of Willamina 411 NE "C" Street PO Box 629 Willamina OR 97396 Telephone: 503-876-2242 Fax: 503-876-1121 ci.willamina.or.us

PLANNING APPLICATION FORM

Property Address: <u>601 Churchman Street</u> Willamina, OR	Property Owner: <u>Willamina Ridgeview Hts, LLC</u> Address: <u>275 N 70th Place</u> Philomath, OR 97370
Assessor's Map & Tax Lot 🗆 Polk 🛛 🖾 Yamhill	Phone: _503-550-0583
T6S-R7W Sec1 Tax Lot(s) R6701 00502	Applicant: Keystone Builders Tim Wenger
Zoning	Address: PO Box 893 Philomath, OR 97370
201111g	Phone:
Project Type (Please check all applicable): Annexation Conditional Use Home Occupation	Authorized Representative (if different from applicant): Steve Ward, Westech Engineering Address: <u>3841 Fairview Ind Dr SE, Suite 100</u>
Lot Line Adjustment	Salem, OR 97302 Phone: 503-585-2474 (C) 503-931-3460
Non-Conforming Use Partition	Pilolie. <u>505-565-2474 (C) 505-951-5460</u>
	Surveyor or Engineer (if applicable):
□ Similar Use	Same as Authorized Representative
Subdivision and Planned Unit Development	Address:
Variance	
Minor	Phone:
Major	
Zone Change	CERTIFICATION: I hereby certify that the information on this
□ Other:	application is correct and that I own the property or the owner
Size of the Project (# of units, lots, sq. ft., etc.): 60 Lot subdivision. See Dwg G-5 for lot details.	has executed a Power of Attorney authorizing me to pursue this application (attached).
Attachments: (4) folded Maps/Site Plan to scale (if larger than 11" x 17") (1) 8 1/2" x 11" reduced copy of site plan	(Signature of Owner or Attorney-in-Fact) Date
 Written Narrative/Response to Criteria Power of Attorney (if applicable) 	(Signature of Additional Owner) Date
	(For Office Use)
Description of Request	Date Application Received:
(include name of project and proposed uses)	Date Application Complete:
Subdivide 10.3 acres into 59 Lots. 26 Lots will	Pre-app required? Y N Pre-app #
be townhouse lots. 33 lots will be conventional	Fee Paid: Initials:
_SF lots	File Number:

(For Office Use) COMPLETE PER: Engineering _____ (Req'd Zn Chg, SPR, & Land Divisions) Planning _____

A Subdivision Application Includes:

- Application cover page (submitted to City)
- □ Explanation of Type II Action (copy for applicant)
- Preliminary Subdivision Plan for the subdivision (submitted to City)
- Submit materials showing compliance with the requirements of Section 3.107.02, A, 2:
 - 2. In addition to the information listed in Subsection 3.106.03 of this ordinance, applicants for subdivisions, and planned unit developments shall submit the following:
 - a. The name, address and phone number of the applicant engineer, land surveyor, or person preparing the application;
 - b. Name of the PUD or subdivision.
 - c. Date the drawing was made.
 - d. Vicinity sketch showing location of the proposed land division.
 - e. Identification of each lot or parcel and block by number.
 - f. Gross acreage of property being subdivided or partitioned.
 - g. Direction of drainage and approximate grade of abutting streets.
 - h. Streets proposed and their names, approximate grade, and radius of curves.
 - i. Any other legal access to the subdivision, PUD or partition other than a public street.
 - j. Existing topography with contour lines at two (2) foot intervals if ten percent (10%) slope or less, five (5) foot intervals if exceeding ten percent (10%) slope, and a statement of the source of contour information.
 - Proposed grading and topographical changes with contour lines at two (2) foot intervals if ten percent (10%) or less slope, five (5) foot intervals if exceeding ten percent (10%) slope.

1. All areas to be offered for public dedication.

Written explanation of the subdivision request: Subdivide 10.3 acres into 59 lots in four phases.

Written response to criteria (attached)

Deposit Fee: \$2,500.00 (\$750.00 plus \$450.00 per lot up to maximum of \$2,500.00) (Resolution No.16-17-013, May 9, 2017)
 Applicants are required to reimburse the City for any and all costs associated with their Land Use Applications. Deposit amounts are based on City Planner, City Engineer, City Attorney and other occurred costs or fees associated with land use applications, must be paid in full by the applicant prior to the City of Willamina signing off on any land use decision. In the event that costs do not exceed the initial application deposit, the City shall reimburse the unused portion of the applicant's deposit.

Subdivision – Written Response to Criteria

Criteria the Planning Commission uses to make a decision.

The applicant is required to submit written responses that provide evidence substantiating all of the following. Zone District resources are referenced on Page 5.

Willamina Development Code, Sections 2.208 and 3.107.01 (see 2.208).

Section 2.208:

A. Explain how the minimum lot area conforms to the requirements of the zoning district in which the lots are located.

Response: <u>All single family lots are a minimum of 5,000 square feet</u>. <u>All townhome lots</u> are a minimum of 3,300 square feet.

B. Acknowledge that the depth of lots shall not be more than 2.5 times the width of the lot (note: Section 2.208.03, B, includes exceptions for *attached* single family dwellings and lots created for public uses).

Response: <u>All lots conform to this standard except lots 65-66</u>. Lots 65 and 66 are forced to be deeper lots due to the street configuration which is required to be ADA compliant.

C. In regards to access, explain how all lots provide a minimum frontage, on an existing or proposed public street, equal to the minimum lot width required by the underlying zone (note: Section 2.208.03, C, includes exceptions for some situations).

Response: <u>All lots meet the minimum lot width standard.</u>

D. If "flag" lots are proposed, explain how the flag lot standards of Section 2.208.03, D, are met (Lot, Flag: A lot or parcel of land taking access by a relatively narrow strip of land between the major portion of the parcel and the point of public access to the parcel, all of which is under the same ownership or title.).

Response: No flag lots are proposed. Lots 80-82 are served by a 30' public R/W which Also serves the City property to the south.

E. Explain how "through" lots have been avoided except where essential to provide separation of residential development from major traffic arteries, adjacent non-residential activities, or to overcome specific disadvantages of topography and orientation (Lot, Through: An interior lot having frontage on two streets).

Response: <u>Through lots have been avoided except for lots 47-52</u>. The site topographic constrains do not allow B Street to be shifted north which forces the double fronting lots.

F. Explain how the side lines of lots, as far as practicable, run at right angles to the right-of-way line of the street upon which the lots face.

Response: With minor exceptions, all lot lines are +/- 90° to the R/W line.

G. Identify any utility easements provided on lot areas, existing or proposed, necessary to accommodate public utilities and state how their minimum width complies with the widths specified in Subsection 2.205.02(I).

Response: <u>A 21' sanitary sewer and storm drain easement is required on the east side of lots 54-67 due to the topographic constraints of the site. Access easements fro Highland Loop is provided to the proposed MH locations. The City has a W/L easement which is not located correctly. We propose to vacate the existing easement and provide a new easement in the correct location.</u>

H. Explain how the length, width, and shape of blocks have been designed with regard to (1) providing adequate building sites for the use contemplated; (2) consideration of needs for convenient access, circulation, control, and safety of street traffic; and (3) recognition of limitations and opportunities of topography.

Response: <u>The site has significant topographic constraints</u>. It is not possible to extend <u>streets to the north to to the topographic constraints</u>. Two street stubs are provided to the east. The property to the south and west is fully developed.

I. Explain how the following requirement is met: Blocks shall not exceed 1,000 feet in length between street lines, except blocks adjacent to arterial streets, or unless the previous adjacent development pattern or topographical conditions justify a variation. The recommended minimum distance between intersections on arterial streets is 1,800 feet.

Response: <u>A variance to the block length is requested due to the existing lot configuration</u> and topographic constraints. The proposed design loops the street system (Highland Loop) 6th street in the most efficient way possible given all of the constraints.

J. Explain how the requirements for public sewer facilities are met.

Response: <u>Public sewer will be extended from the west for Phase III and to the intersection</u> of C and 5th Streets for phases IV, V and VI.

K. Explain how the requirements for public water facilities, including fire protection, are met.

L. Explain how the requirements for public storm drainage facilities are met.

Response: <u>Stormwater detention is proposed for the development through the use of</u> detention pipes similar to Phase I and II.

M.Explain how the requirements for public street improvements are met, including gutters, curbs, sidewalks, and any dedication of public rights-of-way.

Response: All streets will be improved to City Standards.

N. Explain how the requirements for public street improvements for street lights and street signs are met.

Response: Street lights and signing will be installed per City Standards.

O. Explain how the requirement for public park dedication or fee in lieu of is met.

Response: A fee in lieu is proposed to be paid to the City

P. Explain how the proposed subdivision is laid out to provide safe, convenient, and direct vehicle, bicycle and pedestrian access to nearby residential areas, transit neighborhood activity centers such as schools and parks, commercial areas, and industrial areas; and to provide safe, convenient and direct traffic circulation. At a minimum, "nearby" is interpreted to mean uses within one quarter (1/4) mile which can be reasonably expected to be used by pedestrians, and uses within 1 mile of the subdivision boundary which can reasonably expected to be used by bicyclists.

Response: _____The subdivision as proposed is the most efficient way for all modes of ______transportation. All traffic is directed to 6th Street and Willamina Drive which directs ______traffic directly to the City center.

Q. Explain how the pedestrian/bicycle and accessway connections with adjoining arterial and collector streets are provided when any portion of the site's arterial or collector street frontage is over 600 feet from either a subdivision access street or other pedestrian/bicycle accessway. When natural features (e.g., adverse topography, streams, wetlands) exist, explain how they affect the provisions of pedestrian/bicycle and accessways and if they are proposed to be limited. If buildings or other existing developments on adjacent lands may physically preclude a connection now or in the future considering the potential for redevelopment, explain what the application proposes as a solution.

Response: <u>The proposed development has two direct connections to 6th street which is a</u> <u>City Collector street.</u>

R. Explain how the park and recreation requirements of Section 2.208.05, B, 16 are met.

Response: <u>The developer proposes a fee in lieu of payment to satisfy this requirement.</u>

If additional space is needed, please attach an additional page(s).

The property is zoned (check the appropriate box—continued on Page 6):

____Single-family Residential (R-1): Section 2.101.

____Two-family Residential (R-2): Section 2.102.

- ____Multiple-family Residential (R-3): Section 2.103.
- General Commercial (C-1): Section 2.104.
- Commercial Residential (C-2): Section 2.105.
- Industrial (M-1): Section 2.108.

RECEIVED

City of Willamina 411 NE "C" Street PO Box 629 Willamina OR 97396 Telephone: 503-876-2242 Fax: 503-876-1121 ci.willamina.or.us

AUG 2 5 2023

Property Address: Highlands Loop and 6th Street Willamina, OR

Assessor's Map & Tax Lot
Polk
Yamhill
06S - R07W Sec 01 Tax Lot(s) 00502

_____ Tax Lot(s) _____

Zoning

Project Type (Please check all applicable):

- □ Annexation
- Conditional Use
- Home Occupation
- Lot Line Adjustment
- □ Non-Conforming Use
- D Partition
- □ Signs
- Similar Use
- D Subdivision and Planned Unit Development
- ⊠ Variance □ Minor
- 2 Major
- Zone Change
- Other:

Size of the Project (# of units, lots, sq. ft., etc.):

Attachments:

- \Box (4) folded Maps/Site Plan to scale (if larger than 11" x 17") \Box (1) 8 ½" x 11" reduced copy of site plan
- Written Narrative/Response to Criteria
- Power of Attorney (if applicable)

Description of Request

(include name of project and proposed uses)

- Variance Request
- 1 Lot width to Depth Ratio
- 2. Through Lot Standard.
- 3. Block Length Standard.

(For Office Use) COMPLETE PER: Engineering ______ (Req'd Zn Chg, SPR, & Land Divisions) Planning ______

PLANNING APPLICATION FORM

Property Own	ner: Keystone Buildier, LLC - Tim Wenger
	Box 893
Phi	Iomath, OB 97370
Phone:503	-550-0583
	Same as Owner
Phone:	
	Representative (if different from applicant): ame as Owner
Address:	
Surveyor or Steve War	Engineer (if applicable): d - Westech Engineering
	11 Fairview Industrial Dr SE Suite 100 em, OR 97302
	3-585-2474
application is has executed a application (att	
/ /	

(Signature of Owner or Attorney-in-Fact)

(Signature of Additional Owner)

Y

Date

Date

8/25/23

(For Office Use)	
Date Application Receive	d:
Date Application Comple	
Pre-app required? Y N	
Fee Paid:	Initials:
File Number:	

Ridgeview Subdivision Phases III – VI Variance Request

Willamina Development Code 2-100 2.208 DEVELOPMENT STANDARDS FOR LAND DIVISIONS

2.208.3 Standards for Lots or Parcels

A. Minimum lot area: Minimum lot area shall conform to the requirements of the zoning district in which the parcel is located.

B. Lot width and depth: The depth of a lot or parcel shall not be more than two and a half (2.5) times the width of the parcel, with the following exceptions:

> 1. Individual lots for attached dwelling units shall not be less than twenty (20) feet in width. Lot depth may vary, but shall be adequate to provide a minimum of 300 square feet of semiprivate outdoor living space for each unit.

REC. IVED

AUG 2 2 2023

2. Individual lots for single-family attached dwelling units shall be designed so that lot depth is not greater than three (3) times lot width.

Variance request and justification: Lots 33, 35 through 46, 65, 66, 84 and 85 require a variance to the lot width-to-depth ratio. The variance requested is due to the existing property configuration and topographic constraints of the site. The northerly portion of the property is very steep eliminating the possibility of a street which would negate the need for a variance for lots 35 through 46. Because of the existing topography, it is necessary to have long, skinny lots (Lots 35-46). The configuration of Lots 33, 65, 66, 84 and 85 are restricted due to the existing property boundaries and the required street layout required to connect to the existing street network and provide ADA accessible routes. The lot width to depth ratio for these lots is not significantly over the Standard.

3. Parcels created for public utility uses or in zones where there is no minimum lot area requirement shall be exempt from width to depth ratio provisions. E. Through Lots: Through lots shall be avoided except where essential to provide separation of residential development from major traffic arteries, adjacent non-residential activities, or to overcome specific disadvantages of topography and orientation. Screening or buffering, pursuant to the provision of Section 2.207, may be required by the City during the review of the land division request.

Variance request and justification: Lots 47 through 52 require a variance to the Through Lot Standard. The variance requested is due to the existing property configuration and topographic constraints of the site. The northerly portion of the property is very steep eliminating the possibility of moving Kindness Street north to allow lots on north of Lots 47 through 52 negating the need for a variance.

2.208.4 Standards for Blocks

A. General: The length, width, and shape of blocks shall be designed with regard to providing adequate building sites for the use contemplated; consideration of needs for convenient access, circulation, control, and safety of street traffic; and recognition of limitations and opportunities of topography.

B. Sizes: Blocks shall not exceed 1,000 feet in length between street lines, except blocks adjacent to arterial streets, or unless the previous adjacent development pattern or topographical conditions justify a variation. The recommended minimum distance between intersections on arterial streets is 1,800 feet.

Variance request and justification: The block length of Highland Loop and 6th Street is just over 2,300 feet. This is due to the existing property configuration and topographic constraints of the site. The northerly portion of the property is very steep eliminating the possibility of any streets extending north. The City owns a 1.3 acre parcel, occupied by the City's water tank and pump station, in the middle of the development on the south side of the development. It is not possible to extend the Kindness Court south to 6th Street through the City property to eliminate the need for a variance.

	City of Willamina 411 NE C Street Willamina, Oregon 97396 503-876-2242 DATE	№ 12396 8 25/23
Ē	RECEIVED FROM Key Stone Buildors, LLC	\$ <u>1800</u> 00
R E C	FOR-3 VOTICACE Apps Tax Lot 00502	
	AMOUNT OF ACCOUNT THIS PAYMENT 180000 CREDIT CARD BY BALANCE DUE MONEY ORDER	

Aug 25, 2023 Receipt No: 16.000618 Keystone Builders LLC Planning 3 Variance Applications Tax Lot 00502 1,800.00 ------1,800.00 Totals Check 1,800.00 Check No: 13429 Total Applied: 1,800.00 -----.00 Change Tendered: ******

08/25/2023 9:58 AM

DRAWINGS FOR: RIDGEVIEW SUBDIVISION -PHASES III - VI

FOR:

KEYSTONE BUILDERS, LLC P.O. BOX 893 PHILOMATH, OR 97370 TIM WENGER 503-550-0583

PROJECT LOCATION TAX LOT 500, NORTH 1/2 SECTION 1, T.6Ś., R.7W., W.M. WILLAMINA, YAMHILL COUNTY, OREGON





Know what's **below**. Call before you dig.

CIVIL ENGINEERING:

WESTECH ENGINEERING, INC. 3841 FAIRVIEW INDUSTRIAL DR. SE

SALEM, OREGON 97302 CONTACT: MR. STEVE WARD (503) 585-2474

SURVEYOR:

LELAND MCDONALD & ASSOCIATES **3765 RIVERSIDE DRIVE** MCMINNVILLE. OREGON 97128 CONTACT: MR. LELAND MCDONALD (503) 472-7904

PROPOSED LEGEND

	STORM DRAINAGE PIPE	
	SANITARY SEWER PIPE	
	WATER PIPE	
	CATCH BASIN	
<	CULVERT	
S	SANITARY SEWER MANHOLE	
D	STORM DRAINAGE MANHOLE	
\geq	WATER METER	
\otimes	GATE VALVE	
Q	FIRE HYDRANT	
ι¥ι	WATER LINE FITTINGS	
U	GAS METER	
L.	ELECTRICAL VAULT	
□ ¢	STREET LIGHT AND POLE	
	SIGN	
	MAILBOX	



	DRAWING INDEX
DRAWING NO.	DRAWING TITLE
G-1	COVER SHEET, LEGENDS, & VICINITY MAP
G-2	DRAWING INDEX
G-3	CONSTRUCTION NOTES
G-4	CONSTRUCTION NOTES
G-5	PRELIMINARY PLAT PLAN
G-6	OVERALL GRADING PLAN
G-7	INTERIM FIRE ACCESS PLAN - PHASE III DEVELOPMENT
EC-1	EROSION PREVENTION & SEDIMENT CONTROL (EPSC) - NOTES
EC-2	EPSC - NOTES
EC-3	EPSC - DETAILS
EC-4	EPSC - DEMOLITION & CLEARING PLAN (NORTH)
EC-5	EPSC - DEMOLITION & CLEARING PLAN (CENTRAL)
EC-6	EPSC - DEMOLITION & CLEARING PLAN (SOUTH)
EC-7	EPSC - STREETS & UTILITIES PLAN (NORTH)
EC-8	EPSC - STREETS & UTILITIES PLAN (CENTRAL)
EC-9	EPSC - STREETS & UTILITIES PLAN (SOUTH)
ST-1	TYPICAL STREET SECTIONS
ST-2	HIGHLANDS LOOP - PLAN & PROFILE STA. 12+08 - 16+00
ST 2 ST-3	HIGHLANDS LOOP - PLAN & PROFILE STA. 12+08 - 10+00 HIGHLANDS LOOP - PLAN & PROFILE STA. 16+00 - 20+00
ST-4	HIGHLANDS LOOP - PLAN & PROFILE STA. 10+00 - 20+00 HIGHLANDS LOOP - PLAN & PROFILE STA. 20+00 - 24+00
ST-5	HIGHLANDS LOOP - PLAN & PROFILE STA. 20+00 - 24+00 HIGHLANDS LOOP - PLAN & PROFILE STA. 24+00 - END
ST-6	KINDNESS STREET - PLAN & PROFILE STA. 30+00 - 32+50
ST-7	KINDNESS STREET - PLAN & PROFILE STA. 32+50 - END
ST-8	JOYFUL STREET - PLAN & PROFILE
ST-9	KINDNESS COURT - PLAN & PROFILE
ST-10	6TH STREET - PLAN & PROFILE
SD-1	SD-A LINE - PLAN & PROFILE STA. 1+00 - 5+00
SD-2	SD-A LINE - PLAN & PROFILE STA. 5+00 - 9+50
SD-3	SD-A LINE - PLAN & PROFILE STA. 9+50 - 13+50
SD-4	SD-A LINE - PLAN & PROFILE STA. 13+50 - END
U-1	UTILITY PLAN (NORTH)
U-2	UTILITY PLAN (CENTRAL)
U-3	UTILITY PLAN (SOUTH)
U-4	SS-A LINE - PLAN & PROFILE STA. 1+00 - 3+50
U-5	SS-A LINE - PLAN & PROFILE STA. 3+50 - END
U-6	SS-B LINE - PLAN & PROFILE STA. 1+00 - 5+50
U-7	SS-B LINE - PLAN & PROFILE STA. 5+50 - 10+50
U-8	SS-B LINE - PLAN & PROFILE STA. 10+50 - END
U-9	SS-C LINE - PLAN & PROFILE
U-10	SS-D LINE - PLAN & PROFILE STA. 1+00 - 4+50
U-11	SS-D LINE - PLAN & PROFILE STA. 4+50 - END
U-12	SS-E LINE - PLAN & PROFILE
W-1	WATER PLAN (NORTH)
W-2	WATER PLAN (CENTRAL)
W-3	
W-2	





54. Granular trench bedding and backfill shall conform to the requirements of OSSC (ODOT/APWA)

27. For public and private improvements, except as otherwise allowed by the specifications, drawing details or notes, immediately following stripping and grading operations, compact subgrade to 95% of the maximum dry density per AASHTO T-180 test method (Modified Proctor). Subgrade must be inspected and approved by the Owner's authorized representative

28. Engineered fills shall be constructed and compacted in 6" lifts over approved subgrade. All fills shall be engineered and comply with the Oregon Structural Specialty Code, with each lift compacted to 95% of the maximum dry density per AASHTO T-180 test method (Modified

29. Granular baserock shall conform to the requirements of OSSC (ODOT/APWA) 02630.10 (Dense Graded Base Aggregate), with no more than 10% passing the #40 sieve and no more than 5%

30. Compact granular baserock to 95% of the maximum dry density per AASHTO T-180 test method (Modified Proctor). Written baserock compaction test results from an independent testing laboratory must be received by the Owner's authorized representative before placing AC pavement, and a finished rock grade proof-roll (witnessed by the Owners authorized

31. A.C. pavement shall conform to OSSC (ODOT/APWA) 00745 (Hot Mixed Asphalt Concrete Pavement) for standard duty mix. Unless otherwise specified or shown on the drawings, base lifts shall be 3/4" dense graded mix, while wearing courses shall be 1/2" dense graded mix. Unless otherwise specified or shown on the drawings, A.C. pavement for parking lots and streets shall be Level 2 mix (50 blow Marshall) per OSSC (ODOT/APWA) 00744.13. A.C. Pavement shall be compacted to a minimum of 91% of maximum density as determined by the Rice standard method. Written AC pavement compaction test results from an independent testing laboratory must be received by the Owner's authorized representative before final payment. Asphalt cement - use PG64-22 asphalt. Provide asphalt cement conforming to the most current published version of ODOT "Standard Specifications for Asphalt Materials." Use PG64-22 Performance Graded Asphalt Binder with mixes containing 20

32. Pavement surface shall be a smooth, well-sealed, tight mat without depressions or bird baths. Bony or open araded pavement surfaces shall be repaired to the satisfaction of the Owner's

33. HMAC mixtures shall be placed only when the surface is dry and weather conditions are such that proper handling, finishing and compaction can be accomplished. In no case shall bituminous mixtures be placed when the surface temperature is below the minimum established under 2018 OSSC (ODOT/APWA) 00744.40 (AC - Season and Temperature

34. Contractor shall protect new pavement against traffic as required, until it has cooled

35. Unless otherwise shown on the drawings or details, straight grades shall be run between all finish grade elevations and/or finish contour lines shown (exception: where grades are shown across sidewalks, slopes shall be adjusted to ensure that maximum allowable sidewalk cross

36. Finish pavement grades at transition to existing pavement shall match existing pavement grades or be feathered past joints with existing pavement as required to provide a smooth,

37. All existing or constructed manholes, cleanouts, monument boxes, gas valves, water valves and similar structures shall be adjusted to match finish grade of the pavement, sidewalk, landscaped area or median strip wherein they lie. Verify that all valve boxes and risers are

38. Unless otherwise shown on the drawings, no cut or fill slopes shall be constructed steeper

39. Contractor shall seed and mulch (uniformly by hand or hydroseed) all exposed slopes and disturbed areas which are not scheduled to be landscaped, including trench restoration areas. If the Contractor fails to apply seed and mulch in a timely manner during periods favorable for germination, or if the seeded areas fail to germinate, the Owner's Representative may (at his discretion) require the Contractor to install sod to cover such disturbed areas.

40. Unless otherwise shown or indicated on the drawings, 6-inches nominal curb exposure used

41. Where new curbing connects to existing curbing or is installed along existing streets or pavement, the gutter grade shall match the existing street grades so as to allow drainage from the street to the gutter and through any transitions. The Contractor shall notify the Owner's Representative in writing of any grade discrepancies or problems prior to curb

42. Road widening design is based on available survey taken at random intervals. Street pavement widening cross slope shall be a minimum of 2% and a maximum of 5% except at intersections, where the street cross slopes shall not exceed 2% maximum (intersection defined from end of curb radius both directions). Prior to placing curbs, Contractor shall field verify pavement widening cross slope and contact Engineer if the design pavement widening

43. Contractor shall construct all handicap access ramps in accordance with current ADA

44. Sidewalks shall be a minimum of 4-inches thick and standard residential driveways shall be a minimum of 6-inches thick. Commercial use driveways and alley approaches shall be minimum 8-inches thick. All curbs, sidewalks and driveways shall be constructed using 3300-psi concrete, and shall be cured with Type 1 or Type 1D clear curing compound. All

45. Curb & sidewalk concrete shall be placed only during periods when it will not be damaged by rain (protect unhardened concrete from precipitation). Concrete shall not be placed on frozen baserock. Do not begin concrete placement until temperature in the shade is a minimum of 35°F and rising, and stop placement if air temperature falls below 35°F. Protect concrete from freezing for a minimum of 5 days after placement per OSSC (ODOT/APWA) 00440.40.d

46. Contraction joints shall be installed directly over any pipes that cross under the sidewalk, to control cracking. In general, cracks in new curbs or sidewalks (at locations other than contraction joints) are not acceptable, and cracked panels shall be removed & replaced unless

47. All sidewalks shall be ADA compliant. Direction of sidewalk cross slope shall conform with the slope direction shown on the grading plan. Sidewalk cross slopes shall not exceed 1:67 (1.5%)

48. Where trench excavation requires removal of PCC curbs and/or sidewalks, the curbs and/or sidewalks shall be sawcut and removed at a tooled joint unless otherwise authorized in writing by the Approving Agency. The sawcut lines shown on the drawings are schematic and not

49. Unless otherwise shown on the drawings, areas along curbs and sidewalks shall be backfilled

50. All curbs to be marked with a "S" (Sewer), "W" (Water) and "D" (Storm) where services or

51. All tapping of existing sanitary sewer, storm drain mains, and manholes must be done by

52. The Contractor shall have appropriate equipment on site to produce a firm, smooth, undisturbed subgrade at the trench bottom, true to grade. The bottom of the trench excavation shall be smooth, free of loose materials or tooth grooves for the entire width of

53. All pipes shall be bedded with minimum 6-inches of 3/4"-0 crushed rock bedding and backfilled with compacted 3/4"-0 crushed rock in the pipe zone (crushed rock shall extend a minimum of 12-inches over the top of the pipe in all cases). Unless CDF or other backfill is shown or noted on the drawings, crushed rock trench backfill shall be used under all improved 02630.10 (Dense Graded Base Aggregate), 3/4"-0. Unless otherwise shown on the drawings, compact granular backfill to 95% of the maximum dry density per AASHTO T-180 test method (Modified Proctor).

- 55. Contractor shall arrange to abandon existing sewer and water services not scheduled to remain in service in accordance with approving agency requirements.
- 56. All piped utilities abandoned in place shall have all openings closed with concrete plugs with a minimum length equal to 2 times the diameter of the abandoned pipe.
- 57. The end of all utility service lines shall be marked with a 2-x-4 painted white and wired to pipe stub. The pipe depth shall be written on the post in 2" block letters and red lined on the drawings for preparation of As-Built Drawings.
- 58. All non-metallic water, sanitary and storm sewer piping shall have an electrically conductive insulated 12 gauge solid core copper tracer wire the full length of the installed pipe using blue wire for water and green wire for storm and sanitary piping. Tracer wire to be terminated in copperhead industries snake pit roadway box (CISPRB-WATER & CRB14G). Roadway box to be set immediately adjacent to each MH & GV. Terminate wire at each SS & SD stub and inside each WM box. See DWG D-5 for details.
- 59. No trenches in sidewalks, roads, or driveways shall be left in an open condition overnight. All such trenches shall be closed before the end of each workday and normal traffic and pedestrian flows restored.
- 60. Before mandrel testing, TV inspection or final acceptance of gravity pipelines, all trench compaction shall be completed and all sewers and storm drains flushed & cleaned to remove all mud, debris & foreign material from the pipelines, manholes and/or catch basins.
- 61. Where future extensions are shown upstream of new manholes (sewer or storm), catch basins or junction boxes, pipe stubs (with gasketed caps) shall be installed at design grades to a point 2' minimum outside of the structure.

WATER SYSTEM:

62. City forces to operate all valves, including fire hydrants, on existing public mains.

63. All Public water mains shall be C900 PVC.

- 64. All fittings 4-inches through 24-inches in diameter shall be ductile iron fittings in conformance with AWWA C-153 or AWWA C-110. The minimum working pressure for all MJ cast iron or ductile iron fittings 4-inches through 24-inch in diameter shall be 350 psi for MJ fittings and 250 psi for flanged fittings.
- 65. All water mains to be installed with a minimum 36 inch cover to finish grade unless otherwise noted or directed. Water service lines shall be installed with a minimum 30-inch cover. Deeper depths may be required as shown on the drawings or to avoid obstructions.
- 66. Unless otherwise shown or approved by the Engineer, all valves shall be flange connected to adjacent tees or crosses.
- 67. Thrust restraint shall be provided on all bends, tees and other direction changes per Approving Agency requirements and as specified or shown on the drawings.
- 68. Water service pipe shall be 250 PSI rated, ³/₄" CTS Poly or Pex.
- 69. Contractor shall provide all necessary equipment and materials (including plugs, blowoffs, valves, service taps, etc.) required to flush, test and disinfect waterlines per the Approving Agency requirements.
- 70. Where new waterlines cross below or within 18-inches vertical separation above a sewer main or sewer service lateral, center one full length of waterline pipe at point of crossing the sewer line or sewer lateral. In addition (unless otherwise approved in writing by the Approving Agency, existing sewer mains and/or service laterals within this zone shall be replaced with a full length of Class 50 Ductile Iron or C-900 PVC pipe (DR 18) centered at the crossing in accordance with OAR 333-061 and Approving Agency requirements. Connect to existing sewer lines with approved rubber couplings. Example: For an 8-inch waterline with 36-inches cover, 4-inch service lateral inverts within 5.67-feet (68-inches) of finish grade must be DI or C-900 PVC at the crossing.
- 71. All waterlines, services and appurtenances shall be pressure tested for leakage. All testing shall conform to requirements as outlined in the specifications. Approving Agency standards and/or testing forms. The hydrostatic test shall be performed with all service line corporation stops open and meter stops closed, and with all hydrant line valves open. Prior to the start of each pressure test, the position of all mainline valves, hydrant line valves and service line corporation stops in the test segment shall be verified. City forces to witness all testing.
- 72. After the pressure test and prior to disinfecting, the water lines shall be thoroughly flushed through hydrants, blow offs or by other approved means.
- 73. Disinfection & Bacteriological Testing. All water mains and service lines shall be chlorine disinfected per Approving Agency requirements, AWWA C-651 or OAR 333-061 (25 mg/L minimum chlorine solution, 24 hours contact time), whichever is more stringent. Unless otherwise approved by the Approving Agency, a Representative from the Approving Agency shall witness the application of the chlorine solution and the chlorine testing at the end of the 24 hour contact period. After the 24 hour chlorine contact period, the free chlorine concentration shall be checked, and if it is found to be 10 mg/L or more, the chlorine solution shall be drained (otherwise the line shall be rechlorinated), the waterline flushed with potable water, and a minimum of two consecutive samples taken at least 24 hours apart shall be collected from the waterline for microbiological analysis (ie. one sample immediately after flushing, and another sample 24 hours later). Contractor to pay for laboratory analysis of water samples taken under the supervision of the Approving Agency. If the results of both analyses indicate that the water is free of coliform organisms, the waterline may be placed in service. Should the initial treatment prove ineffective, the chlorination shall be repeated until confirmed tests show acceptable results.
- 74. Disinfection of Connections. For connections which cannot be disinfected with the waterline mainlines as noted above, all fittings, valves and appurtenances, including tool surfaces which will come in contact with potable water, shall be thoroughly cleaned by washing with potable water and then swabbed or sprayed with a one percent (1%) hypochlorite solution (10,000 mg/L) in accordance with the requirements of AWWA C-651 and OAR 333-061.

SEWER & STORM MANHOLES:

- 75. All precast manholes shall be provided with integral rubber boots. Where manholes without integral rubber boots are approved by the Owner's Representative and Approving Agency, a pipe joint shall be provided on all mainlines within 1.5 feet of the outside face of the manhole. Where required by Public Works, watertight lockdown lids required on all manholes outside of public right-of-way.
- 76. Openings for connections to existing manholes shall be made by core-drilling the existing manhole structure, and installing a rubber boot. Connections shall be watertight and shall provide a smooth flow into and through the manhole with no ponding. Small chipping hammers or similar light tools which will not damage or crack the manhole base may be used to shape channels, but may be used to enlarge existing openings only if authorized in writing by the Owner's Representative. Use of pneumatic jackhammers shall be prohibited.
- 77. Manhole channels depths (sewer & storm) shall be to the heights shown on the drawings, but in no case shall the channel depth be less than 2/3 of the pipe diameter. Channels, as well as shelves between the channels and the manhole walls, shall be sloped to drain per plan
- 78. Manholes constructed over existing sanitary sewers shall conform to the requirements of OSSC (ODOT/APWA) 490.41, Manholes over Existing Sewers. The existing pipe shall not be broken out until after the completion of the manhole test.

SANITARY SEWER SYSTEM:

79. Unless otherwise specified, sanitary sewer pipe shall be solid wall PVC in conformance with ASTM D3034, SDR 35 (\leq 15") or ATSM F-679, PS 46 (\geq 18"). Minimum stiffness shall be 46 psi per ASTM D-2412 and joint type shall be elastomeric gasket conforming to ASTM D-3212. All other appurtenances and installation to conform to the Approving Agency's specifications. All materials and workmanship for all private sanitary sewers, including sewers located within any building envelope, shall be installed in conformance with Uniform Plumbing Code requirements.

80. Unless otherwise specifically noted on the drawings, manufactured fittings (tee or wye per

84. Upon completion of all sanitary sewer construction, testing and repair, the Contractor shall conduct a color TV acceptance inspection of all mainlines in accordance with OSSC (ODOT/APWA) 445.74 to determine compliance with grade requirements of OSSC (ODOT/APWA) 445.40.b. The TV inspection shall be conducted by an approved technical service which is equipped to make audio-visual recordings of the TV inspections on DVD or flash drive. Unless otherwise required by the Approving Agency, a standard 1-inch diameter ball shall be suspended in front of the camera during the inspection to determine the depth of any standing water. Sufficient water to reveal low areas or reverse grades shall be discharged into the pipe immediately prior to initiation of the TV inspection. The DVD and written report shall be delivered to the Approving Agency. STORM DRAIN SYSTEM: 85. Storm sewer pipe materials shall conform to the construction drawings and Approving Agency's

requirements. Unless otherwise noted or shown on the drawings, storm sewer pipe materials with watertight joints shall conform to the attached "Storm Pipe Table". Contractor shall use uniform pipe material on each pipe run between structures unless otherwise directed or approved. Jointed HDPE pipe shall not be used for slopes exceeding ten percent (10%). All materials and workmanship for all private storm drains, including storm drains located within any building envelope, shall be installed in conformance with Uniform Plumbing Code reauirements.

86. Contractor shall designate the pipe material actually installed on the field record drawings and provide this information for inclusion on the as-built drawings.

87. Catch basins and junction boxes shall be set square with buildings or with the edge of the parking lot or street wherein they lie. Storm drain inlet structures and paving shall be adjusted so water flows into the structure without ponding water.

88. Unless otherwise approved by the Engineer, all storm drain connections shall be by manufactured tees or saddles.

89. Unless otherwise shown on the drawings, all storm pipe inlets & outfalls shall be beveled flush to match the slope wherein they lie.

90. Sweep (deflect) storm sewer pipe into catch basins and manholes as required. Maximum joint deflection shall not exceed 5 degrees or manufacturers recommendations, whichever is less.

91. Unless otherwise shown or directed, install storm sewer pipe in accordance with manufacturer installation guidelines.

92. After manhole channeling and prior to mandrel testing or final acceptance, flush and clean all sewers, and remove all foreign material from the mainlines, manholes and catch basins.

93. Mandrel Testing. Contractor shall conduct deflection test of flexible storm sewer pipes by pulling an approved mandrel through the completed pipeline following trench compaction. The diameter of the mandrel shall be 95% of the initial pipe diameter. Test shall be conducted not more than 30 days after the trench backfilling and compaction has been completed.

STREET LIGHTS 96. Street lights shall be installed after all other earthwork and public utility installations are completed and after rough grading of the property is accomplished to prevent damage to the poles.

5 feet.

FRANCHISE & PRIVATE UTILITIES: 100. Unless otherwise shown on the drawings or approved by jurisdiction having authority, all new franchise and private utilities (power, cable TV, telephone, gas, data, communication, control, alarms, etc.) shall be installed underground. Installation of such utilities or associated conduits in a common trench with public water, sanitary sewer, or storm sewer is prohibited.

101.Contractor shall coordinate with gas, power, telephone, and cable TV Company for location of conduits in common trenches, as well as location or relocation of vaults, pedestals, etc. The Contractor shall be responsible for providing franchise utility companies adequate written notice of availability of the open trench (typically 10 days minimum), and reasonable access to the open trench. Unless otherwise approved in writing by the Approving Agency, all above-grade facilities shall be located in PUEs (where PUEs exist or will be granted by the development), and otherwise shall be placed in a location outside the proposed sidewalk location.

102. Unless otherwise approved by the Approving Agency, installation of private utilities (including either franchise utilities or private water, sewer or storm services) in a common trench with or within 3 feet horizontally of and paralleling public water, sanitary sewer or storm drains is prohibited

104. Contractor shall notify and coordinate with franchise utilities for removal or relocation of power poles, vaults, pedestals, manholes, etc. to avoid conflict with Public utility structures, fire hydrants, meters, sewer or storm laterals, etc.

Approving Agency) shall be used for all lateral connections to new sewer mainlines.

81. Contractor shall provide all necessary materials, equipment and facilities to test sanitary sewer pipe and appurtenances for leakage in accordance with testing schedule herein or the Approving Agency's construction standards, whichever are more stringent. Sanitary sewer pipe and appurtenances shall be tested for leakage. Leakage tests shall include an air test of all sewer mains and laterals and vacuum testing of the manholes. Manhole testing shall be performed after completion of AC pavement and final surface restoration.

82. After manhole channeling and prior to mandrel testing and/or TV inspection, flush and clean all sewers, and remove all foreign material from the mainlines and manholes. Failure to clean all dirt, rock and debris from pipelines prior to TV inspection will result in the need to re-clean and re-TV the sewer lines.

83. Contractor shall conduct deflection test of flexible sanitary sewer pipes by pulling an approved mandrel through the completed pipeline following trench compaction. The diameter of the mandrel shall be 95% of the initial pipe diameter. Test shall be conducted not less than 30 days after the trench backfilling and compaction has been completed, unless otherwise approved by the Approving Agency.

94. TV Inspection. Upon completion of all storm sewer construction, testing and repair, the Contractor shall conduct a color TV acceptance inspection of all mainlines in accordance with OSSC (ODOT/APWA) 445.74 to determine compliance with grade requirements of OSSC (ODOT/APWA) 445.40.b. The TV inspection shall be conducted by an approved technical service which is equipped to make audio-visual recordings of the TV inspections on DVD (VHS video tape acceptable only upon prior written approval by Public Works). Unless otherwise required by the agency with jurisdiction, a standard 1-inch diameter ball shall be suspended in front of the camera during the inspection to determine the depth of any standing water. Sufficient water to reveal low areas or reverse grades shall be discharged into the pipe immediately prior to initiation of the TV inspection. The DVD and written report shall be delivered to the Approving Agency.

95. Prior to acceptance, the Owner's Representative may lamp storm lines upstream & downstream of structures to verify that the pipes are clean and there is no grout or concrete in the mainlines, and that there are no observable bellies in the line. When necessary, sufficient water to reveal low areas shall be discharged into the pipe by the Contractor prior to any such inspection by the Owner's Representative or the Approving Agency.

97. Streetlight poles shall be set to a depth as specified by the manufacturer, but not less than

98. Street light poles shall be installed within one degree (1*) of plumb.

99. Contractor shall coordinate with utility companies and pay all costs for procurement, installation, wiring, hook up and activation of streetlights.

103. Power, telephone and TV trenching and conduits shall be installed per utility company requirements with pull wire. Contractor shall verify with utility company for size, location and type of conduit before construction, and shall ensure that trenches are adequately prepared for installation per utility company requirements. All changes in direction of utility conduit runs shall have long radius steel bends.



- 105. Monuments: Upon completion of street improvements, centerline monuments shall be established and protected in monument boxes
- at every street intersection and all points of curvature and points tangency of street centerlines. 106. Benchmarks: Elevation benchmarks shall be set at intervals established by the City Engineer. The benchmarks shall consist of a brass cap set in a curb or other immovable structure.

STORM PIPE TABLE					
Cover Depth	6" — 18" Diameter				
Less than 2' Cover	Class 50 ductile iron pipe with bell and spigot joints and rubber gasket.				
2' to 2-1/2' Cover	Pipe specified for lesser cover depths —or— Class 3, ASTM C—14 non—reinforced concrete pipe with bell and spigot joints & rubber gaskets, ASTM 150 Type II cement. —or— PVC pipe conforming to AWWA C900 DR 18 (6"—12") or AWWA C—905 (14"—18") with bell and spigot joints and rubber gasket				
2-1/2' to 15' Cover	Pipe specified for lesser cover depths -or- PVC pipe conforming to ASTM D-3034 PVC SDR 35 (6"-15") or ASTM F-679 PVC solid wall SDR 35 (18") with bell and spigot joints and rubber gasketor- HDPE (high density polyethlene) pipe conforming to AASHTO M-252, (8"-10") or AASHTO M-294 (12"-18"). For slopes less than 6% the pipe shall be ADS N-12 IB ST, Hancor Sure-Lok F477, or approved equal. For slopes greater than 6% the pipe shall be ADS N-12 IB WT, Hancor Blue Seal, or approved equal with watertight pressure testable fittings, -except- jointed HDPE (high density polyethylene) pipe referenced above not permitted for depth to invert greater than 12 feet.				
More than 15' Cover	See construction drawings.				
Cover Depth	21" — 30" Diameter				
Less than 2' Cover	Class 50 ductile iron pipe with bell and spigot joints and rubbe gasket.				
2' to 2-1/2' Cover	Pipe specified for lesser cover depths -or- Class IV ASTM C-76 reinforced concrete pipe with bell and spigot joints and rubber gasket, ASTM 150, Type II cement.				
2-1/2' to 15' Cover (**HDPE allowed up to 60" diameter subject to max. depth limits listed)	(**HDPE allowed up to 60" diameter subject to max. ASTM F-679 PVC solid wall SDR 35 pipe with bell and spigot joints and rubber gasket -or-				
More than 15' Cover	See construction drawings.				
Greater than 30" diar	neter and other pipe materials: Case by case basis.				

REOUIRED -	TESTING AND FREQUENCY TABLE	Party	v Responsible fo	or payment				
REQUIRED	(Contractor	Others (see note 1)					
Streets, Fire La	Streets, Fire Lanes, Common Driveways, Parking Lots, Pads, Fills, etc.							
Subgrade	1 Test/4000 S.F./Lift (4 min), locations acceptable to approving agency (typically alternate sides of road or access aisles) ✓ See note 2 & note 3							
Engineered Fills	ngineered Fills 1 Test/4000 S.F./Lift (4 min), locations acceptable to approving agency & note 5							
Baserock	1 Test/4000 S.F./Lift (4 min), locations acceptable to approving agency (typically alternate sides of road or access aisles)							
Asphalt	1 Test/6000 S.F./Lift (4 min), locations acceptable to AA (typ. alternate as above)	\checkmark	See note 2					
Piped Utilities, A	All							
Trench Backfill	1 Test/200 Foot Trench/Lift (4 min)	\checkmark	See note 2					
Trench AC Res	toration 1 Test/300 Foot Trench (4 min)	\checkmark	See note 2					
Water								
Pressure Test	(to be witnessed by Owner's Representative or approving agency)	\checkmark	See note 4					
Bacterial Water	Test Per Oregon Health Division	\checkmark	See note 2					
Chlorine Residu	al Test Per City Requirements	\checkmark						
Sanitary Sewer								
Air Test	Per City or APWA Requirements, whichever is more stringent	\checkmark	See note 4					
Mandrel	95% of actual inside diameter	\checkmark	See note 4					
TV Inspection	All. Lines must be cleaned prior to TV work	\checkmark						
Manhole	(1) Vacuum test per manhole, witnessed by Owner's Representative or approving agency	\checkmark	See note 2					
Pressure Test Hydrostatic pressure test, witnessed by (force main) Owner's Representative or approving agency		See note 4						
Storm								
Mandrel	95% of actual inside diameter	\checkmark	See note 4					
TV Inspection	All. Lines must be cleaned prior to TV work	\checkmark						
Concrete, Block	, etc.							
equipment slabs otherwise specif (or portion ther	ylinders for structural & reinforced concrete, s, curbs, sidewalks & PCC pavements. Unless fied, one set of cylinders per 100 cubic yards eof) of each class of concrete placed per day. sts required on same load as cylinders.	\checkmark	See note 2					
Building permit concrete, reinfo	inspection & Special Inspection for structural rced masonry, epoxy anchors, etc. as licable State Building Codes.	\checkmark	See note 6					
Note 1: "Others" ro applicable.	efers to Owner's authorized Representative or A Contractor responsible for scheduling testing.							
•	completed prior to performing subsequent work. Note 2: Testing must be performed by an approved independent testing laboratory.							
Note 2: In addition to in-place density testing, the subgrade and base rock shall be proof- rolled with a loaded 10 yard dump truck provided by the Contractor. Baserock proofroll shall take place immediately prior to (within 24 hours of) paving, and shall be witnessed by the Owner's authorized Representative or approving agency. Location and pattern of testing and proofroll to be as approved or directed by said Owner's authorized Representative or approving agency.								
shall pert	tnessed by the Owner's Representative or appro form pretests prior to scheduling witnessed wat tests, or pipeline mandrel test.							
certificati subgrade	oved independent laboratory retained by the Co ion (stamped by an engineer licensed in the St was prepared and all engineered fills were places of the construction drawings and the contrac	ate o ced ir	of Oregon) the n accordance	at the				
Note 6: Regardless of who is responsible for payment, the Contractor is responsible for scheduling and coordinating any and all required inspections and Special Inspections as required by applicable building codes or jurisdictions having authority.								









DEQ EROSION CONTROL STANDARD NOTES:

- 1. Include a list of all personnel (by name and position) that are responsible for the design, installation and maintenance of stormwater control measures (e.g. ESCP developer, BMP installer (see Section 4.10), as well as their individual responsibilities. (Section 4.4.c.ii)
- 2. Visual monitoring inspection reports must be made in accordance with DEQ 1200-C permit requirements. (Section 6.5)
- 3. Inspection logs must be kept in accordance with DEQ's 1200-C permit requirements. (Section 6.5.q)
- 4. Retain a copy of the ESCP and all revisions on site and make it available on request to DEQ, Agent, or the local municipality. (Section 4.7)
- 5. The permit registrant must implement the ESCP. Failure to implement any of the control measures or practices described in the ESCP is a violation of the permit. (Sections 4 and 4.11)
- 6. The ESCP must be accurate and reflect site conditions. (Section 4.8)
- 7. Submission of all ESCP revisions is not required. Submittal of the ESCP revisions is only under specific conditions. Submit all necessary revision to DEQ or Agent within 10 days. (Section 4.9)
- 8. Sequence clearing and grading to the maximum extent practical to prevent exposed inactive areas from becoming a source of erosion. (Section 2.2.2)
- 9. Create smooth surfaces between soil surface and erosion and sediment controls to prevent stormwater from bypassing controls and ponding. (section 2.2.3)
- 10. Identify, mark, and protect (by construction fencing or other means) critical riparian areas and vegetation including important trees and associated rooting zones, and vegetation areas to be preserved. Identify vegetative buffer zones between the site and sensitive areas (e.g., wetlands), and other areas to be preserved, especially in perimeter areas. (Section 2.2.1)
- 11. Preserve existing vegetation when practical and re-vegetate open areas. Re-vegetate open areas when practicable before and after grading or construction. Identify the type of vegetative seed mix used. (Section 2.2.5)
- 12. Maintain and delineate any existing natural buffer within the 50-feet of waters of the state. (Section 2.2.4)
- 13. Install perimeter sediment control, including storm drain inlet protection as well as all sediment basins, traps, and barriers prior to land disturbance. (Sections 2.1.3)
- 14. Control both peak flow rates and total stormwater volume, to minimize erosion at outlets and downstream channels and streambanks. (Sections 2.1.1. and 2.2.16)
- 15. Control sediment as needed along the site perimeter and at all operational internal storm drain inlets at all times during construction, both internally and at the site boundary. (Sections 2.2.6 and 2.2.13)
- 16. Establish concrete truck and other concrete equipment washout areas before beginning concrete work. (Section 2.2.14)
- 17. Apply temporary and/or permanent soil stabilization measures immediately on all disturbed areas as arading progresses. Temporary or permanent stabilizations measures are not required for areas that are intended to be left unvegetated, such as dirt access roads or utility pole pads. (Sections 2.2.20 and 2.2.21)
- 18. Establish material and waste storage areas, and other non-stormwater controls. (Section 2.3.7)
- 19. Keep waste container lids closed when not in use and close lids at the end of the business day for those containers that are actively used throughout the day. For waste containers that do not have lids, provide either (1) cover (e.g., a tarp, plastic sheeting, temporary roof) to prevent exposure of wastes to precipitation, or (2) a similarly effective means designed to prevent the discharge of pollutants (e.g., secondary containment). (Section 2.3.7)
- 20. Prevent tracking of sediment onto public or private roads using BMPs such as: construction entrance, graveled (or paved) exits and parking areas, gravel all unpaved roads located onsite, or use an exit tire wash. These BMPs must be in place prior to landdisturbing activities. (Section 2.2.7)
- 21. When trucking saturated soils from the site, either use water-tight trucks or drain loads on site. (Section 2.2.7.f)
- 22. Control prohibited discharges from leaving the construction site, i.e., concrete wash-out, wastewater from cleanout of stucco, paint and curing compounds. (Sections 1.5 and 2.3.9)
- 23. Ensure that steep slope areas where construction activities are not occurring are not disturbed. (Section 2.2.10)
- 24. Prevent soil compaction in areas where post-construction infiltration facilities are to be installed. (Section 2.2.12)
- 25. Use BMPs to prevent or minimize stormwater exposure to pollutants from spills; vehicle and equipment fueling, maintenance, and storage; other cleaning and maintenance activities; and waste handling activities. These pollutants include fuel, hydraulic fluid, and other oils from vehicles and machinery, as well as debris, fertilizer, pesticides and herbicides, paints, solvents, curing compounds and adhesives from construction operations. (Sections 2.2.15 and 2.3)
- 26. Provide plans for sedimentation basins that have been designed per Section 2.2.17 and stamped by an Oregon Professional Engineer. See Section 2.2.17.a
- 27. If engineered soils are used on site, a sedimentation basin/impoundment must be installed. (See Sections 2.2.17 and 2.2.18)
- 28. Provide a dewatering plan for accumulated water from precipitation and uncontaminated groundwater seepage due to shallow excavation activities. (See Section 2.4)
- 29. Implement the following BMPs when applicable: written spill prevention and response procedures, employee training on spill prevention and proper disposal procedures, spill kits in all vehicles, regular maintenance schedule for vehicles and machinery, material delivery and storage controls, training and signage, and covered storage areas for waste and supplies. (Section 2.3)
- 30. Use water, soil-binding agent or other dust control technique as needed to avoid wind-blown soil. (Section 2.2.9)
- 31. The application rate of fertilizers used to reestablish vegetation must follow manufacturer's recommendations to minimize nutrient releases to surface waters. Exercise caution when using time-release fertilizers within any waterway riparian zone. (Section 2.3.5)
- 32. If an active treatment system (for example, electro-coagulation, flocculation, filtration, etc.) for sediment or other pollutant removal is employed, submit an operation and maintenance plan (including system schematic, location of system, location of inlet, location of discharge, discharge dispersion device design, and a sampling plan and frequency) before operating the treatment system. Obtain Environmental Management Plan approval from DEQ before operating the treatment system. Operate and maintain the treatment system according to manufacturer's specifications. (Section 1.2.9)
- 33. Temporarily stabilize soils at the end of the shift before holidays and weekends, if needed. The registrant is responsible for ensuring that soils are stable during rain events at all times of the year. (Section 2.2)
- 34. As needed based on weather conditions, at the end of each workday soil stockpiles must be stabilized or covered, or other BMPs must be implemented to prevent discharges to surface waters or conveyance systems leading to surface waters. (Section 2.2.8)
- 35. Sediment fence: remove trapped sediment before it reaches one third of the above ground fence height and before fence removal. (Section 2.1.5.b)
- 36. Other sediment barriers (such as biobags): remove sediment before it reaches two inches depth above ground height and before BMP removal. (Section 2.1.5.c)
- 37. Catch basins: clean before retention capacity has been reduced by fifty percent. Sediment basins and sediment traps: remove trapped sediments before design capacity has been reduced by fifty percent and at completion of project. (Section 2.1.5.d)
- 38. Within 24 hours, significant sediment that has left the construction site, must be remediated. Investigate the cause of the sediment release and implement steps to prevent a recurrence of the discharge within the same 24 hours. Any in-stream clean-up of sediment shall be performed according to the Oregon Department of State Lands required timeframe. (Section 2.2.19.a)
- 39. The intentional washing of sediment into storm sewers or drainage ways must not occur. Vacuuming or dry sweeping and material pickup must be used to cleanup released sediments. (Section 2.2.19)
- 40. Document any portion(s) of the site where land disturbing activities have permanently ceased or will be temporarily inactive for 14 or more calendar days. (Section 6.5.f.)
- 41. Provide temporary stabilization for that portion of the site where construction activities cease for 14 days or more with a covering of blown straw and a tackifier, loose straw, or an adequate covering of compost mulch until work resumes on that portion of the site. (Section 2.2.20)
- 42. Do not remove temporary sediment control practices until permanent vegetation or other cover of exposed areas is established. Once construction is complete and the site is stabilized, all temporary erosion controls and retained soils must be removed and disposed of properly, unless needed for long term use following termination of permit coverage. (Section 2.2.21)

		1	1		1	1	1	1		1		
YEAR:	'21	'21	'21	'21	'21	'21	'21	'21	'21	'22	'22	'22
MONTH:	04	05	06	07	08	09	10	11	12	01	02	03
CLEARING	x	Х										
EXCAVATION												
GRADING	X	Х	X	X	Х							
CONSTRUCTION	X	Х	X	X	Х	X	Х	X				
SEDIMENT CONTROLS:												
Silt Fencing	X	Х	X	X	Х	X	Х	X				
Sediment Traps	X	Х	X	X	Х	X	Х	X				
Sediment Basins												
Storm Inlet Protection												
Drainage Swales												
Check Dams												
Contour Furrows												
Terracing												
Pipe Slope Drains												
Rock Outlet Protection												
Gravel Construction Entrance	x	x	x	x	x	x	x	x				
Grass—lined Channel (Turf Reinforcement Mats)												
Protection of trees with construction fences												
Temporary Seeding and Planting												
Permanent Seeding and Planting												
Other:												

CONTROL MEASURE	PHASE 1	PHASE 2	PHASE 3	PHASE 4	PHASE 5	
Silt Fencing	X	Х	X	X		
Construction Entrance	X	Х				
Sediment Traps			X	Х		
Storm Inlet Protection			X	X		
Concrete Washout						
Rock Outlet Protection			X	Х	X	
Permanent Seeding and Planting	X					
Phase 1: Prior to Ground Disturbance Phase 2: After Completion of Rough Grading Phase 3: After Installation of Storm Facilities Phase 4: After Paving & Construction Phase 5: After Project Completion and Cleanup						

<u>BMP Rationale</u>

A comprehensive list of available Best Management Practices (BMP) options based on DEQ's 1200-C Permit Application and ESCP Guidance Document has been reviewed to complete this Erosion and Sediment Control Plan. Some of the above listed BMPs were not chosen because they were determined to not effectively manage erosion prevention and sediment control for this project based on specific site conditions, including soil conditions, topographic constraints, accessibility to the site, and other related conditions. As the project progresses and there is a need to revise the ESCP, an Action Plan will be submitted.

SOIL TYPE(S):	PER CO. SOIL SURVEY THE SITE SOILS INCLUDE,
EROSION HAZARD:	PER CO. SOIL SURVEY EROSION HAZARD RANGES FROM "" TO "".
SITE AREA:	x Ac
DISTURBANCE AREA:	y Ac

INSPECTION FREQUENCY FOR BMP

Site Condition	Minimum Frequency
1. Active period	On initial date that land disturbance activities commence.
	Within 24 hours of any storm event, including runoff from snow melt, that results in discharge from the site.
	At least once every 14 days, regardless of whether stormwater runoff is occurring.
2. Inactive periods greater than fourteen (14) consecutive calendar days	The Inspector may reduce the frequency of inspections in any area of the site where the stabilization steps in Section 2.2.20 have been completed to twice per month for the first month, no less than 14 calendar days apart, then once per month.
3. Periods during which the site is inaccessible due to inclement weather	If safe, accessible and practical, inspections must occur daily at a relevant discharge point or downstream location of the receiving waterbody.
4. Periods during which construction activities are suspended and runoff is unlikely due to frozen conditions.	Visual monitoring inspections may be temporarily suspended. Immediately resume monitoring upon thawing, or when weather conditions make discharges likely.
5. Periods during which construction activities are conducted and runoff is unlikely during frozen conditions.	Visual monitoring inspections may be reduced to once a month. Immediately resume monitoring upon thawing, or when weather conditions make discharges likely.

Spill Prevention Procedures and Response

- This data will be posted in an accessible area at the site.

What to do in case of a spill

- 2. Get the spill kit.
- d. Place the absorbent materials in the path of the spill.
- a. Verify that the cover has full contact with the rim of the inlet.
- 3. Notify the following personnel immediately: a. 1200-C Permit Registrant's Representative 1-800-452-0311
- . Any amount of oil to waters of the state;
- i. Oil spills on land in excess of 42 gallons;

applicable regulations.

Responsible Personnel

spills or contacting/retaining a company for the cleanup of major spills.

Waste Management Procedures

- state:
- of a leak or spill;

- prevent leaching of pollutants).

Fertilizers, pesticides, herbicides, & insecticides

insecticide, and fertilizer label. When applying fertilizers, registrants must:

- possible to the period of maximum vegetation uptake and growth;
- 4. Never apply to frozen ground;
- 5. Never apply to stormwater conveyance channels; and

Authorized non-stormwater discharges anticipated for the proposed project:

- 1. Landscape irrigation
- 2. Dust control water
- 3. Water line flushing (potable)

for each activity:

- Mass Grading, Street & Utility Construction a.Sediment
- 2. Vertical Construction
 - a.Paints, caulks, sealants, solvents
 - b.Fluorescent light ballasts c.Sediment
- 3. Landscaping & Irrigation a.Fertilizers
 - b.Pesticides, Herbicides, Insecticides

EROSION CONTROL INSPECTION RESPONSIBILITIES:

- 2. AFTER CONTRACT AWARD AND PRIOR TO CONSTRUCTION, THE



SUPPLEMENTAL WESTECH NOTES:

- 1. Erosion control measures shall be maintained in such a manner as to ensure that sediment and sediment-laden water does not enter the drainge system, roadways, or violate applicable water quality standards.
- The erosion control construction, maintenance, replacement and upgrading of the erosion control facilities is the responsibility of the 1200-C Permit Registrant until all construction is completed and approved, and permanent erosion control (i.e. vegetation/landscaping) is established on all disturbed areas.
- 3. All recommended erosion control procedures are dependent on construction methods, staging, site conditions, weather and scheduling. During the construction period, erosion control facilities shall be upgraded as necessary due to unexpected storm events and to ensure that sediment and sediment laden water does not leave the site.
- 4. The 1200-C Permit Registrant is responsible for control of sediment transport within project limits. If an installed erosion control system does not adequately contain sediment on site, then the erosion control measures shall be adjusted or supplemented by the 1200-C Permit Registrant as necessary to ensure that sediment laden water does not leave the site. Additional measures shall be provided as required to ensure that all paved areas are kept clean for the duration of the project. Additional interim measures will include, at a minimum, installation of silt fences in accordance with the details shown on the drawings. These measures shall be installed along all exposed embankments and cut slopes to prevent sediment transport.
- 5. All existing and newly constructed storm inlets and drains shall be protected until pavement surfaces are completed and/or vegetation is established.
- 6. Erosion control facilities and sediment fences on active sites shall be inspected by the 1200-C Permit Registrant at least daily during any period with measurable precipitation. Any required repairs or maintenance shall be completed immediately. The erosion control facilities on inactive sites shall be inspected and maintained by the 1200-C Permit Registrant a minimum of once a month or within 24 hours following the start of a storm event.
- 7. All catch basins and conveyance lines shall be cleaned prior to paving. The cleaning operation shall not flush sediment—laden water into the downstream system. The 1200—C Permit Registrant shall remove all accumulated sediment from all impacted catch basins and storm pipes prior to acceptance by the Owner.
- 8. The 1200-C Permit Registrant is solely responsible for protection of all adjacent property and downstream facilities from erosion and siltation during project construction. Any damage resulting from such erosion and siltation shall be corrected at the sole expense of the 1200-C Permit Registrant.
- 9. Locate any portable toilets away from waters of the state and stormwater inlets or conveyances. Position portable toilets so they are secure and will not be tipped or knocked over.
- 10. The 1200-C Permit Registrant shall provide site watering as necessary to prevent wind erosion of fine-grained soils.
- 11. Unless otherwise indicated on the drawings, all temporary erosion control facilities, including sediment fences, silt sacks, bio-bags, etc. shall be removed within 30 days after permanent landscaping/vegetation is established.
- 12. Sediment fences shall be constructed of continuous filter fabric to avoid use of joints. When joints are necessary, filter cloth shall be spliced together only at a support post, with a minimum 6-inch overlap, and both ends securely fastened to a post.
- 13. Sediment fence shall be installed per drawing details. Sediment fences shall have adequate support to contain all silt and sediment captured.
- 14. The standard strength filter fabric shall be fastened securely to stitched loops installed on the upslope side of the posts, and 6 inches of the fabric shall be extended into the trench. The fabric shall not extend more than 30 inches above the original ground surface. Filter fabric shall not be stapled to existing trees.
- 15. Bio-filter bags shall be clean 100 percent wood product waste. Bags shall be 18-inch x 18-inch x 30-inch, weigh approximately 45 lbs., and be contained in a bag made of 1/2-inch plastic mesh.
- 16. Sediment barriers shall be maintained until the up-slope area has been permanently stabilized. At no time shall more than 10-inches of sediment be allowed to accumulate behind sediment fences. No more than 2 inches of sediment shall be allowed to accumulate behind bio-filter bags. Sediment shall be removed prior to reaching the above stated depths. New sediment barriers shall be installed uphill as required to control sediment transport.
- 17. Stabilized construction entrances shall be installed at the beginning of construction and maintained for the duration of the project. Additional measures may be required to ensure that all paved areas are kept clean for the duration of the project.
- 18. The 1200-C Permit Registrant shall verify that all trucks are well sealed when transporting saturated soils from the site. Water drippage from trucks transporting saturated soils must be reduced to less than 1 gallon per hour prior to leaving the site.
- 19. The entrance shall be maintained in a condition that will prevent tracking or flow of mud onto the public right—of—way or approved access point. The entrance may require periodic top dressing as conditions demand, and repair and/or cleanout of any structures used to trap sediment.
- 20. All materials spilled, dropped, washed, or tracked from vehicles onto roadways or into storm drains must be removed immediately, and protection provided for downstream inlets and catch basins to ensure sediment laden water does not enter the storm drain system.
- 21. Temporary grass cover measures must be fully established by October 15th, or other cover measures (ie. erosion control blankets with anchors, 3-inches minimum of straw mulch, 6 mil HDPE plastic sheet, etc.) shall be in place over all disturbed soil areas until April 30th. To establish an adequate grass stand for controlling erosion by October 15th, it is recommended that seeding and mulching occur by September 1st. Straw mulch, if used, shall not leave any bare ground visible through the straw.
- 22. Minimum slope protection. For slopes steeper than 3H:1V but less than 2H:1V, use Tensar/North American Green Type S150 erosion control blanket. For slopes 2H:1V or steeper, use Tensar/North American Green Type SC150 erosion control blanket. Use a minimum of 2-inches straw mulch or Tensar/North American Green Type S150 for slopes flatter than 3H:1V. Slope protection shall be placed on all disturbed areas immediately after completion of each section of construction activity, until the erosion control seeding has been established. As an option during temporary or seasonal work stoppages, a 6-mil HDPE plastic sheet may be placed on exposed slopes. The plastic sheet shall be provided with an anchor trench at the top and bottom of the slope, and shall be sandbagged on the slopes as required to prevent damage or displacement by wind.
- 23. Permanent erosion control vegetation on all embankments and disturbed areas shall be re—established as soon as construction is completed.
- 24. Soil preparation. Topsoil should be prepared according to landscape plans, if available, or recommendations of grass seed supplier. It is recommended that slopes be textured before seeding by rack walking (ie. driving a crawling tractor up and down the slopes to leave a pattern of cleat imprints parallel to slope contours) or other method to provide stable areas for seeds to rest.
- 25. When used, hydromulch shall be applied with grass seed at a rate of 2000 lbs. per acre between April 30 and June 10, or between September 1 and October 1. On slopes steeper than 10 percent, hydroseed and mulch shall be applied with a bonding agent (tackifier). Application rate and methodology to be in accordance with seed supplier recommendations.
- 26. When used in lieu of hydromulch, dry, loose, weed free straw used as mulch shall be applied at a rate of 4000 lbs. per acre (double the hydromulch application requirement). Anchor straw by working in by hand or with equipment (rollers, cleat trackers, etc.). Mulch shall be spread uniformly immediately following seeding.
- 27. When conditions are not favorable to germination and establishment of the grass seed, the seeded and mulched areas shall be irrigated as required to establish the grass cover.
- 28. Seeding. Recommended erosion control grass seed mix is as follows. Dwarf grass mix (low height, low maintenance) consisting of dwarf perennial ryegrass (80 % by weight), creeping red fescue (20 % by weight). Application rate shall be 100 lbs. per acre minimum.
- 29. Grass seed shall be fertilized at a rate of 10 lbs. per 1000 S.F with 16-16-16 slow release type fertilizer. Development areas within 50 feet of water bodies and wetlands must use a non-phosphorous fertilizer.
- 30. Prior to starting construction the 1200-C Permit Registrant shall acquire the services of a DEQ Certified Erosion and Sediment Control Inspector and shall submit an "Action Plan" to DEQ identifying their names, contact information, training and experience as required in Schedule A.6.b.i-ii of the 1200-C Permit
- 31. The 1200-C Permit Registrant shall submit "Notice of Termination" to DEQ to end the 1200-C permit coverage once all soil disturbance activities have been completed and final stabilization of exposed soils has occurred.
- 32. If there is any conflict, discrepancy, or inconsistency between the DEQ Erosion Control Standard Notes and the Supplemental Westech Notes, the DEQ Notes will control.





wg\WeNGER\Willamina Highlands\Ridgeview Subdivision Ph II\Civil\Plots\PD-EC Notes & Dtls.dwg, (EC-3 tab





CONTRACTOR TO RELOCATE





















					۔ ب
	8.27			· · · · · · · · · · · · · · · · · · ·	
	4 + 4			· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·
	STA 59		20		
	¥Ö.	כ ש ייייייייייייייייייייייייייייייייייי	<u>3771</u>		
	E BRE		+		
	ELEV				
		FG AT Q	0.759		
			0.35%		
		EG AT Q			
		8"·SS			<u>8" S</u> S
					48" SD L=63 S=0.
48" SD L=20	68 S=0.10%				
			72 " Ø SD	MH 2	
		STA: HIGF	HLANDS LOOP 15+62.97 RIM = 3 48" INV IN (E) = 3	5' R 71.36	
			48" INV IN (E) = 30 48" INV OUT (SW) = 30	61.32 61.22	
					- ب
•••••••••••••••••••••••••••••••••••••••	: :				
			: :		•
· · · · · · · · · · · · · · · · · · ·				·····	····
		·····			













wg\WENGER\Willamina Highlands\Ridgeview Subdivision Ph II\Civil\Plots\PD-STREET Plan & Profiles.dwg, (ST-4 tab)

	36
L 27 L 4.02%	37 37 36 36
BRVCE: EECS: E	37
21+88.77 365.11 367.40 369.06 1	<u> </u>
75' VC	160' VC ► 37



(feet)

PROFILE 20+00 - 24+00 H: 1" = 20' V: 1" = 4'





(feet)





PROFILE 30+00 - 32+50 H: 1" = 20' V: 1" = 4'




























.3 1:07:56 PM WENGER\Willamina Highlands\Ridgeview Subdivision Ph II\Civil\Plots\PD-OFFSITE STORM Plan & Profiles.dwg, (SD-1 1

PROFILE 1+00 - 5+00 H: 1" = 20' V: 1" = 4'





: : · · · · · · · · · · · · · · · · · ·	294
	292
	290
	288
	286
	284
	282
	280
	278
	276
	274
	272
	270
<u>48" EXTG SDMH 2</u> STA: SD-A_1+00.00_0.0	268
RIM = 262.98 2" INV IN (NE) = 258.51	266
	264
	262
	260
NEW 12" SD L=44 S=0.23%	
48" SDMH 19	258
STA: $SD-A$ 1+44.23 0' RIM = 263.38	256
2" INV IN (NW) = 258.71 2" INV OUT (SW) = 258.61	254
	252
1+00 0+6	80
1100 070	







362						-
360						• • • • • • • • • • • • • • • • • • •
358						
356	·····.	· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · · ·	····· ······	. <u>.</u>	
354						
						- - - - - - -
352						- - - - - -
350						- - - -
348			-			· · ·
346						
344		-				
342						
340						
338						• • • • •
336						
334						
332						-
330						
328						· · · ·
326						
324						
13+	-50		13+	-00		





(feet)

/// 2023 1.00.00 F.M 3: \Dwg\WENGER\Willamina Highlands\Ridgeview Subdivision Ph II\Civil\Plots\PD-OFFSITE STORM Plan & Profiles.dwg, (SD-4 t





PROFILE 13+50 - END H: 1" = 20' V: 1" = 4'













(feet)











3154.2000









(feet)











PROFILE H: 1" = 20' V: 1" = 4'



0+80













PROFILE 4+50 - END H: 1" = 20' V: 1" = 4'









WILLAMINA RIDGEFIELD HEIGHTS PHASES III - VI TRANSPORTATION IMPACT ANALYSIS (TIA)

MAY 2023

PREPARED FOR WESTECH ENGINEERING



Steve Ward, P.E.

PREPARED BY DKS ASSOCIATES



Jenna Bogert, P.E., Transportation Engineer Scott Mansur, P.E., PTOE, RSP₁, Principal

DRA

TABLE OF CONTENTS

INTR	ODUCTION
EXIS	TING CONDITIONS
ST	UDY AREA ROADWAY NETWORK
ΡE	DESTRIAN AND BICYCLE FACILITIES
ΡU	BLIC TRANSIT
ЕX	ISTING TRAFFIC VOLUMES
IN	TERSECTION PERFORMANCE MEASURES8
RE	QUIRED OPERATING STANDARDS
	ISTING OPERATING CONDITIONS
SA	FETY ANALYSIS9
MA	IN ST TRIANGLE SAFETY EVALUATION
FUTU	RE CONDITONS
ΤR	IP GENERATION
ΤR	IP DISTRIBUTION
AN	ALYSIS SCENARIOS
FU	TURE TRAFFIC VOLUMES
FU	TURE INTERSECTION OPERATIONS
ΤU	RN LANE WARRANTS
SI	TE PLAN EVALUATION
PROJ	ECT SUMMARY
APPE	NDIX
Α.	TRAFFIC COUNT DATAA
В.	CRASH DATAB
С.	HCM REPORTS - EXISTING CONDITIONSC
D.	HCM REPORTS - NO BUILD CONDITIONSD
Ε.	HCM REPORTS - BUILD CONDITIONSE
F.	LEFT TURN LANE WARRANT EVALUATIONF
G.	SITE PLANG

INTRODUCTION

This study evaluates the transportation impacts associated with Phases III – VI of the Ridgefield Heights development in Willamina, Oregon. The proposed development consists of 60 single-family lots and is located north of NW 6th Street near Churchman Street. The anticipated future year of completion for this development is 2026.

The purpose of this traffic impact analysis (TIA) is to determine the estimated impacts that the proposed development may have on the transportation system within the vicinity of the project. This analysis includes an evaluation of existing conditions, trip generation estimates, trip distribution assumptions, and future year operating conditions at the study intersections. The TIA also includes a site plan evaluation.

EXISTING CONDITIONS

DKS

The traffic impact analysis is focused on three study intersections which are listed below:

- NW B Street/Willamina Drive
- NE Main Street (OR 18B Willamina-Sheridan Highway)/NW B Street
- NE Main Street (OR 18B Willamina-Sheridan Highway)/NE Oaken Hills Drive

Table 1 lists important characteristics of the study area and proposed project. Figure 1 shows the study intersections and location of the project site.

TABLE 1: KEY STUDY AREA AND PROPOSED DEVELOPMENT CHARACTERISTICS

CHARACTERISTICS	INFORMATION				
STUDY AREA					
NUMBER OF STUDY INTERSECTIONS	3				
ANALYSIS PERIOD	Weekday AM Peak and PM Peak Hours (One hour between 6-9 AM and 3-6 PM)				
PROJECT SITE					
PROPOSED DEVELOPMENT	60-lots of single family housing (30 detached, 30 attached)				



FIGURE 1: STUDY AREA

DKS

STUDY AREA ROADWAY NETWORK

Key roadways in the study area are summarized in Table 2 along with their existing roadway characteristics.

ROADWAY	FUNCTIONAL CLASSIFICATION	NO. OF LANES	POSTED SPEED	SIDEWALKS	BICYCLE FACILITIES	ON-STREET PARKING
NE MAIN STREET	District Highway (ODOT)	2	25 mph	Yes	No	Yes
WILLAMINA DRIVE	Local Street (City)	2	25 mph	No	No	Yes
NW B STREET	Local Street (City)	2	25 mph	Yes	No	Yes
NE OAKEN HILLS DRIVE	Minor Collector (City)	2	25 mph	Partial	No	Yes

TABLE 2: STUDY AREA ROADWAY CHARACTERISTICS (WITHIN THE VICINITY OF THE PROJECT)

PEDESTRIAN AND BICYCLE FACILITIES

Currently, there are no dedicated bicycle facilities on NE Main Street (OR 18B), NE Oaken Hills Drive, Willamina Drive, or NW B Street. On-street parking is present on both sides of NE Main Street (OR 18B) between the Main Street Triangle and the Fire Station near the east city limits.

Sidewalks are present on both sides of NE Main Street and NW B Street. Sidewalks are present only on the west side of NE Oaken Hills Drive. A marked school crosswalk is located on the west leg of the NE Main Street/NE Oaken Hills Drive intersection. Marked crosswalks are present on all crossings of the NE Main Street/NW B Street intersection except the east leg.

PUBLIC TRANSIT

DKS

Yamhill County Transit operates several fixed routes that serve a majority of the county. Route 22 Grand Ronde) provides service between McMinnville and Grande Ronde with three stops in Willamina. Two of the bus stops are located on NE Main Street at the intersections of NE C Street and NE Oaken Hills Drive. This route has headways of approximately two to three hours during the weekdays. The route also provides service on Saturdays with headways of about 3 hours.

EXISTING TRAFFIC VOLUMES

Existing AM peak period (6-9 AM) and PM peak period (3-6 PM) traffic volumes were collected at the three study intersections. The turning movement counts were collected on April 26th and May 4, 2023, while schools were in session.

Because two of the study intersections are under Oregon Department of Transportation (ODOT) jurisdiction, the existing 2023 traffic volumes used for analysis were adjusted to represent the 30th Highest Hour Volumes (30HV). A seasonal adjustment factor of 1.038 was applied per guidance found in the Analysis Procedures Manual (APM) by Oregon Department of Transportation (ODOT).¹ See below for details on the seasonal adjustment factor calculations.

Seasonal Adjustment Factor

ODOT's Analysis Procedures Manual (APM) calls for adjustment of raw traffic counts to 30th highest hour volumes (30 HV) to account for seasonal variation through the course of a year. Counts used in this analysis were collected in late April and early May during the AM and PM peak hours.

Because there are no Automatic Traffic Recorders (ATRs) located in close vicinity to Willamina, then an ATR located within a similar roadway context and annual traffic pattern was identified using the ATR Characteristic Table from ODOT. ATR 15-014, which is located in Jackson County on OR99 Rogue Valley Highway, was found to have similar characteristics (commuter trend, located in a rural populated city, and weekday traffic trend) to NE Main Street through Willamina.

The seasonal adjustment factor calculations are shown in Table 3. A factor of 1.038 was applied to all turning movements in the raw traffic count data.

ATR	MONTH	2021	2020	2019	2018	2017	SEASONAL ADJUSTMENT FACTOR			
ATR 15-014	Peak (June)	116	120	114	120	117	1177/1122 - 1 029			
(TALENT, OR)	Traffic Counts (April)	114	88	111	120	115	117.7 / 113.3 = 1.038			
SEASONAL ADJUSTMENT FACTOR					1.038					

TABLE 3: SEASONAL ADJUSTMENT FACTOR

SHADED CELL = HIGHEST AND LOWEST DATA POINT OMMITTED FROM CALCULATIONS PER APM

The adjusted 2023 existing traffic volumes for the AM and Afternoon peak hours are shown in Figure 2.

¹ Chapter 5, Analysis Procedures Manual, Oregon Department of Transportation, updated November 18, 2022.



FIGURE 2: EXISTING 2023 AM AND PM PEAK HOUR VOLUMES

DKS

INTERSECTION PERFORMANCE MEASURES

Level of service (LOS) ratings and volume-to-capacity (v/c) ratios are two commonly used performance measures that provide a good picture of intersection operations.

- Level of Service (LOS): A "report card" rating (A through F) based on the average delay experienced by vehicles at the intersection. LOS A, B, and C indicate conditions where traffic moves without significant delays over periods of peak hour travel demand. LOS D and E represent progressively worse operating conditions. LOS F represents conditions where average vehicle delay has become excessive and demand has exceeded capacity.
- Volume-to-capacity (v/c) ratio: A decimal representation (typically between 0.00 and 1.00) of the proportion of capacity that is being used at a turn movement, approach leg, or intersection. It is determined by dividing the peak hour traffic volume by the hourly capacity of a given intersection or movement. A lower ratio indicates smooth operations and minimal delays. As the ratio approaches 1.00, congestion increases, and performance is reduced. If the ratio is greater than 1.00, the turn movement, approach leg, or intersection is oversaturated and usually results in excessive queues and long delays.

REQUIRED OPERATING STANDARDS

Two of the study intersections are located on Oregon Department of Transportation (ODOT) facilities. Therefore, they are required to meet ODOT's mobility target as prescribed in the 1999 Oregon Highway Plan (OHP). The Sheridan-Willamina Highway is classified as a district highway with a posted speed of 25 mph. Because the study intersections are located within an urban growth boundary, the target volume-to capacity (v/c) ratio is $0.95.^2$

Per the Transportation System Plan (TSP), the City of Willamina has a desired minimum Level of Service (LOS) D for all City arterials and collectors.³ Individual movements may operate at LOS E.

EXISTING OPERATING CONDITIONS

Existing traffic operations at the study intersections were determined for the AM and PM peak hours based on the Highway Capacity Manual (HCM) 6th Edition methodology for unsignalized intersections.⁴ The results were then compared with the ODOT mobility target and the City of Willamina minimum acceptable LOS D standard. Table 4 lists the estimated v/c ratio, delay, and LOS of each study intersection.

² Oregon Highway Plan, Table 6, Oregon Department of Transportation, 1999 with Amendments.

³ Willamina Transportation System Plan, 2022.

⁴ Highway Capacity Manual, 6th Edition, Transportation Research Board, 2016.

TABLE 4: EXISTING INTERSECTION OPERATIONS (2023)

STUDY	OPERATING STANDARD/	MAJOR STREET	AM	MAJOR STREET	PM PEAK HOUR				
INTERSECTION	MOBILITY TARGET	MINOR STREET	V/C RATIO	DELAY (SECS)	LOS	MINOR STREET	V/C RATIO	DELAY (SECS)	LOS
TWO-WAY STOP	CONTROLLED								
NW B ST/ WILLAMINA DR	LOS D (City)	NB	0.02	7.3	А	NB	0.03	7.4	А
		EB	0.04	8.5	А	EB	0.03	8.6	А
NE MAIN ST/	v/c ≤ 0.95 (ODOT)	EB	0.01	8.2	А	EB	0.02	8.3	А
NW B ST		SB	0.18	15.4	С	SB	0.13	16.1	С
	v/c ≤ 0.95 (ODOT)	EB	0.21	8.6	А	EB	0.09	8.4	А
ST/NE OAKEN HILLS DR		SB	0.56	22.7	С	SB	0.41	17.4	С

TWO-WAY STOP CONTROLLED INTERSECTION:

v/c = Critical Movement Volume-to-Capacity Ratio

Delay = Critical Movement Average Vehicle Delay (sec)

LOS = Level of Service

As shown above, the study intersections meet the City's operating standard and ODOT mobility targets.

SAFETY ANALYSIS

A crash analysis was performed for the study area and is presented in the sections below. Crash data was obtained from the ODOT Crash Analysis and Reporting Unit for the five most recent years of published data (2016-2020).

CRASH STATISTICS

There were two reported crashes at the three study intersections on NE Main Street from 2016 to 2020.

- One property damage only (PDO), rear-end crash occurred at the intersection of NE Main Street (OR 18B Willamina-Sheridan Highway)/NE Oaken Hills Drive. The vehicles involved were traveling eastbound on NE Main Street in rainy conditions in February 2018.
- The other crash occurred at the intersection of NW B Street/NW Willamina Drive. The crash occurred on a clear, dry day in March 2016 and involved a westbound right turning vehicle on NW Willamina Drive that failed to stop at the intersection and struck a vehicle on NW B Street, resulting in property damage only (PDO).

SPIS RANKINGS

The Safety Priority Index System (SPIS) is the ranking system developed by ODOT to identify potential safety problems on state highways. SPIS scores are developed based upon crash frequency, severity, and rate for a 0.10 mile or variable length segment along the state highway over a rolling three-year window. A prioritized list of the top 15% of statewide SPIS sites is created for each region, and the top 5% are investigated further.

SPIS data from the last three years of lists (SPIS 2020, SPIS 2019, and SPIS 2018) was evaluated. Based on SPIS 2019 (crashes from 2016-2018), there is one 85th percentile SPIS site on NE Main Street (OR 18B Willamina-Sheridan Highway) northeast of NE Oaken Hills Drive. The SPIS location is driven by two crashes that occurred on NE Main Street (OR 18B Willamina-Sheridan Highway) approximately 700' and 800' east of the intersection. Based on the safety evaluation, no additional safety impacts are expected with the proposed development.

MAIN ST TRIANGLE SAFETY EVALUATION

As requested by the City's consultant staff, a safety evaluation of the NE Main Street/S Main Street intersection (referred to as the "Main Street triangle" in the City's TSP) is included in this traffic study.

The three-leg intersection allows uncontrolled through and right turn movements on the southbound approach (NE Main Street). The northbound approach (S Main Street) is uncontrolled for through movements, but the left turn movements must yield to southbound traffic. The eastbound approach is stop controlled for through movements and yield-controlled for right turn movements. Railroad tracks run east-west through the intersection. The intersection has

DKS



FIGURE 3: MAIN STREET "TRIANGLE"

a railroad crossing warning system (flashing lights and bells). Approximately two trains per day use the railroad through town.

The intersection is unconventional and could be confusing to navigate. There are multiple stop bars and yield markings on the uncontrolled movements and railroad crossings. Turning radii are high for the turning movements that could lead to high vehicle speeds. As a pedestrian, crossing the intersection is also difficult as there are no clear crossing locations or curb ramps within the immediate vicinity of the intersection. Two business driveways are located within the functional area of the intersection on the north side of the triangle.

CRASH ANALYSIS

A total of six crashes have occurred at the intersection based on the last five years of available crash data (2016 – 2020), including one serious injury (Injury A) crash. Four of the crashes were fixed object crashes, one was a rear-end crash, and one involved a vehicle backing into another. None of the crashes involved a pedestrian or bicyclist.

The serious injury crash occurred on a clear, dry day in August 2020 when a semi-tow truck traveling northbound on S Main Street departed from the roadway and struck the bridge guardrail (fixed object) due to the driver experiencing a medical condition. No other vehicles were involved.

The other three fixed object crashes occurred when vehicles traveling either northbound or southbound through the intersection struck either the median or poles within the intersection.

PLANNED IMPROVEMENTS

ODOT is currently in the process of designing and rebuilding new ADA ramps (K22556) to meet current accessibility standards at various locations along OR 18B, including this NE Main Street intersection.

Based on the TSP, there are two enhanced pedestrian crossings that are planned for the west leg (project P3) and east leg (project P4) to improve connectivity to the downtown businesses and parks. A channelization improvement is also planned for the intersection (project R-2) that would reduce turning radii by installing an additional raised median, restripe the yield markings, and improve railroad crossing markings.

SUMMARY

The Main St Triangle is lacking in safe and connected pedestrian and bicycle facilities, roadway striping, and other improvements that would provide clarity for drivers navigating the a-typical intersection. As part of the previously mentioned funded ODOT ADA ramp project, ODOT will be evaluating the safety of the intersections along OR 18B, including the Main St Triangle, during the design process, which is set to begin this year.

FUTURE CONDITONS

The following chapter contains an evaluation of future conditions, including the project trip generation, future year intersection operations, and site plan review.

TRIP GENERATION

DKS

Trip generation is the method used to estimate the number of vehicles added to site roadways and the adjacent roadway network by a development during a specified period. For this study, ITE 11th

Edition trip generation data⁵ was used to determine the trip generation of proposed development, which consists of 60 single-family lots (30 detached homes and 30 attached homes).

Table 5 provides the trip generation for the proposed development. As shown, the development is expected to generate a total of 35 (8 in, 27 out) AM peak hour trips and 46 (28 in, 18 out) PM peak hour trips.

LAND USE	ITE	QUANTITY	AM PEAK HOUR			PM PE	ак н	WEEKDAY	
	CODE		TOTAL	IN	ουτ	TOTAL	IN	ουτ	WEERDAT
SINGLE-FAMILY (UNATTACHED)	210	30 dwelling units	25	6	19	32	20	12	333
SINGLE-FAMILY (ATTACHED)	215	30 dwelling units	10	2	8	14	8	6	178
TOTAL	-	60 dwelling units	35	8	27	46	28	18	511

TABLE 5: SITE TRIP GENERATION

TRIP DISTRIBUTION

DKS

Trip distribution provides an estimate of where project-related trips are expected to be coming from and going to. It is given as percentages at key gateways to the study area and is used to route project trips through the study intersections.

Figure 4 shows the expected vehicle trip distribution and routing for the new vehicle trips generated by the proposed development. The distribution shows 40% of trips traveling to/from the west, 50% of trips traveling to/from the east, and 10% traveling to/from the Willamina schools via Oaken Hills Drive. These trip distribution percentages were estimated based on existing traffic count data.

⁵ Trip Generation Manual, 11th Edition, Institute of Transportation Engineers, 2017.



FIGURE 4: PROJECT TRIPS AND TRIP DISTRIBUTION

ANALYSIS SCENARIOS

Future operating conditions were analyzed at the study intersections for the following future traffic scenarios. The comparison of the following scenarios enables the assessment of project impacts:

- 2026 No Build (background traffic only)
- 2026 Build (background traffic + project trips)

The 2026 No Build scenario represents the traffic conditions of the study area without the project trips for the proposed development. An average growth rate of 0.5% per year was applied to the existing 2023 traffic counts to project 2026 traffic counts. This rate is based on traffic volume projections for NE Main Street (OR 18B) from the ODOT Future Highway Volume Table. An average rate of 0.1% was calculated, but was rounded up to 0.5% for this analysis.

The 2026 Build scenario represents traffic conditions of the study area with the project trips for the proposed development, assuming it is built and fully occupied by 2026.

FUTURE TRAFFIC VOLUMES

DKS

The traffic volumes for the No Build and Build future analysis scenarios are shown in Figure 5 and Figure 6, respectively.



FIGURE 5: NO BUILD AM AND PM PEAK HOUR VOLUMES (2026)

DKS



FIGURE 6: BUILD AM AND PM PEAK HOUR VOLUMES (2026)

DKS
After the project is constructed, the nearby transportation system will see an increase in the number of vehicles traveling through it. The impact of the development at each study intersection is listed in Table 6 and shown as a percentage of total traffic in 2026 for both the AM and PM peak hours.

TABLE 6: SITE TRAFFIC CONTRIBUTION

	PROJEC	T TRIPS	BUILD 2026 TRAFFIC						
INTERSECTION	AM PEAK HOUR	PM PEAK HOUR	AM PEAK HOUR	%	PM PEAK HOUR	%			
NW B ST/ WILLAMINA DR	35	46	105	33%	138	33%			
NE MAIN ST/ NW B ST	35	46	616	6%	776	6%			
NE MAIN ST/NE OAKEN HILLS DR	21	28	673	3%	731	4%			

FUTURE INTERSECTION OPERATIONS

DKS

Future traffic operations at the study intersections were determined for the AM and PM peak hours based on the Highway Capacity Manual (HCM) 6th Edition methodology for unsignalized intersections. Table 7 lists the estimated v/c ratio, delay, and LOS of each study intersection for the AM and PM peak hour under No Build and Build conditions. As shown, all study intersections are estimated to meet the City's operating standard and ODOT mobility targets.

TABLE 7: FUTURE INTERSECTION OPERATIONS (2026)

STUDY	OPERATING	MAJOR STREET	N	O BUILD		MAJOR STREET		BUILD	
INTERSECTION	STANDARD/ MOBILITY TARGET	MINOR STREET	V/C RATIO	DELAY (SECS)	LOS	MINOR STREET	V/C RATIO	DELAY (SECS)	LOS
AM PEAK HOUR									
NW B ST/	LOS D (City)	NB	0.02	7.3	А	NB	0.03	7.4	А
WILLAMINA DR		EB	0.04	8.5	А	EB	0.03	8.6	А
NE MAIN ST/	v/c ≤ 0.95	EB	0.01	8.2	А	EB	0.02	8.4	А
NW B ST	(ODOT)	SB	0.19	15.7	С	SB	0.14	16.2	С
NE MAIN ST/NE OAKEN	v/c ≤ 0.95	EB	0.21	8.6	А	EB	0.09	8.4	А
HILLS DR	(ODOT)	SB	0.59	24.1	С	SB	0.42	17.8	С
PM PEAK HOUR									
NW B ST/	LOS D (City)	NB	0.03	7.3	А	NB	0.05	7.4	А
WILLAMINA DR		EB	0.07	8.6	А	EB	0.06	8.7	А
NE MAIN ST/	v/c ≤ 0.95	EB	0.02	8.2	А	EB	0.03	8.5	А
NW B ST	(ODOT)	SB	0.28	17.2	С	SB	0.21	18.2	С
NE MAIN ST/NE OAKEN	v/c ≤ 0.95	EB	0.22	8.6	А	EB	0.10	8.5	А
HILLS DR	(ODOT)	SB	0.61	26.0	D	SB	0.45	18.8	С

TWO-WAY STOP CONTROLLED INTERSECTION:

Delay = Critical Movement Approach Delay (sec.)

v/c = Critical Movement Volume-to-Capacity Ratio

LOS = Level of Service (Major/Minor Road)

DKS

TURN LANE WARRANTS

DKS

This section evaluates left turn lane warrants at all three study intersections. According to the ODOT Analysis Procedures Manual, a left turn lane is warranted if any of the three following criteria are met:

- Criterion 1: Volume thresholds analyzed using Exhibit 12-1
- Criterion 2: History of crashes that may be mitigated by a left turn lane
- Criterion 3: Special cases such as nearby railroad crossings, geometric or sight distance concerns, or the presence of a non-traversable median

Left turn lane warrants were examined on eastbound approaches of NE Main Street and the northbound approach at NW Willamina Drive & NW B Street using build scenario volumes. Table 8 lists the results for Criterion 1 under the future No Build and Build conditions for the three study intersections. Further details can be found in the appendix. All proposed left turn lanes on state highways must be approved by the Region Traffic Engineer.

STUDY INTERSECTION	MOVEMENT	CRITERION 1 (2026 NO BUILD AM/PM)	CRITERION 1 (2026 BUILD AM/PM)	CRITERION 2	CRITERIA 3	LEFT TURN LANE WARRANTED?
NW WILLAMINA DR/NW B ST	Northbound Left Turn	Not Met/ Not Met	Not Met/ Not Met	Not Met	Not Met	No
NE MAIN ST/ NW B ST	Eastbound Left Turn	Not Met/ Met	Not Met/ Met	Not Met	Not Met	Yes
NE MAIN ST/ NE OAKEN HILLS DR	Eastbound Left Turn	Met/ Met	Met/ Met	Not Met	Not Met	Yes

TABLE 8: LEFT TURN LANE WARRANT EVALUATION

As shown, a left turn lane is warranted under future no build conditions and build for the eastbound approaches of NE Main Street & NW B Street and NE Main Street & NE Oaken Hills Drive (i.e., the left turn lane warrants are met without the proposed development).

There is adequate space for a left turn lane at NE Main Street & NW B Street, however, this would require removal of street parking spaces on NE Main Street, which may not be desirable from the adjacent business owners perspective. Considering there was not a documented safety issue and the intersection meets ODOT mobility targets, no left turn lane is recommended.

The Willamina TSP identifies the need for an eastbound left turn lane at NE Main Street & NE Oaken Hills Drive. As part of the previously mentioned funded ODOT ADA ramp project (K22556), ODOT will be rebuilding the curb ramps and repaving portions of the road along OR 18B in Willamina over the new few years. Considering there was not a documented safety issue and the intersection

meets ODOT mobility targets, a left turn lane is not critical to safety at this time. However, it is recommended that the City coordinate with ODOT throughout the course of the OR 18B ramp project to consider striping an eastbound left turn lane at the NE Oaken Hills Drive intersection.

SITE PLAN EVALUATION

The following site plan evaluation is based on the site plan drawings provided by the project applicant. The site plan can be found in the appendix.

PROJECT SITE FRONTAGE

The roadway along the project site frontage is required to meet the City's cross-section standards for the designated road classification. The future extension of Highlands Loop will be classified as a Minor Collector, and the future proposed Hope Court, Kindness Court, Kindness Street, and Joyful Street will be classified as Local Streets. The City's TSP provides the cross-section requirements for these roadway classifications and the project applicant is required construct the internal streets to these standards.



Figure 31. Cross Section - Typical Minor Collector



Figure 32. Cross Section – Typical Local Street

DKS

FIGURE 7: CROSS SECTION REQUIREMENTS FOR FRONTAGE IMPROVEMENTS

ACCESS SPACING REQUIREMENTS

The City of Willamina adheres to City of Salem access spacing requirements. According to the City of Salem code⁶, there is no required spacing between intersections and driveways on local or collector streets.

SIGHT DISTANCE AT ACCESS POINTS

According to industry standards, the necessary intersection sight distance needed for left-turning vehicles to make a safe turn is 280 feet based on a design speed of 25 mph.⁷ Based on preliminary sight distance measurements, there is sufficient sight distance at the proposed driveways.

Prior to occupancy, sight distance at any proposed access points will need to be verified, documented, and stamped by a registered professional Civil or Traffic Engineer licensed in the State of Oregon to assure that buildings, signs, or landscaping does not restrict sight distance.

PROJECT SUMMARY

A summary of the traffic impact analysis for the proposed residential development is provided below.

STUDY AREA AND PROPOSED DEVELOPMENT

- The proposed Ridgefield Heights development (Phases III VI) in Willamina, Oregon consists of 60 single-family residential lots (30 attached homes and 30 detached homes). The development is estimated to be complete by 2026.
- The study area included analysis of three study intersections at NW B Street & Willamina Drive, NE Main Street (Willamina-Sheridan Highway) & NW B Street, and NE Main Street (Willamina-Sheridan Highway) & NE Oaken Hills Drive.

MAIN STREET TRIANGLE SAFETY EVALUATION

- The intersection of NE Main Street and S Main Street, also known as the Main Street Triangle, has a unique three-leg geometry with a free north-south movement. A railroad crossing runs east-west through the intersection. The intersection currently lacks safe pedestrian and bicycle facilities and is difficult to navigate as a driver.
- According to the TSP, there are three planned projects at this intersection. Two of the planned projects would install enhanced pedestrian crossings on the west leg and east leg to improve connectivity to downtown businesses and parks. One planned project will install a

⁶ Title X, Chapter 804.020(c), Salem Revised Code, Updated July 18, 2022.

⁷ Table 9-7 and Table 9-9, A Policy on Geometric Design of Highways and Streets, 7th Edition, AASHTO, 2018.



raised median to reduce turning radii, restripe yield markings, and improve railroad crossing markings.

• As part of the funded ODOT ADA ramp project, ODOT will be rebuilding the ADA ramps along OR18B and will be evaluating the safety of the intersections along those segments during the design process. This includes the Main St Triangle.

TRIP GENERATION

• The development is estimated to generate a total of 35 (8 in, 27 out) AM peak hour trips, 46 (28 in, 18 out) PM peak hour trips, and 511 total weekday trips.

INTERSECTION OPERATIONS

• All study intersections meet City standards under all analysis scenarios. No mitigations based on vehicle operations are required.

TURN LANE WARRANTS

- According to the ODOT Analysis Procedures Manual, left turn lanes are warranted on the eastbound approaches at NE Main Street & NW B Street and NE Main Street & NE Oaken Hills Drive under both 2026 No Build conditions and 2026 Build conditions.
- An eastbound left turn lane at NW B Street would require removal of street parking spaces on NE Main Street, which may not be desirable from the adjacent business owners perspective. Considering there was not a documented safety issue and the intersection meets ODOT mobility targets, no left turn lane is recommended.
- The Willamina TSP identifies the need for an eastbound left turn lane at the intersection of NE Main Street & NE Oaken Hills Drive. As there is no documented safety issue and the intersection meets ODOT mobility targets, a left turn lane is not critical to safety at the intersection at this time. However, it is recommended that the City coordinate with ODOT throughout the course of the ODOT ADA ramp project (K22556) to consider striping an eastbound left turn lane at the NE Oaken Hills Drive intersection.

SITE PLAN EVALUATION

- The project applicant is required to construct all internal streets to City cross-section standards as described in the TSP.
- Based on preliminary sight distance measurements, there is sufficient sight distance at all proposed driveways for safe turning movements.
- Prior to occupancy, sight distance at any proposed access points will need to be verified, documented, and stamped by a registered professional Civil or Traffic Engineer licensed in the State of Oregon to assure that buildings, signs, or landscaping does not restrict sight distance.

APPENDIX

- A. TRAFFIC COUNT DATA
- **B. CRASH DATA**
- C. HCM REPORTS EXISTING CONDITIONS
- **D. HCM REPORTS NO BUILD CONDITIONS**
- **E. HCM REPORTS BUILD CONDITIONS**
- F. LEFT TURN LANE WARRANT EVALUATION

G. SITE PLAN



117 COMMERCIAL STREET NE, SUITE 310, SALEM, OR 97301 · 503.391.8773 · DKSASSOCIATES.COM

A. TRAFFIC COUNT DATA





Location: 1 SE B ST & NE MAIN ST AM Date: Wednesday, April 26, 2023 Peak Hour: 07:50 AM - 08:50 AM Peak 15-Minutes: 08:20 AM - 08:35 AM

Peak Hour





Note: Total study counts contained in parentheses.

	•	
	HV%	PHF
EB	12.6%	0.66
WB	10.6%	0.58
NB	0.0%	0.25
SB	0.0%	0.90
All	10.5%	0.71

Traffic Counts - Motorized Vehicles

marine oounts	10100	1200	10110	100														
			AIN ST				AIN ST				3 ST			NW				
Interval			bound				bound				bound				bound			Rolling
Start Time	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total	Hour
6:00 AM	0	0	7	0	0	0	3	0	0	0	0	0	0	2	0	3	15	229
6:05 AM	0	0	2	0	0	0	4	0	0	0	0	0	0	1	0	0	7	233
6:10 AM	0	0	8	0	0	0	6	0	0	0	0	0	0	1	0	2	17	252
6:15 AM	0	0	4	0	0	0	6	0	0	0	0	0	0	1	0	0	11	272
6:20 AM	0	0	4	0	0	0	9	2	0	0	0	0	0	1	0	0	16	294
6:25 AM	0	0	12	0	0	0	15	0	0	0	0	0	0	2	0	1	30	321
6:30 AM	0	0	11	0	0	0	4	2	0	0	0	0	0	1	0	0	18	332
6:35 AM	0	0	7	0	0	0	10	1	0	0	0	0	0	0	0	0	18	348
6:40 AM	0	0	12	0	0	0	11	1	0	0	0	0	0	4	0	0	28	362
6:45 AM	0	0	7	0	0	0	12	1	0	0	0	0	0	2	0	1	23	365
6:50 AM	0	0	17	0	0	0	9	0	0	0	0	0	0	2	0	3	31	373
6:55 AM	0	0	5	0	0	0	6	0	0	0	0	0	0	2	0	2	15	380
7:00 AM	0	0	10	0	0	0	7	0	0	0	0	0	0	2	0	0	19	406
7:05 AM	0	0	11	0	0	0	10	1	0	0	0	0	0	3	0	1	26	414
7:10 AM	0	1	20	0	0	0	12	0	0	0	0	0	0	3	0	1	37	430
7:15 AM	0	0	16	1	0	0	11	0	0	0	0	0	0	2	0	3	33	443
7:20 AM	0	0	26	0	0	0	12	0	0	0	0	0	0	1	0	4	43	468
7:25 AM	0	4	18	0	0	0	14	1	0	0	0	0	0	4	0	0	41	495
7:30 AM	0	0	18	1	0	0	7	0	0	1	0	0	0	7	0	0	34	514
7:35 AM	0	0	14	0	0	0	10	0	0	0	0	0	0	4	0	4	32	545
7:40 AM	0	0	16	0	0	0	10	3	0	0	0	0	0	1	0	1	31	545
7:45 AM	0	0	22	0	0	0	3	0	0	0	0	0	0	2	0	4	31	548
7:50 AM	0	1	21	0	0	0	12	1	0	0	0	0	0	1	0	2	38	552
7:55 AM	0	0	27	0	0	0	9	0	0	0	0	0	0	4	0	1	41	544
8:00 AM	0	1	15	0	0	0	10	0	0	0	0	0	0	1	0	0	27	542
8:05 AM	0	3	24	1	0	0	5	2	0	0	0	0	0	5	0	2	42	
8:10 AM	0	0	30	0	0	0	15	0	0	0	0	0	0	2	0	3	50	
8:15 AM	0	2	41	0	0	0	9	2	0	0	0	0	0	3	0	1	58	

0.00.414	0	0	10	0	0	0	10	0	0	•	0	0	0	0	0		70
8:20 AM	0	0	42	0	0	0	19	2	0	0	0	0	0	6	0	1	70
8:25 AM	0	0	26	0	0	0	25	3	0	0	0	0	0	5	0	1	60
8:30 AM	0	1	13	0	0	0	43	3	0	0	0	0	0	2	0	3	65
8:35 AM	0	0	7	0	0	0	17	1	0	1	0	0	0	1	0	5	32
8:40 AM	0	0	14	0	0	0	16	1	0	1	0	1	0	1	0	0	34
8:45 AM	0	1	7	0	0	0	20	3	0	0	0	1	0	2	0	1	35
8:50 AM	0	2	12	0	0	0	14	0	0	0	0	0	0	2	0	0	30
8:55 AM	0	3	21	0	0	0	6	1	0	0	0	0	0	6	0	2	39
Count Total	0	19	567	3	0	0	411	31	0	3	0	2	0	89	0	52	1,177
Peak Hour	0	9	267	1	0	0	200	18	0	2	0	2	0	33	0	20	552

Traffic Counts - Heavy Vehicles, Bicycles on Road, and Pedestrians/Bicycles on Crosswalk

Interval		Hea	avy Vehicle	es	loyolo	Interval			es on Road			Interval		destrians/E	Bicycles or	Crosswa	lk
Start Time	EB	NB	WB	SB	Total	Start Time	EB	NB	WB	SB	Total	Start Time	EB	NB	WB	SB	Total
6:00 AM	0	0	1	0	1	6:00 AM	0	0	0	0	0	6:00 AM	0	0	0	0	0
6:05 AM	1	0	0	0	1	6:05 AM	0	0	0	0	0	6:05 AM	0	0	0	0	0
6:10 AM	2	0	0	0	2	6:10 AM	0	0	0	0	0	6:10 AM	0	0	0	0	0
6:15 AM	1	0	2	0	3	6:15 AM	0	0	0	0	0	6:15 AM	0	0	0	0	0
6:20 AM	2	0	4	0	6	6:20 AM	0	0	0	0	0	6:20 AM	0	0	0	0	0
6:25 AM	3	0	8	1	12	6:25 AM	0	0	0	0	0	6:25 AM	0	0	0	1	1
6:30 AM	6	0	0	0	6	6:30 AM	0	0	0	0	0	6:30 AM	0	0	0	0	0
6:35 AM	1	0	2	0	3	6:35 AM	0	0	0	0	0	6:35 AM	0	0	0	0	0
6:40 AM	2	0	4	0	6	6:40 AM	0	0	0	0	0	6:40 AM	0	0	0	0	0
6:45 AM	2	0	4	0	6	6:45 AM	0	0	0	0	0	6:45 AM	0	0	0	0	0
6:50 AM	3	0	1	1	5	6:50 AM	0	0	0	0	0	6:50 AM	0	0	0	0	0
6:55 AM	1	0	1	0	2	6:55 AM	0	0	0	0	0	6:55 AM	0	0	0	0	0
7:00 AM	3	0	1	0	4	7:00 AM	0	0	0	0	0	7:00 AM	0	0	0	0	0
7:05 AM	1	0	6	0	7	7:05 AM	0	0	0	0	0	7:05 AM	0	0	0	0	0
7:10 AM	4	0	4	0	8	7:10 AM	0	0	0	0	0	7:10 AM	0	0	0	0	0
7:15 AM	6	0	4	0	10	7:15 AM	0	0	0	0	0	7:15 AM	0	0	0	0	0
7:20 AM	4	0	6	0	10	7:20 AM	0	0	0	0	0	7:20 AM	1	1	0	0	2
7:25 AM	3	0	6	0	9	7:25 AM	0	0	0	0	0	7:25 AM	0	0	0	0	0
7:30 AM	2	0	1	0	3	7:30 AM	0	0	0	0	0	7:30 AM	0	0	0	0	0
7:35 AM	2	0	3	0	5	7:35 AM	0	0	0	0	0	7:35 AM	0	1	0	0	1
7:40 AM	4	0	2	1	7	7:40 AM	0	0	0	0	0	7:40 AM	0	0	0	2	2
7:45 AM	2	0	1	0	3	7:45 AM	0	0	0	0	0	7:45 AM	2	2	0	1	5
7:50 AM	3	0	3	0	6	7:50 AM	0	0	0	0	0	7:50 AM	0	0	0	0	0
7:55 AM	1	0	2	0	3	7:55 AM	0	0	0	0	0	7:55 AM	0	0	0	1	1
8:00 AM	5	0	2	0	7	8:00 AM	0	0	0	0	0	8:00 AM	0	1	0	0	1
8:05 AM	3	0	2	0	5	8:05 AM	0	0	0	0	0	8:05 AM	0	0	0	0	0
8:10 AM	5	0	1	0	6	8:10 AM	0	0	0	0	0	8:10 AM	0	1	0	1	2
8:15 AM	6	0	0	0	6	8:15 AM	0	0	0	0	0	8:15 AM	0	0	0	0	0
8:20 AM	1	0	2	0	3	8:20 AM	0	0	0	0	0	8:20 AM	0	1	0	0	1
8:25 AM	3	0	1	0	4	8:25 AM	0	0	0	0	0	8:25 AM	0	1	0	0	1
8:30 AM	3	0	1	0	4	8:30 AM	0	0	0	0	0	8:30 AM	0	0	0	0	0
8:35 AM	3	0	0	0	3	8:35 AM	0	0	0	0	0	8:35 AM	0	0	0	0	0
8:40 AM	1	0	5	0	6	8:40 AM	0	0	0	0	0	8:40 AM	0	0	0	0	0
8:45 AM	1	0	4	0	5	8:45 AM	0	0	0	0	0	8:45 AM	0	0	0	0	0
8:50 AM	3	0	2	0	5	8:50 AM	0	0	0	0	0	8:50 AM	0	0	0	0	0
8:55 AM	2	0	1	0	3	8:55 AM	0	0	0	0	0	8:55 AM	0	0	0	0	0
Count Total	95	0	87	3	185	Count Total	0	0	0	0	0	Count Total	3	8	0	6	17
Peak Hour	35	0	23	0	58	Peak Hour	0	0	0	0	0	Peak Hour	0	4	0	2	6



Location: 2 NE OAKEN HILLS DR & NE MAIN ST AM Date: Wednesday, April 26, 2023 Peak Hour: 07:50 AM - 08:50 AM Peak 15-Minutes: 08:15 AM - 08:30 AM

Peak Hour





Note: Total study counts contained in parentheses.

	HV%	PHF
EB	11.5%	0.64
WB	15.7%	0.74
NB		
SB	1.3%	0.42
All	10.0%	0.64

Traffic Counts - Motorized Vehicles

Interval		NE M. Eastt	AIN ST				AIN ST bound			North	bound		NE		I HILLS E Ibound)R		Rolling
Start Time	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total	Hour
6:00 AM	0	0	10	0	0	0	2	1					0	0	0	0	13	220
6:05 AM	0	0	8	0	0	0	4	0					0	0	0	1	13	227
6:10 AM	0	0	7	0	0	0	4	1					0	0	0	0	12	245
6:15 AM	0	0	5	0	0	0	7	1					0	0	0	1	14	268
6:20 AM	0	0	5	0	0	0	9	1					0	0	0	2	17	281
6:25 AM	0	0	14	0	0	0	11	1					0	0	0	0	26	306
6:30 AM	0	0	14	0	0	0	4	1					0	2	0	0	21	312
6:35 AM	0	0	6	0	0	0	10	0					0	1	0	0	17	324
6:40 AM	0	1	16	0	0	0	6	0					0	0	0	2	25	334
6:45 AM	0	2	7	0	0	0	9	1					0	1	0	0	20	341
6:50 AM	0	2	15	0	0	0	8	0					0	2	0	0	27	346
6:55 AM	0	0	9	0	0	0	5	0					0	1	0	0	15	351
7:00 AM	0	2	8	0	0	0	6	2					0	1	0	1	20	383
7:05 AM	0	3	14	0	0	0	9	1					0	1	0	3	31	400
7:10 AM	0	3	19	0	0	0	11	0					0	2	0	0	35	404
7:15 AM	0	1	10	0	0	0	8	6					0	2	0	0	27	426
7:20 AM	0	4	23	0	0	0	12	0					0	1	0	2	42	474
7:25 AM	0	2	18	0	0	0	7	2					0	1	0	2	32	509
7:30 AM	0	6	19	0	0	0	2	5					0	1	0	0	33	565
7:35 AM	0	5	12	0	0	0	5	3					0	0	0	2	27	599
7:40 AM	0	6	14	0	0	0	8	3					0	1	0	0	32	606
7:45 AM	0	11	9	0	0	0	4	1					0	0	0	0	25	607
7:50 AM	0	7	11	0	0	0	10	2					0	0	0	2	32	618
7:55 AM	0	15	17	0	0	0	7	7					0	0	0	1	47	611
8:00 AM	0	9	10	0	0	0	11	3					0	2	0	2	37	593
8:05 AM	0	2	8	0	0	0	11	4					0	3	0	7	35	
8:10 AM	0	23	13	0	0	0	8	4					0	2	0	7	57	
8:15 AM	0	37	11	0	0	0	6	15					0	2	0	4	75	

8:20 AM	0	27	10	0	0	0	10	11	0	6	0	13	77
8:25 AM	0	30	11	0	0	0	12	2	0	11	0	22	88
8:30 AM	0	9	7	0	0	0	6	2	0	10	0	33	67
8:35 AM	0	3	7	0	0	0	8	1	0	2	0	13	34
8:40 AM	0	2	13	0	0	0	12	0	0	3	0	3	33
8:45 AM	0	5	9	0	0	0	11	3	0	2	0	6	36
8:50 AM	0	2	7	0	0	0	10	1	0	4	0	1	25
8:55 AM	0	3	13	0	0	0	10	0	0	2	0	1	29
Count Total	0	222	409	0	0	0	283	85	0	66	0	131	1,196
Peak Hour	0	169	127	0	0	0	112	54	0	43	0	113	618

Traffic Counts - Heavy Vehicles, Bicycles on Road, and Pedestrians/Bicycles on Crosswalk

Interval		He	avy Vehicles	S		Interval		Bicyc	les on Road	way		Interval	Pe	edestrians	Bicycles or	n Crosswa	lk
Start Time	EB	NB	WB	SB	Total	Start Time	EB	NB	WB	SB	Total	Start Time	EB	NB	WB	SB	Total
6:00 AM	1		1	0	2	6:00 AM	0		0	0	0	6:00 AM	0		0	0	0
6:05 AM	2		0	0	2	6:05 AM	0		0	0	0	6:05 AM	0		0	0	0
6:10 AM	2		1	0	3	6:10 AM	0		0	0	0	6:10 AM	0		0	0	0
6:15 AM	1		2	0	3	6:15 AM	0		0	0	0	6:15 AM	0		0	0	0
6:20 AM	2		4	1	7	6:20 AM	0		0	0	0	6:20 AM	0		0	0	0
6:25 AM	4		4	0	8	6:25 AM	0		0	0	0	6:25 AM	0		0	0	0
6:30 AM	6		0	0	6	6:30 AM	0		0	0	0	6:30 AM	0		0	0	0
6:35 AM	1		2	0	3	6:35 AM	0		0	0	0	6:35 AM	0		0	0	0
6:40 AM	2		4	1	7	6:40 AM	0		0	0	0	6:40 AM	0		0	0	0
6:45 AM	1		2	0	3	6:45 AM	0		0	0	0	6:45 AM	0		0	0	0
6:50 AM	5		2	0	7	6:50 AM	0		0	0	0	6:50 AM	0		0	0	0
6:55 AM	1		0	0	1	6:55 AM	0		0	0	0	6:55 AM	0		0	0	0
7:00 AM	1		0	1	2	7:00 AM	0		0	0	0	7:00 AM	0		0	0	0
7:05 AM	2		3	3	8	7:05 AM	0		0	0	0	7:05 AM	0		0	0	0
7:10 AM	4		3	0	7	7:10 AM	0		0	0	0	7:10 AM	0		0	0	0
7:15 AM	2		3	0	5	7:15 AM	0		0	0	0	7:15 AM	0		0	0	0
7:20 AM	5		5	1	11	7:20 AM	0		0	0	0	7:20 AM	0		0	0	0
7:25 AM	2		4	2	8	7:25 AM	0		0	0	0	7:25 AM	0		0	0	0
7:30 AM	1		0	0	1	7:30 AM	0		0	0	0	7:30 AM	0		0	0	0
7:35 AM	2		2	1	5	7:35 AM	0		0	0	0	7:35 AM	0		0	0	0
7:40 AM	5		2	0	7	7:40 AM	0		0	0	0	7:40 AM	2		0	2	4
7:45 AM	2		1	0	3	7:45 AM	0		0	0	0	7:45 AM	0		0	2	2
7:50 AM	3		4	0	7	7:50 AM	0		0	0	0	7:50 AM	2		0	0	2
7:55 AM	2		1	0	3	7:55 AM	0		0	0	0	7:55 AM	1		0	0	1
8:00 AM	4		2	0	6	8:00 AM	0		0	0	0	8:00 AM	0		0	0	0
8:05 AM	2		1	0	3	8:05 AM	0		0	0	0	8:05 AM	0		0	0	0
8:10 AM	5		1	0	6	8:10 AM	0		0	0	0	8:10 AM	0		0	0	0
8:15 AM	4		2	0	6	8:15 AM	0		0	0	0	8:15 AM	1		0	0	1
8:20 AM	4		3	1	8	8:20 AM	0		0	0	0	8:20 AM	0		0	0	0
8:25 AM	3		1	1	5	8:25 AM	0		0	0	0	8:25 AM	0		0	0	0
8:30 AM	1		1	0	2	8:30 AM	0		0	0	0	8:30 AM	0		0	0	0
8:35 AM	1		1	0	2	8:35 AM	0		0	0	0	8:35 AM	0		0	0	0
8:40 AM	4		6	0	10	8:40 AM	0		0	0	0	8:40 AM	0		0	0	0
8:45 AM	1		3	0	4	8:45 AM	0		0	0	0	8:45 AM	0		0	0	0
8:50 AM	3		2	1	6	8:50 AM	0		0	0	0	8:50 AM	1		0	0	1
8:55 AM	0		3	0	3	8:55 AM	0		0	0	0	8:55 AM	0		0	0	0
Count Total	91		76	13	180	Count Total	0		0	0	0	Count Total	7		0	4	11
Peak Hour	34		26	2	62	Peak Hour	0		0	0	0	Peak Hour	4		0	0	4



 Location:
 1 SE B ST & NE MAIN ST PM

 Date:
 Wednesday, April 26, 2023

 Peak Hour:
 03:25 PM - 04:25 PM

 Peak 15-Minutes:
 03:35 PM - 03:50 PM

Peak Hour





Note: Total study counts contained in parentheses.

	HV%	PHF
EB	7.8%	0.88
WB	6.6%	0.67
NB	0.0%	0.55
SB	5.1%	0.80
All	6.9%	0.82

Traffic Counts - Motorized Vehicles

Interval			AIN ST				AIN ST bound				3 ST bound				B ST Ibound			Rolling
Start Time	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total	Hour
3:00 PM	0	1	15	0	0	0	18	1	0	1	0	0	0	2	0	2	40	674
3:05 PM	0	2	25	0	0	0	16	1	0	0	0	0	0	3	0	2	49	684
3:10 PM	0	1	29	0	0	1	19	0	0	0	0	1	0	1	0	0	52	686
3:15 PM	0	2	19	0	0	0	20	4	0	0	0	0	0	1	0	4	50	687
3:20 PM	0	1	16	0	0	0	26	1	0	0	0	0	0	1	0	1	46	686
3:25 PM	0	2	28	1	0	0	21	6	0	0	0	0	0	4	0	0	62	693
3:30 PM	0	1	27	0	0	2	26	5	0	0	0	0	0	2	0	1	64	688
3:35 PM	0	1	16	0	0	0	52	2	0	1	0	0	0	1	0	0	73	668
3:40 PM	0	2	15	0	0	1	42	6	0	0	0	2	0	1	0	4	73	653
3:45 PM	0	5	22	0	0	0	29	5	0	0	0	0	0	2	0	2	65	624
3:50 PM	0	1	19	1	0	0	26	2	0	0	0	0	0	2	0	2	53	602
3:55 PM	0	1	21	2	0	1	14	4	0	0	0	0	0	2	0	2	47	582
4:00 PM	0	0	18	0	0	0	24	3	0	1	0	0	0	1	0	3	50	573
4:05 PM	0	1	19	0	0	0	23	1	0	2	0	1	0	1	0	3	51	551
4:10 PM	0	0	29	0	0	1	16	3	0	1	0	0	0	3	0	0	53	562
4:15 PM	0	1	28	0	0	0	17	2	0	1	0	0	0	0	0	0	49	554
4:20 PM	0	1	20	1	0	1	23	4	0	0	0	0	0	1	0	2	53	553
4:25 PM	0	0	28	0	0	1	17	5	0	0	0	0	0	3	0	3	57	552
4:30 PM	0	0	14	1	0	0	21	4	0	0	0	1	0	2	0	1	44	537
4:35 PM	0	1	23	1	0	0	28	2	0	0	0	0	0	2	0	1	58	529
4:40 PM	0	3	16	1	0	0	16	4	0	2	0	0	0	1	0	1	44	528
4:45 PM	0	0	14	0	0	0	22	2	0	1	0	0	0	2	0	2	43	541
4:50 PM	0	4	9	1	0	0	10	4	0	1	0	0	0	4	0	0	33	539
4:55 PM	0	1	14	0	0	0	15	5	0	0	0	0	0	1	0	2	38	547
5:00 PM	0	1	9	0	0	0	13	0	0	0	0	0	0	4	0	1	28	554
5:05 PM	0	1	33	2	0	1	16	3	0	0	0	2	0	2	0	2	62	
5:10 PM	0	1	16	0	0	0	22	4	0	1	0	0	0	1	0	0	45	
5:15 PM	0	2	19	0	0	0	20	0	0	0	0	1	0	1	0	5	48	

5:20 PM	0	1	17	0	0	0	24	5	0	0	0	1	0	2	0	2	52
5:25 PM	0	1	18	0	0	0	17	3	0	0	0	0	0	3	0	0	42
5:30 PM	0	1	11	0	0	0	18	2	0	1	0	0	0	1	0	2	36
5:35 PM	0	7	19	0	0	0	19	2	0	0	0	1	0	4	0	5	57
5:40 PM	0	2	24	0	0	0	27	3	0	0	0	0	0	0	0	1	57
5:45 PM	0	2	18	0	0	0	17	2	0	0	0	0	0	1	0	1	41
5:50 PM	0	2	19	0	0	0	15	4	0	0	0	0	0	1	0	0	41
5:55 PM	0	7	20	0	0	0	14	2	0	0	0	0	0	1	0	1	45
Count Total	0	60	707	11	0	9	763	106	0	13	0	10	0	64	0	58	1,801
Peak Hour	0	16	262	5	0	6	313	43	0	6	0	3	0	20	0	19	693

Traffic Counts - Heavy Vehicles, Bicycles on Road, and Pedestrians/Bicycles on Crosswalk

Interval		Hea	avy Vehicl	es		Interval		Bicycle	es on Road	lway		Interval	Peo	destrians/l	Bicycles or	Crosswa	lk
Start Time	EB	NB	WB	SB	Total	Start Time	EB	NB	WB	SB	Total	Start Time	EB	NB	WB	SB	Total
3:00 PM	0	0	2	0	2	3:00 PM	0	0	0	0	0	3:00 PM	0	0	0	1	1
3:05 PM	1	0	0	0	1	3:05 PM	0	0	0	0	0	3:05 PM	0	1	0	0	1
3:10 PM	1	0	1	0	2	3:10 PM	0	0	0	0	0	3:10 PM	0	2	0	0	2
3:15 PM	2	0	2	1	5	3:15 PM	0	0	0	0	0	3:15 PM	0	0	0	0	0
3:20 PM	0	0	2	0	2	3:20 PM	0	0	0	0	0	3:20 PM	0	0	2	2	4
3:25 PM	1	0	4	0	5	3:25 PM	0	0	0	0	0	3:25 PM	0	0	0	2	2
3:30 PM	1	0	2	0	3	3:30 PM	0	0	0	0	0	3:30 PM	0	0	0	0	0
3:35 PM	0	0	3	0	3	3:35 PM	0	0	0	0	0	3:35 PM	0	0	0	4	4
3:40 PM	2	0	5	1	8	3:40 PM	0	0	0	0	0	3:40 PM	0	0	0	2	2
3:45 PM	2	0	1	0	3	3:45 PM	0	0	0	0	0	3:45 PM	0	0	0	4	4
3:50 PM	2	0	0	1	3	3:50 PM	0	0	0	0	0	3:50 PM	2	2	0	0	4
3:55 PM	5	0	1	0	6	3:55 PM	0	0	0	0	0	3:55 PM	3	2	0	1	6
4:00 PM	3	0	2	0	5	4:00 PM	0	0	0	0	0	4:00 PM	2	2	0	0	4
4:05 PM	1	0	2	0	3	4:05 PM	0	0	0	0	0	4:05 PM	0	3	0	1	4
4:10 PM	1	0	0	0	1	4:10 PM	0	0	0	0	0	4:10 PM	0	0	0	0	0
4:15 PM	2	0	2	0	4	4:15 PM	0	0	0	0	0	4:15 PM	0	2	0	1	3
4:20 PM	2	0	2	0	4	4:20 PM	0	0	0	0	0	4:20 PM	0	4	0	0	4
4:25 PM	2	0	0	0	2	4:25 PM	0	0	1	0	1	4:25 PM	0	0	0	2	2
4:30 PM	0	0	1	0	1	4:30 PM	0	0	0	0	0	4:30 PM	3	3	0	3	9
4:35 PM	1	0	1	0	2	4:35 PM	0	0	0	0	0	4:35 PM	1	3	0	1	5
4:40 PM	1	0	1	0	2	4:40 PM	0	0	0	0	0	4:40 PM	1	0	0	1	2
4:45 PM	2	0	1	0	3	4:45 PM	0	0	0	0	0	4:45 PM	2	3	0	0	5
4:50 PM	1	0	0	0	1	4:50 PM	0	0	0	0	0	4:50 PM	0	0	0	1	1
4:55 PM	1	0	1	0	2	4:55 PM	0	0	0	0	0	4:55 PM	1	0	0	4	5
5:00 PM	0	0	1	0	1	5:00 PM	0	0	0	0	0	5:00 PM	1	2	0	0	3
5:05 PM	5	0	0	0	5	5:05 PM	0	0	0	0	0	5:05 PM	0	3	0	0	3
5:10 PM	0	0	3	0	3	5:10 PM	0	0	1	0	1	5:10 PM	0	0	0	1	1
5:15 PM	1	0	1	0	2	5:15 PM	0	0	2	0	2	5:15 PM	0	1	0	0	1
5:20 PM	0	0	1	0	1	5:20 PM	0	0	0	0	0	5:20 PM	0	4	0	0	4
5:25 PM	1	0	0	0	1	5:25 PM	0	0	0	0	0	5:25 PM	0	1	0	0	1
5:30 PM	1	0	3	0	4	5:30 PM	0	0	0	0	0	5:30 PM	1	1	0	2	4
5:35 PM	2	0	3	0	5	5:35 PM	0	0	0	0	0	5:35 PM	1	1	0	0	2
5:40 PM	2	0	2	0	4	5:40 PM	0	0	0	0	0	5:40 PM	2	1	0	4	7
5:45 PM	0	0	0	0	0	5:45 PM	0	0	0	0	0	5:45 PM	0	1	0	0	1
5:50 PM	0	0	0	0	0	5:50 PM	0	0	0	0	0	5:50 PM	0	0	0	0	0
5:55 PM	0	0	0	0	0	5:55 PM	0	0	0	0	0	5:55 PM	0	2	0	0	2
Count Total	46	0	50	3	99	Count Total	0	0	4	0	4	Count Total	20	44	2	37	103
Peak Hour	22	0	24	2	48	Peak Hour	0	0	0	0	0	Peak Hour	7	15	0	15	37



Location: 2 NE OAKEN HILLS DR & NE MAIN ST PM Date: Wednesday, April 26, 2023 Peak Hour: 03:15 PM - 04:15 PM Peak 15-Minutes: 03:25 PM - 03:40 PM

Peak Hour





Note: Total study counts contained in parentheses.

	HV%	PHF
EB	6.9%	0.84
WB	8.5%	0.87
NB		
SB	6.1%	0.46
All	7.3%	0.77

Traffic Counts - Motorized Vehicles

Interval			AIN ST				AIN ST bound			North	bound		NE		I HILLS E Ibound	DR		Rolling
 Start Time	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total	Hour
3:00 PM	0	2	9	0	0	0	20	1					0	3	0	3	38	643
3:05 PM	0	2	25	0	0	0	12	1					0	3	0	2	45	654
3:10 PM	0	8	8	0	0	0	14	5					0	2	0	0	37	653
3:15 PM	0	12	11	0	0	0	21	1					0	6	0	1	52	667
3:20 PM	0	4	14	0	0	0	19	4					0	0	0	2	43	658
3:25 PM	0	16	17	0	0	0	27	2					0	1	0	3	66	662
3:30 PM	0	7	20	0	0	0	15	5					0	7	0	20	74	632
3:35 PM	0	8	11	0	0	0	23	3					0	9	0	22	76	606
3:40 PM	0	3	15	0	0	0	15	5					0	2	0	20	60	578
3:45 PM	0	7	12	0	0	0	21	1					0	4	0	12	57	563
3:50 PM	0	3	17	0	0	0	15	3					0	4	0	6	48	549
3:55 PM	0	2	14	0	0	0	21	3					0	2	0	5	47	536
4:00 PM	0	4	16	0	0	0	16	3					0	7	0	3	49	526
4:05 PM	1	5	14	0	0	0	18	0					0	3	0	3	44	513
4:10 PM	0	6	21	0	0	0	19	0					0	2	0	3	51	513
4:15 PM	0	4	18	0	0	0	16	0					0	2	0	3	43	517
4:20 PM	0	2	24	0	0	0	16	1					0	1	0	3	47	514
4:25 PM	0	8	11	0	0	0	15	0					0	0	0	2	36	512
4:30 PM	0	2	20	0	0	0	21	2					0	1	0	2	48	521
4:35 PM	0	5	11	0	0	0	22	1					0	5	0	4	48	511
4:40 PM	0	4	17	0	0	0	16	3					0	1	0	4	45	501
4:45 PM	0	1	9	0	0	0	19	4					0	3	0	7	43	504
4:50 PM	0	3	12	0	0	0	13	4					0	1	0	2	35	514
4:55 PM	0	2	11	0	0	0	14	3					0	5	0	2	37	514
5:00 PM	0	2	5	0	0	0	19	5					0	2	0	3	36	516
5:05 PM	0	6	18	0	0	0	14	3					0	1	0	2	44	
5:10 PM	0	5	14	0	0	0	19	4					0	4	0	9	55	
5:15 PM	0	2	13	0	0	0	16	1					0	2	0	6	40	

5:20 PM	0	5	13	0	0	0	16	2	0	2	0	7	45
5:25 PM	0	7	12	0	0	0	20	1	0	1	0	4	45
5:30 PM	0	8	5	0	0	0	9	4	0	5	0	7	38
5:35 PM	0	5	9	0	0	0	15	1	0	2	0	6	38
5:40 PM	0	8	12	0	0	0	23	2	0	2	0	1	48
5:45 PM	0	9	10	0	0	0	22	5	0	2	0	5	53
5:50 PM	0	4	9	0	0	0	10	7	0	4	0	1	35
5:55 PM	0	7	6	0	0	0	17	3	0	3	0	3	39
Count Total	1	188	483	0	0	0	628	93	0	104	0	188	1,685
Peak Hour	1	77	182	0	0	0	230	30	0	47	0	100	667

Traffic Counts - Heavy Vehicles, Bicycles on Road, and Pedestrians/Bicycles on Crosswalk

Interval		He	eavy Vehicle	S		Interval		Bicycl	es on Road	way		Interval		destrians/	Bicycles or	n Crosswa	lk
Start Time	EB	NB	WB	SB	Total	Start Time	EB	NB	WB	SB	Total	Start Time	EB	NB	WB	SB	Total
3:00 PM	1		1	0	2	3:00 PM	0		0	0	0	3:00 PM	0		0	0	0
3:05 PM	2		0	0	2	3:05 PM	0		0	0	0	3:05 PM	0		0	0	0
3:10 PM	1		3	0	4	3:10 PM	0		0	0	0	3:10 PM	0		0	2	2
3:15 PM	2		3	2	7	3:15 PM	0		0	0	0	3:15 PM	1		0	0	1
3:20 PM	0		3	0	3	3:20 PM	0		0	0	0	3:20 PM	0		0	1	1
3:25 PM	1		3	0	4	3:25 PM	0		0	0	0	3:25 PM	1		0	1	2
3:30 PM	1		3	1	5	3:30 PM	0		0	0	0	3:30 PM	0		0	0	0
3:35 PM	0		4	1	5	3:35 PM	0		0	1	1	3:35 PM	1		0	0	1
3:40 PM	2		0	5	7	3:40 PM	0		0	0	0	3:40 PM	0		0	0	0
3:45 PM	2		0	0	2	3:45 PM	0		0	0	0	3:45 PM	1		0	3	4
3:50 PM	2		1	0	3	3:50 PM	0		0	0	0	3:50 PM	0		0	4	4
3:55 PM	5		0	0	5	3:55 PM	0		0	0	0	3:55 PM	0		0	2	2
4:00 PM	0		2	0	2	4:00 PM	0		0	0	0	4:00 PM	1		0	0	1
4:05 PM	3		2	0	5	4:05 PM	0		0	0	0	4:05 PM	1		0	0	1
4:10 PM	0		1	0	1	4:10 PM	0		0	0	0	4:10 PM	0		0	0	0
4:15 PM	3		2	0	5	4:15 PM	0		0	0	0	4:15 PM	0		0	0	0
4:20 PM	2		0	0	2	4:20 PM	0		0	0	0	4:20 PM	1		0	2	3
4:25 PM	1		0	0	1	4:25 PM	0		0	0	0	4:25 PM	0		0	0	0
4:30 PM	1		2	0	3	4:30 PM	0		0	0	0	4:30 PM	0		0	0	0
4:35 PM	0		1	0	1	4:35 PM	0		0	0	0	4:35 PM	0		0	0	0
4:40 PM	2		2	0	4	4:40 PM	0		0	0	0	4:40 PM	0		0	0	0
4:45 PM	2		1	0	3	4:45 PM	0		0	0	0	4:45 PM	0		0	0	0
4:50 PM	0		0	0	0	4:50 PM	0		0	0	0	4:50 PM	2		0	2	4
4:55 PM	1		1	0	2	4:55 PM	0		0	0	0	4:55 PM	0		0	0	0
5:00 PM	0		1	0	1	5:00 PM	0		0	0	0	5:00 PM	0		0	0	0
5:05 PM	3		0	0	3	5:05 PM	0		0	0	0	5:05 PM	1		0	1	2
5:10 PM	1		4	0	5	5:10 PM	0		0	0	0	5:10 PM	0		0	0	0
5:15 PM	0		0	1	1	5:15 PM	0		0	0	0	5:15 PM	0		0	0	0
5:20 PM	1		1	0	2	5:20 PM	0		0	0	0	5:20 PM	3		0	1	4
5:25 PM	0		1	0	1	5:25 PM	0		0	0	0	5:25 PM	0		0	0	0
5:30 PM	1		2	0	3	5:30 PM	0		0	0	0	5:30 PM	0		0	2	2
5:35 PM	1		1	0	2	5:35 PM	0		0	0	0	5:35 PM	0		0	0	0
5:40 PM	2		2	0	4	5:40 PM	0		0	0	0	5:40 PM	0		0	0	0
5:45 PM	0		0	0	0	5:45 PM	0		0	0	0	5:45 PM	0		0	0	0
5:50 PM	0		0	0	0	5:50 PM	0		0	0	0	5:50 PM	0		0	0	0
5:55 PM	0		0	0	0	5:55 PM	0		0	0	0	5:55 PM	3		0	2	5
Count Total	43		47	10	100	Count Total	0		0	1	1	Count Total	16		0	23	39
Peak Hour	18		22	9	49	Peak Hour	0		0	1	1	Peak Hour	6		0	11	17

B. CRASH DATA



000 Crash Id 015 Street Name	016 Intersecting Street Name	028 Crash Type	029 Collision Type	031 Weather Conditions	032 Road Surface Conditions	033 Lighting Conditions	034 Traffic Control	036 Crash Cause 1	114 Road Departure Flag	117 Severity	118 Intersection Flag	126 Bike / Ped Related	Week of 001 CRASH Date 00	2 Year 007 County	008 Jurisdiction
1693622 N B ST	WILLAMINA DR	ANGL-OTH	TURN	CLR	DRY	DAY	STOP SIGN	NO-YIELD	No	PDO	Yes	Neither	13-Mar-16	2016 Yamhill	Willamina
1818784 E MAIN ST	OAKEN HILLS DR	S-1STOP	REAR	RAIN	WET	DAY	UNKNOWN	TOO-CLOS	No	PDO	No	Neither	11-Feb-18	2018 Yamhill	Willamina
1876844 S MAIN ST	W MAIN ST	FIX OBJ	FIX	CLR	DRY	DAY	UNKNOWN	ILLNESS	Yes	Serious Injury (A)	No	Neither	2-Aug-20	2020 Yamhill	Willamina
1783321 E MAIN ST	W MAIN ST	FIX OBJ	FIX	CLD	DRY	DARK	UNKNOWN	RECKLESS	No	Minor Injury (B)	Yes	Neither	18-Mar-18	2018 Yamhill	Willamina
1761480 W MAIN ST	S MAIN ST	S-1STOP	REAR	CLR	DRY	DAY	UNKNOWN	TOO-CLOS	No	PDO	Yes	Neither	2-Apr-17	2017 Yamhill	Willamina
1798107 E MAIN ST	W MAIN ST	O-1STOP	BACK	CLR	DRY	DAY	UNKNOWN	OTHR-IMP	No	Minor Injury (B)	Yes	Neither	5-Aug-18	2018 Yamhill	Willamina
1708762 E MAIN ST	W MAIN ST	FIX OBJ	FIX	CLR	DRY	DLIT	STOP SIGN	SPEED	No	PDO	Yes	Neither	31-Jul-16	2016 Yamhill	Willamina
1868364 E MAIN ST	W MAIN ST	FIX OBJ	FIX	CLR	DRY	DAY	CHANNEL	FATIGUE	No	PDO	Yes	Neither	26-May-19	2019 Yamhill	Willamina

119 State Highv	way Flag 005 Region 011 H	wy No 013 Lat	014 Long	001 CRASH Date 021 Road Characteristics	022 Off Roadway Flag	023 Isect Typ Short Desc	024 Isect Rel Fig	025 Drvwy Rel Flg	035 Crash Evnt 1 Short Desc	039 Alcohol Involved Flag	040 Drug Involved Flag	041 Marijuana Flag	042 Speed Involved Flag	054 Veh1 MVMNT SHORT DESC
No	2	45.07971944	-123.486147	2 3/15/2016 INTER	FALSE	3-LEG	FALSE	FALSE		FALSE	FALSE	FALSE	FALSE	TURN-R
Yes	2	157 45.08081111	-123.479433	3 2/16/2018 STRGHT	FALSE		FALSE	FALSE		FALSE	FALSE	FALSE	FALSE	STRGHT
Yes	2	157 45.0781934	-123.486550	9 8/3/2020 CURVE	TRUE		FALSE	FALSE	BR RAIL	FALSE	FALSE	FALSE	FALSE	STRGHT
Yes	2	157 45.07847222	2 -123.486330	6 3/18/2018 INTER	TRUE	3-LEG	FALSE	FALSE	BARRIER	TRUE	FALSE	FALSE	TRUE	STRGHT
No	2	45.07851389	-123.487027	8 4/4/2017 STRGHT	FALSE		TRUE	FALSE		FALSE	FALSE	FALSE	FALSE	STRGHT
No	2	45.078475	-123.486336	1 8/6/2018 INTER	FALSE	3-LEG	FALSE	FALSE		FALSE	FALSE	FALSE	FALSE	BACK
Yes	2	157 45.07847222	-123.486330	6 8/6/2016 INTER	TRUE	3-LEG	FALSE	FALSE	BARRIER	TRUE	FALSE	FALSE	TRUE	STRGHT
Yes	2	157 45.07847525	-123.486339	6 5/27/2019 INTER	TRUE	3-LEG	FALSE	FALSE	RR ROW	FALSE	FALSE	FALSE	FALSE	STRGHT

055 Veh1 VHCL CMPSS DIR FROM SHORT DESC	056 Veh1 VHCL CMPSS DIR TO SHORT DESC	057 Veh1 ACTN SHORT DESC	058 Veh1 VHCL EVNT 1 SHORT DESC	064 Veh2 MVMNT SHORT DESC	065 Veh2 VHCL CMPSS DIR FROM SHORT DESC	066 Veh2 VHCL CMPSS DIR TO SHORT DESC	067 Veh2 ACTN SHORT DESC
W	S	GO A/STOP		TURN-L	S	W	NONE
S	N	NONE		STOP	S	N	STOPPED
S	N	NONE	BR RAIL				
NE	SW	NONE	BARRIER				
W	E	NONE		STOP	W	E	STP/L TRN
E	W	NONE		STOP	W	E	STOPPED
SW	NE	THRU MED					
S	N	OTHER					

C. HCM REPORTS – EXISTING CONDITIONS



Intersection	
Int Delay, s/yeb	5.9

Int Delay, s/veh	5.8								
Movement	EBL	EBR	NBL	NBT	SBT	SBR			
Lane Configurations	Y			÷	et -				
Traffic Vol, veh/h	1	27	23	8	10	1			
Future Vol, veh/h	1	27	23	8	10	1			
Conflicting Peds, #/hr	0	0	1	0	0	1			
Sign Control	Stop	Stop	Free	Free	Free	Free			
RT Channelized	-	None	-	None	-	None			
Storage Length	0	-	-	-	-	-			
Veh in Median Storage,	# 0	-	-	0	0	-			
Grade, %	0	-	-	0	0	-			
Peak Hour Factor	74	74	74	74	74	74			
Heavy Vehicles, %	0	0	5	0	0	0			
Mvmt Flow	1	36	31	11	14	1			

Major/Minor	Minor2	l	Major1	Maj	or2		
Conflicting Flow All	89	16	16	0	-	0	
Stage 1	16	-	-	-	-	-	
Stage 2	73	-	-	-	-	-	
Critical Hdwy	6.4	6.2	4.15	-	-	-	
Critical Hdwy Stg 1	5.4	-	-	-	-	-	
Critical Hdwy Stg 2	5.4	-	-	-	-	-	
Follow-up Hdwy	3.5	3.3	2.245	-	-	-	
Pot Cap-1 Maneuver	917	1069	1582	-	-	-	
Stage 1	1012	-	-	-	-	-	
Stage 2	955	-	-	-	-	-	
Platoon blocked, %				-	-	-	
Mov Cap-1 Maneuver		1068	1580	-	-	-	
Mov Cap-2 Maneuver	897	-	-	-	-	-	
Stage 1	991	-	-	-	-	-	
Stage 2	954	-	-	-	-	-	

Approach	EB	NB	SB
HCM Control Delay, s	8.5	5.4	0
HCM LOS	А		

Minor Lane/Major Mvmt	NBL	NBT E	EBLn1	SBT	SBR
Capacity (veh/h)	1580	-	1061	-	-
HCM Lane V/C Ratio	0.02	-	0.036	-	-
HCM Control Delay (s)	7.3	0	8.5	-	-
HCM Lane LOS	А	Α	Α	-	-
HCM 95th %tile Q(veh)	0.1	-	0.1	-	-

1.7

Intersection

Int Delay, s/veh

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	
Lane Configurations				WDL		WDIX	NDL		HDR	ODL		ODIX	
	•	- (4	10	•	- (•	• •	- ()-	•	
Traffic Vol, veh/h	9	277	1	0	208	19	2	0	2	34	0	21	
Future Vol, veh/h	9	277	1	0	208	19	2	0	2	34	0	21	
Conflicting Peds, #/hr	2	0	4	4	0	2	0	0	0	0	0	0	
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop	
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None	
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-	
Veh in Median Storage,	# -	0	-	-	0	-	-	0	-	-	0	-	
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-	
Peak Hour Factor	71	71	71	71	71	71	71	71	71	71	71	71	
Heavy Vehicles, %	22	12	0	0	12	0	0	0	0	0	0	0	
Mvmt Flow	13	390	1	0	293	27	3	0	3	48	0	30	

Major/Minor	Major1		1	Major2			Minor1		Ν	/linor2			
Conflicting Flow All	322	0	0	395	0	0	743	743	395	727	730	309	
Stage 1	-	-	-	-	-	-	421	421	-	309	309	-	
Stage 2	-	-	-	-	-	-	322	322	-	418	421	-	
Critical Hdwy	4.32	-	-	4.1	-	-	7.1	6.5	6.2	7.1	6.5	6.2	
Critical Hdwy Stg 1	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Critical Hdwy Stg 2	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Follow-up Hdwy	2.398	-	-	2.2	-	-	3.5	4	3.3	3.5	4	3.3	
Pot Cap-1 Maneuver	1133	-	-	1175	-	-	334	346	659	342	352	736	
Stage 1	-	-	-	-	-	-	614	592	-	705	663	-	
Stage 2	-	-	-	-	-	-	694	655	-	616	592	-	
Platoon blocked, %		-	-		-	-							
Mov Cap-1 Maneuver	1131	-	-	1171	-	-	316	339	656	336	345	735	
Mov Cap-2 Maneuver	-	-	-	-	-	-	316	339	-	336	345	-	
Stage 1	-	-	-	-	-	-	602	581	-	693	662	-	
Stage 2	-	-	-	-	-	-	666	654	-	604	581	-	
Approach	EB			WB			NB			SB			
HCM Control Delay, s	0.3			0			13.5			15.4			
HCM LOS							В			С			
Minor Lane/Major Myr	nt N	IRI n1	EBI	EBT	ERD	\//RI	\//RT		Din1				

Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR S	BLn1	
Capacity (veh/h)	427	1131	-	-	1171	-	-	424	
HCM Lane V/C Ratio	0.013	0.011	-	-	-	-	-	0.183	
HCM Control Delay (s)	13.5	8.2	0	-	0	-	-	15.4	
HCM Lane LOS	В	А	А	-	А	-	-	С	
HCM 95th %tile Q(veh)	0	0	-	-	0	-	-	0.7	

Intersection

Int Delay, s/veh	8.1						
Movement	EBL	EBT	WBT	WBR	SBL	SBR	1
Lane Configurations		÷	et –		Y		
Traffic Vol, veh/h	175	132	116	56	45	117	,
Future Vol, veh/h	175	132	116	56	45	117	,
Conflicting Peds, #/hr	0	0	0	0	0	4	ļ
Sign Control	Free	Free	Free	Free	Stop	Stop)
RT Channelized	-	None	-	None	-	None)
Storage Length	-	-	-	-	0	-	•
Veh in Median Storage	, # -	0	0	-	0	-	-
Grade, %	-	0	0	-	0	-	
Peak Hour Factor	64	64	64	64	64	64	ļ
Heavy Vehicles, %	4	21	20	7	5	0)
Mvmt Flow	273	206	181	88	70	183	}

Major/Minor	Major1	Ν	lajor2	1	Vinor2	
Conflicting Flow All	269	0	-	0	977	229
Stage 1	-	-	-	-	225	-
Stage 2	-	-	-	-	752	-
Critical Hdwy	4.14	-	-	-	6.45	6.2
Critical Hdwy Stg 1	-	-	-	-	5.45	-
Critical Hdwy Stg 2	-	-	-	-	5.45	-
Follow-up Hdwy	2.236	-	-	-	3.545	3.3
Pot Cap-1 Maneuver	1283	-	-	-	275	815
Stage 1	-	-	-	-	805	-
Stage 2	-	-	-	-	460	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver		-	-	-	209	812
Mov Cap-2 Maneuver	-	-	-	-	209	-
Stage 1	-	-	-	-	612	-
Stage 2	-	-	-	-	460	-
Approach	EB		WB		SB	
HCM Control Delay, s	4.9		0		22.7	
HCM LOS					С	
Minor Lane/Major Mvn	nt	EBL	EBT	WBT	WBR S	SBLn1
Capacity (veh/h)		1283	-	-	-	451
HCM Lane V/C Ratio		0.213	-	-	-	0.561
HCM Control Delay (s))	8.6	0	-	-	22.7
HCM Lane LOS		А	А	-	-	С
HCM 95th %tile Q(veh	ı)	0.8	-	-	-	3.4

Intersection	

1.1		/ 1	
Int	Delav	c/voh	

Int Delay, s/veh	4.5					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	Y			÷.	et -	
Traffic Vol, veh/h	1	21	30	23	16	1
Future Vol, veh/h	1	21	30	23	16	1
Conflicting Peds, #/hr	0	1	6	0	0	6
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage	# 0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	71	71	71	71	71	71
Heavy Vehicles, %	0	0	3	0	7	0
Mvmt Flow	1	30	42	32	23	1

Major/Minor	Minor2	l	Major1	Maj	jor2		
Conflicting Flow All	146	31	30	0	-	0	
Stage 1	30	-	-	-	-	-	
Stage 2	116	-	-	-	-	-	
Critical Hdwy	6.4	6.2	4.13	-	-	-	
Critical Hdwy Stg 1	5.4	-	-	-	-	-	
Critical Hdwy Stg 2	5.4	-	-	-	-	-	
Follow-up Hdwy	3.5	3.3	2.227	-	-	-	
Pot Cap-1 Maneuver	851	1049	1576	-	-	-	
Stage 1	998	-	-	-	-	-	
Stage 2	914	-	-	-	-	-	
Platoon blocked, %				-	-	-	
Mov Cap-1 Maneuve	r 818	1042	1567	-	-	-	
Mov Cap-2 Maneuve	r 818	-	-	-	-	-	
Stage 1	965	-	-	-	-	-	
Stage 2	909	-	-	-	-	-	

Approach	EB	NB	SB
HCM Control Delay, s	8.6	4.2	0
HCM LOS	А		

Minor Lane/Major Mvmt	NBL	NBT E	EBLn1	SBT	SBR
Capacity (veh/h)	1567	-	1029	-	-
HCM Lane V/C Ratio	0.027	-	0.03	-	-
HCM Control Delay (s)	7.4	0	8.6	-	-
HCM Lane LOS	А	А	А	-	-
HCM 95th %tile Q(veh)	0.1	-	0.1	-	-

1.4

Intersection

Int Delay, s/veh

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	
Lane Configurations		4			4			4			4		
Traffic Vol, veh/h	17	272	5	6	325	45	6	0	3	21	0	20	
Future Vol, veh/h	17	272	5	6	325	45	6	0	3	21	0	20	
Conflicting Peds, #/hr	12	0	15	15	0	12	7	0	0	0	0	7	
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop	
RT Channelized	-	-	None										
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-	
Veh in Median Storage,	# -	0	-	-	0	-	-	0	-	-	0	-	
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-	
Peak Hour Factor	82	82	82	82	82	82	82	82	82	82	82	82	
Heavy Vehicles, %	0	8	0	0	8	0	0	0	0	0	0	11	
Mvmt Flow	21	332	6	7	396	55	7	0	4	26	0	24	

Major/Minor	Major1		I	Major2		l	Minor1		Ν	/linor2			
Conflicting Flow All	463	0	0	353	0	0	849	869	350	829	845	443	
Stage 1	-	-	-	-	-	-	392	392	-	450	450	-	
Stage 2	-	-	-	-	-	-	457	477	-	379	395	-	
Critical Hdwy	4.1	-	-	4.1	-	-	7.1	6.5	6.2	7.1	6.5	6.31	
Critical Hdwy Stg 1	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Critical Hdwy Stg 2	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Follow-up Hdwy	2.2	-	-	2.2	-	-	3.5	4	3.3	3.5		3.399	
Pot Cap-1 Maneuver	1109	-	-	1217	-	-	283	292	698	292	302	596	
Stage 1	-	-	-	-	-	-	637	610	-	592	575	-	
Stage 2	-	-	-	-	-	-	587	559	-	647	608	-	
Platoon blocked, %		-	-		-	-							
Mov Cap-1 Maneuver	1096	-	-	1200	-	-	259	276	688	280	285	585	
Mov Cap-2 Maneuver	-	-	-	-	-	-	259	276	-	280	285	-	
Stage 1	-	-	-	-	-	-	613	587	-	571	564	-	
Stage 2	-	-	-	-	-	-	554	548	-	628	585	-	
Approach	EB			WB			NB			SB			
HCM Control Delay, s	0.5			0.1			16.4			16.1			
HCM LOS							С			С			
Minor Lane/Maior Myn	nt N	IRI n1	FRI	FRT	FRR	WRI	WRT	WRR S	RI n1				

Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR \$	SBLn1	
Capacity (veh/h)	327	1096	-	-	1200	-	-	375	
HCM Lane V/C Ratio	0.034	0.019	-	-	0.006	-	-	0.133	
HCM Control Delay (s)	16.4	8.3	0	-	8	0	-	16.1	
HCM Lane LOS	С	А	А	-	А	А	-	С	
HCM 95th %tile Q(veh)	0.1	0.1	-	-	0	-	-	0.5	

Intersection

Int Delay, s/veh	4.8					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		ب	et 👘		Y	
Traffic Vol, veh/h	80	189	239	31	49	104
Future Vol, veh/h	80	189	239	31	49	104
Conflicting Peds, #/hr	11	0	0	11	0	6
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	e, # -	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	77	77	77	77	77	77
Heavy Vehicles, %	6	7	9	7	9	5
Mvmt Flow	104	245	310	40	64	135

Major/Minor	Major1	Ν	/lajor2		Minor2	
Conflicting Flow All	361	0	-	0	794	347
Stage 1	-	-	-	-	341	-
Stage 2	-	-	-	-	453	-
Critical Hdwy	4.16	-	-	-	6.49	6.25
Critical Hdwy Stg 1	-	-	-	-	5.49	-
Critical Hdwy Stg 2	-	-	-	-	5.49	-
Follow-up Hdwy	2.254	-	-	-	3.581	3.345
Pot Cap-1 Maneuver	1176	-	-	-	347	689
Stage 1	-	-	-	-	705	-
Stage 2	-	-	-	-	626	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver		-	-	-	305	678
Mov Cap-2 Maneuver	• -	-	-	-	305	-
Stage 1	-	-	-	-	626	-
Stage 2	-	-	-	-	620	-
Approach	EB		WB		SB	
HCM Control Delay, s	2.5		0		17.4	
HCM LOS					С	
Minor Lane/Major Mvr	mt	EBL	EBT	WBT	WBR :	SBLn1
Capacity (veh/h)		1164	-	-	-	487
HCM Lane V/C Ratio		0.089	-	-	-	0.408
HCM Control Delay (s	5)	8.4	0	-	-	17.4
HCM Lane LOS		А	А	-	-	С
HCM 95th %tile Q(vel	h)	0.3	-	-	-	2

D. HCM REPORTS – NO BUILD CONDITIONS

Intersection

Int Delay, s/veh	5.8						
Movement	EBL	EBR	NBL	NBT	SBT	SBR	
Lane Configurations	Y			÷	et 👘		
Traffic Vol, veh/h	1	27	23	8	10	1	
Future Vol, veh/h	1	27	23	8	10	1	
Conflicting Peds, #/hr	0	0	1	0	0	1	
Sign Control	Stop	Stop	Free	Free	Free	Free	
RT Channelized	-	None	-	None	-	None	
Storage Length	0	-	-	-	-	-	
Veh in Median Storage,	# 0	-	-	0	0	-	
Grade, %	0	-	-	0	0	-	
Peak Hour Factor	74	74	74	74	74	74	
Heavy Vehicles, %	0	0	5	0	0	0	
Mvmt Flow	1	36	31	11	14	1	

Major/Minor	Minor2	l	Major1	Maj	or2		
Conflicting Flow All	89	16	16	0	-	0	
Stage 1	16	-	-	-	-	-	
Stage 2	73	-	-	-	-	-	
Critical Hdwy	6.4	6.2	4.15	-	-	-	
Critical Hdwy Stg 1	5.4	-	-	-	-	-	
Critical Hdwy Stg 2	5.4	-	-	-	-	-	
Follow-up Hdwy	3.5	3.3	2.245	-	-	-	
Pot Cap-1 Maneuver	917	1069	1582	-	-	-	
Stage 1	1012	-	-	-	-	-	
Stage 2	955	-	-	-	-	-	
Platoon blocked, %				-	-	-	
Mov Cap-1 Maneuver	897	1068	1580	-	-	-	
Mov Cap-2 Maneuver	897	-	-	-	-	-	
Stage 1	991	-	-	-	-	-	
Stage 2	954	-	-	-	-	-	

Approach	EB	NB	SB
HCM Control Delay, s	8.5	5.4	0
HCM LOS	А		

Minor Lane/Major Mvmt	NBL	NBT E	EBLn1	SBT	SBR
Capacity (veh/h)	1580	-	1061	-	-
HCM Lane V/C Ratio	0.02	-	0.036	-	-
HCM Control Delay (s)	7.3	0	8.5	-	-
HCM Lane LOS	А	А	А	-	-
HCM 95th %tile Q(veh)	0.1	-	0.1	-	-

1.8

Intersection

Int Delay, s/veh

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	
Lane Configurations		4			4			4			4		
Traffic Vol, veh/h	9	281	1	0	211	19	2	0	2	35	0	21	
Future Vol, veh/h	9	281	1	0	211	19	2	0	2	35	0	21	
Conflicting Peds, #/hr	2	0	4	4	0	2	0	0	0	0	0	0	
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop	
RT Channelized	-	-	None										
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-	
Veh in Median Storage	# -	0	-	-	0	-	-	0	-	-	0	-	
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-	
Peak Hour Factor	71	71	71	71	71	71	71	71	71	71	71	71	
Heavy Vehicles, %	22	12	0	0	12	0	0	0	0	0	0	0	
Mvmt Flow	13	396	1	0	297	27	3	0	3	49	0	30	

Major/Minor	Major1		Ν	/lajor2		1	Minor1		Ν	/linor2			
Conflicting Flow All	326	0	0	401	0	0	753	753	401	737	740	313	
Stage 1	-	-	-	-	-	-	427	427	-	313	313	-	
Stage 2	-	-	-	-	-	-	326	326	-	424	427	-	
Critical Hdwy	4.32	-	-	4.1	-	-	7.1	6.5	6.2	7.1	6.5	6.2	
Critical Hdwy Stg 1	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Critical Hdwy Stg 2	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Follow-up Hdwy	2.398	-	-	2.2	-	-	3.5	4	3.3	3.5	4	3.3	
Pot Cap-1 Maneuver	1129	-	-	1169	-	-	329	341	653	337	347	732	
Stage 1	-	-	-	-	-	-	610	589	-	702	661	-	
Stage 2	-	-	-	-	-	-	691	652	-	612	589	-	
Platoon blocked, %		-	-		-	-							
Mov Cap-1 Maneuver	1127	-	-	1165	-	-	311	334	651	331	340	731	
Mov Cap-2 Maneuver	-	-	-	-	-	-	311	334	-	331	340	-	
Stage 1	-	-	-	-	-	-	598	578	-	690	660	-	
Stage 2	-	-	-	-	-	-	663	651	-	600	578	-	
Approach	EB			WB			NB			SB			
HCM Control Delay, s	0.3			0			13.7			15.7			
HCM LOS							В			С			
Minor Lane/Major Mvn	nt N	BLn1	EBL	EBT	EBR	WBL	WBT	WBR S	SBLn1				

ivinor Lane/iviajor ivivmt	INBLUI	EBL	ERI	EBK	WBL	WRI	WBK 3	BLUI
Capacity (veh/h)	421	1127	-	-	1165	-	-	416
HCM Lane V/C Ratio	0.013	0.011	-	-	-	-	-	0.19
HCM Control Delay (s)	13.7	8.2	0	-	0	-	-	15.7
HCM Lane LOS	В	А	А	-	А	-	-	С
HCM 95th %tile Q(veh)	0	0	-	-	0	-	-	0.7

Intersection

Int Delay, s/veh	8.4					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		÷	et 👘		Y	
Traffic Vol, veh/h	178	134	118	57	46	119
Future Vol, veh/h	178	134	118	57	46	119
Conflicting Peds, #/hr	0	0	0	0	0	4
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	e, # -	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	64	64	64	64	64	64
Heavy Vehicles, %	4	21	20	7	5	0
Mvmt Flow	278	209	184	89	72	186

Major/Minor	Major1	Ν	/lajor2		Minor2	
Conflicting Flow All	273	0	-	0	994	233
Stage 1	-	-	-	-	229	-
Stage 2	-	-	-	-	765	-
Critical Hdwy	4.14	-	-	-	6.45	6.2
Critical Hdwy Stg 1	-	-	-	-	5.45	-
Critical Hdwy Stg 2	-	-	-	-		-
Follow-up Hdwy	2.236	-	-	-	3.545	3.3
Pot Cap-1 Maneuver	1279	-	-	-		811
Stage 1	-	-	-	-	802	-
Stage 2	-	-	-	-	454	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver		-	-	-	202	808
Mov Cap-2 Maneuver	-	-	-	-	202	-
Stage 1	-	-	-	-	605	-
Stage 2	-	-	-	-	454	-
Approach	EB		WB		SB	
HCM Control Delay, s	4.9		0		24.1	
HCM LOS					С	
Minor Lane/Major Mvn	nt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		1279	-	-	-	440
HCM Lane V/C Ratio		0.217	-	-	-	0.586
HCM Control Delay (s))	8.6	0	-	-	24.1
HCM Lane LOS		А	А	-	-	С
HCM 95th %tile Q(veh	1)	0.8	-	-	-	3.7

Intersection

Int Delay, s/veh	4.5					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	Y			ŧ	4	
Traffic Vol, veh/h	1	21	30	23	16	1
Future Vol, veh/h	1	21	30	23	16	1
Conflicting Peds, #/hr	0	1	6	0	0	6
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage	, # 0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	71	71	71	71	71	71
Heavy Vehicles, %	0	0	3	0	7	0
Mvmt Flow	1	30	42	32	23	1

Major/Minor	Minor2	l	Major1	Maj	or2	
Conflicting Flow All	146	31	30	0	-	0
Stage 1	30	-	-	-	-	-
Stage 2	116	-	-	-	-	-
Critical Hdwy	6.4	6.2	4.13	-	-	-
Critical Hdwy Stg 1	5.4	-	-	-	-	-
Critical Hdwy Stg 2	5.4	-	-	-	-	-
Follow-up Hdwy	3.5	3.3	2.227	-	-	-
Pot Cap-1 Maneuver	851	1049	1576	-	-	-
Stage 1	998	-	-	-	-	-
Stage 2	914	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuve	r 818	1042	1567	-	-	-
Mov Cap-2 Maneuve	r 818	-	-	-	-	-
Stage 1	965	-	-	-	-	-
Stage 2	909	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	8.6	4.2	0
HCM LOS	А		

Minor Lane/Major Mvmt	NBL	NBT E	EBLn1	SBT	SBR
Capacity (veh/h)	1567	-	1029	-	-
HCM Lane V/C Ratio	0.027	-	0.03	-	-
HCM Control Delay (s)	7.4	0	8.6	-	-
HCM Lane LOS	А	А	А	-	-
HCM 95th %tile Q(veh)	0.1	-	0.1	-	-
1.4

Intersection

Int Delay, s/veh

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	
Lane Configurations		4			4			4			4		
Traffic Vol, veh/h	17	276	5	6	330	46	6	0	3	21	0	20	
Future Vol, veh/h	17	276	5	6	330	46	6	0	3	21	0	20	
Conflicting Peds, #/hr	12	0	15	15	0	12	7	0	0	0	0	7	
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop	
RT Channelized	-	-	None										
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-	
Veh in Median Storage,	# -	0	-	-	0	-	-	0	-	-	0	-	
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-	
Peak Hour Factor	82	82	82	82	82	82	82	82	82	82	82	82	
Heavy Vehicles, %	0	8	0	0	8	0	0	0	0	0	0	11	
Mvmt Flow	21	337	6	7	402	56	7	0	4	26	0	24	

Major/Minor	Major1		1	Major2			Minor1		Ν	/linor2			
Conflicting Flow All	470	0	0	358	0	0	860	881	355	840	856	449	
Stage 1	-	-	-	-	-	-	397	397	-	456	456	-	
Stage 2	-	-	-	-	-	-	463	484	-	384	400	-	
Critical Hdwy	4.1	-	-	4.1	-	-	7.1	6.5	6.2	7.1	6.5	6.31	
Critical Hdwy Stg 1	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Critical Hdwy Stg 2	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Follow-up Hdwy	2.2	-	-	2.2	-	-	3.5	4	3.3	3.5	4	3.399	
Pot Cap-1 Maneuver	1102	-	-	1212	-	-	278	288	693	287	297	592	
Stage 1	-	-	-	-	-	-	633	607	-	588	572	-	
Stage 2	-	-	-	-	-	-	583	555	-	643	605	-	
Platoon blocked, %		-	-		-	-							
Mov Cap-1 Maneuver	1089	-	-	1195	-	-	254	272	683	275	280	581	
Mov Cap-2 Maneuver	-	-	-	-	-	-	254	272	-	275	280	-	
Stage 1	-	-	-	-	-	-	609	584	-	567	561	-	
Stage 2	-	-	-	-	-	-	550	544	-	624	582	-	
Approach	EB			WB			NB			SB			
HCM Control Delay, s	0.5			0.1			16.6			16.2			
HCM LOS							С			С			
Minor Lane/Major Myr	nt N	RI n1	FRI	FRT	FRR	W/RI	W/RT	W/RR	2DIn1				

Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR \$	SBLn1	
Capacity (veh/h)	321	1089	-	-	1195	-	-	370	
HCM Lane V/C Ratio	0.034	0.019	-	-	0.006	-	-	0.135	
HCM Control Delay (s)	16.6	8.4	0	-	8	0	-	16.2	
HCM Lane LOS	С	А	А	-	А	А	-	С	
HCM 95th %tile Q(veh)	0.1	0.1	-	-	0	-	-	0.5	

Int Delay, s/veh	4.9					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		र्भ	et -		Y	
Traffic Vol, veh/h	81	192	243	31	50	106
Future Vol, veh/h	81	192	243	31	50	106
Conflicting Peds, #/hr	11	0	0	11	0	6
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	, # -	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	77	77	77	77	77	77
Heavy Vehicles, %	6	7	9	7	9	5
Mvmt Flow	105	249	316	40	65	138

Major/Minor	Major1	Ν	lajor2	I	Minor2	
Conflicting Flow All	367	0	-	0	806	353
Stage 1	-	-	-	-	347	-
Stage 2	-	-	-	-	459	-
Critical Hdwy	4.16	-	-	-	6.49	6.25
Critical Hdwy Stg 1	-	-	-	-	5.49	-
Critical Hdwy Stg 2	-	-	-	-	5.49	-
Follow-up Hdwy	2.254	-	-	-		3.345
Pot Cap-1 Maneuver	1170	-	-	-	342	684
Stage 1	-	-	-	-	700	-
Stage 2	-	-	-	-	622	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1158	-	-	-	300	673
Mov Cap-2 Maneuver	-	-	-	-	300	-
Stage 1	-	-	-	-	620	-
Stage 2	-	-	-	-	616	-
Approach	EB		WB		SB	
HCM Control Delay, s	2.5		0		17.8	
HCM LOS	2.0		Ū		C	
					Ū	
				14/DT		
Minor Lane/Major Mvm	nt	EBL	EBT	WBT	WBR 3	
Capacity (veh/h)		1158	-	-	-	481
HCM Lane V/C Ratio		0.091	-	-		0.421
HCM Control Delay (s)		8.4	0	-	-	17.8
HCM Lane LOS		A	А	-	-	С
HCM 95th %tile Q(veh)	0.3	-	-	-	2.1

E. HCM REPORTS – BUILD CONDITIONS



	-	-	-	-	-	-	-			
		_								
١n	ŧ	n	0		2		0	hin	h	

Int Delay, s/veh	6.7					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	Y			र्भ	4	
Traffic Vol, veh/h	1	54	31	8	10	1
Future Vol, veh/h	1	54	31	8	10	1
Conflicting Peds, #/hr	0	0	1	0	0	1
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage	# 0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	74	74	74	74	74	74
Heavy Vehicles, %	0	0	5	0	0	0
Mvmt Flow	1	73	42	11	14	1

Major/Minor	Minor2	l	Major1	Maj	or2		
Conflicting Flow All	111	16	16	0	-	0	
Stage 1	16	-	-	-	-	-	
Stage 2	95	-	-	-	-	-	
Critical Hdwy	6.4	6.2	4.15	-	-	-	
Critical Hdwy Stg 1	5.4	-	-	-	-	-	
Critical Hdwy Stg 2	5.4	-	-	-	-	-	
Follow-up Hdwy	3.5	3.3	2.245	-	-	-	
Pot Cap-1 Maneuver	891	1069	1582	-	-	-	
Stage 1	1012	-	-	-	-	-	
Stage 2	934	-	-	-	-	-	
Platoon blocked, %				-	-	-	
Mov Cap-1 Maneuver	865	1068	1580	-	-	-	
Mov Cap-2 Maneuver	⁻ 865	-	-	-	-	-	
Stage 1	984	-	-	-	-	-	
Stage 2	933	-	-	-	-	-	

Approach	EB	NB	SB
HCM Control Delay, s	8.6	5.8	0
HCM LOS	А		

Minor Lane/Major Mvmt	NBL	NBT E	EBLn1	SBT	SBR
Capacity (veh/h)	1580	-	1063	-	-
HCM Lane V/C Ratio	0.027	-	0.07	-	-
HCM Control Delay (s)	7.3	0	8.6	-	-
HCM Lane LOS	А	А	А	-	-
HCM 95th %tile Q(veh)	0.1	-	0.2	-	-

2.6

Intersection

Int Delay, s/veh

					MOT			NET		0.01	0.D.T	000	
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	
Lane Configurations		- 4 >			- 44			- 44			- 4 >		
Traffic Vol, veh/h	12	281	1	0	211	24	2	0	2	51	0	32	
Future Vol, veh/h	12	281	1	0	211	24	2	0	2	51	0	32	
Conflicting Peds, #/hr	2	0	4	4	0	2	0	0	0	0	0	0	
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop	
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None	
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-	
Veh in Median Storage,	# -	0	-	-	0	-	-	0	-	-	0	-	
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-	
Peak Hour Factor	71	71	71	71	71	71	71	71	71	71	71	71	
Heavy Vehicles, %	15	12	0	0	12	0	0	0	0	0	0	0	
Mvmt Flow	17	396	1	0	297	34	3	0	3	72	0	45	

Major/Minor	Major1		1	Major2		I	Minor1		Ν	/linor2			
Conflicting Flow All	333	0	0	401	0	0	772	768	401	748	751	316	
Stage 1	-	-	-	-	-	-	435	435	-	316	316	-	
Stage 2	-	-	-	-	-	-	337	333	-	432	435	-	
Critical Hdwy	4.25	-	-	4.1	-	-	7.1	6.5	6.2	7.1	6.5	6.2	
Critical Hdwy Stg 1	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Critical Hdwy Stg 2	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Follow-up Hdwy	2.335	-	-	2.2	-	-	3.5	4	3.3	3.5	4	3.3	
Pot Cap-1 Maneuver	1157	-	-	1169	-	-	319	334	653	331	342	729	
Stage 1	-	-	-	-	-	-	604	584	-	699	659	-	
Stage 2	-	-	-	-	-	-	681	647	-	606	584	-	
Platoon blocked, %		-	-		-	-							
Mov Cap-1 Maneuver	1155	-	-	1165	-	-	294	326	651	324	333	728	
Mov Cap-2 Maneuver	-	-	-	-	-	-	294	326	-	324	333	-	
Stage 1	-	-	-	-	-	-	590	571	-	684	658	-	
Stage 2	-	-	-	-	-	-	639	646	-	592	571	-	
Approach	EB			WB			NB			SB			
HCM Control Delay, s	0.3			0			14			17.2			
HCM LOS							В			С			
Minor Lane/Maior Myn	nt N	IBLn1	EBL	EBT	EBR	WBL	WBT	WBR S	SBI n1				

Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR S	SBLn1
Capacity (veh/h)	405	1155	-	-	1165	-	-	412
HCM Lane V/C Ratio	0.014	0.015	-	-	-	-	-	0.284
HCM Control Delay (s)	14	8.2	0	-	0	-	-	17.2
HCM Lane LOS	В	А	А	-	А	-	-	С
HCM 95th %tile Q(veh)	0	0	-	-	0	-	-	1.2

Int Delay, s/veh	8.8					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		ب	et 👘		Y	
Traffic Vol, veh/h	181	147	122	57	46	120
Future Vol, veh/h	181	147	122	57	46	120
Conflicting Peds, #/hr	0	0	0	0	0	4
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	e, # -	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	64	64	64	64	64	64
Heavy Vehicles, %	4	21	20	7	5	0
Mvmt Flow	283	230	191	89	72	188

Major/Minor	Major1		/lajor2		Minor2	
Conflicting Flow All	280	0	-	0	1032	240
Stage 1	-	-	-	-	236	-
Stage 2	-	-	-	-	796	-
Critical Hdwy	4.14	-	-	-	6.45	6.2
Critical Hdwy Stg 1	-	-	-	-	5.45	-
Critical Hdwy Stg 2	-	-	-	-	5.45	-
Follow-up Hdwy	2.236	-	-	-	3.545	3.3
Pot Cap-1 Maneuver		-	-	-	255	804
Stage 1	-	-	-	-	796	-
Stage 2	-	_	-	-	439	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	r 1271	-	-	-	190	801
Mov Cap-2 Maneuver		-	-	-	190	-
Stage 1	-	_	-	-	593	-
Stage 2	_				439	_
Oldye Z					400	
Approach	EB		WB		SB	
HCM Control Delay, s	s 4.8		0		26	
HCM LOS					D	
Minor Lane/Major Mvi	mt	EBL	EBT	WBT	WBR	
Capacity (veh/h)		1271	-	-	-	424
HCM Lane V/C Ratio		0.223	-	-	-	0.612
HCM Control Delay (s	5)	8.6	0	-	-	26
HCM Lane LOS		А	А	-	-	D

4

HCM 95th %tile Q(veh)

0.9

_

Int Delay, s/veh	5.6					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	Y			ا	et	
Traffic Vol, veh/h	1	39	58	23	16	1
Future Vol, veh/h	1	39	58	23	16	1
Conflicting Peds, #/hr	0	1	6	0	0	6
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage	, # 0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	71	71	71	71	71	71
Heavy Vehicles, %	0	0	3	0	7	0
Mvmt Flow	1	55	82	32	23	1

Major/Minor	Minor2	l	Major1	Maj	jor2	
Conflicting Flow All	226	31	30	0	-	0
Stage 1	30	-	-	-	-	-
Stage 2	196	-	-	-	-	-
Critical Hdwy	6.4	6.2	4.13	-	-	-
Critical Hdwy Stg 1	5.4	-	-	-	-	-
Critical Hdwy Stg 2	5.4	-	-	-	-	-
Follow-up Hdwy	3.5	3.3	2.227	-	-	-
Pot Cap-1 Maneuver	767	1049	1576	-	-	-
Stage 1	998	-	-	-	-	-
Stage 2	842	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuve		1042	1567	-	-	-
Mov Cap-2 Maneuve	r 718	-	-	-	-	-
Stage 1	939	-	-	-	-	-
Stage 2	837	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	8.7	5.3	0
HCM LOS	А		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1567	-	1030	-	-
HCM Lane V/C Ratio	0.052	-	0.055	-	-
HCM Control Delay (s)	7.4	0	8.7	-	-
HCM Lane LOS	А	А	А	-	-
HCM 95th %tile Q(veh)	0.2	-	0.2	-	-

2

Intersection

Int Delay, s/veh

Movement EBL EBT EBR WBL WBT WBR NBL NBT NBR SBL SBT SBR	
Lane Configurations 💠 💠 🛟	
Traffic Vol, veh/h 28 276 5 6 330 63 6 0 3 32 0 27	
Future Vol, veh/h 28 276 5 6 330 63 6 0 3 32 0 27	
Conflicting Peds, #/hr 12 0 15 15 0 12 7 0 0 0 0 7	
Sign Control Free Free Free Free Free Free Stop Stop Stop Stop Stop	
RT Channelized None None None None	
Storage Length	
Veh in Median Storage, # - 0 0 0 0 -	
Grade, % - 0 0 0 0 -	
Peak Hour Factor 82 82 82 82 82 82 82 82 82 82 82 82 82	
Heavy Vehicles, % 0 8 0 0 8 0 0 0 0 0 0 11	
Mvmt Flow 34 337 6 7 402 77 7 0 4 39 0 33	

Major/Minor	Major1		ſ	Major2			Minor1		Ν	linor2			
Conflicting Flow All	491	0	0	358	0	0	901	928	355	877	893	460	
Stage 1	-	-	-	-	-	-	423	423	-	467	467	-	
Stage 2	-	-	-	-	-	-	478	505	-	410	426	-	
Critical Hdwy	4.1	-	-	4.1	-	-	7.1	6.5	6.2	7.1	6.5	6.31	
Critical Hdwy Stg 1	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Critical Hdwy Stg 2	-	-	-	-	-	-	6.1	5.5	-	6.1	5.5	-	
Follow-up Hdwy	2.2	-	-	2.2	-	-	3.5	4	3.3	3.5	4		
Pot Cap-1 Maneuver	1083	-	-	1212	-	-	261	270	693	271	283	583	
Stage 1	-	-	-	-	-	-	613	591	-	580	565	-	
Stage 2	-	-	-	-	-	-	572	544	-	623	589	-	
Platoon blocked, %		-	-		-	-							
Mov Cap-1 Maneuver	1071	-	-	1195	-	-	232	251	683	257	263	572	
Mov Cap-2 Maneuver	-	-	-	-	-	-	232	251	-	257	263	-	
Stage 1	-	-	-	-	-	-	581	560	-	551	554	-	
Stage 2	-	-	-	-	-	-	531	534	-	595	558	-	
Approach	EB			WB			NB			SB			
HCM Control Delay, s	0.8			0.1			17.6			18.2			
HCM LOS							С			С			
Minarl ana/Majar Mun	-1 NE	1	EDI	ГОТ	грр								

Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR S	SBLn1	
Capacity (veh/h)	297	1071	-	-	1195	-	-	344	
HCM Lane V/C Ratio	0.037	0.032	-	-	0.006	-	-	0.209	
HCM Control Delay (s)	17.6	8.5	0	-	8	0	-	18.2	
HCM Lane LOS	С	А	А	-	А	А	-	С	
HCM 95th %tile Q(veh)	0.1	0.1	-	-	0	-	-	0.8	

Int Delay, s/veh	5.1					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		ب	et 👘		Y	
Traffic Vol, veh/h	83	201	257	31	50	109
Future Vol, veh/h	83	201	257	31	50	109
Conflicting Peds, #/hr	11	0	0	11	0	6
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage	, # -	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	77	77	77	77	77	77
Heavy Vehicles, %	6	7	9	7	9	5
Mvmt Flow	108	261	334	40	65	142

Major/Minor	Major1	Ν	/lajor2		Minor2	
Conflicting Flow All	385	0	-	0	842	371
Stage 1	-	-	-	-	365	-
Stage 2	-	-	-	-	477	-
Critical Hdwy	4.16	-	-	-	6.49	6.25
Critical Hdwy Stg 1	-	-	-	-	5.49	-
Critical Hdwy Stg 2	-	-	-	-	5.49	-
Follow-up Hdwy	2.254	-	-	-		3.345
Pot Cap-1 Maneuver	1152	-	-	-	325	668
Stage 1	-	-	-	-	687	-
Stage 2	-	-	-	-	610	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver		-	-	-	283	657
Mov Cap-2 Maneuver	-	-	-	-	283	-
Stage 1	-	-	-	-	605	-
Stage 2	-	-	-	-	604	-
Approach	EB		WB		SB	
HCM Control Delay, s	2.5		0		18.8	
HCM LOS					С	
Minor Lane/Major Mvn	nt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		1140	-	-	-	464
HCM Lane V/C Ratio		0.095	-	-	-	0.445
HCM Control Delay (s))	8.5	0	-	-	18.8
HCM Lane LOS	/	А	А	-	-	С
HCM 95th %tile Q(veh		0.3				2.2

F. LEFT TURN LANE WARRANT EVALUATION



Willamina Ridgefield Heights TIA Left Turn Lane Warrants

According to the ODOT Analysis Procedures Manual Section 12.2.1, a left turn lane is warranted if any of the three following criteria are met:

- Criterion 1: Volume thresholds analyzed using Exhibit 12-1
- · Criterion 2: History of crashes that may be mitigated by a left turn lane
- Criterion 3: Special cases such as nearby railroad crossings, geometric or sight distance concerns, or the presence of a non-traversable mediar

Criterion 1



Study Intersection	No Build Volumes						
	AM Opposing +			PM Opposing +			
	Advancing		Above Line on	Advancing		Above Line on	
	Volumes	AM Left Turns	Exhibit 12-1?	Volumes	PM Left Turns	Exhibit 12-1?	
NW Willamina Drive & NW B Street	42	23	No	70	30	No	
NE Main Street & NW B Street		9	No	675	17	Yes	
NE Main Street & NE Oaken Hills Drive	487	178	Yes	547	81	Yes	

Note: Speed Limit = 25 mph

		Build Volumes					
	AM Opposing +			PM Opposing +			
	Advancing		Above Line on	Advancing		Above Line on	
	Volumes	AM Left Turns	Exhibit 12-1?	Volumes	PM Left Turns	Exhibit 12-1?	
NW Willamina Drive & NW B Street	50	31	No	98	58	No	
NE Main Street & NW B Street	529	12	No	702	28	Yes	
NE Main Street & NE Oaken Hills Drive	507	181	Yes	572	83	Yes	

Note: Speed Limit = 25 mph

*(Advancing Volume/Number of Advancing Through Lanes) + (Opposing Volume/Number of Opposing Through Lanes)

Opposing left turns are not counted as opposing volumes

Criterion 2

Study Intersection	Number of EB Left-Turn Related Crashes	History of Crashes?
NW Willamina Drive & NW B Street	0	No
NE Main Street & NW B Street	0	No
NE Main Street & NE Oaken Hills Drive	0	No

Criterion 3

Study Intersection	Special Circumstances?		
NW Willamina Drive & NW B Street	No		
NE Main Street & NW B Street	No		
NE Main Street & NE Oaken Hills Drive	No		

G. SITE PLAN



