

Sec. 21-83. - Schedule of district regulations.

The following regulations apply to the indicated districts:

Districts As Shown On Zoning District Map	Uses Permitted			Uses Permitted by City Council By Special Permit	Uses Prohibited	MINIMUM YARDS			MINIMUM LOT SIZE	
						Front Depth	Rear Depth	Side Depth	Area Sq. Ft.	Width in Feet
"A-1" Residence	Single-family detached dwelling; garage apartment; school offering general education course; church; home vegetable and flower garden; hobby-type horticultural nursery and greenhouse; accessory use.			Children's nursery; cemetery; golf, tennis or similar athletic club; hospital, except animal hospital; convalescent home; sanitarium; institution; philanthropic use; municipal, parish, state or federal use; public utility; private club not conducted for profit, provided all structures are located 50 ft. from any property line;	All uses not specifically permitted herein.	For all buildings except unattached one-story buildings of accessory use. 30;ft; 12;ft; 12;ft; See Article V, Section 24-10.			9,600 per family	80