

1. FURNISH AND INSTALL ALL MATERIALS FOR A COMPLETE INSTALLATIONS IN ALL RESPECTS INTENDED USE. COMPLY WITH ALL APPLICABLE STATE AND LOCAL CODES AND MANUFACTURE'S RECOMMENDED.
2. COORDINATE NEW CONSTRUCTION WITH EXISTING CONDITIONS, FIELDS VERIFY ALL EXISTING CONDITIONS.
3. LOCATIONS OF SEWER PIPES AND WATER PIPES HAVE NOT BEEN VERIFIED. CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING THEIR LOCATIONS AND SIZES.
4. PROVIDE ACCESS DOOR TO ALL INACCESSIBLE WATER VALVES AND CLEAN-OUTS.
5. ANY NEW OR EXISTING PENETRATIONS IN A FIRE RATED ASSEMBLY SHALL BE SEALED IN A MANNER TO MAINTAIN THE RATING OF THAT ASSEMBLY.

II. EXISTING PIPES SIZE AND LOCATIONS HAVE NOT BEEN VERIFIED. CONTRACTOR IS RESPONSIBLE TO FIELD VERIFY EXACT LOCATION AND SIZES OF ALL EXISTING PIPING THAT IS BEING CONNECTED TO OR MODIFIED, AND TO VERIFY THAT PROPER SLOPES AND ELEVATIONS ARE AVAILABLE.

