



OPENING SCHEDULE

MK.	SIZE	DESCRIPTION	FRAME			REMARKS	QTY.
			ALUM.	STEEL	WOOD		
①	11'-3" x 10'-0" O/O FRAME	ALUM. STOREFRONT, CLEAR, INSUL. GLASS	•			W 4 EQUAL LITES	2
②	15'-0" x 10'-0" O/O FRAME	ALUM. STOREFRONT, CLEAR, INSUL. GLASS	•			W 4 EQUAL LITES	2
③	21'-0" x 10'-0" O/O FRAME	ALUM. STOREFRONT, CLEAR, INSUL. GLASS	•			W 4 EQUAL LITES	2
④	11'-0" x 10'-0" O/O FRAME	ALUM. STOREFRONT, CLEAR, INSUL. GLASS	•			W 4 EQUAL LITES	1
⑤	3'-0" x 6'-8"	S.C. WOOD		•		HDWL. A, E, H,	8

ALL DOORS LEVER HANDLES

ROOM FINISH SCHEDULE

AREA	FLOOR	BASE	WALLS	WAINSCOT	CEILING	REMARKS
SUITE'S 101 THRU 108	CONCRETE	CONCRETE	1" VINYL CORR. TILE	NONE PROVIDED	5/8" GYP. BRO. TAPE & FINISHED	2" x 4" WHITE FLUSH W/ 1" X 1" MESH & 1/8" TIE GRID
RESTROOMS - SUITE'S 101 THRU 108						EPOXY PAINT

HARDWARE SCHEDULE

A	BUTTS	1-1/2 PAIR HAGER 12191 U526D 4 1/2 X 4 1/2
B	BUTTS	1-1/2 PAIR BB01 U526D 4 1/2 X 4 1/2
C	LOCKSET	YALE 5300 SERIES - AU 5301 LN
D	PASSAGE SET	YALE 5300 SERIES - AU 5301 LN
E	PRIVACY SET	YALE 5300 SERIES - AU 5302 LN
F	CLOSER	YALE 3501-PA-AL-SNI (ADA)
G	THRESHOLD	NATIONAL GUARD #846, OR PEMKO #2005 OR ZERO #566
H	STOP	FLOOR OR WALL MOUNT AS REQUIRED
J	WEATHERSTRIP	NATIONAL GUARD 160AV
K	FLUSH BOLT	282D - HAGER

FLOOR PLAN
SCALE: 1/8" = 1'-0"

REVISIONS

BY
DATE
NO.

THIS PLAN IS THE PROPERTY OF SALCO CONSTRUCTION, INC. If This Plan Is Copied and/or Duplicated In Any Way a Consultant & Drafting Fee Will Be charged accordingly.

Your design/build general construction firm

SALCO CONSTRUCTION, INC.
8484 ATHENS AVE. - BATON ROUGE, LA. 70814 - 225/927-3970

A. BUILDING FOR:
HIGHLAND CROSSING

TENANTS: SUITE'S 101 THRU 108 (UNKNOWN)
18411 HIGHLAND ROAD
BATON ROUGE, LOUISIANA

SALES PERSON	SUPERVISOR
DATE 3/15/05	DRAWN KTM
PROJECT NUMBER 08-05-	
SHEET A-1	
2 of 3	