

HDCP ACCESSIBILITY IN RESTROOM NOTES:

1. WHEEL CHAIR TURNING IN ALL RESTROOMS SHALL BE WITH A CLEAR TURNING SPACE OF 60" OR A 4" SHAPED SPACE OF 36" PER FIGURE 3(B).
2. WATER AND DRAIN PIPES FOR SINKS SHALL BE WELL INSULATED OR COVERED/NO SHARP OR ABRASIVE SURFACES ARE PERMITTED UNDER SINK(S) OR SINK COUNTER.
- 3 THE SINK(S) ARE TO HAVE A CLEAR FLOOR SPACE OF A MINIMUM OF 30" WIDE AND 48" IN DEPTH. THE BOTTOM EDGE OF THE SINK IS TO BE NO HIGHER THAN 34" ABOVE THE FLOOR.
- 4 FAUCET CONTROLS AND OPERATING MECHANISM SHALL BE LEVER ACTUATE THE CONTROLS FOR LEVER TYPE IS FORCE REQUIRED TO GRASPING OR TWISTING OF THE MIST, THE FORCE REQUIRED TO GRASPING OR TWISTING OF THE MIST OR TIGHT GRASPING.
- 5 GRAB BARS FOR THE WATER CLOSETS ARE TO BE 1" IN DIAMETER, NO SHARP OR ABRASIVE ELEMENTS ON THEM. EDGES ARE TO HAVE A MIN. 1/8" RADIUS.
- 6 GRAB BARS ARE TO BE SECURELY MOUNTED TO BLOCKING IN WALLS 250 LB POINT LOAD.
- 7 MIRRORS SHALL BE PLACED WITH THE BOTTOM EDGE NO MORE THAN 40" FROM THE FLOOR.

HANDICAPPED ACCESSIBILITY NOTES:

HANDICAPPED ACCESSIBILITY WILL BE PROVIDED IN ACCORDANCE WITH ADA - AG (9/19/90) AND IN COMPLIANCE ACT - ACCESSIBILITY GUIDELINES.

METAL THRESHOLDS AT EXTERIOR DOORS SHALL NOT HIGHER THAN 1/2".

MAINTAINING CLEARANCE AT DOORS SHALL BE PER FIGURE 2B.

EDGE OF THE DOOR SHALL BE 18" MINIMUM ON THE PULL SIDE AND 12" MINIMUM ON THE PUSH SIDE.

3. DOOR HANDWAYS SHALL COMPLY WITH 413-9-1 ALL LEVER HANDLES AND LOCKS SHALL BE OPERABLE WITH ONE HAND AND NOT REQUIRE TWISTING OF THE MIST OR TIGHT GRASPING.

4. FAULT-CONTROL AND OPERATING MECHANISM SHALL BE LEVER GRASPING OF THE HAND. THE FORCE REQUIRED TO GRASPING OF THE HAND SHALL BE MAX. 5 LB. AND 15 LB. FOR PUSH TYPE.
5. GRAB BARS FOR THE WATER CLOSETS ARE TO BE 1" IN DIAMETER 4 MIN. 1/8" RADIUS.
6. GRAB BARS ARE TO BE SECURELY MOUNTED TO BLOCKING IN WALLS 250 LB. POINT LOAD AND 100 LB. POINT LOAD.
7. MISERABLE POINT PLACED WITH THE BOTTOM EDGE ON MORE THAN 4

A diagram showing a vertical dimension line with arrows at both ends, labeled "40" max". To the right of the dimension line is a horizontal line with a thick black bar above it, representing a cabinet. Below the horizontal line is a rectangular box with diagonal lines inside, representing a hanging cabinet.

[illegible]

A diagram showing a person in a wheelchair approaching a counter. A vertical dimension line on the left indicates a clearance of 34" max from the floor to the bottom of the counter.

MARK	DESCRIPTION
	FLUORESCENT LAY-IN 2' X 4'
	FLUORESCENT MOUNT 1' X 6'
	FLUORESCENT MOUNT 2' X 4'
	EXIT SIGN WITH BATTERY BACK UP.
	DUAL HEAD LIGHT, EMERGENCY WALL LIGHT.
	2' X 2' RETURN AIR GRILL
	2' X 2' SUPPLY AIR GRILL
	1' X 1' SUPPLY AIR GRILL
	80 CFM EXHAUST FAN 120 VOLTS

Architectural floor plan of Suite 108. The plan shows a large rectangular room with a grid of columns and beams. The text "SUITE 108" is centered in the room. There are several exits marked with "EXIT" and arrows. A staircase is located on the right side. Dimensions are provided for various areas: 1'-6 1/2" for the top section, 0'-10" for the bottom section, and 0'-4" for the right section. A circular area with the number 10 is at the bottom right.

COMMIT TO THE LORD
WHATEVER YOU DO, AND
YOUR PLANS WILL SUCCEED.
PROVERBS 16:5

PROJECT NO.
201453

AFFORDABLE DESIGN SERVICE, L.L.C.
P.O. BOX 1994 CELL: (225) 675-7350
PRAIRIEVILLE, LA 70769 PHONE: (225) 677-5501

DESCRIPTION:	REFLECTED CEILING LAYOUT
DATE:	07-29-14
REVISION:	ISSUED FOR APPROVAL

PROPOSED BUILD OUT
FOR SUITE 108
PELICAN COMMERCE CENTER
HIGHWAY 44
GONZALES, LA 70737
ASCENSION PARISH

THIS PLAN NOT BEING AN ARCHITECTURAL, OR ENGINEERING FIRM, STATES NO LIABILITY FOR THE STRUCTURAL OR ARCHITECTURAL DESIGN INTEGRITY OF THESE PLANS. EVERY EFFORT HAS BEEN MADE TO INSURE ALL DIMENSIONS ARE CORRECT AND ENVIRONMENTAL, LOCAL, AND STATE REQUIREMENTS ARE MET. THE USER OF THESE PLANS ACCEPTS FULL RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO CORRECTLY FOLLOW THE PLANS AT HIS OWN EXPENSE AND NOT THE RESPONSIBILITY OF THE DESIGN SERVICE.

