



2 DOOR SCHEDULE

MK	SIZE	THK	RATED	DISCUSSION
1	PR 3'-0" x 7'-0"	STD.		ALUM. FRAME / SAFETY GLASS / GROUND FLOOR PROVIDE PANIC EXIT MECHANISM & AUTO CLOSER. DOOR FULL 5' W/TERICK.
2	3'-0" x 7'-0"	1 3/4"		HOLLOW CORE METAL FLUSH PROVIDE FIRE RATED HARDWARE ONLY NO EXTERIOR DOOR HARDWARE
3	PR 3'-0" x 6'-8"	1 3/8"		INT. GR. S.C. FLUSH PART. BR. DEL. PARTING HINGED FLUSH & KICK PLATES @ BOTH SIDES AUTO CLOSER PLASTIC LAMINATE FINISH
4	3'-0" x 6'-8"	1 3/8"		INT. GR. S.C. FLUSH PART. BR. PUSH, PULL & KICK PLATES @ BOTH SIDES AUTO CLOSER PLASTIC LAMINATE FINISH
5	3'-0" x 6'-8"	1 3/8"		INT. GR. S.C. FLUSH PART. BR. KEVED LOCKSET
6	3'-0" x 6'-8"	1 3/8"		INT. GR. S.C. FLUSH PART. BR. PLASTIC LAMINATE FINISH, PUSH, PULL & KICK PLATES @ BOTH SIDES. AUTO CLOSER
7	3'-0" x 6'-8"	1 3/8"		INT. GR. S.C. FLUSH PART. BR. PLASTIC LAMINATE FINISH "DUTCH DOOR" WITH SHELF ON LOWER LEAF KEVED LOCKSETS @ BOTH SIDES.
8	3'-0" x 7'-0"	1 3/4"	3/4 HR.	HOLLOW CORE METAL FLUSH KEVED LOCKSET & AUTO CLOSER
9	3'-0" x 7'-0"	1 3/4"		HOLLOW CORE METAL FLUSH KEVED LOCKSET
10				

GLAZED DOORS INCLUDE DOOR FRAME & HARDWARE.

3 INTERIOR FINISH SCHEDULE

AREA	FLOORS		WALLS		CEILINGS		TRIM	
	CONCRETE	WOOD	PAINT	PLASTER	PLASTER	WOOD	WOOD	WOOD
THEATRE								
FOYER								
BAR								
LOUNGE								
FORMAL DINING								
MANAGER'S / TV CONTROL								
MONEY ROOM								
MUTUEL LINES								
OFFICE								
CONCESSION STAND								
KITCHEN								
RESTROOMS								
HALLS								

- 4 GENERAL NOTES**
- The Contractor is responsible for meeting all Southern Building Code, Zoning Ordinance and State Fire Marshall regulations.
 - Provide accessibility for the physically handicapped conforming to ANSI 1-117-7, 1981 Edition.
 - Bathrooms marked as handicapped (WC lavatory & WC water closet) shall be equipped and constructed to conform with all ANSI 1-117-7, 1981 edition regulations.
 - Exit doors shall not be locked during periods of occupancy.
 - All insulation and insulation assemblies shall have a smoke developed factor of less than 450. Concealed insulation shall have a flame spread rating of 0-75, exposed insulation shall have a flame spread rating of 0-50.
 - Provide safety glazing at hazardous locations to conform with the Federal Glassing Std./ Federal Glassing Act. I.A.N.S. 40.1631-1635.
 - Interior finishes shall comply with table 704.3 of the SBC.
 - All draftstopping to comply with Sec. 705.2 of the SBC. Draftstop attic spaces in areas of less than 3000 sq. ft.
 - Firestopping shall be provided in walls and partitions to cut off all concealed draft openings, both horiz. and vert. and to form a fire barrier between floor and roof spaces. All openings around pipes, ducts or conduit shall be firestopped with approved non-combustible material. Firestopping shall comply with Sec. 705.1 of the SBC.
 - Electrical work shall comply with NFPA 70, National Electrical Code.
 - HVAC work shall comply with NFPA 90, Standard for the Installation of Air Conditioning and Ventilation Systems.

1 FLOOR PLAN
SCALE: 1/4" = 1'-0"

SQUARE FOOTAGE	
BUILDING AREA	8182
PORCH	769
STORAGE	778
TOTAL AREA	9729

FASTING.
P.O. BOX 982
COVINGTON LA.

THE FINISH LINE
BUILDING PLANS FOR
WISCONSIN PARISH, LA.

GERARD W. LANGLOIS, P.E.
1534 TURRET DRIVE (504) 272-4279
BATON ROUGE, LA. 70816

DATE: MAR '89
DRAWN BY: RCB
REVISIONS:

SHEET NO. **A-1** OF **1**
PLAN NO. C-8C